Jones Gillam Renz Architects

Address
730 N 9th St.
Salina, KS 67401

1881 Main St., Suite 301
Kansas City, MO 64108

Contact
jgr@jgrachitects.com
(785) 827-0386

Web
jgrarchitects.com

Project Manual

for

LANDMARK 601
Conroe, TX

February 17, 2026

Project No. 23-3385

LANDMARK 601
EXISTING BUILDING REMODEL
CONROE, TEXAS

Project No. 23-3385

DATE OF DRAWINGS AND SPECIFICATIONS	February 17, 2026
OWNER	OPG LANDMARK 301 PARTNERS, LLC Pat Beatty, Senior Partner Matt Gillam, Managing Partner 250 N. Santa Fe Ave, Suite A, Salina, KS 67401 913 396 6310
ARCHITECT	JONES GILLAM RENZ ARCHITECTS INC Christopher Gillam, Project Architect 730 N. 9th, Salina KS 67401 785 827 0386
STRUCTURAL ENGINEER	BOB D. CAMPBELL & CO. Michael Falbe, P.E. 4338 Belleview, Kansas City, MO 64111 816 531 4144
MECHANICAL/ELECTRICAL	LST CONSULTING ENGINEERS, P.A. John F. Lewis-Smith, PE 4809 Vue Du Lac Place, Ste 201, Manhattan KS 66503 785 587 8042 Fax 785 587 8039
CIVIL ENGINEER	SM Engineering Sam Malinowsky, P.E. 5507 High Meadow Circle, Manhattan, KS 66503 785 341 9747

Table of Contents

		Page
GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION		A201-2007-1 - 38
SUPPLEMENTARY CONDITIONS OF THE CONTRACT		SC-1 - SC-3
LIST OF DRAWINGS		LOD-1
ASBESTOS REPORT		AR1 – AR56
LEAD BASED PAINT REPORT		LBP1 – LBP162
NOISE STUDY REPORT		NS1 – NS34
CONTRACTOR SUBMITTAL REVIEWS		CSR1 – CSR12
GEOTECHNICAL REPORT		GR1 – GR41
Division 1 - General Requirements		
Section 01010	General Work Requirements	01010-1 – 01010-4
Section 01019	Special Provisions	01019-1 – 01019-3
Section 01500	Temporary Facilities	01500-1 – 01500-2
Division 2 - Site Work		
Section 02110	Site Clearing	02110-1
Section 02205	Soil Materials	02205-1
Section 02211	Rough Grading	02211-1 – 02211-2
Section 02222	Excavating	02222-1
Section 02223	Backfilling	02223-1 – 02223-2
Section 02225	Trenching	02225-1 – 02225-2
Section 02281	Termite Control	02281-1 – 02281-2
Section 024119	Selective Demolition	024119-1 – 024119-4
Section 02520	Portland Cement Concrete Paving	02520-1 – 02520-2
Section 02810	Irrigation Systems	02810-1 – 02810-6
Section 02920	Lawns and Grasses	02920-1 – 02920-5
Section 02930	Exterior Plants	02930-1 – 02930-8
Division 3 - Concrete		
Section 03100	Concrete Formwork	03100-1 – 03100-2
Section 03200	Concrete Reinforcement	03200-1 – 03200-2
Section 03300	Cast-In-Place Concrete	03300-1 – 03300-3
Division 4 - Masonry		
Section 04011 PB1	Assessing Cleaning & Water Repellant Treatments	04011PB1-1 - 04011PB1-11
Section 04011 PB2	Repointing Mortar Joints	04011PB2-1 – 04011PB2-11
Section 04011 PB6	Dangers of Abrasive Cleaning	04011PB6-1 – 04011PB6-8
Section 04011 PB7	Preservation of Historic Terra-Cotta	01011PB7-1 – 04011PB7-20
Section 040120 .63	Brick Masonry Repair	04012.63-1 – 04012.63-4
Section 040120 .64	Brick Masonry Repointing	04012.64-1 – 04012.64-3
Section 04100	Mortar and Masonry Grout	04100-1 – 04100-2
Section 04300	Unit Masonry	04300-1 – 04300-4
Section 04719 PB42	Repair & Replacement of Historical Cast Stone	04719PB42-1 – 04719PB42-8
Section 04720 0	Cast Stone Masonry	047200-1 – 047200-3
Division 5 - Metals		
Section 05120	Structural Steel	05120-1 – 05120-2
Section 05400	Cold-Formed Metal Framing	05400-1 – 05400-6
Section 05500	Metal Fabrication	05500-1 – 05500-6
Section 05520	Handrail and Railings	05520-1 – 05520-2
Division 6 - Wood and Plastics		
Section 06100	Rough Carpentry	06100-1 – 06100-7
Section 06112	Framing and Sheathing	06112-1 – 06112-2
Section 06114	Wood Blocking	06114-1
Section 06200	Finish Carpentry	06200-1 – 06200-2
Section 06410	Custom Casework	06410-1 – 06410-3
Division 7 - Thermal and Moisture Protection		
Section 07213	Batt Insulation	07213-1 – 07213-2
Section 07272 9	Liquid-Applied Rough Opening Flashing Membrane for Restoration of Existing Conditions	072729-1 – 072729-5
Section 07620	Sheet Metal Flashing and Trim	07620-1 – 07620-2
Section 07900	Joint Sealers	07900-1 – 07900-2

Table of Contents, (Cont'd) **Page**

Division 8 - Doors and Windows

Section 08111	Standard Steel Doors and Frames	08111-1 – 08111-2
Section 08211	Panel Masonite Doors	08211-1 – 08211-2
Section 08410	Aluminum Entrances and Curtain Walls	08410-1 – 08410-3
Section 08520	Aluminum Windows	08520-1 – 08520-5
Section 08540 0	Composite Windows	085400-1 – 085400-4
Section 08710	Door Hardware	08710-1 – 08710-5
Section 08800	Glazing	08800-1 – 08800-2

Division 9 – Finishes

Section 09016	Terrazzo (Floor Restoration)	09016-1 – 09016-2
Section 09239 PB21	Repairing Historic Flat Plaster Walls and Ceilings	09239PB21-1 – 09239PB21-9
Section 09240 0	Cement Plastering	092400-1 – 092400-5
Section 09241	Gypsum Veneer Plastering	09241-1 – 09241-4
Section 09290	Gypsum Board	09290-1 – 09290-4
Section 09300 PB40	Preserving Historic Ceramic Tile Floors	09300PB40-1 – 09300PB40-6
Section 09306	Floor and Wall Tile	09306-1 – 09306-2
Section 09640 0	Existing Wood Flooring	096400-1 – 096400-2
Section 09650	Resilient Flooring	09650-1 – 09650-2
Section 09900	Painting	09900-1 – 09900-4
Section 09900 PB28	Painting Historic Interiors	09900PB28 – 1 – 0900PB28-8

Division 10 – Specialties

Section 10431	Signage	10431-1 – 10431-3
Section 10522	Fire Extinguishers, Cabinets, and Accessories	10522-1
Section 10800	Toilet and Bath Accessories	10800-1
Section 10850	Building Specialties	10850-1

Division 11 - Equipment

Section 11451	Residential Appliances	11451-1 – 11451-4

Division 12 - Furnishings

Section 12356	Kitchen Casework	12356-1 – 12356-7
Section 124910	Horizontal Louver Blinds	124910-1 – 124910-3

Division 21 – Fire Suppression

Section 210500	Common Work Results for Fire Suppression	210500-1 – 210500-6
Section 210523	General-Duty Valves for Water-Based Fire-Suppression Piping	210523-1 – 210523-5
Section 210553	Identification for Fire Suppression Piping and Equipment	210553-1 – 210553-2
Section 211300	Fire Suppression Sprinklers	211300-1 – 211300-4
Section 213000	Fire Pumps	213000-1 – 213000-4

Division 22 - Plumbing

Section 220501	Plumbing Demolition	220501-1
Section 220553	Identification for Plumbing Piping and Equipment	220553-1 – 220553-2
Section 220719	Plumbing Piping Insulation	220719-1 – 220719-3
Section 221005	Plumbing Piping	221005-1 – 221005-11
Section 221006	Plumbing Piping Specialties	221006-1 – 221006-2
Section 223000	Plumbing Equipment	223000-1 – 223000-5
Section 224000	Plumbing Fixtures	224000-1 – 224000-2

Division 23 – Heating, Ventilating, and Air Conditioning (HVAC)

Section 230001	Mechanical Demolition	230001-1
Section 230593	Testing, Adjusting, and Balancing for HVAC	230593-1 – 230593-4
Section 230713	Duct Insulation	230713-1 – 230713-3
Section 230719	HVAC Piping Insulation	230719-1 – 230719-2
Section 232100	General Requirements for HVAC Piping	232100-1 – 232100-2
Section 232300	Refrigerant Piping	232300-1 – 232300-3
Section 233100	HVAC Ducts and Casings	233100-1 – 233100-3
Section 233300	Air Duct Accessories	233300-1 – 233300-4
Section 233700	Air Outlets and Inlets	233700-1
Section 234000	HVAC Air Cleaning Devices	234000-1 – 234000-2
Section 237210	Air-To-Air Energy Recovery Equipment	237210-1 – 237210-2
Section 237413	Packaged Outdoor Central-Station Air-Handling Units	237413-1 – 237413-3
Section 238127	Mini-Split Heat Pump Systems	238127-1 – 238127-3
Section 238128	Small-Split System Heating & Cooling	238128-1 – 238128-3

26 - Electrical

Section 260501	Electrical Demolition	260501-1
Section 260519	Low-Voltage Electrical Power Conductors and Cables	260519-1 – 260519-7
Section 260526	Grounding and Bonding for Electrical Systems	260526-1 – 260526-5
Section 260529	Hangers and Supports for Electrical Systems	260529-1 – 260529-2
Section 260534	Conduit	260534-1 – 260534-8
Section 260537	Boxes	260537-1 – 260537-5
Section 260553	Identification for Electrical Systems	260553-1 – 260553-5
Section 260919	Enclosed Contactors	260919-1 – 260919-2
Section 260923	Lighting Control Devices	260923-1 – 260923-6
Section 262100	Low Voltage Electrical Service Entrance	262100-1 – 262100-2
Section 262413	Switchboards	262413-1 – 262413-5
Section 262416	Panelboards	262416-1 – 262416-6
Section 262717	Equipment Wiring	262717-1 – 262717-2
Section 262726	Wiring Devices	262726-1 – 262726-5
Section 262813	Fuses	262813-1 – 262813-2
Section 262818	Enclosed Switches	262818-1 – 262818-3
Section 264300	Surge Protective Devices	264300-1 – 264300-4
Section 265100	Interior Lighting	265100-1 – 265100-8
Section 265600	Exterior Lighting	265600-1 – 265600-4

Division 28 – Electronic Safety and Security

Section 283100	Fire Detection and Alarm	283100-1 – 283100-6

AIA® Document A201™ – 2017

General Conditions of the Contract for Construction

for the following PROJECT:
(Name and location or address)

Landmark 601
Conroe, TX
JGR Project #23-3385

THE OWNER:
(Name, legal status and address)

OPG 601 Partners, LLC
Matt Gillam, Managing Partner
250 N. Santa Fe Ave, Suite A, Salina, KS 67401
913-396-6310

THE ARCHITECT:
(Name, legal status and address)

Jones Gillam Renz Architects
Christopher Gillam, Principal
730 N. Ninth St., Salina, KS 67401
785-827-0386

TABLE OF ARTICLES

1 GENERAL PROVISIONS

2 OWNER

3 CONTRACTOR

4 ARCHITECT

5 SUBCONTRACTORS

6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

7 CHANGES IN THE WORK

8 TIME

9 PAYMENTS AND COMPLETION

10 PROTECTION OF PERSONS AND PROPERTY

11 INSURANCE AND BONDS

12 UNCOVERING AND CORRECTION OF WORK

13 MISCELLANEOUS PROVISIONS

14 TERMINATION OR SUSPENSION OF THE CONTRACT

15 CLAIMS AND DISPUTES

ADDITIONS AND DELETIONS:
The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

For guidance in modifying this document to include supplementary conditions, see AIA Document A503™, Guide for Supplementary Conditions.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

INDEX
(Topics and numbers in bold are Section headings.)

Acceptance of Nonconforming Work
9.6.6, 9.9.3, **12.3**
Acceptance of Work
9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3
Access to Work
3.16, 6.2.1, 12.1
Accident Prevention
10
Acts and Omissions
3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5, 10.2.8, 13.3.2, 14.1, 15.1.2, 15.2
Addenda
1.1.1
Additional Costs, Claims for
3.7.4, 3.7.5, 10.3.2, 15.1.5
Additional Inspections and Testing
9.4.2, 9.8.3, 12.2.1, **13.4**
Additional Time, Claims for
3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, **15.1.6**
Administration of the Contract
3.1.3, **4.2**, 9.4, 9.5
Advertisement or Invitation to Bid
1.1.1
Aesthetic Effect
4.2.13
Allowances
3.8
Applications for Payment
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5.1, 9.5.4, 9.6.3, 9.7, 9.10
Approvals
2.1.1, 2.3.1, 2.5, 3.1.3, 3.10.2, 3.12.8, 3.12.9, 3.12.10.1, 4.2.7, 9.3.2, 13.4.1
Arbitration
8.3.1, 15.3.2, **15.4**
ARCHITECT
4
Architect, Definition of
4.1.1
Architect, Extent of Authority
2.5, 3.12.7, 4.1.2, 4.2, 5.2, 6.3, 7.1.2, 7.3.4, 7.4, 9.2, 9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1, 13.4.1, 13.4.2, 14.2.2, 14.2.4, 15.1.4, 15.2.1
Architect, Limitations of Authority and Responsibility
2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2, 4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4, 9.4.2, 9.5.4, 9.6.4, 15.1.4, 15.2
Architect's Additional Services and Expenses
2.5, 12.2.1, 13.4.2, 13.4.3, 14.2.4
Architect's Administration of the Contract
3.1.3, 3.7.4, 15.2, 9.4.1, 9.5
Architect's Approvals
2.5, 3.1.3, 3.5, 3.10.2, 4.2.7
Architect's Authority to Reject Work
3.5, 4.2.6, 12.1.2, 12.2.1
Architect's Copyright
1.1.7, 1.5
Architect's Decisions
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1, 13.4.2, 15.2
Architect's Inspections
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.4
Architect's Instructions
3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.4.2
Architect's Interpretations
4.2.11, 4.2.12
Architect's Project Representative
4.2.10
Architect's Relationship with Contractor
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5, 3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16, 3.18, 4.1.2, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.3.2, 13.4, 15.2
Architect's Relationship with Subcontractors
1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3
Architect's Representations
9.4.2, 9.5.1, 9.10.1
Architect's Site Visits
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Asbestos
10.3.1
Attorneys' Fees
3.18.1, 9.6.8, 9.10.2, 10.3.3
Award of Separate Contracts
6.1.1, 6.1.2
Award of Subcontracts and Other Contracts for Portions of the Work
5.2
Basic Definitions
1.1
Bidding Requirements
1.1.1
Binding Dispute Resolution
8.3.1, 9.7, 11.5, 13.1, 15.1.2, 15.1.3, 15.2.1, 15.2.5, 15.2.6.1, 15.3.1, 15.3.2, 15.3.3, 15.4.1
Bonds, Lien
7.3.4.4, 9.6.8, 9.10.2, 9.10.3
Bonds, Performance, and Payment
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**, 11.1.3, **11.5**
Building Information Models Use and Reliance
1.8
Building Permit
3.7.1
Capitalization
1.3
Certificate of Substantial Completion
9.8.3, 9.8.4, 9.8.5

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

Certificates for Payment
4.2.1, 4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.4
Certificates of Inspection, Testing or Approval
13.4.4
Certificates of Insurance
9.10.2
Change Orders
1.1.1, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3, 7.1.2, 7.1.3, **7.2**, 7.3.2, 7.3.7, 7.3.9, 7.3.10, 8.3.1, 9.3.1.1, 9.10.3, 10.3.2, 11.2, 11.5, 12.1.2
Change Orders, Definition of
7.2.1
CHANGES IN THE WORK
2.2.2, 3.11, 4.2.8, **7**, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1, 11.5
Claims, Definition of
15.1.1
Claims, Notice of
1.6.2, 15.1.3
CLAIMS AND DISPUTES
3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, **15**, 15.4
Claims and Timely Assertion of Claims
15.4.1
Claims for Additional Cost
3.2.4, 3.3.1, 3.7.4, 7.3.9, 9.5.2, 10.2.5, 10.3.2, **15.1.5**
Claims for Additional Time
3.2.4, 3.3.1, 3.7.4, 6.1.1, 8.3.2, 9.5.2, 10.3.2, **15.1.6**
Concealed or Unknown Conditions, Claims for
3.7.4
Claims for Damages
3.2.4, 3.18, 8.3.3, 9.5.1, 9.6.7, 10.2.5, 10.3.3, 11.3, 11.3.2, 14.2.4, 15.1.7
Claims Subject to Arbitration
15.4.1
Cleaning Up
3.15, 6.3
Commencement of the Work, Conditions Relating to
2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3, 6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.2, **15.1.5**
Commencement of the Work, Definition of
8.1.2
Communications
3.9.1, **4.2.4**
Completion, Conditions Relating to
3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1, 9.10, 12.2, 14.1.2, 15.1.2
COMPLETION, PAYMENTS AND
9
Completion, Substantial
3.10.1, 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3, 12.2, 15.1.2
Compliance with Laws
2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14.1.1, 14.2.1.3, 15.2.8, 15.4.2, 15.4.3
Concealed or Unknown Conditions
3.7.4, 4.2.8, 8.3.1, 10.3
Conditions of the Contract
1.1.1, 6.1.1, 6.1.4
Consent, Written
3.4.2, 3.14.2, 4.1.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 13.2, 15.4.4.2
Consolidation or Joinder
15.4.4
CONSTRUCTION BY OWNER OR BY
SEPARATE CONTRACTORS
1.1.4, **6**
Construction Change Directive, Definition of
7.3.1
Construction Change Directives
1.1.1, 3.4.2, 3.11, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3, **7.3**, 9.3.1.1
Construction Schedules, Contractor's
3.10, 3.11, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Contingent Assignment of Subcontracts
5.4, 14.2.2.2
Continuing Contract Performance
15.1.4
Contract, Definition of
1.1.2
CONTRACT, TERMINATION OR
SUSPENSION OF THE
5.4.1.1, 5.4.2, 11.5, **14**
Contract Administration
3.1.3, 4, 9.4, 9.5
Contract Award and Execution, Conditions Relating to
3.7.1, 3.10, 5.2, 6.1
Contract Documents, Copies Furnished and Use of
1.5.2, 2.3.6, 5.3
Contract Documents, Definition of
1.1.1
Contract Sum
2.2.2, 2.2.4, 3.7.4, 3.7.5, 3.8, 3.10.2, 5.2.3, 7.3, 7.4, **9.1**, 9.2, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.5, 12.1.2, 12.3, 14.2.4, 14.3.2, 15.1.4.2, **15.1.5, 15.2.5**
Contract Sum, Definition of
9.1
Contract Time
1.1.4, 2.2.1, 2.2.2, 3.7.4, 3.7.5, 3.10.2, 5.2.3, 6.1.5, 7.2.1.3, 7.3.1, 7.3.5, 7.3.6, 7, 7, 7.3.10, 7.4, 8.1.1, 8.2.1, 8.2.3, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 12.1.2, 14.3.2, 15.1.4.2, 15.1.6.1, 15.2.5
Contract Time, Definition of
8.1.1
CONTRACTOR
3
Contractor, Definition of
3.1, 6.1.2
Contractor's Construction and Submittal
Schedules
3.10, 3.12.1, 3.12.2, 4.2.3, 6.1.3, 15.1.6.2

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

Contractor's Employees
2.2.4, 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3, 11.3, 14.1, 14.2.1.1
Contractor's Liability Insurance
11.1
Contractor's Relationship with Separate Contractors and Owner's Forces
3.12.5, 3.14.2, 4.2.4, 6, 11.3, 12.2.4
Contractor's Relationship with Subcontractors
1.2.2, 2.2.4, 3.3.2, 3.18.1, 3.18.2, 4.2.4, 5, 9.6.2, 9.6.7, 9.10.2, 11.2, 11.3, 11.4
Contractor's Relationship with the Architect
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5.1, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.4, 15.1.3, 15.2.1
Contractor's Representations
3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2
Contractor's Responsibility for Those Performing the Work
3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8
Contractor's Review of Contract Documents
3.2
Contractor's Right to Stop the Work
2.2.2, 9.7
Contractor's Right to Terminate the Contract
14.1
Contractor's Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2, 9.8.3, 9.9.1, 9.10.2, 9.10.3
Contractor's Superintendent
3.9, 10.2.6
Contractor's Supervision and Construction Procedures
1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 7.3.6, 8.2, 10, 12, 14, 15.1.4
Coordination and Correlation
1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1
Copies Furnished of Drawings and Specifications
1.5, 2.3.6, 3.11
Copyrights
1.5, **3.17**
Correction of Work
2.5, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, **12.2**, 12.3, 15.1.3.1, 15.1.3.2, 15.2.1
Correlation and Intent of the Contract Documents
1.2
Cost, Definition of
7.3.4
Costs
2.5, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3, 7.3.3.3, 7.3.4, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6, 11.2, 12.1.2, 12.2.1, 12.2.4, 13.4, 14
Cutting and Patching
3.14, 6.2.5
Damage to Construction of Owner or Separate Contractors
3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damage to the Work
3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damages, Claims for
3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.3.2, 11.3, 14.2.4, 15.1.7
Damages for Delay
6.2.3, 8.3.3, 9.5.1.6, 9.7, 10.3.2, 14.3.2
Date of Commencement of the Work, Definition of
8.1.2
Date of Substantial Completion, Definition of
8.1.3
Day, Definition of
8.1.4
Decisions of the Architect
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1, 13.4.2, 14.2.2, 14.2.4, 15.1, 15.2
Decisions to Withhold Certification
9.4.1, **9.5**, 9.7, 14.1.1.3
Defective or Nonconforming Work, Acceptance, Rejection and Correction of
2.5, 3.5, 4.2.6, 6.2.3, 9.5.1, 9.5.3, 9.6.6, 9.8.2, 9.9.3, 9.10.4, 12.2.1
Definitions
1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1, 5.1, 6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1, 15.1.1
Delays and Extensions of Time
3.2, **3.7.4**, 5.2.3, 7.2.1, 7.3.1, **7.4**, **8.3**, 9.5.1, **9.7**, 10.3.2, **10.4**, 14.3.2, **15.1.6**, 15.2.5
Digital Data Use and Transmission
1.7
Disputes
6.3, 7.3.9, 15.1, 15.2
Documents and Samples at the Site
3.11
Drawings, Definition of
1.1.5
Drawings and Specifications, Use and Ownership of
3.11
Effective Date of Insurance
8.2.2
Emergencies
10.4, 14.1.1.2, **15.1.5**
Employees, Contractor's
3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3.3, 11.3, 14.1, 14.2.1.1
Equipment, Labor, or Materials
1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Execution and Progress of the Work
1.1.3, 1.2.1, 1.2.2, 2.3.4, 2.3.6, 3.1, 3.3.1, 3.4.1, 3.7.1, 3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.6, 8.2, 9.5.1, 9.9.1, 10.2, 10.3, 12.1, 12.2, 14.2, 14.3.1, 15.1.4

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

Extensions of Time
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2, 10.4, 14.3, 15.1.6, **15.2.5**
Failure of Payment
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Faulty Work
(See Defective or Nonconforming Work)
Final Completion and Final Payment
4.2.1, 4.2.9, 9.8.2, **9.10**, 12.3, 14.2.4, 14.4.3
Financial Arrangements, Owner's
2.2.1, 13.2.2, 14.1.1.4
GENERAL PROVISIONS
1
Governing Law
13.1
Guarantees (See Warranty)
Hazardous Materials and Substances
10.2.4, **10.3**
Identification of Subcontractors and Suppliers
5.2.1
Indemnification
3.17, **3.18**, 9.6.8, 9.10.2, 10.3.3, 11.3
Information and Services Required of the Owner
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10.1, 6.1.3, 6.1.4, 6.2.5, 9.6.1, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Initial Decision
15.2
Initial Decision Maker, Definition of
1.1.8
Initial Decision Maker, Decisions
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Initial Decision Maker, Extent of Authority
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Injury or Damage to Person or Property
10.2.8, 10.4
Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 12.2.1, 13.4
Instructions to Bidders
1.1.1
Instructions to the Contractor
3.2.4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.4.2
Instruments of Service, Definition of
1.1.7
Insurance
6.1.1, 7.3.4, 8.2.2, 9.3.2, 9.8.4, 9.9.1, 9.10.2, 10.2.5, **11**
Insurance, Notice of Cancellation or Expiration
11.1.4, 11.2.3
Insurance, Contractor's Liability
11.1
Insurance, Effective Date of
8.2.2, 14.4.2
Insurance, Owner's Liability
11.2
Insurance, Property
10.2.5, 11.2, 11.4, 11.5
Insurance, Stored Materials
9.3.2
INSURANCE AND BONDS
11
Insurance Companies, Consent to Partial Occupancy
9.9.1
Insured loss, Adjustment and Settlement of
11.5
Intent of the Contract Documents
1.2.1, 4.2.7, 4.2.12, 4.2.13
Interest
13.5
Interpretation
1.1.8, 1.2.3, **1.4**, 4.1.1, 5.1, 6.1.2, 15.1.1
Interpretations, Written
4.2.11, 4.2.12
Judgment on Final Award
15.4.2
Labor and Materials, Equipment
1.1.3, 1.1.6, **3.4**, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Labor Disputes
8.3.1
Laws and Regulations
1.5, 2.3.2, 3.2.3, 3.2.4, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Liens
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Limitations, Statutes of
12.2.5, 15.1.2, 15.4.1.1
Limitations of Liability
3.2.2, 3.5, 3.12.10, 3.12.10.1, 3.17, 3.18.1, 4.2.6, 4.2.7, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 9.6.8, 10.2.5, 10.3.3, 11.3, 12.2.5, 13.3.1
Limitations of Time
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7, 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15, 15.1.2, 15.1.3, 15.1.5
Materials, Hazardous
10.2.4, **10.3**
Materials, Labor, Equipment and
1.1.3, 1.1.6, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2
Means, Methods, Techniques, Sequences and Procedures of Construction
3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2
Mechanic's Lien
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Mediation
8.3.1, 15.1.3.2, 15.2.1, 15.2.5, 15.2.6, **15.3**, 15.4.1, 15.4.1.1
Minor Changes in the Work
1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1, **7.4**

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

MISCELLANEOUS PROVISIONS
13
Modifications, Definition of
1.1.1
Modifications to the Contract
1.1.1, 1.1.2, 2.5, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7, 10.3.2
Mutual Responsibility
6.2
Nonconforming Work, Acceptance of
9.6.6, 9.9.3, **12.3**
Nonconforming Work, Rejection and Correction of
2.4, 2.5, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4, 12.2
Notice
1.6, 1.6.1, 1.6.2, 2.1.2, 2.2.2., 2.2.3, 2.2.4, 2.5, 3.2.4, 3.3.1, 3.7.4, 3.7.5, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 7.4, 8.2.2 9.6.8, 9.7, 9.10.1, 10.2.8, 10.3.2, 11.5, 12.2.2.1, 13.4.1, 13.4.2, 14.1, 14.2.2, 14.4.2, 15.1.3, 15.1.5, 15.1.6, 15.4.1
Notice of Cancellation or Expiration of Insurance
11.1.4, 11.2.3
Notice of Claims
1.6.2, 2.1.2, 3.7.4, 9.6.8, 10.2.8, **15.1.3**, 15.1.5, 15.1.6, 15.2.8, 15.3.2, 15.4.1
Notice of Testing and Inspections
13.4.1, 13.4.2
Observations, Contractor's
3.2, 3.7.4
Occupancy
2.3.1, 9.6.6, 9.8
Orders, Written
1.1.1, 2.4, 3.9.2, 7, 8.2.2, 11.5, 12.1, 12.2.2.1, 13.4.2, 14.3.1
OWNER
2
Owner, Definition of
2.1.1
Owner, Evidence of Financial Arrangements
2.2, 13.2.2, 14.1.1.4
Owner, Information and Services Required of the
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5, 9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Owner's Authority
1.5, 2.1.1, 2.3.32.4, 2.5, 3.4.2, 3.8.1, 3.12.10, 3.14.2, 4.1.2, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1, 7.3.1, 8.2.2, 8.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2, 10.3.2, 11.4, 11.5, 12.2.2, 12.3, 13.2.2, 14.3, 14.4, 15.2.7
Owner's Insurance
11.2
Owner's Relationship with Subcontractors
1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2
Owner's Right to Carry Out the Work
2.5, 14.2.2
Owner's Right to Clean Up
6.3
Owner's Right to Perform Construction and to Award Separate Contracts
6.1
Owner's Right to Stop the Work
2.4
Owner's Right to Suspend the Work
14.3
Owner's Right to Terminate the Contract
14.2, 14.4
Ownership and Use of Drawings, Specifications and Other Instruments of Service
1.1.1, 1.1.6, 1.1.7, **1.5**, 2.3.6, 3.2.2, 3.11, 3.17, 4.2.12, 5.3
Partial Occupancy or Use
9.6.6, **9.9**
Patching, Cutting and
3.14, 6.2.5
Patents
3.17
Payment, Applications for
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1, 14.2.3, 14.2.4, 14.4.3
Payment, Certificates for
4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4
Payment, Failure of
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Payment, Final
4.2.1, 4.2.9, **9.10**, 12.3, 14.2.4, 14.4.3
Payment Bond, Performance Bond and
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Payments, Progress
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4
PAYMENTS AND COMPLETION
9
Payments to Subcontractors
5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2
PCB
10.3.1
Performance Bond and Payment Bond
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Permits, Fees, Notices and Compliance with Laws
2.3.1, **3.7**, 3.13, 7.3.4.4, 10.2.2
PERSONS AND PROPERTY, PROTECTION OF
10
Polychlorinated Biphenyl
10.3.1
Product Data, Definition of
3.12.2
Product Data and Samples, Shop Drawings
3.11, **3.12**, 4.2.7
Progress and Completion
4.2.2, **8.2**, 9.8, 9.9.1, 14.1.4, 15.1.4
Progress Payments
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

Project, Definition of
1.1.4
Project Representatives
4.2.10
Property Insurance
10.2.5, **11.2**
Proposal Requirements
1.1.1
PROTECTION OF PERSONS AND PROPERTY
10
Regulations and Laws
1.5, 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Rejection of Work
4.2.6, 12.2.1
Releases and Waivers of Liens
9.3.1, 9.10.2
Representations
3.2.1, 3.5, 3.12.6, 8.2.1, 9.3.3, 9.4.2, 9.5.1, 9.10.1
Representatives
2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.10, 13.2.1
Responsibility for Those Performing the Work
3.3.2, 3.18, 4.2.2, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10
Retainage
9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3
Review of Contract Documents and Field Conditions by Contractor
3.2, 3.12.7, 6.1.3
Review of Contractor's Submittals by Owner and Architect
3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2
Review of Shop Drawings, Product Data and Samples by Contractor
3.12
Rights and Remedies
1.1.2, 2.4, 2.5, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1, 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.1, 12.2.2, 12.2.4, **13.3**, 14, 15.4
Royalties, Patents and Copyrights
3.17
Rules and Notices for Arbitration
15.4.1
Safety of Persons and Property
10.2, 10.4
Safety Precautions and Programs
3.3.1, 4.2.2, 4.2.7, 5.3, **10.1**, 10.2, 10.4
Samples, Definition of
3.12.3
Samples, Shop Drawings, Product Data and
3.11, **3.12**, 4.2.7
Samples at the Site, Documents and
3.11
Schedule of Values
9.2, 9.3.1
Schedules, Construction
3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Separate Contracts and Contractors
1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2
Separate Contractors, Definition of
6.1.1
Shop Drawings, Definition of
3.12.1
Shop Drawings, Product Data and Samples
3.11, **3.12**, 4.2.7
Site, Use of
3.13, 6.1.1, 6.2.1
Site Inspections
3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.9.2, 9.4.2, 9.10.1, 13.4
Site Visits, Architect's
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Special Inspections and Testing
4.2.6, 12.2.1, 13.4
Specifications, Definition of
1.1.6
Specifications
1.1.1, **1.1.6**, 1.2.2, 1.5, 3.12.10, 3.17, 4.2.14
Statute of Limitations
15.1.2, 15.4.1.1
Stopping the Work
2.2.2, 2.4, 9.7, 10.3, 14.1
Stored Materials
6.2.1, 9.3.2, 10.2.1.2, 10.2.4
Subcontractor, Definition of
5.1.1
SUBCONTRACTORS
5
Subcontractors, Work by
1.2.2, 3.3.2, 3.12.1, 3.18, 4.2.3, 5.2.3, 5.3, 5.4, 9.3.1.2, 9.6.7
Subcontractual Relations
5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1
Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.4, 9.2, 9.3, 9.8, 9.9.1, 9.10.2, 9.10.3
Submittal Schedule
3.10.2, 3.12.5, 4.2.7
Subrogation, Waivers of
6.1.1, **11.3**
Substances, Hazardous
10.3
Substantial Completion
4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, **9.8**, 9.9.1, 9.10.3, 12.2, 15.1.2
Substantial Completion, Definition of
9.8.1
Substitution of Subcontractors
5.2.3, 5.2.4
Substitution of Architect
2.3.3
Substitutions of Materials
3.4.2, 3.5, 7.3.8
Sub-subcontractor, Definition of
5.1.2

Init.
/

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

Subsurface Conditions
3.7.4
Successors and Assigns
13.2
Superintendent
3.9, 10.2.6
Supervision and Construction Procedures
1.2.2, **3.3**, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.4
Suppliers
1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.5.4, 9.6, 9.10.5, 14.2.1
Surety
5.4.1.2, 9.6.8, 9.8.5, 9.10.2, 9.10.3, 11.1.2, 14.2.2, 15.2.7
Surety, Consent of
9.8.5, 9.10.2, 9.10.3
Surveys
1.1.7, 2.3.4
Suspension by the Owner for Convenience
14.3
Suspension of the Work
3.7.5, 5.4.2, 14.3
Suspension or Termination of the Contract
5.4.1.1, 14
Taxes
3.6, 3.8.2.1, 7.3.4.4
Termination by the Contractor
14.1, 15.1.7
Termination by the Owner for Cause
5.4.1.1, **14.2,** 15.1.7
Termination by the Owner for Convenience
14.4
Termination of the Architect
2.3.3
Termination of the Contractor Employment
14.2.2

TERMINATION OR SUSPENSION OF THE CONTRACT
14
Tests and Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 10.3.2, 12.2.1, **13.4**
TIME
8
Time, Delays and Extensions of
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, **8.3**, 9.5.1, 9.7, 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5
Time Limits
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2, 5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15.1.2, 15.1.3, 15.4
Time Limits on Claims
3.7.4, 10.2.8, 15.1.2, 15.1.3
Title to Work
9.3.2, 9.3.3
UNCOVERING AND CORRECTION OF WORK
12
Uncovering of Work
12.1
Unforeseen Conditions, Concealed or Unknown
3.7.4, 8.3.1, 10.3
Unit Prices
7.3.3.2, 9.1.2
Use of Documents
1.1.1, 1.5, 2.3.6, 3.12.6, 5.3
Use of Site
3.13, 6.1.1, 6.2.1
Values, Schedule of
9.2, 9.3.1
Waiver of Claims by the Architect
13.3.2
Waiver of Claims by the Contractor
9.10.5, 13.3.2, **15.1.7**
Waiver of Claims by the Owner
9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.3.2, 14.2.4, **15.1.7**
Waiver of Consequential Damages
14.2.4, 15.1.7
Waiver of Liens
9.3, 9.10.2, 9.10.4
Waivers of Subrogation
6.1.1, **11.3**
Warranty
3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.2, 9.10.4, 12.2.2, 15.1.2
Weather Delays
8.3, 15.1.6.2
Work, Definition of
1.1.3
Written Consent
1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.10.3, 13.2, 13.3.2, 15.4.4.2
Written Interpretations
4.2.11, 4.2.12
Written Orders
1.1.1, 2.4, 3.9, 7, 8.2.2, 12.1, 12.2, 13.4.2, 14.3.1

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Basic Definitions

§ 1.1.1 The Contract Documents

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement, and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive, or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding or proposal requirements.

§ 1.1.2 The Contract

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants, or (4) between any persons or entities other than the Owner and the Contractor. The Architect shall, however, be entitled to performance and enforcement of obligations under the Contract intended to facilitate performance of the Architect's duties.

§ 1.1.3 The Work

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by Separate Contractors.

§ 1.1.5 The Drawings

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

§ 1.1.6 The Specifications

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 Initial Decision Maker

The Initial Decision Maker is the person identified in the Agreement to render initial decisions on Claims in accordance with Section 15.2. The Initial Decision Maker shall not show partiality to the Owner or Contractor and shall not be liable for results of interpretations or decisions rendered in good faith.

§ 1.2 Correlation and Intent of the Contract Documents

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 1.2.1.1 The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.

§ 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.

§ 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 Capitalization

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles, or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 Interpretation

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

§ 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.

§ 1.5.2 The Contractor, Subcontractors, Sub-subcontractors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to any protocols established pursuant to Sections 1.7 and 1.8, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and suppliers may not use the Instruments of Service on other projects or for additions to the Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.6 Notice

§ 1.6.1 Except as otherwise provided in Section 1.6.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission if a method for electronic transmission is set forth in the Agreement.

§ 1.6.2 Notice of Claims as provided in Section 15.1.3 shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.7 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.8 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

G202™–2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its contractors or consultants, the authors of, or contributors to, the building information model, and each of their agents and employees.

ARTICLE 2 OWNER

§ 2.1 General

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's authorized representative.

§ 2.1.2 The Owner shall furnish to the Contractor, within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to evaluate, give notice of, or enforce mechanic's lien rights. Such information shall include a correct statement of the record legal title to the property on which the Project is located, usually referred to as the site, and the Owner's interest therein.

§ 2.2 Evidence of the Owner's Financial Arrangements

§ 2.2.1 Prior to commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. The Contractor shall have no obligation to commence the Work until the Owner provides such evidence. If commencement of the Work is delayed under this Section 2.2.1, the Contract Time shall be extended appropriately.

§ 2.2.2 Following commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract only if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due; or (3) a change in the Work materially changes the Contract Sum. If the Owner fails to provide such evidence, as required, within fourteen days of the Contractor's request, the Contractor may immediately stop the Work and, in that event, shall notify the Owner that the Work has stopped. However, if the request is made because a change in the Work materially changes the Contract Sum under (3) above, the Contractor may immediately stop only that portion of the Work affected by the change until reasonable evidence is provided. If the Work is stopped under this Section 2.2.2, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided in the Contract Documents.

§ 2.2.3 After the Owner furnishes evidence of financial arrangements under this Section 2.2, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

§ 2.2.4 Where the Owner has designated information furnished under this Section 2.2 as "confidential," the Contractor shall keep the information confidential and shall not disclose it to any other person. However, the Contractor may disclose "confidential" information, after seven (7) days' notice to the Owner, where disclosure is required by law, including a subpoena or other form of compulsory legal process issued by a court or governmental entity, or by court or arbitrator(s) order. The Contractor may also disclose "confidential" information to its employees, consultants, sureties, Subcontractors and their employees, Sub-subcontractors, and others who need to know the content of such information solely and exclusively for the Project and who agree to maintain the confidentiality of such information.

§ 2.3 Information and Services Required of the Owner

§ 2.3.1 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements, assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.

§ 2.3.2 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 2.3.3 If the employment of the Architect terminates, the Owner shall employ a successor to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.

§ 2.3.4 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. The Contractor shall be entitled to rely on the accuracy of information furnished by the Owner but shall exercise proper precautions relating to the safe performance of the Work.

§ 2.3.5 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services.

§ 2.3.6 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one copy of the Contract Documents for purposes of making reproductions pursuant to Section 1.5.2.

§ 2.4 Owner's Right to Stop the Work

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.5 Owner's Right to Carry Out the Work

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. Such action by the Owner and amounts charged to the Contractor are both subject to prior approval of the Architect and the Architect may, pursuant to Section 9.5.1, withhold or nullify a Certificate for Payment in whole or in part, to the extent reasonably necessary to reimburse the Owner for the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect, or failure. If current and future payments are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. If the Contractor disagrees with the actions of the Owner or the Architect, or the amounts claimed as costs to the Owner, the Contractor may file a Claim pursuant to Article 15.

ARTICLE 3 CONTRACTOR

§ 3.1 General

§ 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.

§ 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.

§ 3.1.3 The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 Review of Contract Documents and Field Conditions by Contractor

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed, and correlated personal observations with requirements of the Contract Documents.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.3.4, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall submit Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner, subject to Section 15.1.7, as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 3.3 Supervision and Construction Procedures

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences, and procedures, and for coordinating all portions of the Work under the Contract. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences, or procedures, the Contractor shall evaluate the jobsite safety thereof and shall be solely responsible for the jobsite safety of such means, methods, techniques, sequences, or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely notice to the Owner and Architect, and shall propose alternative means, methods, techniques, sequences, or procedures. The Architect shall evaluate the proposed alternative solely for conformance with the design intent for the completed construction. Unless the Architect objects to the Contractor's proposed alternative, the Contractor shall perform the Work using its alternative means, methods, techniques, sequences, or procedures.

§ 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.

§ 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 Labor and Materials

§ 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

§ 3.4.2 Except in the case of minor changes in the Work approved by the Architect in accordance with Section 3.12.8 or ordered by the Architect in accordance with Section 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 Warranty

§ 3.5.1 The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements may be considered defective. The Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.5.2 All material, equipment, or other special warranties required by the Contract Documents shall be issued in the name of the Owner, or shall be transferable to the Owner, and shall commence in accordance with Section 9.8.4.

§ 3.6 Taxes

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 3.7 Permits, Fees, Notices and Compliance with Laws

§ 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for the building permit as well as for other permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.

§ 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.

§ 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 3.7.4 Concealed or Unknown Conditions

If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 14 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend that an equitable adjustment be made in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may submit a Claim as provided in Article 15.

§ 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Requests for adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 15.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 3.8 Allowances

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

§ 3.8.2 Unless otherwise provided in the Contract Documents,

- **.1** allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
- **.2** Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and
- **.3** whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 3.8.2.1 and (2) changes in Contractor's costs under Section 3.8.2.2.

§ 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 *Superintendent*

§ 3.9.1 The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.

§ 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the name and qualifications of a proposed superintendent. Within 14 days of receipt of the information, the Architect may notify the Contractor, stating whether the Owner or the Architect (1) has reasonable objection to the proposed superintendent or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 Contractor's Construction and Submittal Schedules

§ 3.10.1 The Contractor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall contain detail appropriate for the Project, including (1) the date of commencement of the Work, interim schedule milestone dates, and the date of Substantial Completion; (2) an apportionment of the Work by construction activity; and (3) the time required for completion of each portion of the Work. The schedule shall provide for the orderly progression of the Work to completion and shall not exceed time limits current under the Contract Documents. The schedule shall be revised at appropriate intervals as required by the conditions of the Work and Project.

§ 3.10.2 The Contractor, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, shall submit a submittal schedule for the Architect's approval. The Architect's approval shall not be unreasonably delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, or fails to provide submittals in accordance with the approved submittal schedule, the Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 The Contractor shall perform the Work in general accordance with the most recent schedules submitted to the Owner and Architect.

§ 3.11 Documents and Samples at the Site

The Contractor shall make available, at the Project site, the Contract Documents, including Change Orders, Construction Change Directives, and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and the approved Shop Drawings, Product Data, Samples, and similar required submittals. These shall be in electronic form or paper copy, available to the Architect and Owner, and

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

§ 3.12 Shop Drawings, Product Data and Samples

§ 3.12.1 Shop Drawings are drawings, diagrams, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.

§ 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.

§ 3.12.3 Samples are physical examples that illustrate materials, equipment, or workmanship, and establish standards by which the Work will be judged.

§ 3.12.4 Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. Their purpose is to demonstrate how the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.

§ 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve, and submit to the Architect, Shop Drawings, Product Data, Samples, and similar submittals required by the Contract Documents, in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of Separate Contractors.

§ 3.12.6 By submitting Shop Drawings, Product Data, Samples, and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so, and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

§ 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples, or similar submittals, until the respective submittal has been approved by the Architect.

§ 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals, unless the Contractor has specifically notified the Architect of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals, by the Architect's approval thereof.

§ 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples, or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such notice, the Architect's approval of a resubmission shall not apply to such revisions.

§ 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to provide professional services in violation of applicable law.

§ 3.12.10.1 If professional design services or certifications by a design professional related to systems, materials, or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall be entitled to rely

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

upon the adequacy and accuracy of the performance and design criteria provided in the Contract Documents. The Contractor shall cause such services or certifications to be provided by an appropriately licensed design professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings, and other submittals prepared by such professional. Shop Drawings, and other submittals related to the Work, designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy and accuracy of the services, certifications, and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor the performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review and approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.

§ 3.12.10.2 If the Contract Documents require the Contractor's design professional to certify that the Work has been performed in accordance with the design criteria, the Contractor shall furnish such certifications to the Architect at the time and in the form specified by the Architect.

§ 3.13 Use of Site

The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, lawful orders of public authorities, and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.14 Cutting and Patching

§ 3.14.1 The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting, or patching shall be restored to the condition existing prior to the cutting, fitting, or patching, unless otherwise required by the Contract Documents.

§ 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or Separate Contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter construction by the Owner or a Separate Contractor except with written consent of the Owner and of the Separate Contractor. Consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold, from the Owner or a Separate Contractor, its consent to cutting or otherwise altering the Work.

§ 3.15 Cleaning Up

§ 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery, and surplus materials from and about the Project.

§ 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and the Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 Access to Work

The Contractor shall provide the Owner and Architect with access to the Work in preparation and progress wherever located.

§ 3.17 Royalties, Patents and Copyrights

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications, or other documents prepared by the Owner or Architect. However, if an infringement of a copyright or patent is discovered by, or made known to, the Contractor, the Contractor shall be responsible for the loss unless the information is promptly furnished to the Architect.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 3.18 Indemnification

§ 3.18.1 To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

ARTICLE 4 ARCHITECT

§ 4.1 General

§ 4.1.1 The Architect is the person or entity retained by the Owner pursuant to Section 2.3.2 and identified as such in the Agreement.

§ 4.1.2 Duties, responsibilities, and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified, or extended without written consent of the Owner, Contractor, and Architect. Consent shall not be unreasonably withheld.

§ 4.2 Administration of the Contract

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents.

§ 4.2.2 The Architect will visit the site at intervals appropriate to the stage of construction, or as otherwise agreed with the Owner, to become generally familiar with the progress and quality of the portion of the Work completed, and to determine in general if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner reasonably informed about the progress and quality of the portion of the Work completed, and promptly report to the Owner (1) known deviations from the Contract Documents, (2) known deviations from the most recent construction schedule submitted by the Contractor, and (3) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of, and will not be responsible for acts or omissions of, the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 Communications

The Owner and Contractor shall include the Architect in all communications that relate to or affect the Architect's services or professional responsibilities. The Owner shall promptly notify the Architect of the substance of any direct communications between the Owner and the Contractor otherwise relating to the Project. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and suppliers shall be through the Contractor. Communications by and with Separate Contractors shall be through the Owner. The Contract Documents may specify other communication protocols.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 4.2.5 Based on the Architect's evaluations of the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.

§ 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.4.2 and 13.4.3, whether or not the Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, suppliers, their agents or employees, or other persons or entities performing portions of the Work.

§ 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Sections 3.3, 3.5, and 3.12. The Architect's review shall not constitute approval of safety precautions or of any construction means, methods, techniques, sequences, or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

§ 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may order minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.

§ 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.

§ 4.2.10 If the Owner and Architect agree, the Architect will provide one or more Project representatives to assist in carrying out the Architect's responsibilities at the site. The Owner shall notify the Contractor of any change in the duties, responsibilities and limitations of authority of the Project representatives.

§ 4.2.11 The Architect will interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness.

§ 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, will not show partiality to either, and will not be liable for results of interpretations or decisions rendered in good faith.

§ 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.

§ 4.2.14 The Architect will review and respond to requests for information about the Contract Documents. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

ARTICLE 5 SUBCONTRACTORS

§ 5.1 Definitions

§ 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a Separate Contractor or the subcontractors of a Separate Contractor.

§ 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 Award of Subcontracts and Other Contracts for Portions of the Work

§ 5.2.1 Unless otherwise stated in the Contract Documents, the Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the persons or entities proposed for each principal portion of the Work, including those who are to furnish materials or equipment fabricated to a special design. Within 14 days of receipt of the information, the Architect may notify the Contractor whether the Owner or the Architect (1) has reasonable objection to any such proposed person or entity or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.

§ 5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection. If the proposed but rejected Subcontractor was reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

§ 5.2.4 The Contractor shall not substitute a Subcontractor, person, or entity for one previously selected if the Owner or Architect makes reasonable objection to such substitution.

§ 5.3 Subcontractual Relations

By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work that the Contractor, by these Contract Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.

§ 5.4 Contingent Assignment of Subcontracts

§ 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that

- **.1** assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor; and
- **.2** assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

When the Owner accepts the assignment of a subcontract agreement, the Owner assumes the Contractor's rights and obligations under the subcontract.

§ 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.

§ 5.4.3 Upon assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

§ 6.1 Owner's Right to Perform Construction and to Award Separate Contracts

§ 6.1.1 The term "Separate Contractor(s)" shall mean other contractors retained by the Owner under separate agreements. The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and with Separate Contractors retained under Conditions of the Contract substantially similar to those of this Contract, including those provisions of the Conditions of the Contract related to insurance and waiver of subrogation.

§ 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.

§ 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each Separate Contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with any Separate Contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to its construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, Separate Contractors, and the Owner until subsequently revised.

§ 6.1.4 Unless otherwise provided in the Contract Documents, when the Owner performs construction or operations related to the Project with the Owner's own forces or with Separate Contractors, the Owner or its Separate Contractors shall have the same obligations and rights that the Contractor has under the Conditions of the Contract, including, without excluding others, those stated in Article 3, this Article 6, and Articles 10, 11, and 12.

§ 6.2 Mutual Responsibility

§ 6.2.1 The Contractor shall afford the Owner and Separate Contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.

§ 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a Separate Contractor, the Contractor shall, prior to proceeding with that portion of the Work, promptly notify the Architect of apparent discrepancies or defects in the construction or operations by the Owner or Separate Contractor that would render it unsuitable for proper execution and results of the Contractor's Work. Failure of the Contractor to notify the Architect of apparent discrepancies or defects prior to proceeding with the Work shall constitute an acknowledgment that the Owner's or Separate Contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work. The Contractor shall not be responsible for discrepancies or defects in the construction or operations by the Owner or Separate Contractor that are not apparent.

§ 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a Separate Contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a Separate Contractor's delays, improperly timed activities, damage to the Work or defective construction.

§ 6.2.4 The Contractor shall promptly remedy damage that the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or Separate Contractor as provided in Section 10.2.5.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 6.2.5 The Owner and each Separate Contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 Owner's Right to Clean Up

If a dispute arises among the Contractor, Separate Contractors, and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK

§ 7.1 General

§ 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.

§ 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor, and Architect. A Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor. An order for a minor change in the Work may be issued by the Architect alone.

§ 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents. The Contractor shall proceed promptly with changes in the Work, unless otherwise provided in the Change Order, Construction Change Directive, or order for a minor change in the Work.

§ 7.2 Change Orders

§ 7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, Contractor, and Architect stating their agreement upon all of the following:

.1 The change in the Work;
.2 The amount of the adjustment, if any, in the Contract Sum; and
.3 The extent of the adjustment, if any, in the Contract Time.

§ 7.3 Construction Change Directives

§ 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions, or other revisions, the Contract Sum and Contract Time being adjusted accordingly.

§ 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.

§ 7.3.3 If the Construction Change Directive provides for an adjustment to the Contract Sum, the adjustment shall be based on one of the following methods:

.1 Mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
.2 Unit prices stated in the Contract Documents or subsequently agreed upon;
.3 Cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
.4 As provided in Section 7.3.4.

§ 7.3.4 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall determine the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in the Agreement, or if no such amount is set forth in the Agreement, a reasonable amount. In such case, and also under Section 7.3.3.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.4 shall be limited to the following:

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

.1 Costs of labor, including applicable payroll taxes, fringe benefits required by agreement or custom, workers' compensation insurance, and other employee costs approved by the Architect;

.2 Costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed;

.3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;

.4 Costs of premiums for all bonds and insurance, permit fees, and sales, use, or similar taxes, directly related to the change; and

.5 Costs of supervision and field office personnel directly attributable to the change.

§ 7.3.5 If the Contractor disagrees with the adjustment in the Contract Time, the Contractor may make a Claim in accordance with applicable provisions of Article 15.

§ 7.3.6 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.

§ 7.3.7 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.

§ 7.3.8 The amount of credit to be allowed by the Contractor to the Owner for a deletion or change that results in a net decrease in the Contract Sum shall be actual net cost as confirmed by the Architect. When both additions and credits covering related Work or substitutions are involved in a change, the allowance for overhead and profit shall be figured on the basis of net increase, if any, with respect to that change.

§ 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.

§ 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 Minor Changes in the Work

The Architect may order minor changes in the Work that are consistent with the intent of the Contract Documents and do not involve an adjustment in the Contract Sum or an extension of the Contract Time. The Architect's order for minor changes shall be in writing. If the Contractor believes that the proposed minor change in the Work will affect the Contract Sum or Contract Time, the Contractor shall notify the Architect and shall not proceed to implement the change in the Work. If the Contractor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Contractor waives any adjustment to the Contract Sum or extension of the Contract Time.

ARTICLE 8 TIME

§ 8.1 Definitions

§ 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.

§ 8.1.2 The date of commencement of the Work is the date established in the Agreement.

§ 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 Progress and Completion

§ 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.

§ 8.2.2 The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, commence the Work prior to the effective date of insurance required to be furnished by the Contractor and Owner.

§ 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 Delays and Extensions of Time

§ 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by (1) an act or neglect of the Owner or Architect, of an employee of either, or of a Separate Contractor; (2) by changes ordered in the Work; (3) by labor disputes, fire, unusual delay in deliveries, unavoidable casualties, adverse weather conditions documented in accordance with Section 15.1.6.2, or other causes beyond the Contractor's control; (4) by delay authorized by the Owner pending mediation and binding dispute resolution; or (5) by other causes that the Contractor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine.

§ 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.

§ 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION

§ 9.1 Contract Sum

§ 9.1.1 The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Owner to the Contractor for performance of the Work under the Contract Documents.

§ 9.1.2 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed so that application of such unit prices to the actual quantities causes substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.

§ 9.2 Schedule of Values

Where the Contract is based on a stipulated sum or Guaranteed Maximum Price, the Contractor shall submit a schedule of values to the Architect before the first Application for Payment, allocating the entire Contract Sum to the various portions of the Work. The schedule of values shall be prepared in the form, and supported by the data to substantiate its accuracy, required by the Architect. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. Any changes to the schedule of values shall be submitted to the Architect and supported by such data to substantiate its accuracy as the Architect may require, and unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's subsequent Applications for Payment.

§ 9.3 Applications for Payment

§ 9.3.1 At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. The application shall be notarized, if required, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage if provided for in the Contract Documents.

§ 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or supplier, unless such Work has been performed by others whom the Contractor intends to pay.

§ 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage, and transportation to the site, for such materials and equipment stored off the site.

§ 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances, in favor of the Contractor, Subcontractors, suppliers, or other persons or entities that provided labor, materials, and equipment relating to the Work.

§ 9.4 Certificates for Payment

§ 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either (1) issue to the Owner a Certificate for Payment in the full amount of the Application for Payment, with a copy to the Contractor; or (2) issue to the Owner a Certificate for Payment for such amount as the Architect determines is properly due, and notify the Contractor and Owner of the Architect's reasons for withholding certification in part as provided in Section 9.5.1; or (3) withhold certification of the entire Application for Payment, and notify the Contractor and Owner of the Architect's reason for withholding certification in whole as provided in Section 9.5.1.

§ 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data in the Application for Payment, that, to the best of the Architect's knowledge, information, and belief, the Work has progressed to the point indicated, the quality of the Work is in accordance with the Contract Documents, and that the Contractor is entitled to payment in the amount certified. The foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion, and to specific qualifications expressed by the Architect. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences, or procedures; (3) reviewed copies of requisitions received from Subcontractors and suppliers and other data requested by the Owner to substantiate the Contractor's right to payment; or (4) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

§ 9.5 Decisions to Withhold Certification

§ 9.5.1 The Architect may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

- **.1** defective Work not remedied;
- **.2** third party claims filed or reasonable evidence indicating probable filing of such claims, unless security acceptable to the Owner is provided by the Contractor;
- **.3** failure of the Contractor to make payments properly to Subcontractors or suppliers for labor, materials or equipment;

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

.4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
.5 damage to the Owner or a Separate Contractor;
.6 reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
.7 repeated failure to carry out the Work in accordance with the Contract Documents.

§ 9.5.2 When either party disputes the Architect's decision regarding a Certificate for Payment under Section 9.5.1, in whole or in part, that party may submit a Claim in accordance with Article 15.

§ 9.5.3 When the reasons for withholding certification are removed, certification will be made for amounts previously withheld.

§ 9.5.4 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or supplier to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Contractor shall reflect such payment on its next Application for Payment.

§ 9.6 Progress Payments

§ 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.

§ 9.6.2 The Contractor shall pay each Subcontractor, no later than seven days after receipt of payment from the Owner, the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.

§ 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.

§ 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors and suppliers to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay, or to see to the payment of money to, a Subcontractor or supplier, except as may otherwise be required by law.

§ 9.6.5 The Contractor's payments to suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors or provided by suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, create any fiduciary liability or tort liability on the part of the Contractor for breach of trust, or entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.6.8 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Contractor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any Subcontractor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Contractor. If approved by the applicable court, when required, the Contractor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 9.7 Failure of Payment

If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the date established in the Contract Documents, the amount certified by the Architect or awarded by binding dispute resolution, then the Contractor may, upon seven additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 Substantial Completion

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion; establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance; and fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in the Certificate. Upon such acceptance, and consent of surety if any, the Owner shall make payment of retainage applying to the Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 Partial Occupancy or Use

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor, and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 Final Completion and Final Payment

§ 9.10.1 Upon receipt of the Contractor's notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect will promptly make such inspection. When the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect, (3) a written statement that the Contractor knows of no reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment, (5) documentation of any special warranties, such as manufacturers' warranties or specific Subcontractor warranties, and (6) if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts and releases and waivers of liens, claims, security interests, or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner. If a Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify the Owner against such lien, claim, security interest, or encumbrance. If a lien, claim, security interest, or encumbrance remains unsatisfied after payments are made, the Contractor shall refund to the Owner all money that the Owner may be compelled to pay in discharging the lien, claim, security interest, or encumbrance, including all costs and reasonable attorneys' fees.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed, corrected, and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of the surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

§ 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from

- **.1** liens, Claims, security interests, or encumbrances arising out of the Contract and unsettled;
- **.2** failure of the Work to comply with the requirements of the Contract Documents;
- **.3** terms of special warranties required by the Contract Documents; or
- **.4** audits performed by the Owner, if permitted by the Contract Documents, after final payment.

§ 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor, or a supplier, shall constitute a waiver of claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

§ 10.1 Safety Precautions and Programs

The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 Safety of Persons and Property

§ 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

.1 employees on the Work and other persons who may be affected thereby;

.2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor, a Subcontractor, or a Sub-subcontractor; and

.3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.

§ 10.2.2 The Contractor shall comply with, and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities, bearing on safety of persons or property or their protection from damage, injury, or loss.

§ 10.2.3 The Contractor shall implement, erect, and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards; promulgating safety regulations; and notifying the owners and users of adjacent sites and utilities of the safeguards.

§ 10.2.4 When use or storage of explosives or other hazardous materials or equipment, or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.

§ 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3. The Contractor may make a Claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.

§ 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.

§ 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

§ 10.2.8 Injury or Damage to Person or Property

If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, notice of the injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 Hazardous Materials and Substances

§ 10.3.1 The Contractor is responsible for compliance with any requirements included in the Contract Documents regarding hazardous materials or substances. If the Contractor encounters a hazardous material or substance not addressed in the Contract Documents and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition.

§ 10.3.2 Upon receipt of the Contractor's notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of the material or substance or who are to perform the task of removal or safe containment of the material or substance. The Contractor and the Architect will

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable additional costs of shutdown, delay, and start-up.

§ 10.3.3 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Contractor, Subcontractors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area if in fact the material or substance presents the risk of bodily injury or death as described in Section 10.3.1 and has not been rendered harmless, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for hazardous materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for hazardous materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 The Contractor shall reimburse the Owner for the cost and expense the Owner incurs (1) for remediation of hazardous materials or substances the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 If, without negligence on the part of the Contractor, the Contractor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall reimburse the Contractor for all cost and expense thereby incurred.

§ 10.4 Emergencies

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury, or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7.

ARTICLE 11 INSURANCE AND BONDS

§ 11.1 Contractor's Insurance and Bonds

§ 11.1.1 The Contractor shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Contractor shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Owner, Architect, and Architect's consultants shall be named as additional insureds under the Contractor's commercial general liability policy or as otherwise described in the Contract Documents.

§ 11.1.2 The Contractor shall provide surety bonds of the types, for such penal sums, and subject to such terms and conditions as required by the Contract Documents. The Contractor shall purchase and maintain the required bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.

§ 11.1.3 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

§ 11.1.4 Notice of Cancellation or Expiration of Contractor's Required Insurance. Within three (3) business days of the date the Contractor becomes aware of an impending or actual cancellation or expiration of any insurance required by the Contract Documents, the Contractor shall provide notice to the Owner of such impending or actual cancellation or

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

expiration. Upon receipt of notice from the Contractor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Contractor. The furnishing of notice by the Contractor shall not relieve the Contractor of any contractual obligation to provide any required coverage.

§ 11.2 Owner's Insurance

§ 11.2.1 The Owner shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Owner shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located.

§ 11.2.2 Failure to Purchase Required Property Insurance. If the Owner fails to purchase and maintain the required property insurance, with all of the coverages and in the amounts described in the Agreement or elsewhere in the Contract Documents, the Owner shall inform the Contractor in writing prior to commencement of the Work. Upon receipt of notice from the Owner, the Contractor may delay commencement of the Work and may obtain insurance that will protect the interests of the Contractor, Subcontractors, and Sub-Subcontractors in the Work. When the failure to provide coverage has been cured or resolved, the Contract Sum and Contract Time shall be equitably adjusted. In the event the Owner fails to procure coverage, the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent the loss to the Owner would have been covered by the insurance to have been procured by the Owner. The cost of the insurance shall be charged to the Owner by a Change Order. If the Owner does not provide written notice, and the Contractor is damaged by the failure or neglect of the Owner to purchase or maintain the required insurance, the Owner shall reimburse the Contractor for all reasonable costs and damages attributable thereto.

§ 11.2.3 Notice of Cancellation or Expiration of Owner's Required Property Insurance. Within three (3) business days of the date the Owner becomes aware of an impending or actual cancellation or expiration of any property insurance required by the Contract Documents, the Owner shall provide notice to the Contractor of such impending or actual cancellation or expiration. Unless the lapse in coverage arises from an act or omission of the Contractor: (1) the Contractor, upon receipt of notice from the Owner, shall have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by either the Owner or the Contractor; (2) the Contract Time and Contract Sum shall be equitably adjusted; and (3) the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent any loss to the Owner would have been covered by the insurance had it not expired or been cancelled. If the Contractor purchases replacement coverage, the cost of the insurance shall be charged to the Owner by an appropriate Change Order. The furnishing of notice by the Owner shall not relieve the Owner of any contractual obligation to provide required insurance.

§ 11.3 Waivers of Subrogation

§ 11.3.1 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) Separate Contractors, if any, and any of their subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by the Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The Owner or Contractor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, Separate Contractors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this section 11.3.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 11.3.2 If during the Project construction period the Owner insures properties, real or personal or both, at or adjacent to the site by property insurance under policies separate from those insuring the Project, or if after final payment property insurance is to be provided on the completed Project through a policy or policies other than those insuring the Project during the construction period, to the extent permissible by such policies, the Owner waives all rights in accordance with the terms of Section 11.3.1 for damages caused by fire or other causes of loss covered by this separate property insurance.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 11.4 Loss of Use, Business Interruption, and Delay in Completion Insurance

The Owner, at the Owner's option, may purchase and maintain insurance that will protect the Owner against loss of use of the Owner's property, or the inability to conduct normal operations, due to fire or other causes of loss. The Owner waives all rights of action against the Contractor and Architect for loss of use of the Owner's property, due to fire or other hazards however caused.

§11.5 Adjustment and Settlement of Insured Loss

§ 11.5.1 A loss insured under the property insurance required by the Agreement shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.5.2. The Owner shall pay the Architect and Contractor their just shares of insurance proceeds received by the Owner, and by appropriate agreements the Architect and Contractor shall make payments to their consultants and Subcontractors in similar manner.

§ 11.5.2 Prior to settlement of an insured loss, the Owner shall notify the Contractor of the terms of the proposed settlement as well as the proposed allocation of the insurance proceeds. The Contractor shall have 14 days from receipt of notice to object to the proposed settlement or allocation of the proceeds. If the Contractor does not object, the Owner shall settle the loss and the Contractor shall be bound by the settlement and allocation. Upon receipt, the Owner shall deposit the insurance proceeds in a separate account and make the appropriate distributions. Thereafter, if no other agreement is made or the Owner does not terminate the Contract for convenience, the Owner and Contractor shall execute a Change Order for reconstruction of the damaged or destroyed Work in the amount allocated for that purpose. If the Contractor timely objects to either the terms of the proposed settlement or the allocation of the proceeds, the Owner may proceed to settle the insured loss, and any dispute between the Owner and Contractor arising out of the settlement or allocation of the proceeds shall be resolved pursuant to Article 15. Pending resolution of any dispute, the Owner may issue a Construction Change Directive for the reconstruction of the damaged or destroyed Work.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 Uncovering of Work

§ 12.1.1 If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it must, if requested in writing by the Architect, be uncovered for the Architect's examination and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an equitable adjustment to the Contract Sum and Contract Time as may be appropriate. If such Work is not in accordance with the Contract Documents, the costs of uncovering the Work, and the cost of correction, shall be at the Contractor's expense.

§ 12.2 Correction of Work

§ 12.2.1 Before Substantial Completion

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, discovered before Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the Contractor's expense.

§ 12.2.2 After Substantial Completion

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of notice from the Owner to do so, unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor and to make a claim for breach of warranty. If the Contractor fails to correct nonconforming Work within a reasonable time during

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.5.

§ 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.

§ 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2.

§ 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.

§ 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction of the Owner or Separate Contractors, whether completed or partially completed, caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.

§ 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 Acceptance of Nonconforming Work

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS

§ 13.1 Governing Law

The Contract shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rules. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4.

§ 13.2 Successors and Assigns

§ 13.2.1 The Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to covenants, agreements, and obligations contained in the Contract Documents. Except as provided in Section 13.2.2, neither party to the Contract shall assign the Contract as a whole without written consent of the other. If either party attempts to make an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.2.2 The Owner may, without consent of the Contractor, assign the Contract to a lender providing construction financing for the Project, if the lender assumes the Owner's rights and obligations under the Contract Documents. The Contractor shall execute all consents reasonably required to facilitate the assignment.

§ 13.3 Rights and Remedies

§ 13.3.1 Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

§ 13.3.2 No action or failure to act by the Owner, Architect, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed upon in writing.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 13.4 Tests and Inspections

§ 13.4.1 Tests, inspections, and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules, and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of tests, inspections, or approvals that do not become requirements until after bids are received or negotiations concluded. The Owner shall directly arrange and pay for tests, inspections, or approvals where building codes or applicable laws or regulations so require.

§ 13.4.2 If the Architect, Owner, or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection, or approval not included under Section 13.4.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection, or approval, by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.4.3, shall be at the Owner's expense.

§ 13.4.3 If procedures for testing, inspection, or approval under Sections 13.4.1 and 13.4.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure, including those of repeated procedures and compensation for the Architect's services and expenses, shall be at the Contractor's expense.

§ 13.4.4 Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.

§ 13.4.5 If the Architect is to observe tests, inspections, or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.

§ 13.4.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.5 Interest

Payments due and unpaid under the Contract Documents shall bear interest from the date payment is due at the rate the parties agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

§ 14.1 Termination by the Contractor

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 30 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, for any of the following reasons:

- **.1** Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped;
- **.2** An act of government, such as a declaration of national emergency, that requires all Work to be stopped;
- **.3** Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents; or
- **.4** The Owner has failed to furnish to the Contractor reasonable evidence as required by Section 2.2.

§ 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, repeated suspensions, delays, or interruptions of the entire Work by the Owner as described in Section 14.3, constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, as well as reasonable overhead and profit on Work not executed, and costs incurred by reason of such termination.

§ 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, or their agents or employees or any other persons or entities performing portions of the Work because the Owner has repeatedly failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 Termination by the Owner for Cause

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- **.1** repeatedly refuses or fails to supply enough properly skilled workers or proper materials;
- **.2** fails to make payment to Subcontractors or suppliers in accordance with the respective agreements between the Contractor and the Subcontractors or suppliers;
- **.3** repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- **.4** otherwise is guilty of substantial breach of a provision of the Contract Documents.

§ 14.2.2 When any of the reasons described in Section 14.2.1 exist, and upon certification by the Architect that sufficient cause exists to justify such action, the Owner may, without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:

- **.1** Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- **.2** Accept assignment of subcontracts pursuant to Section 5.4; and
- **.3** Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.

§ 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.

§ 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance, the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Initial Decision Maker, upon application, and this obligation for payment shall survive termination of the Contract.

§ 14.3 Suspension by the Owner for Convenience

§ 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work, in whole or in part for such period of time as the Owner may determine.

§ 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay, or interruption under Section 14.3.1. Adjustment of the Contract Sum shall include profit. No adjustment shall be made to the extent

- **.1** that performance is, was, or would have been, so suspended, delayed, or interrupted, by another cause for which the Contractor is responsible; or
- **.2** that an equitable adjustment is made or denied under another provision of the Contract.

§ 14.4 Termination by the Owner for Convenience

§ 14.4.1 The Owner may, at any time, terminate the Contract for the Owner's convenience and without cause.

§ 14.4.2 Upon receipt of notice from the Owner of such termination for the Owner's convenience, the Contractor shall

- **.1** cease operations as directed by the Owner in the notice;

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

.2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work; and

.3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.

§ 14.4.3 In case of such termination for the Owner's convenience, the Owner shall pay the Contractor for Work properly executed; costs incurred by reason of the termination, including costs attributable to termination of Subcontracts; and the termination fee, if any, set forth in the Agreement.

ARTICLE 15 CLAIMS AND DISPUTES

§ 15.1 Claims

§ 15.1.1 Definition

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, a change in the Contract Time, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. The responsibility to substantiate Claims shall rest with the party making the Claim. This Section 15.1.1 does not require the Owner to file a Claim in order to impose liquidated damages in accordance with the Contract Documents.

§ 15.1.2 Time Limits on Claims

The Owner and Contractor shall commence all Claims and causes of action against the other and arising out of or related to the Contract, whether in contract, tort, breach of warranty or otherwise, in accordance with the requirements of the binding dispute resolution method selected in the Agreement and within the period specified by applicable law, but in any case not more than 10 years after the date of Substantial Completion of the Work. The Owner and Contractor waive all Claims and causes of action not commenced in accordance with this Section 15.1.2.

§ 15.1.3 Notice of Claims

§ 15.1.3.1 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered prior to expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party and to the Initial Decision Maker with a copy sent to the Architect, if the Architect is not serving as the Initial Decision Maker. Claims by either party under this Section 15.1.3.1 shall be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later.

§ 15.1.3.2 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party. In such event, no decision by the Initial Decision Maker is required.

§ 15.1.4 Continuing Contract Performance

§ 15.1.4.1 Pending final resolution of a Claim, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 15.1.4.2 The Contract Sum and Contract Time shall be adjusted in accordance with the Initial Decision Maker's decision, subject to the right of either party to proceed in accordance with this Article 15. The Architect will issue Certificates for Payment in accordance with the decision of the Initial Decision Maker.

§ 15.1.5 Claims for Additional Cost

If the Contractor wishes to make a Claim for an increase in the Contract Sum, notice as provided in Section 15.1.3 shall be given before proceeding to execute the portion of the Work that is the subject of the Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.6 Claims for Additional Time

§ 15.1.6.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, notice as provided in Section 15.1.3 shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 15.1.6.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated, and had an adverse effect on the scheduled construction.

§ 15.1.7 Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

.1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and

.2 damages incurred by the Contractor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business and reputation, and for loss of profit, except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages due to either party's termination in accordance with Article 14. Nothing contained in this Section 15.1.7 shall be deemed to preclude assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

§ 15.2 Initial Decision

§ 15.2.1 Claims, excluding those where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2 or arising under Sections 10.3, 10.4, and 11.5, shall be referred to the Initial Decision Maker for initial decision. The Architect will serve as the Initial Decision Maker, unless otherwise indicated in the Agreement. Except for those Claims excluded by this Section 15.2.1, an initial decision shall be required as a condition precedent to mediation of any Claim. If an initial decision has not been rendered within 30 days after the Claim has been referred to the Initial Decision Maker, the party asserting the Claim may demand mediation and binding dispute resolution without a decision having been rendered. Unless the Initial Decision Maker and all affected parties agree, the Initial Decision Maker will not decide disputes between the Contractor and persons or entities other than the Owner.

§ 15.2.2 The Initial Decision Maker will review Claims and within ten days of the receipt of a Claim take one or more of the following actions: (1) request additional supporting data from the claimant or a response with supporting data from the other party, (2) reject the Claim in whole or in part, (3) approve the Claim, (4) suggest a compromise, or (5) advise the parties that the Initial Decision Maker is unable to resolve the Claim if the Initial Decision Maker lacks sufficient information to evaluate the merits of the Claim or if the Initial Decision Maker concludes that, in the Initial Decision Maker's sole discretion, it would be inappropriate for the Initial Decision Maker to resolve the Claim.

§ 15.2.3 In evaluating Claims, the Initial Decision Maker may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who may assist the Initial Decision Maker in rendering a decision. The Initial Decision Maker may request the Owner to authorize retention of such persons at the Owner's expense.

§ 15.2.4 If the Initial Decision Maker requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of the request, and shall either (1) provide a response on the requested supporting data, (2) advise the Initial Decision Maker when the response or supporting data will be furnished, or (3) advise the Initial Decision Maker that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Initial Decision Maker will either reject or approve the Claim in whole or in part.

§ 15.2.5 The Initial Decision Maker will render an initial decision approving or rejecting the Claim, or indicating that the Initial Decision Maker is unable to resolve the Claim. This initial decision shall (1) be in writing; (2) state the reasons therefor; and (3) notify the parties and the Architect, if the Architect is not serving as the Initial Decision Maker, of any change in the Contract Sum or Contract Time or both. The initial decision shall be final and binding on the parties but subject to mediation and, if the parties fail to resolve their dispute through mediation, to binding dispute resolution.

§ 15.2.6 Either party may file for mediation of an initial decision at any time, subject to the terms of Section 15.2.6.1.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 15.2.6.1 Either party may, within 30 days from the date of receipt of an initial decision, demand in writing that the other party file for mediation. If such a demand is made and the party receiving the demand fails to file for mediation within 30 days after receipt thereof, then both parties waive their rights to mediate or pursue binding dispute resolution proceedings with respect to the initial decision.

§ 15.2.7 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

§ 15.2.8 If a Claim relates to or is the subject of a mechanic's lien, the party asserting such Claim may proceed in accordance with applicable law to comply with the lien notice or filing deadlines.

§ 15.3 Mediation

§ 15.3.1 Claims, disputes, or other matters in controversy arising out of or related to the Contract, except those waived as provided for in Sections 9.10.4, 9.10.5, and 15.1.7, shall be subject to mediation as a condition precedent to binding dispute resolution.

§ 15.3.2 The parties shall endeavor to resolve their Claims by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedures in effect on the date of the Agreement. A request for mediation shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the mediation. The request may be made concurrently with the filing of binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section 15.3.2, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.

§ 15.3.3 Either party may, within 30 days from the date that mediation has been concluded without resolution of the dispute or 60 days after mediation has been demanded without resolution of the dispute, demand in writing that the other party file for binding dispute resolution. If such a demand is made and the party receiving the demand fails to file for binding dispute resolution within 60 days after receipt thereof, then both parties waive their rights to binding dispute resolution proceedings with respect to the initial decision.

§ 15.3.4 The parties shall share the mediator's fee and any filing fees equally. The mediation shall be held in the place where the Project is located, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

§ 15.4 Arbitration

§ 15.4.1 If the parties have selected arbitration as the method for binding dispute resolution in the Agreement, any Claim subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Arbitration Rules in effect on the date of the Agreement. The Arbitration shall be conducted in the place where the Project is located, unless another location is mutually agreed upon. A demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The party filing a notice of demand for arbitration must assert in the demand all Claims then known to that party on which arbitration is permitted to be demanded.

§ 15.4.1.1 A demand for arbitration shall be made no earlier than concurrently with the filing of a request for mediation, but in no event shall it be made after the date when the institution of legal or equitable proceedings based on the Claim would be barred by the applicable statute of limitations. For statute of limitations purposes, receipt of a written demand for arbitration by the person or entity administering the arbitration shall constitute the institution of legal or equitable proceedings based on the Claim.

§ 15.4.2 The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

§ 15.4.3 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly consented to by parties to the Agreement, shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 15.4.4 Consolidation or Joinder

§ 15.4.4.1 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation, (2) the arbitrations to be consolidated substantially involve common questions of law or fact, and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 15.4.4.2 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration, provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of any claim, dispute or other matter in question not described in the written consent.

§ 15.4.4.3 The Owner and Contractor grant to any person or entity made a party to an arbitration conducted under this Section 15.4, whether by joinder or consolidation, the same rights of joinder and consolidation as those of the Owner and Contractor under this Agreement.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved.** **WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 17:31:49 ET on 02/12/2019 under Order No.2122530122 which expires on 02/12/2020, and is not for resale.
User Notes: (1869164890)

SUPPLEMENTARY CONDITIONS OF THE CONTRACT

1. DEFINITIONS - Supplement Paragraph 1.1 as follows:

   a. When words such as approved, proper, satisfactory, equal, and as directed are used, they imply such reference to the Architect's specific approval and directions.

   b. Provide means to furnish and install.

   c. The provisions of the Agreement take precedence over all other Contract Documents.

2. WARRANTY - Supplement Paragraph 3.5.1 as follows:

   a. Contractor warrants to Owner and Architect that on receipt of notice from either of them, within the period of one (1) year following date of Substantial Completion, that defects in materials and/or workmanship have appeared in the Work, Contractor will promptly correct such defects to the state of condition originally required by the Contract Documents at Contractor's expense.

3. SHOP DRAWINGS - Supplement Paragraph 3.12 as follows:

   a. The Contractor shall submit **one (1) electronic copy** of all Shop or Setting Drawings and Schedules required for the work of the various trades, after same have been checked and compared with the Contract Document Requirements, and after checking with field conditions at the job and so certified on the Drawings by the Contractor. Above Drawings will not be checked by Architect unless same bear certification.

   b. Architect's approval is subject to notations on Drawings, Compliance with Drawings and Specifications, and conditions and measurements at project. Measurements and quantity will not be checked or approved.

4. SAMPLES - Supplement Subparagraph 3.12.3 as follows:

   a. All samples as called for in the various Sections of this Specification and any other samples, as directed, shall be furnished by the Contractor for approval.

   b. All samples of materials that require approval as to color, texture, finish and type shall be furnished at the same time, so that an intelligent selection of colors and textures may be made by the Architect.

5. COLOR SELECTIONS

   a. The Contractor shall provide for and coordinate into the project construction schedule, a 6-week time frame for the Architect/Designer to make final color selections from Contractor's submittals, obtain approval from the Owner and to submit a color schedule, indicating what colors go where, to the Contractor. Time frame begins when Architect has received 100% of submittals listed below.

   b. Submittals, i.e., actual samples, manufacturers' literature, full color line options, etc., shall include as a minimum, but not limited to:
      Masonry, Stone, Brick, etc.
      Carpet Types
      Sheet Vinyl Flooring
      Vinyl Composition Tile & Plank Flooring
      Vinyl Base
      Ceramic Tile
      Ceiling Types
      Paint
      Corner Guards
      Flooring transitions
      Plastic Laminate (Manufacturer)
      Wood Stain for Doors and Woodwork
      Aluminum Storefront System

6. CLEAN UP - Supplement Paragraph 3.15 as follows:
   a. Each Contractor shall, at all times, remove any and all of his rubbish from the buildings and grounds and keep the building site clean.

b. In addition to the general broom cleaning, the General Contractor shall do the following special cleaning for all trades at the completion of the work:

1) Glass. Remove putty, stains and paint from all glass and wash and polish same. Care shall be taken not to scratch the glass.

2) Painted, Decorated, and Stained Work. Remove all marks, stains, fingerprints and other soil or dirt from all painted, decorated, and stained work.

3) Temporary Protection. Remove all temporary protections; clean and polish all floors at completion.

4) Woodwork. Clean and polish all woodwork upon completion.

5) Hardware. Clean and polish all hardware for all trades. This shall include removal of all stains, dust, dirt, paint, etc., upon completion.

6) Tile Work. Remove all spots, soil, and paint from all tile work, wash same upon completion.

7) Fixtures and Equipment. Clean all fixtures and equipment, removing all stains, paint, dirt, and dust.

c. All combustible rubbish, and all debris and other rubbish shall be removed entirely from the premises.

7. MUTUAL RESPONSIBILITY OF CONTRACTORS - Supplement Paragraph 6.2 as follows:

a. General Contractor shall assume general coordination and direction of the project. General Contractor shall cooperate with Mechanical and Electrical Contractors and other subcontractors and/or suppliers on the Work and install their work in sequence to facilitate and not delay the completion of the project. The Architect is not the coordinator or expeditor of the work of the contractors and/or subcontractors referred to hereinbefore.

8. CHANGES IN THE WORK

Refer to Paragraph 7.2 and insert the following:

a. Whenever a Change Order involves net cost decrease, the CREDIT to the Owner shall be such net cost decrease. Whenever a Change Order involves a summary net increase, the Contract shall be increased by the amount of such net cost increase plus max. 10% of such net cost for overhead and profit. The General Contractor will furnish supervision and coordination for max. 10% of the cost of additional Mechanical and Electrical work ordered by the Owner.

b. The Contractor shall furnish the Owner an itemized accounting with supporting data used in computing the value of any change that might be ordered.

c. Change Orders must state a number of added days or days to be deleted from completion time. If no change in days is required by the change order, write NONE. Failure to comply with above voids any later request for extra time.

9. APPLICATION FOR PROGRESS PAYMENTS AND CERTIFICATION FOR PAYMENT

a. Amend Subparagraph 9.3.1 and insert the following: On or before the 25th day of each month, the Contractor shall submit to the Architect an itemized Application for Payment supported by such data substantiating the Contractor's right to payment as the Owner or Architect may require.

b. Amend Subparagraph 9.4.1 and insert: If the Contractor has made application for payment as above, the Architect will, with reasonable promptness and within seven (7) days after receipt of the application, issue an application for payment to the Owner, with a copy to the Contractor in the amount of 90% of the value of the Contract the Architect determines has been completed to the date of application, thus a 10% retainage, less any amount paid to the Contractor, or state in writing his reason for withholding an application as provided in Subparagraph 9.5.1.

c. Date of payment of the Application for Payment by the Owner is hereby defined as the earliest possible date that the Owner can prepare vouchers after receipt of Application for Payment from the Architect and approval of same by any governing body of the Owner and issuance of vouchers to cover Application for Payment.

10. CONTRACTOR'S LIABILITY INSURANCE

a. Workers' Compensation and Employers Liability Insurance - Refer to Subparagraph 11.1.1.

b. Bodily Injury and Property Damage - Refer to Subparagraph 11.1.2. Limits shall be as follows:
(1) Limits of liability coverage shall be $2,000,000.00 Combined Single Limit for Bodily Injury and Property Damage.

c. Owner's Protective Liability Insurance - Refer to Paragraph 11.2 - Owner's Option.

11. PERFORMANCE AND PAYMENT BONDS - Supplement Subparagraph 11.4.1 as follows:

a. Bond shall be equivalent to AIA Form A311, two-part Performance Bond and Labor and Materials Bond with amount shown on each part equal to 100% of the total amount payable by the terms of the Contract. Surety shall be company licensed to do business at the place of building and shall be acceptable to the Owner.

END OF SECTION

List of Drawings

General

	Cover Sheet
	Survey
CFP1	Code Footprint
CFP2	Code Footprint
CFP3	Code Footprint
FH1	Fair Housing Diagrams
FH2	Fair Housing Diagrams
FH3	Fair Housing Diagrams
TAS1	Texas Accessibility Standards
TAS2	Texas Accessibility Standards
ADA	2010 ADA Standard for Accessibility Design

Civil

C1.0	Cover Sheet
C3.0	Demolition Plan
C4.0	Site Plan
C5.0	Utility Plan
C6.0	Grading Plan
C7.0	Erosion Control Plan
C8.0	Details
C9.0	Details

Demolition

D1.1	Site Demolition Plan
D2.1	First Floor Demolition Plan
D2.2	Second Floor Demolition Plan
D2.3	Third Floor Demolition Plan
D5.1	Roof Demolition Plan
Site Plan	

Architectural

A1.1	Site Plan
A1.2	Details
A1.3	Enlarged Ramp Plans and Sections
A1.4	Enlarged Ramp Plan
A2.0	Relocated Cabinet Diagram
A2.1	General Notes
A2.2	Composite Floor Plans
A2.3	Area A - First Floor Plan
A2.4	Area B & D - First Floor Plan
A2.5	Area C – First Floor Plan
A2.6	Area A – Second Floor Plan
A2.7	Area B – Second Floor Plan
A2.8	Third Floor Plan
A3.0	Photographic Elevations
A3.1	Photographic Elevations
A3.2	Exterior Elevations
A3.3	Exterior Elevations
A3.4	Exterior Elevations
A4.1	Raised Floor Framing Plan & Sections
A5.1	Roof Plan
A5.2	Details
A6.1	Stair Finishes
A6.2	Elevator
A7.1	First Floor Reflected Ceiling Plan
A7.2	Second & Third Floor Reflected Ceiling Plans
A8.0	Public Restrooms
A8.1	Historic Nurses Stations Details
A8.2	Community Room Interior Elevations
A8.3	Activity Room Interior Elevations
A8.4	Interior Elevations
A8.5	Interior Elevations
A8.6	Interior Elevations
A8.7	Interior Elevations
A8.8	Interior Elevations
A9.0	Reception Casework Elevations & Sections
A9.1	First Floor, Floor Finish Plan
A9.2	Second & Third Floor, Floor Finish Plans
A9.3	Unit Baths Type 1-3 Enlarged Plan & Interior Elevations
A9.4	Unit Baths Type 4-6 Enlarged Plan & Interior Elevations
A9.5	Unit Baths Type 7-9 Enlarged Plan & Interior Elevations
A9.6	Unit Baths Type 10 Enlarged Plan & Interior Elevations
A9.7	Casework Sections
A9.8	Unit Kitchens Type 1-4 Interior Elevations
A9.9	Unit Kitchens Type 5-9 Interior Elevations
A9.10	Unit Kitchens Type 10-14 Interior Elevations
A10.0	Window Schedules
A10.1	’38 Building Window Details
A10.2	’53 Building Window Details
A10.3	’53 Building Window Details
A10.4	’67 Building Window Details
A10.5	’67 Building Window Details
A10.6	Door Schedules & Details
A10.7	Door Schedule & Details
A10.8	Finish Schedules

Mechanical

ME1.1	Photographic Demo Elevations
ME1.2	Photographic Demo Elevations
ME1.3	
ME1.4	Roof M/E Plan
M1.1	First Floor Mechanical Plan
M1.2	Second Floor Mechanical Plan
M1.3	Third Floor Mechanical Plan
M1.4	Under Floor Waste and Vent Plan
M1.5	First Floor Waste and Vent Plan
M1.6	Second Floor Waste and Vent Plan
M1.7	Third Floor Waste and Vent Plan
M1.8	First Floor Domestic Water Plan
M1.9	Second Floor Domestic Water Plan
M1.10	Third Floor Domestic Water Plan
M1.11	Basement Waste/Vent & Domestic Water Plan
M4.1	Enlarged Unit Mechanical Plans
M4.2	Enlarged Unit Mechanical Plans
M4.3	Enlarged Unit Mechanical Plans
M4.4	Enlarged Unit Mechanical Plans
M4.5	Enlarged Unit Mechanical Plans
M4.6	Enlarged Unit Domestic Water Plan
M4.7	Enlarged Unit Domestic Water Plan
M4.8	Enlarged Domestic Water Plan
M5.1	Riser Diagram
M6.1	Schedules
M6.2	Schedules
M6.3	Details

Electrical

E1.0	Electrical Site Plan
E1.1	First Floor Lighting Plans
E1.2	Second Floor Lighting Plans
E1.3	Third Floor Lighting Plans
E1.4	First Floor Power Plan
E1.5	Second Floor Power Plan
E1.6	Third Floor Power Plan
E1.7	First Floor Power Plan
E1.8	Second Floor Power Plan
E1.9	Third Floor Power Plan
E1.10	Enlarged Basement Power, Lighting, Systems Plan
E4.1	Enlarged Unit Electrical Plans
E4.2	Enlarged Unit Electrical Plans
E4.3	Enlarged Unit Electrical Plans
E4.4	Enlarged Unit Electrical Plans
E6.1	Electrical Service
E6.2	Electrical Riser Diagram
E6.3	Schedules

Limited Asbestos Inspection Report

Landmark 601

601 West Lewis Street

Conroe, Montgomery County, Texas 77301

PE Project No.: 202511026
November 20, 2025

Prepared for:
Overland Property Group
254 North Santa Fe Avenue, Suite A
Salina, Kansas 67401

Prepared by:
Phase Engineering, LLC
5524 Cornish Street
Houston, Texas 77007

Overland Property Group
c/o Caroline Hurst
254 North Santa Fe Avenue, Suite A
Salina, Kansas 67401
Phone: (785) 200-7489 Email: churst@overlandpg.com

RE: 202511026

Dear Caroline Hurst:

Phase Engineering, LLC (Texas Department of State Health Services [TDSHS] license #10-0224) has conducted an asbestos inspection for renovation purposes of the building materials in the Landmark 601 buildings located at 601 West Lewis Street, Conroe, Montgomery County, Texas 77301.

PROJECT SUMMARY	
Site Elements	**Comments**
Subject Property Address	601 West Lewis Street, Conroe, Montgomery County, Texas 77301
Location Contact	Caroline Hurst, (785) 200-7489
Date of Inspection	November 14, 2025
Building Plans / Prior Inspection Reports	Landmark 601 - Historic Submittal Arch Set
Known Areas Not Available for Access	None
Inspector Name	Matt White
Inspector License #	TDSHS Asbestos Consultant License 105849
Company License #	TDSHS Asbestos Consultant Firm #10-0224
Number of Samples Collected	98
Number of Samples Analyzed	98
Number of samples containing or assumed to contain more than 1% asbestos via Polarized Light Microscopy (PLM)	0
Number of samples containing or assumed to contain more than 1% asbestos that were analyzed by Point Counting	0
Number of samples containing asbestos but less than 1% via Point Count analysis	0
Number of samples containing more than 1% asbestos	**0**

Laboratory Conducting Analysis and Method: Micro Analytical Services. (TDSHS License Number 30-0304), Methods - Polarized Light Microscopy with Dispersion Staining EPA Test Method 600/M4-82-020; (40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116.

Under EPA 600/R-93/116; Interim 40CFR Part 763 Appendix E to Subpart E it is not necessary to separate layers for point counting in the individual components are proportioned equally.

The potential Asbestos Containing Building Material (ACBM) samples collected, their descriptions, and their locations are summarized in the following table. ACBMs that tested positive over 1% for asbestos are shaded in yellow. Material that tested positive over 1% for asbestos via PLM, but tested to be 1% or less via Point Count analysis are shaded in blue.

Sample Number	Sample Description	Unit / Location	Percent Asbestos
See lab results, sample photographs, licenses and certifications and scope of work in the appendices of this report.			
01	1×1 Ceiling tile	Main building - Basement	None detected
02	1×1 Ceiling tile	Main building - Basement	None detected
03	1×1 Ceiling tile	Main building - Basement	None detected
04	Plaster ceiling	Main building - 1st floor classroom	None detected
05	Plaster ceiling	Main building - 1st floor classroom	None detected
06	Plaster ceiling	Main building - 2nd floor classroom	None detected
07	Plaster ceiling	Main building - Auditorium	None detected
08	Plaster ceiling	Main building - Basement	None detected
09	2×4 Pinhole ceiling tile	Hallways - 1st floor	None detected
10	2×4 Pinhole ceiling tile	Hallways - 2nd floor	None detected
11	2×4 Pinhole ceiling tile	Hallways - 3rd floor	None detected
12	2×2 Pinhole ceiling tile	Hallways - 1st floor	None detected
13	2×2 Pinhole ceiling tile	Hallways - 2nd floor	None detected
14	2×2 Pinhole ceiling tile	Hallways - 3rd floor	None detected
15	Plaster walls	Main building - 1st floor classroom	None detected
16	Plaster walls	Main building - 1st floor classroom	None detected
17	Plaster walls	Main building - 2nd floor classroom	None detected
18	Plaster walls	Main building - Auditorium	None detected
19	Plaster walls	Main building - Basement	None detected
20	Carpet mastic	Classrooms and hallways	None detected
21	Carpet mastic	Classrooms and hallways	None detected
22	Carpet mastic	Classrooms and hallways	None detected
23	Carpet mastic	Classrooms and hallways	None detected
24	Carpet mastic	Classrooms and hallways	None detected
25	Carpet mastic	Auditorium	None detected
26	Carpet mastic	Auditorium	None detected

Sample Number	Sample Description	Unit / Location	Percent Asbestos
27	Carpet mastic	Auditorium	None detected
28	Ceramic tile	Bathroom 1st floor	None detected
29	Ceramic tile	Bathroom 2nd floor	None detected
30	Ceramic tile	Entryways	None detected
31	12×12 Floor tile (white)	Principals office	None detected
32	12×12 Floor tile (white)	Chimney room 1st floor	None detected
33	12×12 Floor tile (white)	Chimney room 2nd floor	None detected
34	Sink undercoat	Classroom	None detected
35	Sink undercoat	Classroom	None detected
36	Sink undercoat	Clinic	None detected
37	Chalkboard	Classrooms	None detected
38	Chalkboard	Classrooms	None detected
39	Chalkboard	Classrooms	None detected
40	Auditorium curtains	Auditorium	None detected
41	Auditorium curtains	Auditorium	None detected
42	Auditorium curtains	Auditorium	None detected
43	HVAC mastic	Classroom 108	None detected
44	HVAC mastic	Classroom 210	None detected
45	HVAC mastic	Hallway	None detected
46	TSI 2 inch elbow		None detected
47	TSI 2 inch elbow		None detected
48	TSI 2 inch elbow		None detected
49	TSI 6 inch elbow		None detected
50	TSI 6 inch elbow		None detected
51	TSI 6 inch elbow		None detected
52	TSI 10 inch elbow		None detected
53	TSI 10 inch elbow		None detected
54	TSI 10 inch elbow		None detected
55	2×4 ceiling tile (sheetrock)	Cafeteria building - Kitchen	None detected
56	2×4 ceiling tile (sheetrock)	Cafeteria building - Kitchen	None detected
57	2×4 ceiling tile (sheetrock)	Cafeteria building - Kitchen	None detected
58	2×2 ceiling tile	Cafeteria building - Cafeteria	None detected
59	2×2 ceiling tile	Cafeteria building - Cafeteria	None detected
60	2×2 ceiling tile	Cafeteria building - Cafeteria	None detected
61	Sheetrock wall components	Cafeteria building - throughout	None detected
62	Sheetrock wall components	Cafeteria building - throughout	None detected
63	Sheetrock wall components	Cafeteria building - throughout	None detected
64	Covebase	Cafeteria building - throughout	None detected

Sample Number	Sample Description	Unit / Location	Percent Asbestos
65	Covebase	Cafeteria building - throughout	None detected
66	Covebase	Cafeteria building - throughout	None detected
67	Ceramic floor	Cafeteria building - first floor	None detected
68	Ceramic floor	Cafeteria building - first floor	None detected
69	Ceramic floor	Cafeteria building - first floor	None detected
70	Wall mastic	Cafeteria building - kitchen	None detected
71	Wall mastic	Cafeteria building - kitchen	None detected
72	Wall mastic	Cafeteria building - kitchen	None detected
73	Carpet mastic	Cafeteria building - second floor	None detected
74	Carpet mastic	Cafeteria building - second floor	None detected
75	Carpet mastic	Cafeteria building - second floor	None detected
76	Roofing materials	School building roof	None detected
77	Roof flashing	School building roof	None detected
78	Ceiling insulation	Gym building	None detected
79	Ceiling insulation	Gym building	None detected
80	Ceiling insulation	Gym building	None detected
81	Sheetrock wall components	Gym building	None detected
82	Sheetrock wall components	Gym building	None detected
83	Sheetrock wall components	Gym building	None detected
84	CMU block walls	Gym building	None detected
85	CMU block walls	Gym building	None detected
86	CMU block walls	Gym building	None detected
87	Wall mastic	Gym building	None detected
88	Wall mastic	Gym building	None detected
89	Wall mastic	Gym building	None detected
90	Boiler insulation	Mechanical building	None detected
91	Boiler insulation	Mechanical building	None detected
92	Boiler insulation	Mechanical building	None detected
93	TSI Elbows	Mechanical building	None detected
94	TSI Elbows	Mechanical building	None detected
95	TSI Elbows	Mechanical building	None detected
96	TSI Straights	Mechanical building	None detected
97	TSI Straights	Mechanical building	None detected
98	TSI Straights	Mechanical building	None detected

Site Specific Details:

The inspection performed by Phase Engineering, LLC was a suspect asbestos containing building materials (ACBMs) inspection for renovation purposes of the building materials in the Landmark 601 buildings located at 601 West Lewis Street, Conroe, Montgomery County, Texas 77301 following the Texas Asbestos Health Protection Rules (TAHPR) and the National Emission Standards for Hazardous Air Pollutants (Title 40 CFR, Part 61) for any exterior samples required. **This inspection is not intended to comply with AHERA 40 CFR 763**.

Site Specific Details
Item Description
The inspector was provided no historical documentation of original construction or renovations of the building. No previous asbestos inspection reports or abatement reports were provided to the inspector.
The sampling protocol followed for this inspection was intended for renovation purposes of the building materials in the Landmark 601 buildings located at 601 West Lewis Street, Conroe, Montgomery County, Texas 77301.
Inspection was limited due to building occupancy.
The building consisted of vinyl tile flooring,TSI and boiler insulation, roofing materials, cmu walls, ceramic tile (grout), auditorium curtains, HVAC mastic, chalk boards, plaster ceilings and walls, sink undercoat, carpet mastic, sheetrock walls, ceiling tile ceilings and sheetrock ceilings.
The first-second floor flooring types appear to be installed onto concrete.
Any other suspect material found during renovation that was not sampled during this inspection is to be considered ACBM until tested.
The mirrors within the building inspected appeared to be hung to the sheetrock walls. During the course of renovation, any suspect material observed behind mirrors (black mastic) or behind any observed ceramic tile is to be considered ACBM until tested.
Areas behind walls and above ceilings were observed for suspect ACBMs where possible. Phase Engineering, LLC does not warrant that all suspect ACBMs above ceilings, under flooring, and behind walls have been identified.
The specific square footage of each homogeneous suspect ACBM area is not included as a part of this limited asbestos inspection.

Although Phase Engineering, LLC uses trained and licensed inspectors in attempting to locate and identify materials potentially containing asbestos, Phase Engineering, LLC does not warrant that all materials containing asbestos have been identified. It is possible that there are materials containing asbestos that were not found because they were not visible or accessible to the inspector, or for various other reasons, were not sampled. Moreover, it is possible that the actual quantities of materials will differ from the quantities of materials estimated during this survey.

Samples taken are categorized as either friable or non-friable. The term friable refers to the ease with which the material can be crumbled or made to produce dust using hand pressure alone. For example, ceiling tiles are generally considered friable, while floor tiles are generally considered non-friable. Sheet rock wall materials are considered friable when damaged and non-friable when intact. The condition of the materials sampled is also categorized as good, damaged or significantly damaged.

A construction material is considered to be an ACBM if it is composed of more than 1% asbestiform components.

Findings:

The results found during the asbestos inspection indicate that the following suspect ACBM(s) contain more than 1% asbestos. The material found to be an ACBM is summarized in the following table:

Type of Material	Approximate Location of ACBM	Friable / Non-Friable - Condition	Asbestos % and Type
None			

No suspect ACBMs analyzed were found to contain more than 1% asbestos in the Landmark 601 buildings located at 601 West Lewis Street, Conroe, Montgomery County, Texas 77301.

Recommendations:

If the buildings are to be demolished or renovated it is recommended that any other ACBMs or assumed ACBMs that will be disturbed be removed by a licensed abatement contractor and if applicable, a licensed asbestos consultant. The TDSHS Demolition/Renovation Notification form combines the requirements of the National Emission Standards for Hazardous Air Pollutants, 40 CFR, Subpart M (NESHAP) and the Texas Asbestos Health Protection Rules (TAHPR). Both of these regulations require that written notification be submitted before beginning renovation projects that include the disturbance of any asbestos-containing material in a facility. A notification form is required before the demolition of a building or facility, even when no asbestos is present. This form must be used to fulfill either of these requirements. Please call either 512-834-6610 or 1-800-572-5548 (within Texas), or your local regional office for assistance in completing this form.

If any ACBM is left in place the TDSHS may require an asbestos Management Plan in accordance with the TAHPR, section 295.34 (h). In the event that maintenance and repair are necessary, it is required by OSHA that anyone in contact with the disruption of these ACBMs be notified through an onsite, up-to-date asbestos Management Plan. This Management Plan should be developed to include emergency procedures for handling leaks, breaks, fire, etc. to ensure minimal release of asbestos fibers into the air. This plan should also ensure that when asbestos fibers are released, either accidentally or intentionally, proper control and cleanup procedures are implemented.

During renovation or demolition activities, care should be exercised in dealing with all construction materials even those shown to be non-asbestos containing (this would include materials technically considered as non-asbestos containing because they are below the one percent limit). If these non-asbestos materials are to be disturbed work practices should be used that will limit exposure to dust and debris. Contractors performing this work should conform to OSHA regulations outlined in 29 CFR 1926.55 (exposure limits can be found in 29 CFR 1910.1000 Table Z-3).

The Texas Asbestos Health Protection Rules (TAHPR) dated March 2003, §295.34 (c) (1) state “During the construction of or renovation in a public building, a person appropriately licensed in accordance with these rules, Texas-registered architect or Texas-licensed professional engineer may compile the information from material safety data sheets (MSDS) of all products used in the construction of the building and, finding no asbestos in any of those products, prepare a signed written certification that he has reviewed the MSDSs for all products used in the construction and that none of those products contain ACBM and: therefore, the building material do not contain asbestos. This certification, together with copies of the MSDSs and copies of any previous asbestos surveys, may be used as an asbestos survey.”

Further TAHPR §295.34 (i) states that “A person may not install building materials or replacement parts as stated in subsection (j) of this section, in a public building unless: (1) the person obtains a required MSDS showing that the materials or replacement parts contain 1.0% or less of asbestos; or (2) the materials or replacement parts, according to the MSDS, contain more than 1.0% asbestos but there is no alternative material or part as demonstrated by the building owner or contractor.” In the event of future renovation and or demolition, further sampling may be required of suspect asbestos containing materials prior to these activities to satisfy the Environmental Protection Agency (EPA), Occupational Safety and Health Administration (OSHA), and Texas Department of State Health Services (TDSHS) rules and regulations at that time. If suspect asbestos containing building

materials (not noted during this inspection) should be found during any renovation or demolition, these materials should be sampled for asbestos and handled appropriately following all local, state and federal rules and regulations at that time.

If improper renovation or demolition occurs the owner is subject to a $10,000 a day fine, enforced by the Texas Department of State Health Services (TDSHS).

Thank you for the opportunity to work with you on your environmental needs. If you have any questions, feel free to contact us at (832)-485-2241 or 1-800-419-8881.

Sincerely,



Matt White
Asbestos Consultant
TDSHS License #105849



Parker Lemm
Asbestos Inspector
TDSHS License #604104

APPENDIX I


PHOTOGRAPHIC DOCUMENTATION



1. 1×1 ceiling tiles



2. Plaster ceilings



3. 2×4 ceiling tile




4. 2×2 ceiling tile



5. plaster walls




6. carpet mastic



7. carpet mastic



8. ceramic tile



9. 12×12 vinyl tile




10. sink undercoat




11. Chalkboard



12. auditorium curtain




13. TSI




14. TSI



15. TSI



16. 2×4 ceiling tile



17. 2×2 ceiling tile



18. Sheetrock walls



19. Covebase




20. Roofing Materials




21. Roof flashing



22. Ceramic tile




23. Wall panel mastic




24. carpet mastic



25. ceiling insulation



26. Sheetrock ceilings



27. CMU block



28. Carpet mastic



29. Wall mastic



30. Boiler insulation



31. TSI



32. TSI

APPENDIX II

LABORATORY RESULTS

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	601 W. Lewis ST. Conroe
		Project #:
City: Houston	Email:	20251026
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected: 11/14/25	MAS Project #: 20206

Turn around time (circle): Emergency 1-day 2-day (3-day) 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	Comments
01	619507	1x1 ct (Button Mastic)	Basement	Main Bldg
02	↓	↓	↓	↓
03	↓	↓	↓	↓
04	↓	Plaster Ceiling	Classrooms 1	↓
05	↓	↓	↓	↓
06	↓	↓	Auditorium	↓
07	↓	↓	Classrooms 2	↓
08	↓	↓	Basement	↓
09	↓	2x4 CT - pinhole	Hallway 1	↓
10	↓	↓	↓ #1	↓
11	↓	↓	↓ #2	↓
12	↓	2x2 CT - pinhole	Hallway drop downs 1	↓
13	↓	↓	#1	↓
14	↓	↓	#2	↓
15	↓	Plaster Walls	Florist 1	↓
16	↓	↓	↓ 1	↓
17	↓	↓	2	↓
18	↓	↓	2	↓
19	619525	↓	Basement	↓

Relinquished by: _____ Date: 11/17/25 Time: _____

Received by: TONY DANG Date: 11/17/25 Time: 4:00 PM

Relinquished by: _____ Date: _____ Time: _____

Received by: _____ Date: _____ Time: _____

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	
		Project #: 20251102L
City: Houston	Email:	
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected:	MAS Project #: 20206

Turn around time (circle): Emergency 1-day 2-day 3-day 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	Comments
20	619526	Carpet Mastic	Classroom 1st	Main Bldg
21		↓	Classroom 1st	
22			Hallway 1st	
23			Classroom 2nd	
24		↓	Hall way 2nd	
25		Carpet Mastic	Auditorium	
26		↓	↓	
27				
28		Ceramic tiles	RR 1st	
29		↓	RR 2nd	
30			Entries	
31		12x12 FT(White)	Principals office	} Under Carpet
32		↓	Chimney RR	
33			Chimney Room	
34		SINK Undercoating	Classroom 1st	
35		↓	Classroom 1st	
36	619542	↓	Clinic	

Relinquished by:_____ Date:_____ Time:_____

Received by: TONY DANG Date: 11/07/25 Time: 4:00 pm

Relinquished by:_____ Date:_____ Time:_____

Received by:_____ Date:_____ Time:_____

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	
		Project #: 20251026
City: Houston	Email:	
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected:	MAS Project #: 20206

Turn around time (circle): Emergency 1-day 2-day 3-day 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	Comments
37	619543	Chalk Boards	Classroom 1st	Main Bldg
38		〃	〃 1st	
39		〃	〃 2nd	
40		Auditorium Curtains	Auditorium	
41		〃	〃	
42		〃	〃	
43		HVAC Mastic	108	
44		〃	210	
45		〃	Hallway 1st 2nd	
46		TSI 2" Elbows	Auditorium	
47		〃	Kitchen	
48		〃	Kitchen	
49		TSI 6" Elbows	Auditorium	
50		〃	〃	
51		〃	〃	
52		TSI 10" Elbows	Auditorium	
53		〃	〃	
54	619560	〃	〃	

Relinquished by:_____ Date:_____ Time:_____

Received by: TONY DANG Date: 11/17/25 Time: 4:00 PM

Relinquished by:_____ Date:_____ Time:_____

Received by:_____ Date:_____ Time:_____

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	
		Project #: 20251026
City: Houston	Email:	
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected:	MAS Project #: 70206

Turn around time (circle): Emergency 1-day 2-day 3-day 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	*Comments*
55	619561	2x4 CT (SR)	Kitchen	2nd Bldg
56		〃	〃	
57		〃	〃	
58		2x2 CT-pinhole	Cafeteria	
59		〃	〃	
60		〃	〃	
61		SPW	T.O. - 1st	
62		〃	2nd	
63		〃	2nd	
64		CB	T.O. 1st	
65		〃	2nd	
66		〃	2nd	
67		Ceramic 12/oor	Kitchen	
68		〃	Cafeteria	
69		〃	Cafeteria	
70		Wall Mastic	Kitchen	
71		〃	〃	
72	619578	〃	〃	

Relinquished by:_____ Date:_____ Time:_____

Received by: TONY DANG Date: 11/17/25 Time: 4:00 PM

Relinquished by:_____ Date:_____ Time:_____

Received by:_____ Date:_____ Time:_____

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	
		Project #: 20251102Lo
City: Houston	Email:	
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected:	MAS Project #: 20206

Turn around time (circle): Emergency 1-day 2-day 3-day 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	Comments
73	619579	Carpet Mastic	1st entry	2nd Bldg
74		〃	2nd Hallway	〃
75		〃	2nd office	〃
76		Roofing Mats	Mens 2nd Bldg	〃
77		Roof Flashing	〃	〃
78		Ceiling Insulation	T.O.	Gym
79		〃	〃	〃
80		〃	〃	〃
81		Sheetrock	storage room	〃
82		〃	〃	〃
83		〃	〃	〃
84		CMU Walls	North	〃
85		〃	West	〃
86		〃	South	〃
87		Wall mastic	East wall	〃
88		〃	〃	〃
89	619595	〃	〃	〃

Relinquished by:_____ Date:_____ Time:_____

Received by: TONY DANG Date: 11/17/25 Time: 4:00 PM

Relinquished by:_____ Date:_____ Time:_____

Received by:_____ Date:_____ Time:_____

Micro Analytical Services, Inc. 11301 Richmond Ave. Suite K100B♦Houston♦Texas 77082♦Phone (281) 497-4500♦Fax (281) 497-4517

Asbestos Bulk Sample Chain of Custody

Company: Phase Engineering LLC	Contact:	Project Name:
Address: 5524 Cornish Street	Bill to: Mr. Matt White	
		Project #: 20251102L
City: Houston	Email:	
State/Zip: Texas 77007	MattW@PhaseEngineering.com	PO #:
Phone: (832)485-2241		
Fax: (713)476-9797	Date Collected:	MAS Project #: 20206

Turn around time (circle): Emergency 1-day 2-day 3-day 4-day 5-day

Field ID	Lab ID	Sample Description	Sample Location	Comments
90	619596	Boiler	Mech. Bldg	~~Mech~~
91		"	"	
92		"	"	
93		TSI Elbows	"	
94		"	"	
95		"	"	
96		TSI straight	"	
97		"	"	
98	619604	"	"	

Relinquished by: _____ Date: 11/17/25 Time: _____

Received by: TONY BANG Date: 11/17/25 Time: 4:00 pm

Relinquished by: _____ Date: _____ Time: _____

Received by: _____ Date: _____ Time: _____

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste.K100B♦Houston♦Tx 77082♦Phone(281)497-4500♦Fax(281)497-4517

NVLAP Lab Code: 200618-0 TDSHS License No. 30-0341

PLM BULK ASBESTOS ANALYSIS REPORT

CLIENT: Phase Engineering, Inc. **MAS JOB NO.:** 20206-00

PROJECT: 601 W. Lewis St. Conroe **REPORT DATE:** November 18, 2025

IDENTIFICATION: Asbestos, Bulk Sample Analysis, Quantitation by Visual Area Estimation

TEST METHOD: Polarized Light Microscopy with Dispersion Staining
EPA - 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples
EPA - 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Material

STATEMENT OF LABORATORY ACCREDITATION

These samples were analyzed at Micro Analytical Services, Inc. in the Asbestos Laboratory at 11301 Richmond Ave. Suite K100B, Houston, Texas, 77082. The Laboratory holds accreditation from the National Institute of Standards and Technology under the National Voluntary Laboratory Accreditation Program (NVLAP). This laboratory is also licensed and authorized to perform as an Asbestos Laboratory in the State of Texas within the purview of Texas Civil Statutes, Article 4477-3a, as amended, so long as this license is not suspended or revoked and is renewed according to the rules adopted by the Texas Board of Health.

The samples were analyzed in general accordance with the procedures outlined in the EPA - 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples, EPA - 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Material, under AHERA, for the analysis of asbestos in building materials by polarized light microscopy. The results of each bulk sample relate only to the material tested as submitted to the laboratory and the results shall not be used to claim product endorsement by NVLAP or any agency of the U.S. Government.

Specific questions concerning bulk sample results shall be directed to the Asbestos Bulk Laboratory at Micro Analytical Services, Inc.

Analyst: Tony T. Dang

Approved Signatory: 

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
01 MAS619507	1	Grey fibrous ceiling tile with white paint	No		10% Cellulose 50% Mineral Wool 20% Perlite 20% Other
01 MAS619507	2	Dark brown non-fibrous mastic	No		100% Mastic
02 MAS619508	1	Grey fibrous ceiling tile with white paint	No		10% Cellulose 50% Mineral Wool 20% Perlite 20% Other
02 MAS619508	2	Dark brown non-fibrous mastic	No		100% Mastic
03 MAS619509	1	Grey fibrous ceiling tile with white paint	No		10% Cellulose 50% Mineral Wool 20% Perlite 20% Other
03 MAS619509	2	Dark brown non-fibrous mastic	No		100% Mastic
04 MAS619510	1	Beige fibrous plaster ceiling with white paint	No		2% Synthetic 78% Aggregate 20% Other
05 MAS619511	1	Beige fibrous plaster ceiling with white paint	No		2% Synthetic 78% Aggregate 20% Other
06 MAS619512	1	White non-fibrous texture with beige paint	No		100% Other
07 MAS619513	1	Beige fibrous plaster wall with white paint	No		2% Synthetic 78% Aggregate 20% Other

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
08 MAS619514	1	Beige fibrous plaster wall with white paint	No		2% Synthetic 78% Aggregate 20% Other
09 MAS619515	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
10 MAS619516	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
11 MAS619517	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
12 MAS619518	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
13 MAS619519	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
14 MAS619520	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
15 MAS619521	1	Beige fibrous plaster wall with white paint	No		2% Synthetic 78% Aggregate 20% Other

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
16 MAS619522	1	Beige fibrous plaster wall with white paint	No		2% Synthetic 78% Aggregate 20% Other
17 MAS619523	1	White non-fibrous texture with beige paint	No		100% Other
17 MAS619523	2	Beige non-fibrous plaster	No		2% Synthetic 78% Aggregate 20% Other
18 MAS619524	1	Beige fibrous plaster wall with beige paint	No		2% Synthetic 78% Aggregate 20% Other
19 MAS619525	1	Beige fibrous plaster wall with beige paint	No		2% Synthetic 78% Aggregate 20% Other
20 MAS619526	1	Yellow non-fibrous mastic	No		100% Mastic
20 MAS619526	2	Grey fibrous floor substrate	No		2% Cellulose 98% Other
21 MAS619527	1	Yellow non-fibrous mastic	No		100% Mastic
21 MAS619527	2	Grey fibrous floor substrate	No		2% Cellulose 98% Other
22 MAS619528	1	Yellow non-fibrous mastic	No		100% Mastic
22 MAS619528	2	Grey fibrous floor substrate	No		2% Cellulose 98% Other
23 MAS619529	1	Tan non-fibrous mastic	No		100% Mastic

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
24 MAS619530	1	Tan non-fibrous mastic	No		100% Mastic
25 MAS619531	1	Yellow non-fibrous mastic	No		100% Mastic
26 MAS619532	1	Yellow non-fibrous mastic	No		100% Mastic
27 MAS619533	1	Yellow non-fibrous mastic	No		100% Mastic
28 MAS619534	1	Grey non-fibrous ceramic tile	No		80% Aggregate 20% Other
29 MAS619535	1	Grey non-fibrous ceramic tile	No		80% Aggregate 20% Other
30 MAS619536	1	Grey non-fibrous ceramic tile	No		80% Aggregate 20% Other
31 MAS619537	1	White non-fibrous floor tile with black specks	No		100% Other
31 MAS619537	2	Yellow non-fibrous mastic	No		100% Mastic
32 MAS619538	1	White non-fibrous floor tile with black specks	No		100% Other
32 MAS619538	2	Yellow non-fibrous mastic	No		100% Mastic
33 MAS619539	1	White non-fibrous floor tile with black specks	No		100% Other
33 MAS619539	2	Yellow non-fibrous mastic	No		100% Mastic
34 MAS619540	1	Black non-fibrous sink undercoating	No		100% Bitumen

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
35 MAS619541	1	Black non-fibrous sink undercoating	No		100% Bitumen
36 MAS619542	1	Black non-fibrous sink undercoating	No		100% Bitumen
37 MAS619543	1	Dark grey non-fibrous chalk board	No		100% Other
38 MAS619544	1	Dark grey non-fibrous chalk board	No		100% Other
39 MAS619545	1	Dark grey non-fibrous chalk board	No		100% Other
40 MAS619546	1	Blue fibrous curtain	No		20% Synthetic 60% Cellulose 20% Other
41 MAS619547	1	Blue fibrous curtain	No		20% Synthetic 60% Cellulose 20% Other
42 MAS619548	1	Tan fibrous curtain	No		20% Synthetic 80% Cellulose
43 MAS619549	1	White non-fibrous mastic	No		100% Mastic
44 MAS619550	1	White non-fibrous mastic	No		100% Mastic
45 MAS619551	1	White non-fibrous mastic	No		100% Mastic
46 MAS619552	1	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
46 MAS619552	2	Yellow fibrous glass insulation	No		100% fibrous Glass

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
47 MAS619553	1	White non-fibrous mastic	No		100% Mastic
47 MAS619553	2	Beige fibrous canvas	No		100% Cellulose
47 MAS619553	3	Yellow fibrous glass insulation	No		100% fibrous Glass
48 MAS619554	1	White non-fibrous mastic	No		100% Mastic
48 MAS619554	2	Beige fibrous canvas	No		100% Cellulose
48 MAS619554	3	Yellow fibrous glass insulation	No		100% fibrous Glass
49 MAS619555	1	White fibrous mastic	No		3% Cellulose 97% Mastic
49 MAS619555	2	Yellow fibrous glass insulation	No		100% fibrous Glass
50 MAS619556	1	White fibrous mastic	No		3% Cellulose 97% Mastic
50 MAS619556	2	Yellow fibrous glass insulation	No		100% fibrous Glass
51 MAS619557	1	White fibrous mastic	No		3% Cellulose 97% Mastic
51 MAS619557	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
51 MAS619557	3	Yellow fibrous glass insulation	No		100% fibrous Glass
52 MAS619558	1	White fibrous mastic	No		3% Cellulose 97% Mastic

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
52 MAS619558	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
52 MAS619558	3	Yellow fibrous glass insulation	No		100% fibrous Glass
53 MAS619559	1	White fibrous mastic	No		3% Cellulose 97% Mastic
53 MAS619559	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
53 MAS619559	3	Yellow fibrous glass insulation	No		100% fibrous Glass
54 MAS619560	1	White fibrous mastic	No		3% Cellulose 97% Mastic
54 MAS619560	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
54 MAS619560	3	Yellow fibrous glass insulation	No		100% fibrous Glass
55 MAS619561	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
56 MAS619562	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
57 MAS619563	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
58 MAS619564	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
59 MAS619565	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
60 MAS619566	1	Beige fibrous ceiling tile with white paint	No		10% Mineral Wool 40% Cellulose 30% Perlite 20% Other
61 MAS619567	1	White non-fibrous texture with white paint	No		100% Other
61 MAS619567	2	White fibrous gypsum with brown paper	No		60% Cellulose 40% Gypsum
62 MAS619568	1	White non-fibrous texture with white paint	No		100% Other
62 MAS619568	2	White fibrous gypsum with brown paper	No		60% Cellulose 40% Gypsum
63 MAS619569	1	White non-fibrous texture with white paint	No		100% Other
63 MAS619569	2	White fibrous gypsum with brown paper	No		60% Cellulose 40% Gypsum

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
64 MAS619570	1	Dark brown non-fibrous cove base	No		100% Vinyl
64 MAS619570	2	Beige non-fibrous mastic	No		100% Mastic
65 MAS619571	1	Dark brown non-fibrous cove base	No		100% Vinyl
65 MAS619571	2	Beige non-fibrous mastic	No		100% Mastic
66 MAS619572	1	Dark brown non-fibrous cove base	No		100% Vinyl
66 MAS619572	2	Beige non-fibrous mastic	No		100% Mastic
67 MAS619573	1	Grey non-fibrous ceramic tile	No		70% Aggregate 30% Other
68 MAS619574	1	Grey non-fibrous ceramic tile	No		70% Aggregate 30% Other
69 MAS619575	1	Grey non-fibrous ceramic tile	No		70% Aggregate 30% Other
70 MAS619576	1	White fibrous fiberglass panel	No		80% fibrous Glass 20% Other
70 MAS619576	2	Beige non-fibrous mastic	No		100% Mastic
71 MAS619577	1	White fibrous fiberglass panel	No		80% fibrous Glass 20% Other
71 MAS619577	2	Beige non-fibrous mastic	No		100% Mastic
72 MAS619578	1	White fibrous fiberglass panel	No		80% fibrous Glass 20% Other

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
72 MAS619578	2	Beige non-fibrous mastic	No		100% Mastic
73 MAS619579	1	Multi-color fibrous carpet	No		65% Synthetic 35% Other
73 MAS619579	2	Clear non-fibrous glue	No		100% Glue
74 MAS619580	1	Multi-color fibrous carpet	No		65% Synthetic 35% Other
74 MAS619580	2	Clear non-fibrous glue	No		100% Glue
75 MAS619581	1	Multi-color fibrous carpet	No		65% Synthetic 35% Other
75 MAS619581	2	Clear non-fibrous glue	No		100% Glue
76 MAS619582	1	Black fibrous roofing material	No		3% Cellulose 20% Aggregate 77% Bitumen
77 MAS619583	1	Black fibrous roofing material	No		3% Cellulose 20% Aggregate 77% Bitumen
78 MAS619584	1	White fibrous ceiling insulation	No		100% Cellulose
79 MAS619585	1	White fibrous ceiling insulation	No		100% Cellulose
80 MAS619586	1	White fibrous ceiling insulation	No		100% Cellulose
81 MAS619587	1	Tan non-fibrous paint	No		100% Other

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
81 MAS619587	2	White non-fibrous gypsum with brown paper	No		40% Cellulose 60% Gypsum
82 MAS619588	1	Tan non-fibrous paint	No		100% Other
82 MAS619588	2	White non-fibrous gypsum with brown paper	No		40% Cellulose 60% Gypsum
83 MAS619589	1	Tan non-fibrous paint	No		100% Other
83 MAS619589	2	White non-fibrous gypsum with brown paper	No		40% Cellulose 60% Gypsum
84 MAS619590	1	Dark grey non-fibrous CMU with orange paint	No		80% Aggregate 20% Other
85 MAS619591	1	Dark grey non-fibrous CMU with orange paint	No		80% Aggregate 20% Other
86 MAS619592	1	Dark grey non-fibrous CMU with orange paint	No		80% Aggregate 20% Other
87 MAS619593	1	Tan non-fibrous mastic	No		100% Mastic
88 MAS619594	1	Tan non-fibrous mastic	No		100% Mastic
89 MAS619595	1	Tan non-fibrous mastic	No		100% Mastic
90 MAS619596	1	Beige fibrous mastic	No		5% Wollastonite 95% Mastic
90 MAS619596	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
90 MAS619596	3	Black non-fibrous foam	No		100% Foam

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
91 MAS619597	1	Tan non-fibrous foam	No		100% Foam
92 MAS619598	1	Tan non-fibrous foam	No		100% Foam
93 MAS619599	1	White fibrous mastic	No		20% fibrous Glass 80% Mastic
93 MAS619599	2	Yellow fibrous glass insulation	No		100% fibrous Glass
94 MAS619600	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic
94 MAS619600	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
93 MAS619599	3	Tan non-fibrous foam	No		100% Foam
94 MAS619600	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic
94 MAS619600	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
94 MAS619600	3	Tan non-fibrous foam	No		100% Foam
95 MAS619601	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

Micro Analytical Services, Inc. 11301 Richmond Ave. Ste. K100B♦Houston♦Texas 77082♦Phone(281) 497-4500♦Fax(281) 497-4517

Polarized Light Microscopy Analysis

Phase Engineering, Inc.
5524 Cornish St.
Houston, Texas 77007

MAS Project #: 20206-00
Date Received: 11/17/2025
Date Analyzed: 11/18/2025

Project Name: 601 W. Lewis St. Conroe

Field ID/ Lab ID	Layer #	Sample Description	Asbestos Detected? (Yes/No)	Asbestos Constituents (%)	Non-Asbestos Constituents (%)
95 MAS619601	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
95 MAS619601	3	Tan non-fibrous foam	No		100% Foam
96 MAS619602	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic
96 MAS619602	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
96 MAS619602	3	Tan non-fibrous foam	No		100% Foam
97 MAS619603	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic
97 MAS619603	2	White fibrous paper with foil backing	No		10% fibrous Glass 45% Cellulose 45% Foil
97 MAS619603	3	Tan non-fibrous foam	No		100% Foam
98 MAS619604	1	White fibrous mastic	No		5% Wollastonite 15% fibrous Glass 80% Mastic
98 MAS619604	2	Tan non-fibrous foam	No		100% Foam

Samples have been analyzed by the EPA Interim Method 600/M4-82-020(40CFR Part 763 Appendix E to Subpart E) & EPA 600/R-93/116. The test results herein relate only to the sample submitted and analyzed. This report may only be reproduced in full with the approval of the Bulk Asbestos Laboratory of Micro Analytical Services (MAS). The above percentages are visual estimates of area percent. MAS is not responsible for any errors resulting from improper or incorrect sampling or shipping procedures. These samples will be retained for a period of 30 days. Accreditation by NVLAP in no way constitutes or implies product certification, approval, or endorsement by NIST. Some materials, especially floor tiles, contain asbestos fibers too thin to be detected by this method.
NVLAP Lab Code: 200618 TDSHS License: 30-0341

Analyzed by: Tony Dang

Approved NVLAP Signatory: Tony Dang

APPENDIX III

LICENSES AND CERTIFICATIONS

Texas Department of State Health Services

PHASE ENGINEERING INC

is certified to perform as an

Asbestos Consultant Agency

in the State of Texas and is hereby governed by the rights, privileges and responsibilities set forth in Texas Occupations Code, Chapter 1954 and Title 12, Texas Administrative Code, Chapter 295 relating to Texas Asbestos Health Protection, as long as this license is not suspended or revoked.

License Number: 100224

Expiration Date: 12/26/2025

Jennifer Shuford, MD, MPH,
Commissioner of Health

Control Number: 97616

(Void After Expiration Date)

VOID IF ALTERED NON-TRANSFERABLE

SEE BACK

TEXAS
Health and Human Services

Texas Department of State Health Services

Asbestos Individual Consultant

MATTHEW T WHITE

License Number: 105849

Control Number: 98494

Expiration Date: 27-Dec-2026



TEXAS
Health and Human Services

Texas Department of State Health Services

Asbestos Inspector

PARKER THOMAS LEMM

License Number: 604104

Control Number: 101202

Expiration Date: 23-May-2027



Texas Department of State Health Services

MICRO ANALYTICAL SERVICES INC

is certified to perform as an

Asbestos Laboratory

PCM, PLM

in the State of Texas and is hereby governed by the rights, privileges and responsibilities set forth in Texas Occupations Code, Chapter 1954 and Title 12, Texas Administrative Code, Chapter 295 relating to Texas Asbestos Health Protection, as long as this license is not suspended or revoked.

License Number: 300341

Expiration Date: 01/25/2026

Jennifer Shuford, MD, MPH,
Commissioner of Health

Control Number: 96774

(Void After Expiration Date)

VOID IF ALTERED NON-TRANSFERABLE

SEE BACK

APPENDIX IV

AGREEMENT FOR SERVICES

AGREEMENT FOR PROFESSIONAL ENVIRONMENTAL CONSULTING SERVICES

Section 1 – General Terms and Conditions

1.1 Definitions

"Agreement" means this Agreement for Professional Environmental Consulting Services.
"Party" (or collectively, "Parties") means Phase and Client, unless expressly stated otherwise in this Agreement.
"Phase" means Phase Engineering, LLC
"Engagement Letter" the instrument delivered by Phase to the Parties
"Services" has the meaning set forth in Section 1.2 below.
Any capitalized terms not otherwise defined in this Agreement have the meanings given to them under the Engagement Letter.

1.2 Services

The professional environmental consulting services to be provided by Phase for the Client are set forth in the Engagement Letter, and such services, including subsequent services, changed, altered or additional services are hereinafter called the "Services".

1.3 Standard of Care

Phase shall perform the services under this agreement with that degree of care, skill and diligence generally accepted as typical of the industry in the performance of such services as contemplated by the Agreement at the time and location such services are rendered. Phase shall employ only competent staff and sub-contractors who will be under the supervision of a senior member of Phase's staff.

1.4 Rights of Entry, Site Information and Utilities

The Client shall provide right of entry for Phase and its subcontractors to carry out the Services, unless specified otherwise in the Engagement Letter. The Client warrants that it has furnished to Phase all information known to, or in possession or control of, the Client relating to the past and existing conditions of the site, including but not limited to soil and geologic data, contaminants, wastes, petroleum products, controlled substances, hazardous materials, and subsurface utilities. The Client shall extend use and reliance of this information to Phase, unless stated otherwise and to the extent permitted by law. Such information shall be and remain confidential as between the Client and Phase and Phase shall not disclose same to any third party unless required by law.

1.5 Safety

1.5.1 Phase maintains a General Health and Safety Plan, a copy of which will be provided to the Client on written request and will fall under Section 1.8 Subsequent Changes of this Agreement unless this service is included in the Engagement Letter.

1.5.2 Phase shall take every precaution reasonable in the circumstances for the protection of the workers providing any of the Services. When required and prior to any field work being carried out, Phase shall provide the Client with a comprehensive site-specific safety plan for providing the Services. Such request must be made in writing by the Client prior to commencement of the Services by Phase and will fall under Section 1.9 Subsequent Changes of this Agreement unless included in the Engagement Letter.

1.6 Investigations and Reports

1.6.1 Findings: The findings of any investigation undertaken as part of the Services will be based upon information generated as a result of the specific scope of the Services as described in the Engagement Letter.

1.6.2 Restoration: The Client accepts that in the normal course of the Services some damage to existing ground or other surface finishes may occur, the restoration of which shall be the responsibility of the client or as specified in the Engagement Letter.

1.6.3 Investigations: The parties acknowledge and accept that unique risks exist whenever engineering or related disciplines are applied to identify environmental conditions and even a comprehensive sampling and testing program may fail to detect certain conditions. Because of the inherent uncertainties in environmental evaluations, changed or unanticipated conditions may occur or become known subsequent to Phase's investigation that could affect conclusions, recommendations, total Project cost and/or execution. Changes in conditions are subject to amendments to the Scope of Services.

1.6.4 Confidentiality and Reliance: Any Final Report or draft reports and the information contained therein shall be treated as confidential and, unless otherwise agreed to by Phase and the Client, the information, sampling data, analysis, findings, conclusions and recommendations (if any), may be used and relied upon only by the Client, its officers, directors and employees and professional advisors in the performance of their obligations for or on behalf of the Client. Any such use and reliance shall be subject to the limitations set forth in this agreement. In addition, the Client may submit any report to a regulatory authority or lender for the purpose of obtaining financing on a property.

1.6.5 Third Party Reliance: This Agreement and the Services provided are for Consultant and Client's sole benefit and exclusive use with no third party beneficiaries intended. Reliance upon the Services and any work product is limited to Client, and is not intended for third parties. In the event Phase agrees, in its sole and absolute discretion, to make the Report available to a third party not mentioned in Paragraph 1.6.4, the Third Party shall be required to obtain the original Clients release, sign Phase's standard Authorized User Agreement (AUA) and pay Phase a fee of not less than $350.00. Any such use shall be subject to the terms, conditions and limitations set forth in this Agreement, the Report and the AUA.

1.7 Ownership of Records/Reports:

All documents or records created or prepared by Phase in the performance of the Services are considered Phase's professional work product and shall remain the copyright property of Phase, subject to any reasonable disclosure request from the Client as may be necessary and for which reasonable reimbursement for copies is provided.

1.8 Disposal and Samples

1.8.1 Disposal of all wastes generated from the subject property shall be the responsibility of the Client.

1.8.2 Phase shall be responsible for appropriate disposal of sample material and sample residuals after 30 days following submission of the FinalReport unless the Client specifically requests otherwise.

1.9 Subsequent Changes
With the consent of Phase, the Client may in writing at any time after the execution of this Agreement or the commencement of the Services delete, extend, increase, vary or otherwise alter the Services. The Parties further agree that such changes shall alter the Services, schedule and/or the costs. Any such changes shall be made in writing with reference to this Agreement, and accepted in writing by both Parties.

1.10 Delays
Neither Party shall be liable or penalized for delays or failure to perform its Services if the same is caused directly or indirectly by circumstances beyond a Party's reasonable control. The Client shall not hold Phase responsible for damages or delays in performance caused by the Client, acts of God, acts and/or omissions of governmental authorities and regulatory agencies or other events which are beyond the reasonable control of the Parties.

1.11 Payment
1.11.1 Phase shall invoice the Client in accordance with the provisions set forth in the Engagement Letter. Except as stated in the Engagement Letter, the Client shall pay to Phase at its corporate office each invoice within 30 days of the date of the invoice without holdback. Interest at a rate of 10% per year or the maximum rate allowed by law, whichever is lower, may be charged on all overdue amounts.
1.11.2 In the event of a disputed billing, only the disputed portion will be withheld from payment, and the undisputed portion will be paid. The Client shall exercise reasonableness in disputing any bill or portion thereof. No interest will accrue on any disputed portion of the billing until mutually resolved.
1.11.3 If the Client fails to make payment of any sum due hereunder within a reasonable time period, Client acknowledges and agrees that the subject Invoice will be referred to legal collections, and any amount in aggregate less than Ten Thousand Dollars U.S. ($10,000) will be referred to small claims court in Harris County, Texas.

1.12 Suspension or Termination
The Client may at any time by notice in writing to Phase, suspend or terminate the Services or any portion thereof at any stage of the Project. Upon receipt of such written notice by the Client, Phase shall perform no further Services other than those reasonably necessary to close out its Services. In such an event, Phase shall invoice the Client for the portion of the Services completed and shall be entitled to payment in accordance with Section 1.9. Once the Services are completed the Client assumes the risk of Frustration of Purpose.

1.13 Insurance
1.13.1 Phase agrees to carry and maintain the following **minimum** insurance coverages for the term of this Agreement:
Worker's Compensation Insurance: Statutory requirement amounts
Commercial General Liability: $1,000,000 per occurrence
Automobile Liability Insurance: $1,000,000 per occurrence for both owned and non-owned vehicles
Umbrella Liability (including Professional Liability and Contractors Professional Insurance): $10,000,000 aggregate

1.13.2 Phase's current Certificate of Insurance is provided with the Engagement Letter. If the Client requests to be a named as a certificate holder,
this request must be made in writing to Phase prior to commencement of the Services.
1.13.3 Phase will renew the Professional Liability Insurance at or above the minimum coverage for period of two (2) years after completion of the Services.
1.13.4 If the Client requests that Phase increase the amount of insurance coverage or obtain other special insurance for the Project, Phase shall endeavor forthwith to obtain such increased or special insurance at the Client's expense.
1.13.5 Each of Phase and Client waive all claims, losses, damages and rights of recovery against the other to extent of the limits of coverage under any commercial general liability or property insurance policy actually obtained by a Party to this Agreement (or, in the case of Phase, to the extent obtained or required to be obtained by Phase under this Agreement). In addition, each Party shall exercise commercially reasonable efforts to cause to waive subrogation under its commercial general liability and property insurance policies and provide any necessary endorsements thereto.

1.14 Indemnity/Statute of Limitations.
EACH OF Phase AND CLIENT SHALL INDEMNIFY AND HOLD HARMLESS THE OTHER AND THEIR RESPECTIVE AGENTS, EMPLOYEES, SUCCESSORS AND ASSIGNS FROM AND AGAINST LEGAL LIABILITY FOR CLAIMS, LOSSES, DAMAGES, AND EXPENSES TO THE EXTENT SUCH CLAIMS, LOSSES, DAMAGES, OR EXPENSES ARE LEGALLY DETERMINED TO BE CAUSED BY THEIR NEGLIGENT ACTS, ERRORS, OR OMISSIONS. IN THE EVENT SUCH CLAIMS, LOSSES, DAMAGES, OR EXPENSES ARE LEGALLY DETERMINED TO BE CAUSED BY THE JOINT OR CONCURRENT NEGLIGENCE OF Phase AND CLIENT, THE PARTIES SHALL BEAR LIABILITY IN PROPORTION TO ITS OWN NEGLIGENCE UNDER COMPARATIVE FAULT PRINCIPLES. NEITHER PARTY SHALL HAVE A DUTY TO DEFEND THE OTHER PARTY, AND NO DUTY TO DEFEND IS HEREBY CREATED BY THIS INDEMNITY PROVISION AND SUCH DUTY IS EXPLICITLY WAIVED UNDER THIS AGREEMENT. CAUSES OF ACTION ARISING OUT OF Phase's SERVICES OR THIS AGREEMENT, REGARDLESS OF CAUSE OR THE THEORY OF LIABILITY, INCLUDING NEGLIGENCE, INDEMNITY OR OTHER RECOVERY, SHALL BE DEEMED TO HAVE ACCRUED AND THE APPLICABLE STATUTE OF LIMITATIONS SHALL COMMENCE TO RUN NO LATER THAN THE DATE OF Phase's SUBSTANTIAL COMPLETION OF SERVICES ON THE PROJECT.

1.15 Limitation of Liability.
1.15.1 Notwithstanding any other provisions contained herein, it is understood and agreed that Phase's liability to the Client for all claims arising out of this Agreement, or in any way relating to the Services, will be limited to direct damages and/or to the specific performance of any Services not meeting the Standard of Care set forth herein and such liability will, in the aggregate, not exceed the sum of the coverages shown on Phase's Certificate of Insurance in effect at the time of the claim.
1.15.2 No claim may be brought against Phase more than Two (2) years after the Services were completed under this Agreement, or as negotiated between Phase and the Client.

1.15.3. **TO THE FULLEST EXTENT PERMITTED BY LAW, THE TOTAL AGGREGATE LIABILITY OF Phase (AND ITS DIRECTORS, EMPLOYEES, AGENTS AND AFFILIATES) TO CLIENT AND THIRD PARTIES GRANTED RELIANCE IS LIMITED TO THE GREATER OF $50,000 OR Phase's FEE FOR ANY AND ALL INJURIES, DAMAGES, CLAIMS, LOSSES, OR EXPENSES (INCLUDING ATTORNEYAND EXPERT FEES) ARISING OUT OF Phase's SERVICES OR THIS AGREEMENT. THIS LIMITATION SHALL APPLY REGARDLESS OF AVAILABLE PROFESSIONAL LIABILITY INSURANCE COVERAGE, CAUSE OR THE THEORY OF LIABILITY, INCLUDING NEGLIGENCE, INDEMNITY, OR OTHER RECOVERY; PROVIDED, HOWEVER, THAT THIS LIMITATION SHALL NOT APPLY TO THE EXTENT OF ANY AVAILABLE COVERAGE UNDER Phase's COMMERCIAL GENERAL LIABILITY POLICY.**

1.16 Consequential Damages.
EXCEPT AS EXPRESSLY PROVIDED IN THIS AGREEMENT, NEITHER PARTY SHALL BE LIABLE TO THE OTHER FOR LOSS OF PROFITS OR REVENUE, LOSS OF USE OR OPPORTUNITY, LOSS OF GOOD WILL, COST OF SUBSTITUTE FACILITIES, GOODS, OR SERVICES, COST OF CAPITAL, OR FOR ANY SPECIAL, CONSEQUENTIAL, INDIRECT, PUNITIVE, OR EXEMPLARY DAMAGES.

1.17 Regulatory Reporting Requirements
Client recognizes that hazardous substances or contaminates may be discovered at the subject property in the course of provision of the Services by Phase under conditions that may be reportable to Federal or State environmental regulatory agencies. The "duty to report" is ultimately the responsibility of the landowner unless the condition represents an acute threat to human health or the environment. Phase will notify the Client of any such reportable condition. The Client will notify the Landowner, or under mutual agreement, authorize Phase to perform such notification to the landowner.

Section 2 – MISCELLANEOUS PROVISIONS

2.1 Notices:
All notices under this Agreement shall be in writing. It shall be sufficient in all respects if the Notice is delivered by hand, sent by any electronic means, including email or facsimile transmission, with confirmation ("Transmission") during normal business hours, or sent by registered mail, postage prepaid, addressed to the Parties shown on the Engagement Letter or to such other address as either Party shall designate by written notice to the other Party. Any notice so given shall be deemed to have been given and to have been received on the day of delivery, if so delivered, on the third Business Day (excluding each day during which there exists any interruption of postal services due to strike, lockout or other cause) following the mailing thereof, if so mailed, and on the day that notice was sent by Transmission, provided such day is a Business Day (a Business Day being any day of the week save and except for Saturday and Sunday) and if not, on the first Business Day thereafter.

2.2 Entire Agreement, Modifications, Headings, Severability:
The Parties acknowledge that this Agreement and the Engagement Letter constitutes the entire agreement between them and supersedes all prior representations, warranties, agreements, and understandings, oral or written, between the Parties with respect to its subject matter. Unless stated otherwise in this Agreement, this Agreement may not be modified except in writing signed by both Parties. The headings to this Agreement are for convenience and reference purposes only and shall not constitute a part of the Agreement. If any element of this Agreement is later held to violate the law or a regulation, it shall be deemed void, and all remaining provisions shall continue in force.

2.3 Effect:
This Agreement shall be binding upon and inure to the benefit of the Parties hereto and their respective successors and assigns provided that it may not be assigned by either Party without the consent of the other, which consent shall not be unreasonably withheld.

2.4 Survival:
All representations and obligations (including without limitation the mutual obligations of indemnification) shall survive the termination of this Agreement and expire five (5) years from the date of completion of Services.

2.5 Waiver of Rights:
Any waiver of, or consent to depart from, the requirements of any provision of this Agreement shall be effective only if made in writing and signed by the Party granting such waiver or consent, and is valid only in the specific instance and for the specific purpose for which it has been granted. No failure on the part of any Party to exercise, and no delay in exercising, any right under this Agreement shall operate as a waiver of such right. No single or partial exercise of any such right shall preclude any other or further exercise of such right or the exercise of any other right.

2.6 Applicable Law:
This Agreement shall be governed by, and interpreted and enforced in accordance with, the laws in the State of Texas and the laws of The United States of America, as applicable.

2.7 Dispute Resolution:
Excepting Section 1.11 for the purpose of this Agreement, any disagreement arising between the Parties to this Agreement with reference to the interpretation of this Agreement or any matter arising hereunder and upon which the Parties cannot agree shall be referred to mediation. Reference to mediation shall be to a single mediator and in accordance with the laws of mediation in the State of Texas. The costs of the mediator shall be shared equally by the Parties on an interim basis as may be necessary provided however that the mediator shall have the discretion to award costs of the proceeding, including costs of the mediator. The venue for such mediation is agreed to be Harris County, Texas

2.8 Contract Documents:
The Contract Documents consist of the documents listed. If there is a conflict with the Contract Documents, the conflicting terms will be governed in the order of priority set forth as follows: 1. Agreement 2. Engagement Letter

PHASE ENGINEERING

Lead Based Paint Inspection

Vacant Two-Story Historic School and Two Metallic Buildings

Proposed Repurpose to a Residential Loft Use

601 W. Lewis Street, Conroe, Montgomery County, TX 77301

November 26, 28, 29, 30, and
December 2, 2025

PE Project No.: 202511026

Prepared for:

Overland Property Group
ATTN: Ms. April Engstrom
5341 W. 151st Terrace
Leawood, KS 66224

Prepared by:

Phase Engineering, LLC
5524 Cornish Street
Houston, Texas 77007

December 5, 2025

Overland Property Group
ATTN: Ms. April Engstrom
Development Associate
5341 W. 151st Terrace
Leawood, KS 66224
phone: 785-212-0810 email: aengstrom@overlandpg.com

RE: 202511026

Dear Ms. Engstrom:

Phase Engineering, LLC (PELLC) has conducted a lead-based paint (LBP) inspection following HUD guidelines of the vacant two-story former Sam Houston Elementary School building, with the attached cafeteria and classroom Annex, as well as two metallic buildings, one being a multi-purpose/Gymnasium and a mechanical building for the chiller unit, located at 601 N. Lewis Street, Conroe, Montgomery County, Texas 77301. The lead paint inspection was conducted by using a XRF spectrum analyzer for non-destructive testing (NDT) of accessible painted surfaces that include assays that are representative of the building materials.

The LBP inspection was conducted on November 26, 28, 29, 30, and December 2, 2025 by Thomas A. Bazan, Texas Department State Health Services (TDSHS) Licensed Risk Assessor # 2070001. The LBP paint inspection has been conducted on building materials, and does not include potential lead contaminated dust or lead contaminated soil as described in the definition of lead based paint hazard in Title X, CFR Vol. 61 No. 169 Subpart L 745.233 or the Texas Environmental Lead Reduction Rules 295.202. No water or air samples were taken as part of this evaluation. This lead-based paint inspection is in accordance with the updated TDSHS Texas Environmental Lead Reduction Rules (TELRR) and the Residential Lead Based Paint Reduction Act (Title X) because this facility is already or is going to be child occupied or used for private housing, public housing, federally owned housing or housing receiving federal assistance according to the Environmental Protection Agency (EPA), U.S. Department of Housing and Urban Development (HUD) and TDSHS rules and regulations.

The inspector's first step was a visual examination (ASTM E2255M-22) of the property to be tested. The date of construction of the 35,925 square foot school building was reported to be in 1937, with the Annex addition of the 29,661 square feet, built in 1993. A 4,228 square foot multi-purpose/gymnasium building has an unknown date of construction, and the metallic building that supports the chiller unit also was constructed at an unknown time. The exterior walls are brick with decorative stone. The construction and painting history of all the rooms was found to be similar; therefore the architectural components of the subject property could be grouped together for sampling purposes. The second edition of the *HUD Guidelines for the Evaluation and Control of Lead-Based Hazards in Housing (July 2012) was not needed as*, the inspector determined that the former school structure was older, and had not yet been gutted, although remodeled over the years.

The client representative was not present at the start for the field sampling of the facility, and the maintenance supervisor provided the access key in a lock box.

The building components identified for the LBP inspection are described in the following Summary Report. Floor plans were provided for the school and annex but not for the multi-purpose/gymnasium building. The inspector conducted an inventory of all potential lead-contaminated paint surfaces on the building exterior as well as within the structures which were to be tested with an EPA certified and factory calibrated XRF spectrum analyzer, and in observance of ASTM E2120-10 (2016) even though it was withdrawn in 2025 with no replacement. The substrates were identified as painted plaster, concrete, CMU, brick, ceramic tile, drywall, wood (including hardboard), and metal. The components were identified as 1) interior doors, door jambs, or casings, 2) window frames, sashes, and sills or stools, 3) interior walls, wainscots and ceilings, 4) painted wood or other baseboard, chair rails, crown molding, and trim, 5) wooden and painted concrete floors, 6) painted wood cabinets or shelves, 7) painted chalkboards and surfaces, 8) exterior doors and jambs, 9) exterior window frames, and trim, 10) exterior painted common area components, 11) metal components, and, 12) miscellaneous.

The inspector removed the XRF instrument from the hard-shell carry case, and the shielded storage pouch. The unit was examined for any exterior damage, the battery pack was inserted, and the snout was wiped with a 99% isopropyl alcohol wipe prior to performing the XRF manufacturer's recommended warm up and quality control procedures successfully. Then the inspector took calibration check readings on a test pad of a N.I.S.T. certified concentration of lead that was provided by the instrument manufacturer. The calibration checks were within the prescribed instrument range, indicating that the XRF instrument was in calibration and that XRF testing could begin. The instrument was checked for calibration prior to being turned off after the morning testing, prior to the afternoon testing, and after completion of each day of testing. The school building was not heated, and the ambient air temperature at the time of testing was noted so as to document that the instrument was operating within the manufacturers specifications.

The architectural components inspected were recorded on the Viken (f/k/a Heuresis) Detection Corp. Pb200e, s/n 1013 instrument as to room equivalent, room description, substrate, component, color, condition, and location. Side A was the side first encountered as the room was entered, and Sides B, C, and D were lettered in a clockwise direction. The Viken Detection Pb200e recorded the lead content in mg/cm of each reading (assay) and the calculated result as either Positive (POS), Negative (NEG), or Incomplete (Null). Incomplete readings occur when the instrument is unintentionally moved prior to completion of a reading.

Although Phase Engineering, LLC uses trained and competent certified/licensed inspectors in attempting to locate and identify surfaces potentially containing lead based paint, Phase Engineering, LLC does not warrant that all surfaces containing lead based paint will be identified. It is possible that there are surfaces containing lead based paint that were not found because they were not visible or accessible to the inspector, or for various other reasons, were not sampled. The XRF measurements contained within are accurate to the best of our knowledge.

Lead Based Paint Project Summary	
Site Elements	
Subject Property Address	601 W. Lewis Street, Conroe, Montgomery County, TX 77301
Number of Buildings & Square Footage	Three +1 of Eleven; 35,925 SF / 29,661 SF / 4,228 SF (per MCAD PID: 53085)
Date(s) of Construction	2-story school building 1937, two additional buildings. in 1993 and Unknown
Site Location Contact & Relationship to Subject Property	Ms. April Engstrom, Overland Property Group, cell: 785-212-0810
Date of Inspection	November 26, 28, 29, 30 & December 2, 2025
Purpose of Inspection	Renovation, Repurpose
Instrument Manufacturer	Viken (f/k/a Heuresis) Detection Corp.
Instrument Model	Pb200e Spectrum Analyzer Serial Number: 1013
Mode of Operation	Lead-Based Paint
Radio Active Source	5 mCi Co57
Building Plans and/or Prior Lead Reports Provided	No prior LBP report – building floor plans provided.
Known Areas Not Available for Access	Did not climb onto all roofs
Inspector(s) Names and License #	Thomas Bazan 2070001
Company License Name and #	Phase Engineering, LLC 2110073
Total XRF Readings Including Calibration Readings	1,334
Total XRF LBP Positive Readings	8 plus 1 Roof vent jack; and caution for lead-in-glazing of 5 ceramic baseboard tiles
Total XRF LBP Interior Positive Readings	4 (All associated with the School building), plus 1 lead roof jack & 5 Ceramic tiles.
Total XRF LBP Exterior Positive Readings	4 plus 1 lead roof jack
Total XRF LBP Negative Readings	1,290 (No LBP detected with Annex, on metallic mechanical building or Gymnasium)
Paint Chip Analysis	A sufficient number of assays were taken on both the interior and exterior of the structural components of the building, therefore, no paint chips were collected for analysis
Total Lead Chip Samples Taken	N/A
Total Lead Chip Positive Samples & Components	N/A
Total Lead Chip Negative Samples	N/A

Site Specific Details:

- The vacant two-story brick building was used as an elementary school until the Conroe ISD ceased operations, and eventually sold the site to the City of Conroe, Texas to repurpose. The City decided to sell the property in 2025.
- The larger structure is a 2-story, brick and a block building that is reported to have been constructed in 1937, and is approximately 35,925 square feet of Gross Building Area, plus a 2-story Annex building with an elevator that is approximately 29,661 square feet with the cafeteria occupying the ground floor and support offices on the second floor. Both structures are irregular- shaped buildings with a flat, built-up roof and are scheduled for renovation and repurposing.
- The multi-purpose/gymnasium building is steel-framed with CMU walls with an unknown date of construction. It has a flat roof and an overhead door. The smaller metallic building is a rectangular-shaped structure with a pitched, metal roof and is the mechanical support building for the chiller unit.
- This vacant historic property has a few architectural components covered with LBP that is in intact-to-poor condition and the interior is scheduled for major renovation.
- The contractor(s) must comply with O.S.H.A. rules, and the waste stream should be segregated into separate piles of debris; painted aggregate (plaster, concrete, and CMU), painted drywall, painted metal, and painted wood. Each pile of debris shall be T-CLP tested to determine the lead level for waste disposal.
- There will need to be clearance testing completed after the conversion to a residential use. It is absolutely critical that lead-contaminated dust be contained as the EPA standards will be lowered, effective January 12, 2026 to any detectable level, with the clearance threshold lowered from the current 10 µg/ft ^{2} on floors down to 5 µg/ft ^{2}.
- The site is partially fenced with 6-foot chain-link fencing. There is asphalt paving that is used for off-street parking on the north, south, and west sides of the structures.
- Roof access was by way of a ladder. The inspector did get on the school and auditorium roofs but not the roof for the Annex or the multi-purpose/gymnasium.
- The plumbing may be 88-years-old, or more, and it is highly probable that lead pipe was used for service lines in the City of Conroe, Texas in 1937, consistent with common practices of the era across the United States. According to the 2024 Water Quality Report for Conroe, the City has cured the main potable water service lines, but it is unknown if the underground lines at the site are lead pipe. The owner should plan on a total replacement of all water lines as part of any renovation. Much of the original wiring has been upgraded by the school.

https://www.cityofconroe.org/news_detail_T22_R44.php

https://cms3.revize.com/revize/conroetx/2024%20Water%20Quality%20Report-English.pdf

Findings:

There were 1,227 readings taken, including calibration readings for the structures. Of the 1,203 suspect lead-based paint surfaces tested for the buildings, the positive lead-based paint readings were all associated with the original 3-story school building. All of the exterior common area, canopies, illuminated sign, and parking lot readings were evaluated as negative (<1.0 mg/cm2). The two metallic classroom buildings are also free of lead-based paint.

Based on the data collected and evaluated at, or subsequent to, the field inspection: Lead Based Paint exists on the following surfaces:

- Exterior – Original Irving Elementary School Building, the painted metal downspout boots, metal brick plates and the painted wood ceilings and crown molding of the porticos.

- Interior - Original Irving Elementary School Building, the painted wooden and plaster baseboards, painted wooden door jambs, chair rails, crown molding, trim, chalkboards and chalkboard surfaces, closet shelves, as well as most painted plaster wainscots

Table 1

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)
91 / 12	Exterior	SW Exit Door	Metal	Brick Plate	Brown	Poor	West	**3.7**
94 / 15	Exterior	Double Exit	Metal	Brick Plate	Brown	Poor	South	**1.2**
155 / 76	Exterior	Original School Exit	Metal	Brick Plate	Brown	Poor	East	**3.6**
160 / 81	Exterior	Exit Doors East of Aud.	Metal	Brick Plate	Brown	Fair	South	**1.6**
68 / 65	38	Library-Above Shelves	Plaster	Wall	Beige	Intact	Wall "B" West	**1.0**
241/235	64	Girl's Restroom - Window	Wood	Right Frame	Ivory	Intact	Wall "B" East	**1.0**
298/292	71	E. Entry Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" South	**14.0**
353/347	77	Boys' Restroom Windows	Wood	Frame	Ivory	Fair	Wall "C" South	**1.1**
163/160	82-B	Principal's Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" East	**14.4**
184/181	83	Asst. P. Shower / Closet	Ceramic Tile	Threshold	Black	Intact	Floor - West	**16.0**
192/189	83	Asst. P. Shower Wainscot	Ceramic Tile	Top Trim	Black	Intact	Wall "A" West	**21.7**
281/275	90-A	Clinic Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" West	**14.6**
324/318	94	Boys' Restroom Windows	Wood	Frame	Ivory	Fair	Wall "C" West	**1.2**
337/331	Exterior	School Roof	Metal	Vent Jack	Bare	-	South	**55/Caution**

As a caution, some painted surfaces may contain levels of lead below the federal abatement level of <1.0 mg/cm^2, which could create lead dust or lead-contaminated soil hazards if the paint is turned into dust by abrasion, scraping, or sanding.

For more detailed information see Attachment 1: XRF Readings, Attachment 2: Site Plan and Floor Plan Drawings, and Attachment 3: Licenses / Certifications.

RECOMMENDATIONS:

Any construction or maintenance activity associated with the vacant building identified above is subject to O.S.H.S.A. regulations. Please review the Occupational Safety and Health Administration (OSHA) regulations found in 29 CFR, Part 1926.62, known as the OSHA Lead Exposure in Construction Industry Standard.

During any partial demolition, debris should be segregated between painted metal, painted wood and drywall, and painted brick, stucco, and aggregate materials.

Painted older components should be presumed to be covered with some lead-contaminated paint and along with other lead-contaminated building materials, should be either remediated or analyzed for Toxicity Characteristics Leaching Procedure (TCLP) by any demolition contractor before disposal that is compliant with the T.C.E.Q.

Any metal, such as structural steel, plumbing, and the miscellaneous metal, can be sold as salvage scrap for recycling to any scrap dealer.

As an additional caution, the lead-contaminated surfaces should not be power washed without containment of the run-off.

Noting that this may be a historical property, the windows and other components that could be restored should be taken off-site and properly deleaded if necessary. Many of the windows have anodized metal frames.

The 2nd floor Library walls and various painted window frames can be deleaded. The plaster walls may also be encapsulated or properly encased if allowed. The painted metal brick ledge components not removed can be deleaded or properly encapsulated if allowed.

There are ceramic tiles on floors and wainscots in the restrooms. There are detectable levels of lead in the glazing, and the tiles should not be mechanically abraded, etched, or pulverized during any future repair or remodeling activity. Soft scrubs are advised for cleaning these tiles.

The contractor's O.S.H.A. competent person must decide the level of engineering controls, and worker personal protection equipment (ppe), depending on the activity that will create air-borne dust.

The contractor is deemed the generator of any lead-contaminated waste stream, and should dispose of debris in an appropriate level land fill.

A visual assessment is all that would be required for the exterior of the building after any exterior remediation activities are complete.

After the interior demolition activities, it is recommended that there be a special cleaning, following the HUD Guidelines before the attempt at clearance.

Please be advised that the EPA has lowered the clearance levels, effective January 12, 2026. Please see the provided links below concerning lead based paint controls and maintenance.

New dust-lead action levels

Location	**Old Standard**	**New Standard (effective Jan. 12, 2026)**
Floors	10 µg/ft²	5 µg/ft²
Interior Windowsills	100 µg/ft²	40 µg/ft²

SPECIAL CLEANING FOLLOWING LEAD HAZARD CONTROL ACTIVITIES

After any lead hazard control activities have been completed, the treated area of the structure must be inspected and properly cleaned following HUD specified cleaning protocols, as detailed in the Guidelines for the Evaluation and Control of LBP Hazards in Housing (Second Edition - July 2012), published by the U.S. Department of Housing and Urban Development. Some of the required steps include removing large debris and paint chips followed by HEPA vacuuming of all horizontal surfaces (floors, windowsills, troughs, etc.). The cleaning protocols described in this publication guide the contractor in doing a proper cleaning and improving the chances of passing clearance inspections after remediation.

If the interior of the historic structure is remediated with an encapsulant or encasement, the historic property may be subject to the EPA Renovation and Repair Rule for future repair activities.

The de minimus areas (40 CFR 93 § 153 defines de minimis levels, that is, the minimum threshold for which a conformity determination must be performed, for various criteria pollutants in various areas) are slightly larger under the EPA Renovation and Repair Rule than the LBP guidelines. Any deteriorated paint

film surfaces can be stabilized, in areas below the de minimus levels, and a liquid deglosser used to prepare these surfaces for painting.

(1) Minor repair and maintenance exception changes to < 6 ft2 per room for interiors, 20 ft2 for exteriors. To qualify, the project cannot involve the use of high dust generating (prohibited) practices or window replacement.

(2) Emergency renovations specifically include interim controls performed in response to an elevated blood lead level in a child.

(3) Persons performing renovations for compensation in pre-1978 housing may use either Protect Your Family or Renovate Right to comply with the existing requirement to provide a lead hazard information pamphlet to the owners and occupants of target (pre-1978) housing before beginning renovations.

§ 745.65 Lead-based paint hazards. (Currently Promulgated)

(b) *Dust-lead hazard.* A dust-lead hazard is surface dust in a residential dwelling or child-occupied facility that contains a mass-per-area concentration of lead equal to or exceeding 10 µg/ft ^{2} on floors or 100 µg/ft ^{2} on interior window sills based on wipe samples.

http://portal.hud.gov/hudportal/HUD?src=/program_offices/healthy_homes/trai ning/rrp/rrp

Please review the Occupational Safety and Health Administration (OSHA) regulations found in 29 CFR, Part 1926.62, known as the OSHA Lead Exposure in Construction Industry Standard.

Links to HUD Lead-Based Paint Information:

https://portal.hud.gov/hudportal/HUD?src=/program_offices/healthy_homes/lb p/hudguidelines

Chapter 11: Interim Controls

https://portal.hud.gov/hudportal/documents/huddoc?id=lbph-13.pdf

Chapter 6: Ongoing Lead-Safe Maintenance

https://portal.hud.gov/hudportal/documents/huddoc?id=lbph-08.pdf

Chapter 18: Historic preservation

http://www.hud.gov/offices/lead/lbp/hudguidelines/Ch18.pdf

Link to EPA Clearance Standards:

https://www.federalregister.gov/documents/2019/07/09/2019-14024/review-of-the-dust-lead-hazard-standards-and-the-definition-of-lead-based-paint

Please review the Occupational Safety and Health Administration (OSHA) regulations found in 29 CFR, Part 1926.62, known as the OSHA Lead Exposure in Construction Industry Standard.

Links to HUD Lead-Based Paint Information:

https://portal.hud.gov/hudportal/HUD?src=/program_offices/healthy_homes/lb p/hudguidelines

A summary report is attached in the body of this report. As per the second edition (July 2012) of the *HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing*, "a copy of this summary must be provided to new lessees (tenants) and purchasers of this property under Federal law (24CFR part 35 and 40 CFR part 745) before they become obligated under a lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to new tenants. Landlords (lessors) and sellers are also required to distribute an educational pamphlet approved by the U.S. Environmental Protection Agency and include standard warning language in their leases or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards."

If additional suspect lead paint or dust hazards should be found during any renovation or demolition, these materials should be sampled for lead and handled appropriately following all local, state and federal rules and regulations at that time.

The client agreed to Scope of Work, a sequential XRF reading report, Site Plan, Licenses and Certifications are attached to this letter.



Thomas A. Bazan CRS, CEI

Risk Assessor

TDSHS #: 2070001

A summary report is attached in the body of this report. As per the second edition (July 2012) of the *HUD Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing*, “a copy of this summary must be provided to new lessees (tenants) and purchasers of this property under Federal law (24CFR part 35 and 40 CFR part 745) before they become obligated under a lease or sales contract. The complete report must also be provided to new purchasers and it must be made available to new tenants. Landlords (lessors) and sellers are also required to distribute an educational pamphlet approved by the U.S. Environmental Protection Agency and include standard warning language in their leases or sales contracts to ensure that parents have the information they need to protect their children from lead-based paint hazards.”

If additional suspect lead paint or dust hazards should be found during any renovation or demolition, these materials should be sampled for lead and handled appropriately following all local, state and federal rules and regulations at that time.

The client agreed to Scope of Work, a sequential XRF reading report, Site Plan, Licenses and Certifications are attached to this letter.



Thomas A. Bazan CRS, CEI

Risk Assessor

TDSHS #: 2070001

Attachment 1: XRF Sequential Readings

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		Mechanical Building								
4 / 1	Exterior	Mechanical Building	Metal	Left Door	Ivory	Poor	East	0.0	Auto	**Negative**
5 / 2	Exterior	Mechanical Building	Metal	Louvers	Ivory	Poor	East	0.3	Auto	**Negative**
6 / 3	Exterior	Mechanical Building	Metal	Left Door Jamb	Ivory	Poor	East	0.0	Auto	**Negative**
7 / 4	Exterior	Mechanical Building	Metal	Siding	Ivory	Fair	East	0.0	Auto	**Negative**
8 / 5	Exterior	Conduit Raceway	Metal	Side	Ivory	Poor	East	0.1	Auto	**Negative**
9 / 6	Exterior	Mechanical Building	Metal	Fascia	Charcoal	Poor	East	0.2	Auto	**Negative**
10 / 7	Exterior	Gutters	Metal	Channel	Charcoal	Poor	South	0.1	Auto	**Negative**
11 / 8	Interior	Doorway	Metal	Right Door	Charcoal	Fair	Wall "A" East	0.0	Auto	**Negative**
12 / 9	Interior	Structural	Metal	Vertical C- Beam	Red	Fair	Wall "A" East	0.0	Auto	**Negative**
13 / 10	Interior	Structural	Metal	Vertical I-Beam	Red	Fair	Wall "B" South	0.1	Auto	**Negative**
14 / 11	Interior	Structural	Metal	Siding	Ivory	Intact	Wall "B" South	0.1	Auto	**Negative**
15 / 12	Interior	Power Panel Board	Wood	Mounting Board	Gray	Fair	Wall "C" West	0.1	Auto	**Negative**
16 / 13	Interior	Main Disconnect	Metal	Cover	Gray	Poor	Wall "C" West	0.2	Auto	**Negative**
17 / 14	Interior	Pump Pedestal	Metal	Frame	Black	Poor	NW Corner	0.4	Auto	**Negative**
18 / 15	Interior	Boiler #1	Metal	Side	Green	Fair	East Side	0.1	Auto	**Negative**
19 / 16	Interior	Boiler #2	Metal	Side	Gray	Fair	East Side	0.1	Auto	**Negative**
20 / 17	Interior	Vertical Vessel	Metal	Side	Red	Fair	West Side	0.0	Auto	**Negative**
21 / 18	Interior	Support Post	Metal	Post	Gray	Poor	West Center	0.1	Auto	**Negative**
22 / 19	Exterior	Standby Generator	Metal	Side	Green	Poor	North	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
23 / 20	Exterior	Chiller Vent	Metal	Side	Beige	Fair	North	0.1	Auto	Negative
24 / 21	Exterior	Chiller	Metal	Frame	Beige	Intact	North	0.1	Auto	Negative
25 / 22	Exterior	Mechanical Building	Metal	Louver Vent	Beige	Fair	South	0.1	Auto	Negative
26 / 23	Exterior	Gutters	Metal	Downpipe	Beige	Fair	South	0.0	Auto	Negative
27 / 24	Exterior	Fencing / Gate	Metal	Post	Silver	Poor	East	0.5	Auto	Negative
28 / 25	Exterior	Platform	Metal	Post	Brown	Fair	South	0.1	Auto	Negative
29 / 26	Exterior	Railing	Metal	Rail Cap	Brown	Poor	South	0.0	Auto	Negative
30 / 27	Exterior	Steps	Metal	Handrail	Silver	Poor	West	0.2	Auto	Negative
31 / 28	Exterior	Corner Building	Metal	Junction Box	Gray	Poor	West - SWC	0.2	Auto	Negative
32 / 29	Exterior	South Serve Panel	Metal	Door	Beige	Poor	West	0.0	Auto	Negative
33 / 30	Exterior	Westinghouse	Metal	Door	Gray	Poor	North	0.1	Auto	Negative
		Gymnasium Building								
34 / 1	Exterior	Gymnasium - Doors	Metal	Left Door	Charcoal	Fair	North	0.1	Auto	Negative
35 / 2	Exterior	Gymnasium - Doors	Metal	Left Door Jamb	Charcoal	Fair	North	0.4	Auto	Negative
36 / 3	Exterior	Covered Walkway	Metal	Post	Charcoal	Fair	East	0.1	Auto	Negative
37 / 4	Exterior	Covered Walkway	Metal	Tie Plate	Charcoal	Fair	North	0.0	Auto	Negative
38 / 5	Exterior	Covered Walkway	Metal	Roof Panel	Charcoal	Fair	North	0.2	Auto	Negative
39 / 6	Exterior	South Double Doors	Metal	Left Door	Brown	Fair	South	0.2	Auto	Negative
40 / 7	Exterior	South Double Doors	Metal	Left Door Jamb	Brown	Fair	South	0.4	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2 Bldgs/Ext. & S. Bsmt.
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:32 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
41 / 8	Exterior	Covered Walkway	Metal	Brick Plate	Brown	Fair	South	0.3	Auto	Negative
42 / 9	Exterior	Overhead Door	Metal	Panel	Brown	Fair	South	0.2	Auto	Negative
43 / 10	Exterior	Overhead Door Jamb	Metal	Left Door Guide	Brown	Intact	South	0.1	Auto	Negative
44 / 11	Exterior	Overhead Door	Metal	Left OHD Jamb	Brown	Fair	South	0.1	Auto	Negative
45 / 12	Exterior	Overhead Door Ramp	Concrete	Side - Caution	Yellow	Poor	West	0.2	Auto	Negative
46 / 13	Exterior	Light Standard	Metal	Base	Brown	Poor	West	0.1	Auto	Negative
47 / 14	Exterior	Square Post	Metal	Pole	Brown	Poor	West	0.0	Auto	Negative
48 / 15	1	Structural	Metal	Angled Brace	Red	Fair	Wall "C" South	0.2	Auto	Negative
49 / 16	1	Overhead Door	Metal	Right Guide	Brown	Fair	Wall "C" South	0.1	Auto	Negative
50 / 17	1	Overhead Door	Metal	Panel	Brown	Fair	Wall "C" South	0.2	Auto	Negative
51 / 18	1	South Exit	Metal	Left Door	Charcoal	Fair	Wall "C" South	0.1	Auto	Negative
52 / 19	1	South Exit	Metal	Left Door Jamb	Charcoal	Fair	Wall "C" South	0.5	Auto	Negative
53 / 20	1	Vent Louvers	Metal	Top Vent	Orange	Fair	Wall "B" East	0.1	Auto	Negative
54 / 21	1	North Doorway	Metal	Left Door	Brown	Fair	Wall "A" North	0.2	Auto	Negative
55 / 22	1	North Doorway	Metal	Center Jamb	Brown	Fair	Wall "A" North	0.0	Auto	Negative
56 / 23	1	Wall	CMU	Lower Wall	Orange	Intact	Wall "A" North	0.5	Auto	Negative
57 / 24	1	Wall	CMU	Upper Wall	Ivory	Intact	Wall "A" North	0.5	Auto	Negative
58 / 25	1	Wall	CMU	Upper Wall	Ivory	Intact	Wall "B" East	0.5	Auto	Negative
59 / 26	1	Wall	CMU	Upper Wall	Ivory	Intact	Wall "C" South	0.5	Auto	Negative
60 / 27	1	Wall	CMU	Upper Wall	Ivory	Intact	Wall "D" West	0.5	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
61 / 28	1	Structural	Metal	Web Joist	Beige	Intact	Wall "B" East	0.5	Auto	Negative
62 / 29	1	3-Gang Window	Metal	Frame	Charcoal	Intact	Wall "B" East	0.1	Auto	Negative
63 / 30	1	3-Gang Window	Metal	Brick Plate	Brown	Intact	Wall "B" East	0.2	Auto	Negative
64 / 31	2	Weight Room	Metal	Right Door	Brown	Fair	Wall "A" West	0.1	Auto	Negative
65 / 32	2	Weight Room	Metal	Right Door Jamb	Brown	Fair	Wall "A" West	0.4	Auto	Negative
66 / 33	2	Vent	Metal	Grate	Beige	Intact	Wall "D" South	0.2	Auto	Negative
67 / 34	2	Power Panel	Metal	Cover	Gray	Fair	Wall "A" West	0.1	Auto	Negative
68 / 35	2	Light Fixture	Metal	Side	White	Fair	Ceiling - Center	0.3	Auto	Negative
69 / 36	2	Weight Room	Drywall	Ceiling	White	Intact	Ceiling - Center	0.1	Auto	Negative
70 / 37	2	Access Panel	Metal	Cover	Beige	Intact	Wall "D" South	0.1	Auto	Negative
71 / 38	2	Weight Room	Concrete	Floor	Gray	Fair	Floor - West	0.2	Auto	Negative
72 / 39	2	Weight Room	CMU	Wall	Beige	Intact	Wall "A" West	0.4	Auto	Negative
73 / 40	2	Weight Room	CMU	Wall	Beige	Intact	Wall "B" North	0.5	Auto	Negative
74 / 41	2	Weight Room	CMU	Wall	Beige	Intact	Wall "C" East	0.5	Auto	Negative
75 / 42	2	Weight Room	Drywall	Wall	Beige	Intact	Wall "D" South	0.1	Auto	Negative
76 / 43	2	Ladder Up	Metal	Side	Brown	Intact	Wall "B" North	0.1	Auto	Negative
77 / 44	Exterior	Water Fountain	Metal	Side	Blue	Intact	North	0.1	Auto	Negative
78 / 45	Exterior	West Lot	Concrete	Fire Stripe	Red	Poor	West	0.1	Auto	Negative
79 / 46	Exterior	Parking Space	Concrete	Stripe	White	Fair	West	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		School & Annex Bldg.								
80 / 1	Exterior	School - Basement	Metal	Landing Grate	Brown	Poor	Deck - North	0.0	Auto	**Negative**
81 / 2	Exterior	Exit Doorway	Metal	Door	Brown	Intact	South	0.2	Auto	**Negative**
82 / 3	Exterior	Exit Doorway	Metal	Left Door Jamb	Brown	Intact	South	0.0	Auto	**Negative**
83 / 4	Exterior	Window - Stairwell	Metal	Frame	Black	Fair	South	0.2	Auto	**Negative**
84 / 5	Exterior	Vent Ducting	Metal	Bracket	Brown	Door	South	0.1	Auto	**Negative**
85 / 6	Exterior	SWC Auditorium	Concrete	Base	Black	Fair	West	0.3	Auto	**Negative**
86 / 7	Exterior	Open Drain Pipe	Metal	Pipe	Brown	Poor	West	0.1	Auto	**Negative**
87 / 8	Exterior	Window with Vent	Metal	Frame	Black	Fair	West	0.2	Auto	**Negative**
88 / 9	Exterior	Window Well Grate	Metal	Angle Plate	Red	Poor	West	0.1	Auto	**Negative**
89 / 10	Exterior	SW Exit Door	Metal	Door	Brown	Poor	West	0.0	Auto	**Negative**
90 / 11	Exterior	SW Exit Door	Metal	Left Door Jamb	Brown	Poor	West	0.1	Auto	**Negative**
91 / 12	Exterior	SW Exit Door	Metal	Brick Plate	Brown	Poor	West	**3.7**	Auto	**Positive**
92 / 13	Exterior	Double Exit	Metal	Left Door	Brown	Poor	South	0.1	Auto	**Negative**
93 / 14	Exterior	Double Exit	Metal	Left Door Jamb	Brown	Fair	South	0.2	Auto	**Negative**
94 / 15	Exterior	Double Exit	Metal	Brick Plate	Brown	Poor	South	**1.2**	Auto	**Positive**
95 / 16	Exterior	2-Gang Windows	Metal	Frame	Charcoal	Fair	South	0.2	Auto	**Negative**
96 / 17	Exterior	Open Drain Pipe	Metal	Pipe	Silver	Poor	South	0.1	Auto	**Negative**
97 / 18	Exterior	Vent Cover	Metal	Cover	Rust	Bare	South - SWC	0.2	Auto	**Negative**
98 / 19	Exterior	West Window	Metal	Frame	Black	Intact	West	0.2	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
99 / 20	Exterior	NWC Windows	Metal	Mullion	Black	Fair	North - NWC	0.4	Auto	Negative
100 / 21	Exterior	NW Entry	Stone	Wall	Ivory	Fair	North	0.2	Auto	Negative
101 / 22	Exterior	Double Doors	Metal	Left Door	Brown	Intact	North	0.1	Auto	Negative
102 / 23	Exterior	Double Doors	Metal	Left Door Jamb	Brown	Intact	North	0.1	Auto	Negative
103 / 24	Exterior	Stoop Cover	Hardboard	Ceiling	Silver	Fair	Ceiling - Center	0.1	Auto	Negative
104 / 25	Exterior	Front Flag Pole	Metal	Pole	Silver	Intact	North	0.4	Auto	Negative
105 / 26	Exterior	Front Fence	Metal	Post	Black	Intact	North	0.2	Auto	Negative
106 / 27	Exterior	Monument Sign	Metal	Frame	Charcoal	Poor	West	0.2	Auto	Negative
107 / 28	Exterior	Monument Sign	Metal	Letter "1"	Black	Intact	West	0.2	Auto	Negative
108 /29	Exterior	Main School Entry Steps	Metal	Handrail	Beige	Poor	East	0.0	Auto	Negative
109 / 30	Exterior	Porch	Stone	Wall	Ivory	Fair	East Side	0.0	Auto	Negative
110 / 31	Exterior	Porch	Metal	Ceiling	White	Fair	Ceiling - East	0.1	Auto	Negative
111 / 32	Exterior	Porch	Wood	Crown Molding	Ivory	Poor	South / Building	0.3	Auto	Negative
112 / 33	Exterior	Doorway	Metal	Brick Plate	Brown	Poor	North	0.3	Auto	Negative
113 / 34	Exterior	Doorway	Metal	Frame	Brown	Poor	North	0.1	Auto	Negative
114 / 35	Exterior	Doorway	Metal	Left Door	Brown	Fair	North	0.1	Auto	Negative
115 / 36	Exterior	Decorative Overhang	Hardboard	Ceiling	Silver	Fair	North / East	0.1	Auto	Negative
116 / 37	Exterior	Control Box	Metal	Cover	Ivory	Poor	North	0.2	Auto	Negative
117 / 38	Exterior	East Entry	Metal	Left Door	Brown	Intact	North	0.1	Auto	Negative
118 / 39	Exterior	East Entry	Metal	Left Door Jamb	Brown	Intact	North	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
119 / 40	Exterior	Overhang	Hardboard	Ceiling	Silver	Fair	North	0.2	Auto	Negative
120 / 41	Exterior	Entry	Stone	Wall	Ivory	Fair	North	0.1	Auto	Negative
121 / 42	Exterior	East Addition	Metal	Door Frame	Charcoal	Fair	North	0.1	Auto	Negative
122 / 43	Exterior	Porch	Plaster	Ceiling	White	Intact	Ceiling - Center	0.1	Auto	Negative
123 / 44	Exterior	Decorative Entry	Plaster	Frame	Brown	Intact	North / East	0.5	Auto	Negative
124 / 45	Exterior	Doorway	Metal	Frame	Charcoal	Fair	East	0.1	Auto	Negative
125 / 46	Exterior	Porch	Plaster	Ceiling	White	Intact	Ceiling - Center	0.0	Auto	Negative
126 / 47	Exterior	Canopy	Metal	Frame	Brown	Poor	East	0.3	Auto	Negative
127 / 48	Exterior	Canopy	Metal	Roof Panels	Ivory	Poor	Ceiling - East	0.1	Auto	Negative
128 / 49	Exterior	East Parking Entry	Concrete	Curb	Red	Poor	North - NEC	0.3	Auto	Negative
129 / 50	Exterior	Light Standard	Metal	Pole	Charcoal	Poor	East	0.0	Auto	Negative
130 / 51	Exterior	Parking Space	Concrete	Stripe	White	Poor	East	0.5	Auto	Negative
131 / 52	Exterior	Stairs - South Cafeteria	Metal	Handrail	Brown	Poor	East	0.4	Auto	Negative
132 / 53	Exterior	South Entry - Cafeteria	Metal	Door	Charcoal	Poor	South	0.1	Auto	Negative
133 / 54	Exterior	South Entry - Cafeteria	Metal	Left Door Jamb	Charcoal	Poor	South	0.3	Auto	Negative
134 / 55	Exterior	Louver Vent	Metal	Vent	Charcoal	Fair	South	0.2	Auto	Negative
135 / 56	Exterior	Door by Truck Well	Metal	Door	Brown	Fair	East	0.2	Auto	Negative
136 / 57	Exterior	Door by Truck Well	Metal	Left Door Jamb	Brown	Poor	East	0.3	Auto	Negative
137 / 58	Interior	Small Mechanical	Metal	Left Door Jamb	Brown	Intact	Wall "A" East	0.1	Auto	Negative
138 / 59	Interior	Small Mechanical	Drywall	Wall	Ivory	Intact	Wall "A" East	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 10:15 AM	
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:32 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
139 / 60	Interior	Doors to West Exit	Metal	Left Door	Brown	Fair	Wall "C" West	0.2	Auto	Negative
140 / 61	Interior	Doors to West Exit	Metal	Left Door Jamb	Brown	Fair	Wall "C" West	0.0	Auto	Negative
141 / 62	Interior	TCP1 Panel	Metal	Cover	Beige	Poor	Wall "D" North	0.1	Auto	Negative
142 / 63	Interior	Fenced Chiller	Metal	Fence Gate	Brown	Poor	East	0.2	Auto	Negative
143 / 64	Interior	Double Doors	Metal	Left Door	Charcoal	Poor	South	0.1	Auto	Negative
144 / 65	Exterior	Stairs - Up	Metal	Vertical I-Beam	Brown	Fair	South	0.4	Auto	Negative
145 / 66	Exterior	Stairs - Up	Metal	Handrail	Brown	Fair	South	0.3	Auto	Negative
146 / 67	Exterior	Stairs - Up	Metal	Stringer	Brown	Fair	South	0.5	Auto	Negative
147 / 68	Exterior	Stairs - Up	Metal	Tread	Brown	Fair	South	0.2	Auto	Negative
148 / 69	Exterior	Balcony Walkway	Metal	Rail Cap	Brown	Fair	South	0.1	Auto	Negative
149 / 70	Exterior	2nd Floor South Exit	Metal	Left Door Jamb	Black	Intact	South	0.4	Auto	Negative
150 / 71	Exterior	Stoop	Plaster	Ceiling	White	Intact	Ceiling - Center	0.0	Auto	Negative
151 / 72	Exterior	Stoop	Metal	Brick Plate	Brown	Fair	South	0.3	Auto	Negative
152 / 73	Exterior	Mechanical Room Exit	Metal	Left Door	Brown	Fair	West	0.0	Auto	Negative
153 / 74	Exterior	Original School Exit	Metal	Door	Brown	Fair	East	0.0	Auto	Negative
154 / 75	Exterior	Original School Exit	Metal	Left Door Jamb	Brown	Door	East	0.1	Auto	Negative
155 / 76	Exterior	Original School Exit	Metal	Brick Plate	Brown	Poor	East	3.6	Auto	Positive
156 / 77	Exterior	Window North of Exit	Metal	Frame	Charcoal	Fair	East	0.2	Auto	Negative
157 / 78	Exterior	Small Access Door	Metal	Door	Brown	Poor	South	0.2	Auto	Negative
158 / 79	Exterior	Exit Doors	Metal	Left Door	Brown	Intact	South	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2 Bldgs/Ext. & S. Bsmt.
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:32 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
159 / 80	Exterior	Exit Doors	Metal	Left Door Jamb	Brown	Intact	South	0.0	Auto	Negative
160 / 81	Exterior	Exit Doors	Metal	Brick Plate	Brown	Fair	South	1.6	Auto	Negative
161 / 82	Exterior	Auditorium - East Exit	Metal	Door	Brown	Intact	East	0.1	Auto	Negative
162 / 83	Exterior	Auditorium - East Exit	Metal	Left Door Jamb	Brown	Intact	East	0.0	Auto	Negative
163 / 84	Exterior	Auditorium - East Exit	Metal	Brick Plate	Brown	Poor	East	0.2	Auto	Negative
168 / 85	1	Basement	Metal	Door	Charcoal	Fair	Wall "C" South	0.2	Auto	Negative
169 / 86	1	Basement	Metal	Left Door Jamb	Charcoal	Fair	Wall "C" South	0.1	Auto	Negative
170 / 87	1	Hall	Plaster	Wall	Beige	Fair	Wall "B" East	0.1	Auto	Negative
171 / 88	1	Hall	Plaster	Wall	Beige	Fair	Wall "D" West	0.2	Auto	Negative
172 / 89	1	Hall	Plaster	Ceiling	Beige	Fair	Ceiling - Center	0.5	Auto	Negative
173 / 90	1	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - Center	0.1	Auto	Negative
174 / 91	2	Boiler Room	Metal	Door	Ivory	Fair	Wall "A" West	0.6	Auto	Negative
175 / 92	2	Boiler Room	Metal	Left Door Jamb	Yellow	Fair	Wall "A" West	0.3	Auto	Negative
176 / 93	2	Boiler Room	Brick	Wall	Ivory	Fair	Wall "A" West	0.0	Auto	Negative
177 / 94	2	Boiler Room	Brick	Wall	Ivory	Fair	Wall "B" North	0.0	Auto	Negative
178 / 95	2	Boiler Room	Concrete	Wall	Ivory	Fair	Wall "C" East	0.2	Auto	Negative
179 / 96	2	Boiler Room	Concrete	Wall	Ivory	Fair	Wall "D" South	0.1	Auto	Negative
180 / 97	2	Boiler Room	Ceiling Tile	Ceiling	Ivory	Fair	Ceiling - East	0.1	Auto	Negative
181 / 98	2	Water Line	Metal	Vertical Pipe	Ivory	Fair	Wall "C" East	0.4	Auto	Negative
182 / 99	2	Drain / Sewer	Metal	Vertical Pipe	Ivory	Fair	Wall "C" East	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
183/100	2	Conduit	Metal	Vertical Pipe	Ivory	Fair	Wall "B" North	0.5	Auto	Negative
184/101	2	Power Panel	Metal	Cover	Gray	Fair	Wall "B" North	0.0	Auto	Negative
185/102	2	Large Pipe	Metal	Cover	Ivory	Fair	Wall "B" North	0.7	Auto	Negative
186/103	2	Window	Wood	Frame	Ivory	Fair	Wall "D" South	0.3	Auto	Negative
187/104	2	Window	Metal	Frame	Charcoal	Fair	Wall "D" South	0.2	Auto	Negative
188/105	2	Boiler Room	Concrete	Floor	Brown	Poor	Floor - West	0.1	Auto	Negative
189/106	2	Loose Doors	Wood	Door	Ivory	Fair	Wall "B" North	0.1	Auto	Negative
190/107	2	Loose Doors	Wood	Door	Ivory	Fair	Wall "B" North	0.1	Auto	Negative
191/108	2	Loose Doors	Metal	Vent	Beige	Fair	Wall "B" North	0.0	Auto	Negative
192/109	2	Sump	Metal	Cover	Brown	Poor	Floor - South	0.1	Auto	Negative
193/110	3	Storage	Wood	Door	Ivory	Fair	Wall "A" East	0.1	Auto	Negative
194/111	3	Storage	Wood	Left Door Casing	Ivory	Fair	Wall "A" East	0.1	Auto	Negative
195/112	3	Window	Wood	Frame	Ivory	Fair	Wall "B" South	0.2	Auto	Negative
196/113	3	Window	Metal	Frame	Charcoal	Intact	Wall "B" South	0.2	Auto	Negative
197/114	3	Shelves	Wood	Shelf	Beige	Poor	Wall "C" West	0.0	Auto	Negative
198/115	3	Window	Brick	Window Sill	Beige	Intact	Wall "B" South	0.0	Auto	Negative
199/116	3	Storage	Plaster	Wall	Beige	Fair	Wall "A" East	0.0	Auto	Negative
200/117	3	Storage	Plaster	Wall	Beige	Poor	Wall "B" South	0.1	Auto	Negative
201/118	3	Storage	Plaster	Wall	Beige	Fair	Wall "C" West	0.1	Auto	Negative
202/119	3	Storage	Plaster	Wall	Beige	Fair	Wall "D" North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2 Bldgs/Ext. & S. Bsmt.
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:32 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
203/120	3	Storage	Plaster	Ceiling	Beige	Intact	Ceiling - Center	0.0	Auto	Negative
204/121	4	East / West Hall	Plaster	Ceiling	Beige	Fair	Ceiling - West	0.3	Auto	Negative
205/122	4	East / West Hall	Plaster	Wall	Beige	Fair	Wall "A" North	0.1	Auto	Negative
206/123	4	East / West Hall	Plaster	Wall	Beige	Poor	Wall "C" South	0.2	Auto	Negative
207/124	4	Doorway to South Hall	Wood	Left Door Casing	Beige	Fair	Wall "C" South	0.6	Auto	Negative
208/125	5	Storage Room	Wood	Left Door Jamb	Yellow	Intact	Wall "A" West	0.0	Auto	Negative
209/126	5	Window	Wood	Frame	Beige	Fair	Wall "C" East	0.3	Auto	Negative
210/127	5	Window	Metal	Frame	Charcoal	Intact	Wall "C" East	0.1	Auto	Negative
211/128	5	Window	Brick	Window Sill	Ivory	Fair	Wall "C" East	0.1	Auto	Negative
212/129	5	Storage Room	Plaster	Wall	Beige	Fair	Wall "B" North	0.3	Auto	Negative
213/130	5	Storage Room	Plaster	Wall	Beige	Poor	Wall "C" East	0.3	Auto	Negative
214/131	5	Storage Room	Plaster	Wall	Beige	Fair	Wall "D" South	0.2	Auto	Negative
215/132	5	Storage Room	Plaster	Ceiling	Beige	Fair	Ceiling - Center	0.2	Auto	Negative
216/133	5	Shelves	Wood	Shelf	Beige	Fair	Wall "B" North	0.0	Auto	Negative
217/134	6	Kitchen Area	Wood	Top Jamb	Ivory	Fair	Wall "A" North	0.2	Auto	Negative
218/135	6	Kitchen Area	Plaster	Wall	Beige	Fair	Wall "A" North	0.0	Auto	Negative
219/136	6	Kitchen Area	Plaster	Wall	Beige	Fair	Wall "B" East	0.3	Auto	Negative
220/137	6	Kitchen Area	Hardboard	Wall	Beige	Fair	Wall "C" South	0.1	Auto	Negative
221/138	6	Window	Brick	Window Sill	Beige	Fair	Wall "C" South	0.0	Auto	Negative
222/139	6	Window	Wood	Frame	Beige	Fair	Wall "C" South	0.4	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
223/140	6	Window	Metal	Frame	Charcoal	Fair	Wall "C" South	0.2	Auto	Negative
224/141	6	Center Wall	Plaster	Wall	Beige	Poor	Wall "D" West	0.4	Auto	Negative
225/142	6	Outer Wall	Plaster	Wall	Beige	Poor	Wall "D" West	0.1	Auto	Negative
226/143	6	Kitchen Area	Plaster	Ceiling	Beige	Poor	Ceiling - West	0.1	Auto	Negative
227/144	6	Window	Brick	Window Sill	Beige	Fair	Ceiling - West	0.3	Auto	Negative
228/145	6	Window	Wood	Frame	Beige	Fair	Wall "D" West	0.0	Auto	Negative
229/146	6	Window	Metal	Frame	Charcoal	Fair	Wall "D" West	0.3	Auto	Negative
230/147	7	Pantry	Wood	Door	Beige	Fair	Wall "A" West	0.1	Auto	Negative
231/148	7	Pantry	Wood	Top Door Jamb	Beige	Fair	Wall "A" West	0.1	Auto	Negative
232/149	7	Shelves	Wood	Shelf	Beige	Fair	Wall "D" South	0.3	Auto	Negative
233/150	7	Pantry	Plaster	Wall	Beige	Fair	Wall "A" West	0.1	Auto	Negative
234/151	7	Pantry	Plaster	Wall	Beige	Fair	Wall "B" North	0.2	Auto	Negative
235/152	7	Pantry	Plaster	Wall	Beige	Fair	Wall "C" East	0.6	Auto	Negative
236/153	7	Pantry	Plaster	Wall	Beige	Fair	Wall "D" South	0.1	Auto	Negative
237/154	7	Pantry	Plaster	Ceiling	Beige	Intact	Ceiling - West	0.1	Auto	Negative
238/155	8	Main Room	Wood	Left Door	Beige	Fair	Wall "A" North	0.2	Auto	Negative
239/156	8	East Entry	Wood	Left Door Jamb	Beige	Fair	Wall "A" North	0.3	Auto	Negative
240/157	8	Window	Wood	Frame	Brown	Fair	Wall "B" East	0.2	Auto	Negative
241/158	8	Window	Metal	Frame	Charcoal	Fair	Wall "B" East	0.1	Auto	Negative
242/159	8	Window	Metal	Frame	Charcoal	Fair	Wall "D" West	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
243/160	8	Window	Wood	Frame	Brown	Fair	Wall "D" West	0.0	Auto	Negative
244/161	8	West Entry	Wood	Left Door	Beige	Fair	Wall "A" North	0.1	Auto	Negative
245/162	8	West Entry	Wood	Left Door Jamb	Beige	Fair	Wall "A" North	0.2	Auto	Negative
246/163	8	Main Room	Stone	Floor	Brown	Poor	Floor - North	0.2	Auto	Negative
247/164	8	Power Panel	Metal	Cover	Beige	Fair	Wall "A" North	0.0	Auto	Negative
248/165	8	Main Room	Drywall	Wall	Beige	Fair	Wall "A" North	0.0	Auto	Negative
249/166	8	Main Room	Plaster	Wall	Beige	Poor	Wall "B" East	0.2	Auto	Negative
250/167	8	Main Room	Plaster	Wall	Beige	Fair	Wall "C" South	0.0	Auto	Negative
251/168	8	Main Room	Plaster	Wall	Beige	Fair	Wall "D" West	0.2	Auto	Negative
252/169	8	Main Room	Plaster	Ceiling	Beige	Fair	Ceiling - Center	0.5	Auto	Negative
253/170	8	Newer Door	Metal	Left Door Jamb	Ivory	Intact	Wall "A" North	0.1	Auto	Negative
254/171	9	East Landing	Wood	Upper Door	Beige	Fair	Wall "D" West	0.1	Auto	Negative
255/172	10	Small Room	Wood	Door	Beige	Fair	Wall "A" West	0.0	Auto	Negative
256/173	10	Small Room	Wood	Left Door Jamb	Beige	Fair	Wall "A" West	0.3	Auto	Negative
257/174	8	Main Room	Wood	Vent	Ivory	Intact	Wall "A" North	0.1	Auto	Negative
258/175	11	West Landing	Wood	Upper Door	Beige	Fair	Wall "B" East	0.0	Auto	Negative
259/176	12	Small Room	Wood	Door	Beige	Fair	Wall "A" East	0.1	Auto	Negative
260/177	12	Small Room	Wood	Left Door Jamb	Beige	Fair	Wall "A" East	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2 Bldgs/Ext. & S. Bsmt.	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	10:15 AM
XRF INTERNAL REPORT NUMBER: 11/28/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:32 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		XRF Calibration								
1		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
2		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
3		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
164		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.3	Auto	**Retest**
165		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
166		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
167		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
261		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
262		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
263		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
--END--	----------	--END OF UNIT--	----------	--END--	----------	--END--	----------	--END--	----------	--END--

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2nd FL School & Annex	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:11 AM	
XRF INTERNAL REPORT NUMBER: 11/29/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:05 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		2nd Level - School								
4 / 1	1	East Stairs / 1.5 Landing	Plaster	Post Wall	Ivory	Intact	Wall "A" South	0.3	Auto	**Negative**
5 / 2	1	East Stairs	Plaster	Wall	Ivory	Fair	Wall "B" West	0.2	Auto	**Negative**
6 / 3	1	East Stairs	Plaster	Wall	Ivory	Fair	Wall "C" North	0.0	Auto	**Negative**
7 / 4	1	East Stairs	Plaster	Wall	Ivory	Fair	Wall "D" East	0.3	Auto	**Negative**
8 / 5	1	East Stairs	Plaster	Ceiling	White	Intact	Ceiling - South	0.0	Auto	**Negative**
9 / 6	1	Window	Wood	Frame	White	Intact	Wall "C" North	0.1	Auto	**Negative**
10 / 7	1	Stairs Up to 2nd Floor	Wood	Handrail	Brown	Intact	Wall "D" East	0.1	Auto	**Negative**
11 / 8	1	Stairs Up to 2nd Floor	Wood	Chair Rail	Brown	Intact	Wall "D" East	0.2	Auto	**Negative**
12 / 9	1	Stairs Up to 2nd Floor	Wood	Rail Cap	Brown	Intact	Wall "B" West	0.1	Auto	**Negative**
13 / 10	1	Stairs Up to 2nd Floor	Wood	Handrail	Brown	Intact	Wall "B" West	0.0	Auto	**Negative**
14 / 11	1	Brass Hardware	Metal	Handrail Bracket	Ivory	Intact	Wall "B" West	0.3	Auto	**Negative**
15 / 12	2	2nd Floor Hallway	Wood	Baseboard	Beige	Fair	Wall "A" North	0.0	Auto	**Negative**
16 / 13	2	Lockers - #251	Metal	Frame	Brown	Fair	Wall "A" North	0.2	Auto	**Negative**
17 / 14	2	2nd Floor Hallway	Concrete	Opening Header	Ivory	Intact	Wall "A" North	0.2	Auto	**Negative**
18 / 15	2	2nd Floor Hallway	Plaster	Wall	Ivory	Fair	Wall "A" North	0.2	Auto	**Negative**
19 / 16	2	2nd Floor Hallway	Drywall	Wall	Ivory	Intact	Wall "B" East	0.1	Auto	**Negative**
20 / 17	2	2nd Floor Hallway	Plaster	Wall	Ivory	Fair	Wall "C" South	0.2	Auto	**Negative**
21 / 18	2	2nd Floor Hallway	Plaster	Wall	Ivory	Intact	Wall "D" West	0.3	Auto	**Negative**
22 / 19	2	Window	Wood	Frame	Brown	Intact	Wall "D" West	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2nd FL School & Annex	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:11 AM	
XRF INTERNAL REPORT NUMBER: 11/29/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:05 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
23 / 20	2	2nd Floor Hallway	Wood	Baseboard	Beige	Fair	Wall "D" West	0.1	Auto	Negative
24 / 21	2	3rd Floor Hallway	Wood	Crown Molding	White	Fair	Wall "A" North	0.1	Auto	Negative
25 / 22	2	Older Bulletin Board	Wood	Frame	Brown	Fair	Wall "C" South	0.3	Auto	Negative
26 / 23	2	Light Fixture	Metal	Side	White	Intact	Ceiling - Center	0.0	Auto	Negative
27 / 24	2	Power Panel	Metal	Cover	Ivory	Fair	Wall "D" West	0.2	Auto	Negative
28 / 25	2	Power Panel	Metal	Cover	Ivory	Fair	Wall "B" East	0.1	Auto	Negative
29 / 26	2	East Doorway	Metal	Frame	Charcoal	Fair	Wall "B" East	0.1	Auto	Negative
30 / 27	3	Classroom #201	Wood	Door	Brown	Fair	Wall "A" South	0.0	Auto	Negative
31 / 28	3	Classroom #201	Metal	Vent	Beige	Fair	Wall "A" South	0.3	Auto	Negative
32 / 29	3	Classroom #201	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
33 / 30	3	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
34 / 31	3	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.1	Auto	Negative
35 / 32	3	Window Box	Wood	Back	White	Fair	Wall "A" South	0.2	Auto	Negative
36 / 33	3	Classroom #201	Wood	Crown Molding	Ivory	Intact	Wall "A" South	0.2	Auto	Negative
37 / 34	3	Classroom #201	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	Negative
38 / 35	3	Cabinets	Wood	Facing	Brown	Fair	Wall "B" West	0.0	Auto	Negative
39 / 36	3	Window	Wood	Frame	Brown	Intact	Wall "C" North	0.1	Auto	Negative
40 / 37	3	Speaker Box	Wood	Side	Brown	Fair	Wall "D" East	0.1	Auto	Negative
41 / 38	3	Cabinets	Wood	Facing	Brown	Fair	Wall "D" East	0.1	Auto	Negative
42 / 39	3	Light Fixture	Metal	Side	White	Intact	Ceiling - East	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
43 / 40	3	Flag Mount	Wood	Plate	White	Intact	Wall "D" East	0.3	Auto	Negative
44 / 41	3	Classroom #201	Plaster	Wall	Ivory	Fair	Wall "A" South	0.4	Auto	Negative
45 / 42	3	Classroom #201	Plaster	Wall	Ivory	Fair	Wall "B" West	0.3	Auto	Negative
46 / 43	3	Classroom #201	Plaster	Wall	Ivory	Fair	Wall "C" North	0.5	Auto	Negative
47 / 44	3	Classroom #201	Plaster	Wall	Ivory	Fair	Wall "D" East	0.4	Auto	Negative
		Second Level Annex								
48 / 45	4 - Exterior	Connector Breezeway	Concrete	Floor	Gray	Fair	Floor - West	0.1	Auto	Negative
49 / 46	4 - Exterior	School Doorway	Metal	Door Frame	Charcoal	Poor	West	0.0	Auto	Negative
50 / 47	4 - Exterior	Walkway	Metal	Vertical I-Beam	Charcoal	Fair	North	0.1	Auto	Negative
51 / 48	4 - Exterior	Walkway	Metal	Top Cross Beam	Charcoal	Fair	West	0.1	Auto	Negative
52 / 49	4 - Exterior	Walkway	Metal	Root Panel	Charcoal	Poor	Ceiling - West	0.0	Auto	Negative
53 / 50	4 - Exterior	Fencing	Metal	Top Plate	Charcoal	Fair	North	0.5	Auto	Negative
54 / 51	4 - Exterior	Pony Wall - North	Metal	Rail Cap	Charcoal	Fair	North	0.1	Auto	Negative
55 / 52	4 - Exterior	Top Railing Pipe	Metal	Rail Cap	Charcoal	Fair	North	0.5	Auto	Negative
56 / 53	4 - Exterior	Pony Wall	Plaster	Wall	Ivory	Fair	North	0.2	Auto	Negative
57 / 54	4 - Exterior	Annex Entry	Metal	Brick Plate	Brown	Intact	West	0.5	Auto	Negative
58 / 55	4 - Exterior	Annex Entry	Plaster	Ceiling	White	Intact	Ceiling - Center	0.1	Auto	Negative
59 / 56	4 - Exterior	Doors to Annex	Metal	Left Door Jamb	Charcoal	Fair	East Entry	0.1	Auto	Negative
60 / 57	5	2nd FL Elevator Lobby	Metal	Rail Cap	Brown	Intact	Wall "D" North	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:05 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
61 / 58	5	Pony Wall	Wood	Rail Cap	Brown	Intact	Wall "D" North	0.1	Auto	Negative
62 / 59	5	2nd FL Elevator Lobby	Drywall	Wall	Ivory	Intact	Wall "A" East	0.2	Auto	Negative
63 / 60	5	2nd FL Elevator Lobby	Drywall	Wall	Ivory	Intact	Wall "B" South	0.1	Auto	Negative
64 / 61	5	2nd FL Elevator Lobby	Drywall	Wall	Ivory	Intact	Wall "C" West	0.2	Auto	Negative
65 / 62	5	2nd FL Elevator Lobby	Drywall	Wall	Ivory	Intact	Wall "D" North	0.1	Auto	Negative
66 / 63	5	Elevator	Metal	Door	Charcoal	Fair	Wall "A" East	0.0	Auto	Negative
67 / 64	5	Elevator	Metal	Left Door Jamb	Charcoal	Fair	Wall "A" East	0.1	Auto	Negative
68 / 65	5	NEC Stairs / Landing	Metal	Handrail	Charcoal	Intact	Wall "A" East	0.0	Auto	Negative
69 / 66	5	NEC Stairs	Metal	Stringer	Charcoal	Intact	Wall "A" East	0.1	Auto	Negative
70 / 67	5	Window	Metal	Window Sill	Charcoal	Intact	Wall "A" East	0.1	Auto	Negative
71 / 68	5	Arched Windows	Metal	Frame	Charcoal	Intact	Wall "A" East	0.1	Auto	Negative
72 / 69	5	Closet - North Elevator	Metal	Left Door Jamb	Charcoal	Fair	Wall "A" East	0.2	Auto	Negative
73 / 70	5	Closet - North Elevator	Wood	Door	Brown	Intact	Wall "A" West	0.1	Auto	Negative
74 / 71	5	Closet - North Elevator	Drywall	Wall	Ivory	Intact	Wall "A" West	0.2	Auto	Negative
75 / 72	5	Closet Behind Elevator	Drywall	Wall	Ivory	Intact	Wall "D" East	0.1	Auto	Negative
76 / 73	5	Power Panel	Metal	Cover	Gray	Intact	Wall "D" East	0.1	Auto	Negative
77 / 74	5	Closet Behind Elevator	Metal	Left Door Jamb	Black	Intact	Wall "A" South	0.1	Auto	Negative
78 / 75	5	Closet Behind Elevator	Wood	Door	Brown	Intact	Wall "A" South	0.1	Auto	Negative
79 / 76	5	East Exit Doorway	Metal	Left Door Jamb	Charcoal	Fair	Wall "C" West	0.2	Auto	Negative
80 / 77	5	East Exit Doorway	Metal	Left Door	Charcoal	Fair	Wall "C" West	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
81 / 78	5	Fire Extinguisher Cabinet	Metal	Back Wall	White	Intact	Wall "C" South	0.2	Auto	Negative
82 / 79	5	Light Fixture	Metal	Frame	White	Intact	Ceiling - Center	0.2	Auto	Negative
83 / 80	5	Air Diffuser	Metal	Frame	Beige	Intact	Ceiling - Center	0.1	Auto	Negative
84 / 81	6	Classroom #201A	Metal	Left Door Jamb	Charcoal	Intact	Wall "A" South	0.2	Auto	Negative
85 / 82	6	Classroom #201A	Wood	Door	Brown	Intact	Wall "A" South	0.0	Auto	Negative
86 / 83	6	Shelves	Wood	Shelf	Green	Fair	Wall "A" South	0.0	Auto	Negative
87 / 84	6	Shelves	Wood	Top	Green	Fair	Wall "B" West	0.1	Auto	Negative
88 / 85	6	Cabinets	Wood	Shelf	Ivory	Fair	Wall "C" North	0.1	Auto	Negative
89 / 86	6	Window	Metal	Window Sill	Charcoal	Intact	Wall "C" North	0.1	Auto	Negative
90 / 87	6	Chalkboard	Hardboard	Surface	Brown	Intact	Wall "D" East	0.4	Auto	Negative
91 / 88	6	Control Box	Metal	Cover	Ivory	Intact	Wall "A" South	0.2	Auto	Negative
92 / 89	6	Classroom #201A	Drywall	Wall	Ivory	Intact	Wall "A" South	0.0	Auto	Negative
93 / 90	6	Classroom #201A	Drywall	Wall	Ivory	Intact	Wall "B" West	0.0	Auto	Negative
94 / 91	6	Classroom #201A	Drywall	Wall	Ivory	Intact	Wall "C" North	0.1	Auto	Negative
95 / 92	6	Classroom #201A	Drywall	Wall	Ivory	Intact	Wall "D" East	0.1	Auto	Negative
96 / 93	7	North/South Hallway	Drywall	Wall	Ivory	Intact	Wall "B" East	0.1	Auto	Negative
97 / 94	7	South Exit	Drywall	Left Door Jamb	Charcoal	Intact	Wall "C" South	0.0	Auto	Negative
98 / 95	7	Wet Bar Area	Metal	Wall	Ivory	Intact	Wall "D" West	0.1	Auto	Negative
99 / 96	8	Suite #202A	Drywall	Left Door Jamb	Charcoal	Fair	Wall "A" West	0.2	Auto	Negative
100 / 97	8	Suite #202A	Wood	Door	Brown	Fair	Wall "A" West	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
101 / 98	8	East Wall	Metal	Window Frame	Charcoal	Fair	Wall "C" East	0.3	Auto	Negative
102 / 99	8	Suite #202A	Drywall	Wall	Ivory	Intact	Wall "A" West	0.2	Auto	Negative
103/100	8	Suite #202A	Drywall	Wall	Ivory	Intact	Wall "B" North	0.2	Auto	Negative
104/101	8	Suite #202A	Drywall	Wall	Ivory	Intact	Wall "C" East	0.2	Auto	Negative
105/102	8	Suite #202A	Drywall	Wall	Ivory	Intact	Wall "D" South	0.1	Auto	Negative
106/103	9	Suite #204A	Wood	Door	Brown	Intact	Wall "A" West	0.1	Auto	Negative
107/104	9	Suite #204A	Metal	Left Door Jamb	Black	Intact	Wall "A" West	0.0	Auto	Negative
108/105	9	Window	Metal	Window Sill	Black	Fair	Wall "C" East	0.2	Auto	Negative
109/106	9	Suite #204A	Drywall	Wall	Ivory	Intact	Wall "A" West	0.1	Auto	Negative
110/107	9	Suite #204A	Drywall	Wall	Ivory	Intact	Wall "B" North	0.1	Auto	Negative
111/108	9	Suite #204A	Drywall	Wall	Ivory	Intact	Wall "C" East	0.1	Auto	Negative
112/109	9	Suite #204A	Drywall	Wall	Ivory	Intact	Wall "D" South	0.0	Auto	Negative
113/110	9	Panel	Metal	Cover	Ivory	Intact	Wall "B" North	0.3	Auto	Negative
114/111	10	Suite #206A	Metal	Left Door Jamb	Black	Intact	Wall "A" West	0.1	Auto	Negative
115/112	10	Suite #206A	Wood	Door	Brown	Intact	Wall "A" West	0.0	Auto	Negative
116/113	10	Window	Metal	Window Sill	Charcoal	Intact	Wall "C" East	0.1	Auto	Negative
117/114	10	Suite #206A	Drywall	Wall	Ivory	Intact	Wall "A" West	0.2	Auto	Negative
118/115	10	Suite #206A	Drywall	Wall	Ivory	Intact	Wall "B" North	0.2	Auto	Negative
119/116	10	Suite #206A	Drywall	Wall	Ivory	Intact	Wall "C" East	0.2	Auto	Negative
120/117	10	Suite #206A	Drywall	Wall	Ivory	Intact	Wall "D" South	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
121/118	11	Girls' Restroom	Wood	Door	Brown	Fair	Wall "A" East	0.1	Auto	Negative
122/119	11	Girls' Restroom	Metal	Left Door Jamb	Black	Fair	Wall "A" East	0.3	Auto	Negative
123/120	11	Girls' Restroom	Ceramic Tile	Floor	Brown	Intact	Floor - East	0.1	Auto	Negative
124/121	11	Girls' Restroom	CMU	Wall	Ivory	Intact	Wall "A" East	0.1	Auto	Negative
125/122	11	Girls' Restroom	CMU	Wall	Ivory	Intact	Wall "B" South	0.5	Auto	Negative
126/123	11	Girls' Restroom	CMU	Wall	Ivory	Intact	Wall "C" West	0.5	Auto	Negative
127/124	11	Girls' Restroom	CMU	Wall	Ivory	Intact	Wall "D" North	0.0	Auto	Negative
128/125	12	Boys' Restroom	CMU	Wall	Ivory	Intact	Wall "A" East	0.0	Auto	Negative
129/126	12	Boys' Restroom	CMU	Wall	Ivory	Intact	Wall "B" South	0.4	Auto	Negative
130/127	12	Boys' Restroom	CMU	Wall	Ivory	Intact	Wall "C" West	0.0	Auto	Negative
131/128	12	Boys' Restroom	CMU	Wall	Ivory	Intact	Wall "D" North	0.0	Auto	Negative
132/129	12	Boys' Restroom	Metal	Left Door Jamb	Black	Intact	Wall "A" East	0.3	Auto	Negative
133/130	12	Boys' Restroom	Wood	Door	Brown	Intact	Wall "A" East	0.1	Auto	Negative
134/131	13	Suite #205A	Wood	Door	Brown	Intact	Wall "A" East	0.0	Auto	Negative
135/132	13	Suite #205A	Metal	Left Door Jamb	Black	Fair	Wall "A" East	0.2	Auto	Negative
136/133	13	Window	Metal	Window Sill	Charcoal	Intact	Wall "B" West	0.1	Auto	Negative
137/134	13	Cabinets	Metal	Cover	Beige	Intact	Wall "C" North	0.0	Auto	Negative
138/135	13	Suite #205A	Drywall	Wall	Ivory	Intact	Wall "A" South	0.1	Auto	Negative
139/136	13	Suite #205A	Drywall	Wall	Ivory	Intact	Wall "B" West	0.1	Auto	Negative
140/137	13	Suite #205A	Drywall	Wall	Ivory	Intact	Wall "C" North	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2nd FL School & Annex	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:11 AM	
XRF INTERNAL REPORT NUMBER: 11/29/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:05 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
141/138	13	Suite #205A	Drywall	Wall	Ivory	Intact	Wall "D" East	0.1	Auto	Negative
142/139	14	Suite #203A	Wood	Door	Brown	Intact	Wall "A" East	0.2	Auto	Negative
143/140	14	Suite #203A	Metal	Left Door Jamb	Black	Fair	Wall "A" East	0.1	Auto	Negative
144/141	14	Suite #203A	Drywall	Wall	Ivory	Intact	Wall "A" East	0.1	Auto	Negative
145/142	14	Suite #203A	Drywall	Wall	Ivory	Intact	Wall "B" South	0.1	Auto	Negative
146/143	14	Suite #203A	Drywall	Wall	Ivory	Intact	Wall "C" West	0.1	Auto	Negative
147/144	14	Suite #203A	Drywall	Wall	Ivory	Intact	Wall "D" North	0.2	Auto	Negative
		2nd Level - School								
148/145	15	School North/South Hall	Plaster	Wall	Ivory	Fair	Wall "B" East	0.1	Auto	Negative
149/146	15	School North/South Hall	Wood	Baseboard	Beige	Fair	Wall "B" East	0.3	Auto	Negative
150/147	15	Lockers by #270	Metal	Facing	Brown	Fair	Wall "B" East	0.2	Auto	Negative
151/148	15	Window	Metal	Frame	Brown	Fair	Wall "D" West	0.1	Auto	Negative
152/149	15	School North/South Hall	Plaster	Wall	Ivory	Fair	Wall "D" West	0.2	Auto	Negative
153/150	16	Classroom #215	Wood	Left Door Jamb	Brown	Fair	Wall "A" West	0.0	Auto	Negative
154/151	16	Classroom #215	Wood	Baseboard	Brown	Fair	Wall "A" West	0.2	Auto	Negative
155/152	16	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" West	0.0	Auto	Negative
156/153	16	Cabinets	Wood	Facing	Brown	Fair	Wall "B" North	0.1	Auto	Negative
157/154	16	Windows	Wood	Frame	Brown	Intact	Wall "C" East	0.0	Auto	Negative
158/155	16	Speaker	Wood	Facing	Brown	Fair	Wall "D" South	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
159/156	16	Flag Mount	Wood	Board	Ivory	Intact	Wall "D" South	0.2	Auto	Negative
160/157	16	Cabinets	Wood	Facing	Brown	Fair	Wall "D" South	0.1	Auto	Negative
161/158	16	Classroom #215	Wood	Crown Molding	Beige	Intact	Wall "A" West	0.1	Auto	Negative
162/159	16	Chalkboard	Slate	Surface	Black	Fair	Wall "D" South	0.1	Auto	Negative
163/160	16	Classroom #215	Plaster	Ceiling	White	Intact	Ceiling - West	0.0	Auto	Negative
164/161	16	Classroom #215	Plaster	Wall	Beige	Intact	Wall "A" West	0.4	Auto	Negative
165/162	16	Classroom #215	Plaster	Wall	Beige	Intact	Wall "B" North	0.2	Auto	Negative
166/163	16	Classroom #215	Plaster	Wall	Beige	Intact	Wall "C" East	0.5	Auto	Negative
167/164	16	Classroom #215	Plaster	Wall	Beige	Intact	Wall "D" South	0.5	Auto	Negative
168/165	16	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.2	Auto	Negative
169/166	17	Classroom #216	Wood	Transom	Brown	Intact	Wall "A" West	0.1	Auto	Negative
170/167	17	Classroom #216	Wood	Baseboard	Brown	Intact	Wall "A" West	0.1	Auto	Negative
171/168	17	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" West	0.1	Auto	Negative
172/169	17	Chalkboard	Slate	Surface	Black	Fair	Wall "A" West	0.1	Auto	Negative
173/170	17	Cabinets	Wood	Facing	Brown	Fair	Wall "B" North	0.1	Auto	Negative
174/171	17	Window	Wood	Frame	Brown	Fair	Wall "C" East	0.0	Auto	Negative
175/172	17	Cabinets	Wood	Shelf	Brown	Fair	Wall "D" South	0.0	Auto	Negative
176/173	17	Flag Mount	Wood	Board	White	Intact	Wall "D" South	0.2	Auto	Negative
177/174	17	Classroom #216	Wood	Crown Molding	Beige	Intact	Wall "D" South	0.2	Auto	Negative
178/175	17	Classroom #216	Plaster	Ceiling	White	Intact	Ceiling - West	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
179/176	17	CR#16 - Light Fixture	Metal	Side	Ivory	Intact	Ceiling - West	0.1	Auto	Negative
180/177	17	Classroom #216	Plaster	Wall	Beige	Intact	Wall "A" - West	0.4	Auto	Negative
181/178	17	Classroom #216	Plaster	Wall	Beige	Intact	Wall "B" - North	0.2	Auto	Negative
182/179	17	Classroom #216	Plaster	Wall	Beige	Intact	Wall "C - East	0.4	Auto	Negative
183/180	17	Classroom #216	Plaster	Wall	Beige	Intact	Wall "D" - South	0.3	Auto	Negative
184/181	18	Classroom #214	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
185/182	18	Classroom #214	Wood	Baseboard	Brown	Fair	Wall "A" North	0.2	Auto	Negative
186/183	18	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.1	Auto	Negative
187/184	18	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.2	Auto	Negative
188/185	18	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.1	Auto	Negative
189/186	18	Classroom #214	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.1	Auto	Negative
190/187	18	Classroom #214	Plaster	Ceiling	White	Intact	Ceiling - North	0.2	Auto	Negative
191/188	18	Classroom #214	Plaster	Wall	Ivory	Intact	Wall "A" North	0.0	Auto	Negative
192/189	18	Classroom #214	Plaster	Wall	Ivory	Intact	Wall "B" East	0.1	Auto	Negative
193/190	18	Classroom #214	Plaster	Wall	Ivory	Intact	Wall "C" South	0.5	Auto	Negative
194/191	18	Classroom #214	Plaster	Wall	Ivory	Intact	Wall "D" West	0.4	Auto	Negative
195/192	18	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - North	0.2	Auto	Negative
196/193	19	Classroom #213	Metal	Side	Ivory	Intact	Ceiling - North	0.1	Auto	Negative
197/194	19	Classroom #213	Wood	Transom	Brown	Intact	Wall "A" North	0.1	Auto	Negative
198/195	19	Classroom #213	Wood	Baseboard	Brown	Intact	Wall "A" North	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
199/196	19	Chalkboard	Wood	Chalk Sill	Brown	Intact	Wall "A" North	0.1	Auto	Negative
200/197	19	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
201/198	19	Windows	Wood	Frame	Brown	Intact	Wall "C" South	0.1	Auto	Negative
202/199	19	Classroom #213	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.2	Auto	Negative
203/200	19	Classroom #213	Plaster	Ceiling	White	Intact	Ceiling - North	0.1	Auto	Negative
204/201	19	Classroom #213	Plaster	Wall	Ivory	Intact	Wall "A" North	0.1	Auto	Negative
205/202	19	Classroom #213	Plaster	Wall	Ivory	Intact	Wall "B" East	0.2	Auto	Negative
206/203	19	Classroom #213	Plaster	Wall	Ivory	Intact	Wall "C" South	0.4	Auto	Negative
207/204	19	Classroom #213	Plaster	Wall	Ivory	Intact	Wall "D" West	0.4	Auto	Negative
208/205	20	Janitor Closet	Wood	Door	Ivory	Fair	Wall "A" North	0.0	Auto	Negative
209/206	20	Janitor Closet	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	Negative
210/207	20	Janitor Closet	Plaster	Wall	Beige	Fair	Wall "B" East	0.3	Auto	Negative
211/208	20	Ladder	Metal	Side	Red	Fair	Wall "B" East	0.2	Auto	Negative
212/209	20	Framed Ceiling	Wood	Ceiling	Beige	Intact	Ceiling - Center	0.3	Auto	Negative
213/210	20	Vertical Conduit	Metal	3/4 Conduit	Beige	Fair	Wall "C" South	0.4	Auto	Negative
214/211	21	Boys' Restroom	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.3	Auto	Negative
215/212	21	Window	Wood	Frame	Charcoal	Fair	Wall "C" South	0.4	Auto	Negative
216/213	21	Boys' Restroom	Ceramic Tile	Window Sill	Ivory	Intact	Wall "C" South	0.1	Auto	Negative
217/214	21	Boys' Restroom	Wood	Frame	Ivory	Intact	Wall "C" South	0.8	Auto	Negative
218/215	21	Decorative	Ceramic Tile	Wall	Gold	Intact	Wall "B" East	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
219/216	21	Decorative	Ceramic Tile	Wall	Blue	Intact	Wall "B" East	0.3	Auto	Negative
220/217	21	Decorative	Ceramic Tile	Wall	Red	Intact	Wall "D" West	0.2	Auto	Negative
221/218	21	Decorative	Ceramic Tile	Floor	Blue	Intact	Floor - North	0.0	Auto	Negative
222/219	21	Decorative	Ceramic Tile	Floor	Gray	Intact	Floor - North	0.2	Auto	Negative
223/220	21	Decorative	Ceramic Tile	Floor	Beige	Intact	Floor - North	0.0	Auto	Negative
227/221	22	South / East Stairs	Plaster	Wall	Ivory	Fair	Wall "D" West	0.3	Auto	Negative
228/222	22	South / East Stairs	Plaster	Ceiling	White	Intact	Ceiling - West	0.1	Auto	Negative
229/223	22	South / East Stairs	Wood	Baseboard	Beige	Fair	Wall "D" West	0.3	Auto	Negative
230/224	22	Stairs	Wood	Rail Cap	Brown	Intact	Center	0.1	Auto	Negative
231/225	22	Stairs	Wood	Handrail	Brown	Intact	Wall "B" East	0.0	Auto	Negative
232/226	22	Handrail	Metal	Bracket	Beige	Intact	Wall "B" East	0.2	Auto	Negative
233/227	22	Handrail	Wood	Handrail	Brown	Fair	Wall "D" West	0.0	Auto	Negative
234/228	22	Stairs	Wood	Chair Rail	Brown	Fair	Wall "D" West	0.3	Auto	Negative
235/229	22	1.5 Landing - Window	Wood	Window Frame	Brown	Fair	Wall "C" South	0.1	Auto	Negative
236/230	23	Balcony	Wood	Door	Beige	Fair	Wall "A" North	0.6	Auto	Negative
237/231	23	Balcony	Wood	Left Door Jamb	Blue	Fair	Wall "A" North	0.2	Auto	Negative
238/232	23	Pony Wall	Wood	Rail Cap	Blue	Fair	Wall "C" South	0.1	Auto	Negative
239/233	23	Railing	Metal	Rail Cap	Blue	Fair	Wall "C" South	0.5	Auto	Negative
240/234	23	Pony Wall	Drywall	Wall	White	Fair	Wall "C" South	0.1	Auto	Negative
241/235	23	Balcony	Plaster	Wall	White	Intact	Wall "A" North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
242/236	23	Balcony	Plaster	Wall	White	Intact	Wall "B" East	0.3	Auto	Negative
243/237	23	Balcony	Plaster	Wall	White	Intact	Wall "D" West	0.2	Auto	Negative
244/238	23	Balcony	Plaster	Trim	White	Intact	Wall "D" West	0.4	Auto	Negative
245/239	23	Balcony	Wood	Trim	White	Intact	Wall "D" West	0.2	Auto	Negative
246/240	23	Balcony	Wood	Crown Molding	Blue	Intact	Wall "B" East	0.0	Auto	Negative
247/241	23	Balcony	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
248/242	23	Balcony	Wood	Crown Molding	White	Fair	Wall "A" North	0.3	Auto	Negative
249/243	24	Control Room	Metal	Door	Beige	Poor	Wall "A" West	0.5	Auto	Negative
250/244	24	Control Room	Metal	Left Door Jamb	Blue	Poor	Wall "A" West	0.2	Auto	Negative
251/245	24	Control Room	Plaster	Wall	Blue	Fair	Wall "A" West	0.2	Auto	Negative
252/246	24	Control Room	Plaster	Wall	Blue	Fair	Wall "B" North	0.2	Auto	Negative
253/247	24	Control Room	Plaster	Ceiling	Blue	Fair	Ceiling - West	0.3	Auto	Negative
254/248	23	Seats 15	Wood	Arm Rest	Brown	Fair	NWC Balcony	0.1	Auto	Negative
255/249	23	Seats 15	Wood	Back	Brown	Fair	NWC Balcony	0.1	Auto	Negative
256/250	23	Seats 15	Metal	Frame	Black	Fair	NWC Balcony	0.1	Auto	Negative
257/251	23	Seats 15	Metal	Side	Brown	Fair	NWC Balcony	0.1	Auto	Negative
258/252	25	So. Stairs West Auditorium	Plaster	Wall	Ivory	Intact	Wall "D" West	0.2	Auto	Negative
259/253	25	So. Stairs West Auditorium	Plaster	Ceiling	White	Intact	Ceiling - West	0.2	Auto	Negative
260/254	25	So. Stairs West Auditorium	Wood	Baseboard	Beige	Fair	Wall "D" West	0.0	Auto	Negative
261/255	25	Stairs Down	Wood	Rail Cap	Brown	Fair	Center	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
262/256	25	Stairs Down	Wood	Handrail	Brown	Fair	Wall "B" East	0.1	Auto	Negative
263/257	25	Handrail	Metal	Bracket	Ivory	Intact	Wall "B" East	0.2	Auto	Negative
264/258	25	1.5 Landing - Down	Wood	Handrail	Brown	Intact	Center	0.1	Auto	Negative
265/259	25	Stairs Down	Wood	Chair Rail	Brown	Fair	Wall "D" West	0.1	Auto	Negative
266/260	25	Window	Wood	Frame	Brown	Fair	Wall "C" South	0.2	Auto	Negative
267/261	26	Girls' Restroom	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
268/262	26	Window	Wood	Frame	Ivory	Fair	Wall "C" South	0.7	Auto	Negative
269/263	26	Girls' Restroom	Ceramic Tile	Window Sill	Ivory	Intact	Wall "C" South	0.0	Auto	Negative
270/264	26	Decorative	Ceramic Tile	Wall	Yellow	Intact	Wall "B" East	0.3	Auto	Negative
271/265	26	Decorative	Ceramic Tile	Wall	Blue	Intact	Wall "B" East	0.2	Auto	Negative
272/266	26	Decorative	Ceramic Tile	Wall	Red	Intact	Wall "D" West	0.3	Auto	Negative
273/267	26	Decorative	Ceramic Tile	Floor	Ivory	Intact	Floor - North	0.1	Auto	Negative
274/268	26	Decorative	Ceramic Tile	Floor	Light Brown	Intact	Floor - North	0.1	Auto	Negative
275/269	26	Decorative	Ceramic Tile	Floor	Red	Intact	Floor - North	0.1	Auto	Negative
276/270	27	Classroom #212	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
277/271	27	Classroom #212	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	Negative
278/272	27	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.0	Auto	Negative
279/273	27	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
280/274	27	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.1	Auto	Negative
281/275	27	Classroom #212	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
282/276	27	Classroom #212	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
283/277	27	Classroom #212	Plaster	Wall	Beige	Intact	Wall "A" North	0.4	Auto	Negative
284/278	27	Classroom #212	Plaster	Wall	Beige	Intact	Wall "B" East	0.2	Auto	Negative
285/279	27	Classroom #212	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative
286/280	27	Classroom #212	Plaster	Wall	Beige	Intact	Wall "D" West	0.4	Auto	Negative
287/281	27	Classroom #212 - Light	Metal	Side	Ivory	Intact	Ceiling - North	0.1	Auto	Negative
288/282	28	Classroom #211 - Light	Metal	Side	Ivory	Intact	Ceiling - North	0.0	Auto	Negative
289/283	28	Classroom #211 - Door	Wood	Transom	Brown	Intact	Wall "A" North	0.2	Auto	Negative
290/284	28	Classroom #211	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	Negative
291/285	28	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.1	Auto	Negative
292/286	28	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
293/287	28	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.1	Auto	Negative
294/288	28	Classroom #211	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.2	Auto	Negative
295/289	28	Classroom #211	Plaster	Ceiling	White	Intact	Ceiling - North	0.0	Auto	Negative
296/290	28	Classroom #211	Plaster	Wall	Beige	Intact	Wall "A" North	0.3	Auto	Negative
297/291	28	Classroom #211	Plaster	Wall	Beige	Intact	Wall "B" East	0.3	Auto	Negative
298/292	28	Classroom #211	Plaster	Wall	Beige	Intact	Wall "C" South	0.5	Auto	Negative
299/293	28	Classroom #211	Plaster	Wall	Beige	Intact	Wall "D" West	0.2	Auto	Negative
300/294	29	West North/South Hall	Plaster	Wall	Beige	Intact	Wall "B" East	0.4	Auto	Negative
301/295	29	West North/South Hall	Plaster	Wall	Beige	Intact	Wall "D" West	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
302/296	29	West North/South Hall	Wood	Baseboard	Beige	Fair	Wall "B" East	0.2	Auto	Negative
303/297	29	Window	Wood	Frame	Brown	Fair	Wall "B" East	0.1	Auto	Negative
304/298	29	Locker by #171	Metal	Frame	Brown	Fair	Wall "D" West	0.0	Auto	Negative
305/299	29	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.2	Auto	Negative
306/300	30	South Storage Room	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
307/301	30	South Storage Room	Wood	Baseboard	Brown	Fair	Wall "A" North	0.0	Auto	Negative
308/302	30	Windows	Wood	Frame	Brown	Fair	Wall "B" East	0.2	Auto	Negative
309/303	30	Shelves	Wood	Shelf	Brown	Intact	Wall "C" South	0.1	Auto	Negative
310/304	30	Shelves	Wood	Shelf	Ivory	Intact	Wall "D" West	0.0	Auto	Negative
311/305	30	South Storage Room	Plaster	Wall	Ivory	Intact	Wall "D" West	0.3	Auto	Negative
312/306	30	South Storage Room	Plaster	Wall	Ivory	Intact	Wall "B" East	0.3	Auto	Negative
313/307	30	Heater	Metal	Side	Brown	Fair	Ceiling - Center	0.1	Auto	Negative
314/308	31	Classroom #210 - Light	Metal	Side	Ivory	Intact	Ceiling - East	0.1	Auto	Negative
315/309	31	Classroom #210	Wood	Left Door Jamb	Brown	Fair	Wall "A" East	0.1	Auto	Negative
316/310	31	Classroom #210	Wood	Baseboard	Brown	Fair	Wall "A" East	0.2	Auto	Negative
317/311	31	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" East	0.0	Auto	Negative
318/312	31	Chalkboard	Slate	Surface	Black	Fair	Wall "A" East	0.1	Auto	Negative
319/313	31	Windows	Wood	Frame	Brown	Fair	Wall "C" West	0.1	Auto	Negative
320/314	31	Classroom #210	Wood	Crown Molding	Beige	Intact	Wall "A" East	0.3	Auto	Negative
321/315	31	Classroom #210	Plaster	Ceiling	White	Intact	Ceiling - East	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 2nd FL School & Annex
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:11 AM
XRF INTERNAL REPORT NUMBER: 11/29/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:05 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
322/316	31	Classroom #210	Plaster	Wall	Ivory	Intact	Wall "A" East	0.3	Auto	**Negative**
323/317	31	Classroom #210	Plaster	Wall	Ivory	Intact	Wall "B" South	0.2	Auto	**Negative**
324/318	31	Classroom #210	Plaster	Wall	Ivory	Intact	Wall "C" West	0.5	Auto	**Negative**
325/319	31	Classroom #210	Plaster	Wall	Ivory	Intact	Wall "D" North	0.4	Auto	**Negative**
326/320	32	Classroom #209	Wood	Left Door Jamb	Brown	Fair	Wall "A" East	0.0	Auto	**Negative**
327/321	32	Classroom #209	Wood	Baseboard	Brown	Fair	Wall "A" East	0.1	Auto	**Negative**
328/322	32	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" East	0.0	Auto	**Negative**
329/323	32	Chalkboard	Slate	Surface	Black	Fair	Wall "A" East	0.0	Auto	**Negative**
330/324	32	Window	Wood	Frame	Brown	Fair	Wall "C" West	0.1	Auto	**Negative**
331/325	32	Classroom #209	Wood	Crown Molding	Beige	Intact	Wall "A" East	0.2	Auto	**Negative**
332/326	32	Classroom #209	Plaster	Ceiling	White	Intact	Ceiling - East	0.0	Auto	**Negative**
333/327	32	Classroom #209	Plaster	Wall	Ivory	Intact	Wall "A" East	0.2	Auto	**Negative**
334/328	32	Classroom #209	Plaster	Wall	Ivory	Intact	Wall "B" South	0.1	Auto	**Negative**
335/329	32	Classroom #209	Plaster	Wall	Ivory	Intact	Wall "C" West	0.5	Auto	**Negative**
336/330	32	Classroom #209	Plaster	Wall	Ivory	Intact	Wall "D" North	0.3	Auto	**Negative**
337/331	32	Classroom #209	Metal	Side	Ivory	Intact	Ceiling - East	0.0	Auto	**Negative**
		XRF Calibration								

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 2nd FL School & Annex	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:11 AM	
XRF INTERNAL REPORT NUMBER: 11/29/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:05 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		XRF Calibration								
1		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
2		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
3		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
224		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
225		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
226		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
338		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
339		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
340		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
--END--	----------	--END OF UNIT--	----------	--END--	----------	--END--	----------	--END--	----------	--END--

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM	
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		2ndStory - School								
4 / 1	33	Classroom #208	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
5 / 2	33	Classroom #208	Wood	Baseboard	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
6 / 3	33	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
7 / 4	33	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	**Negative**
8 / 5	33	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.2	Auto	**Negative**
9 / 6	33	Classroom #208	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	**Negative**
10 / 7	33	Classroom #208	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	**Negative**
11 / 8	33	Classroom #208	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	**Negative**
12 / 9	33	Classroom #208	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	**Negative**
13 / 10	33	Classroom #208	Plaster	Wall	Beige	Intact	Wall "C" North	0.5	Auto	**Negative**
14 / 11	33	Classroom #208	Plaster	Wall	Beige	Intact	Wall "D" East	0.1	Auto	**Negative**
15 / 12	33	Light Fixture	Metal	Side	Beige	Intact	Ceiling - South	0.1	Auto	**Negative**
16 / 13	33	West Staircase	Plaster	Wall	Ivory	Intact	Wall "B" East	0.3	Auto	**Negative**
17 / 14	34	West Staircase	Plaster	Ceiling	White	Intact	Ceiling - East	0.2	Auto	**Negative**
18 / 15	34	West Staircase	Wood	Baseboard	Beige	Fair	Wall "B" East	0.1	Auto	**Negative**
19 / 16	34	Stairs - Down	Wood	Rail Cap	Brown	Fair	Center	0.2	Auto	**Negative**
20 / 17	34	Stairs - Down	Wood	Handrail	Brown	Fair	Center	0.1	Auto	**Negative**
21 / 18	34	Stairs - Down	Wood	Handrail	Brown	Fair	Wall "D" West	0.1	Auto	**Negative**
22 / 19	34	1.5 Landing - Window	Wood	Frame	Ivory	Fair	Wall "A" North	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
23 / 20	34	1.5 Landing - Window	Plaster	Window Stool	Ivory	Intact	Wall "A" North	0.1	Auto	Negative
24 / 21	34	1.5 Landing - W. Stairs	Wood	Baseboard	Beige	Fair	Wall "A" North	0.0	Auto	Negative
25 / 22	35	Classroom #207	Wood	Transom	Brown	Fair	Wall "A" South	0.0	Auto	Negative
26 / 23	35	Classroom #207	Wood	Baseboard	Brown	Fair	Wall "A" South	0.0	Auto	Negative
27 / 24	35	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.1	Auto	Negative
28 / 25	35	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.2	Auto	Negative
29 / 26	35	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.2	Auto	Negative
30 / 27	35	Classroom #207	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.1	Auto	Negative
31 / 28	35	Classroom #207	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	Negative
32 / 29	35	Classroom #207	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	Negative
33 / 30	35	Classroom #207	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	Negative
34 / 31	35	Classroom #207	Plaster	Wall	Beige	Intact	Wall "C" North	0.4	Auto	Negative
35 / 32	35	Classroom #207	Plaster	Wall	Beige	Intact	Wall "D" East	0.4	Auto	Negative
36 / 33	35	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	Negative
37 / 34	36	Classroom #206	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	Negative
38 / 35	36	Classroom #206	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
39 / 36	36	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
40 / 37	36	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
41 / 38	36	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
42 / 39	36	Classroom #206	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
43 / 40	36	Classroom #206	Plaster	Ceiling	White	Intact	Ceiling - South	0.2	Auto	Negative
44 / 41	36	Classroom #206	Plaster	Wall	Beige	Intact	Wall "A" South	0.3	Auto	Negative
45 / 42	36	Classroom #206	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	Negative
46 / 43	36	Classroom #206	Plaster	Wall	Beige	Intact	Wall "C" North	0.3	Auto	Negative
47 / 44	36	Classroom #206	Plaster	Wall	Beige	Intact	Wall "D" East	0.2	Auto	Negative
48 / 45	36	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.2	Auto	Negative
49 / 46	36	Surface Wire Raceway	Metal	Cover	Ivory	Intact	Wall "A" South	0.1	Auto	Negative
50 / 47	37	Classroom #205 - Light	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	Negative
51 / 48	37	Classroom #205	Wood	Door	Brown	Fair	Wall "A" South	0.1	Auto	Negative
52 / 49	37	Classroom #205	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
53 / 50	37	Chalkboard	Wood	Frame	Brown	Fair	Wall "A" South	0.4	Auto	Negative
54 / 51	37	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
55 / 52	37	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
56 / 53	37	Classroom #205	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	Negative
57 / 54	37	Classroom #205	Plaster	Ceiling	White	Intact	Ceiling - South	0.5	Auto	Negative
58 / 55	37	Classroom #205	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	Negative
59 / 56	37	Classroom #205	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	Negative
60 / 57	37	Classroom #205	Plaster	Wall	Beige	Intact	Wall "C" North	0.4	Auto	Negative
61 / 58	37	Classroom #205	Plaster	Wall	Beige	Intact	Wall "D" East	0.0	Auto	Negative
62 / 59	37	Buildout	Drywall	Wall	Ivory	Intact	Wall "A" North	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
63 / 60	37	Door to Library	Wood	Door	Brown	Fair	Wall "D" East	0.1	Auto	Negative
64 / 61	38	Library	Wood	Transom	Brown	Intact	Wall "A" South	0.1	Auto	Negative
65 / 62	38	Library	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	Negative
66 / 63	38	Library	Plaster	Ceiling	White	Intact	Ceiling - South	0.0	Auto	Negative
67 / 64	38	Library	Plaster	Wall	Beige	Intact	Wall "A" South	0.8	Auto	Negative
68 / 65	38	Library-Above Shelves	Plaster	Wall	Beige	Intact	Wall "B" West	1.0	Auto	Positive
69 / 66	38	Library	Plaster	Wall	Beige	Intact	Wall "C" North	0.7	Auto	Negative
70 / 67	38	Library	Plaster	Wall	Beige	Intact	Wall "D" East	0.8	Auto	Negative
71 / 68	38	Library	Wood	Baseboard	Brown	Fair	Wall "C" North	0.1	Auto	Negative
72 / 69	38	Window	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
73 / 70	38	Bookshelf	Wood	Shelf	Brown	Fair	Wall "C" North	0.1	Auto	Negative
74 / 71	38	Historic Clock	Wood	Frame	Brown	Fair	Wall "D" East	0.1	Auto	Negative
75 / 72	38	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	Negative
76 / 73	38	Flag Mount	Wood	Plate	Ivory	Intact	Wall "B" West	0.2	Auto	Negative
77 / 74	39	Media Room #204	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	Negative
78 / 75	39	Media Room #204	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
79 / 76	39	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
80 / 77	39	Doorway to Library	Wood	Left Door Jamb	Brown	Fair	Wall "B" West	0.1	Auto	Negative
81 / 78	39	Media Room #204	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	Negative
82 / 79	39	Media Room #204	Plaster	Ceiling	White	Intact	Ceiling - South	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
83 / 80	39	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	**Negative**
84 / 81	39	Media Room #204	Plaster	Wall	Beige	Intact	Wall "A" South	0.2	Auto	**Negative**
85 / 82	39	Media Room #204	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	**Negative**
86 / 83	39	Media Room #204	Plaster	Wall	Beige	Intact	Wall "C" North	0.3	Auto	**Negative**
87 / 84	39	Media Room #204	Plaster	Wall	Beige	Intact	Wall "D" East	0.0	Auto	**Negative**
88 / 85	39	Older Surface Wire Mold	Metal	Raceway Side	Brown	Intact	Wall "C" North	0.2	Auto	**Negative**
89 / 86	40	Classroom #203	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
90 / 87	40	Classroom #203	Wood	Baseboard	Brown	Fair	Wall "A" South	0.2	Auto	**Negative**
91 / 88	40	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**
92 / 89	40	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	**Negative**
93 / 90	40	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.2	Auto	**Negative**
94 / 91	40	Classroom #203	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.0	Auto	**Negative**
95 / 92	40	Classroom #203	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	**Negative**
96 / 93	40	Classroom #203	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	**Negative**
97 / 94	40	Classroom #203	Plaster	Wall	Beige	Intact	Wall "B" West	0.4	Auto	**Negative**
98 / 95	40	Classroom #203	Plaster	Wall	Beige	Fair	Wall "C" North	0.3	Auto	**Negative**
99 / 96	40	Classroom #203	Plaster	Wall	Beige	Intact	Wall "D" East	0.5	Auto	**Negative**
100 / 97	40	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	**Negative**
101 / 98	41	Classroom #202	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**
102 / 99	41	Classroom #202	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM	
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
103/100	41	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
104/101	41	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	**Negative**
105/102	41	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	**Negative**
106/103	41	Classroom #202	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.1	Auto	**Negative**
107/104	41	Classroom #202	Plaster	Ceiling	White	Intact	Ceiling - South	0.3	Auto	**Negative**
108/105	41	Classroom #202	Plaster	Wall	Beige	Intact	Wall "A" South	0.3	Auto	**Negative**
109/106	41	Classroom #202	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	**Negative**
110/107	41	Classroom #202	Plaster	Wall	Beige	Intact	Wall "C" North	0.2	Auto	**Negative**
111/108	41	Classroom #202	Plaster	Wall	Beige	Fair	Wall "D" East	0.3	Auto	**Negative**
112/109	41	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.0	Auto	**Negative**
		1st Floor Annex								
113/110	42	Annex North Entry	Metal	Center Jamb	Black	Fair	Wall "A" North	0.4	Auto	**Negative**
114/111	42	Foyer / Elevator	Metal	Door	Black	Fair	Wall "B" East	0.2	Auto	**Negative**
115/112	42	Foyer / Elevator	Metal	Left Door Jamb	Black	Fair	Wall "B" East	0.1	Auto	**Negative**
116/113	42	Stairs	Metal	Post	Black	Fair	Wall "A" North	0.1	Auto	**Negative**
117/114	42	Fire Suppression	Metal	Water Pipe	Black	Fair	Under Stairs	0.1	Auto	**Negative**
118/115	42	3-Gang Windows	Metal	Frame	Charcoal	Fair	Wall "C" South	0.4	Auto	**Negative**
119/116	42	Doors to Cafeteria	Metal	Frame	Charcoal	Fair	Wall "C" South	0.3	Auto	**Negative**
120/117	42	Doors to Cafeteria	Drywall	Ceiling	Ivory	Intact	Ceiling - South	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
121/118	42	Foyer / Elevator	Drywall	Wall	Beige	Intact	Wall "B" East	0.1	Auto	Negative
122/119	43	Storage #104	Drywall	Wall	Beige	Intact	Wall "B" North	0.1	Auto	Negative
123/120	43	Storage #104	Metal	Left Door Jamb	Black	Intact	Wall "B" North	0.1	Auto	Negative
124/121	44	Elevator Closet #103	Metal	Left Door Jamb	Salmon	Intact	Wall "A" South	0.1	Auto	Negative
125/122	44	Elevator Closet #103	Drywall	Wall	Beige	Fair	Wall "A" South	0.1	Auto	Negative
126/123	44	Reservoir Tank	Metal	Side	Black	Intact	Wall "B" West	0.0	Auto	Negative
127/124	45	Cafeteria #101	Metal	Left Door Jamb	Black	Fair	Wall "A" North	0.1	Auto	Negative
128/125	45	East Entry	Metal	Left Door Jamb	Black	Fair	Wall "B" East	0.1	Auto	Negative
129/126	45	West Exit	Metal	Left Door Jamb	Black	Fair	Wall "D" West	0.1	Auto	Negative
130/127	45	Cafeteria #101	Metal	Left Door	Black	Fair	Wall "D" West	0.3	Auto	Negative
131/128	45	Doorway to Connector Hall	Metal	Left Door	Black	Fair	Wall "D" West	0.1	Auto	Negative
132/129	45	Doorway to Connector Hall	Metal	Left Door Jamb	Black	Fair	Wall "D" West	0.2	Auto	Negative
133/130	45	Cafeteria #101	Drywall	Wall	Beige	Intact	Wall "A" North	0.2	Auto	Negative
134/131	45	Cafeteria #101	Drywall	Wall	Beige	Intact	Wall "B" East	0.1	Auto	Negative
135/132	45	Cafeteria #101	Drywall	Wall	Beige	Intact	Wall "C" South	0.1	Auto	Negative
136/133	45	Cafeteria #101	Drywall	Wall	Beige	Intact	Wall "D" West	0.2	Auto	Negative
137/134	45	Furrdown	Drywall	Ceiling	Beige	Intact	Ceiling - North	0.2	Auto	Negative
138/135	45	Cafeteria #101	Ceramic Tile	Floor	Ivory	Intact	Floor - South	0.4	Auto	Negative
139/136	45	Cafeteria #101	Ceramic Tile	Floor	Red	Intact	Floor - South	0.2	Auto	Negative
140/137	46	Unisex Restroom	Metal	Left Door Jamb	Beige	Fair	Wall "A" West	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
141/138	46	Unisex Restroom	Drywall	Wall	Beige	Intact	Wall "C" East	0.2	Auto	Negative
142/139	46	Unisex Restroom	Ceramic Tile	Wainscot	Ivory	Intact	Wall "B" North	0.2	Auto	Negative
143/140	46	Unisex Restroom	Ceramic Tile	Wainscot	Green	Intact	Wall "B" North	0.3	Auto	Negative
144/141	46	Unisex Restroom	Ceramic Tile	Floor	Brown	Intact	Floor - North	0.2	Auto	Negative
145/142	47	Prep Room	Ceramic Tile	Wainscot	Green	Intact	Wall "A" North	0.4	Auto	Negative
146/143	47	Prep Room	Ceramic Tile	Wainscot	Ivory	Intact	Wall "A" North	0.3	Auto	Negative
147/144	47	Door to Cafeteria	Metal	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
148/145	47	Door to Kitchen	Metal	Left Door Jamb	Brown	Fair	Wall "D" West	0.2	Auto	Negative
149/146	47	Prep Room	Drywall	Wall	White	Intact	Wall "D" West	0.1	Auto	Negative
150/147	48	Kitchen	Ceramic Tile	Floor	Gray	Intact	Floor - North	0.1	Auto	Negative
151/148	48	Rear Entry	Metal	Door	Brown	Fair	Wall "D" South	0.1	Auto	Negative
152/149	48	Rear Entry	Metal	Left Door Jamb	Beige	Fair	Wall "D" South	0.2	Auto	Negative
153/150	48	Power Panel	Metal	Cover	Gray	Fair	Wall "C" East	0.1	Auto	Negative
154/151	49	Room #113 - Custodian	Metal	Left Door Jamb	Beige	Fair	Wall "A" West	0.1	Auto	Negative
155/152	49	Room #113 - Custodian	Drywall	Wall	Beige	Intact	Wall "B" North	0.1	Auto	Negative
156/153	50	Room #112 - Dry Storage	Metal	Left Door Jamb	Beige	Fair	Wall "C" East	0.1	Auto	Negative
157/154	51	Room #114 - Office	Metal	Left Door Jamb	Beige	Fair	Wall "A" East	0.2	Auto	Negative
158/155	51	Window	Metal	Frame	Beige	Fair	Wall "D" North	0.2	Auto	Negative
159/156	51	Room #114 - Office	Drywall	Wall	Ivory	Fair	Wall "D" North	0.1	Auto	Negative
160/157	51	Panel #15	Metal	Cover	Ivory	Fair	Wall "A" East	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
161/158	48	Kitchen - Floor Drain	Metal	Drain	White	Poor	Floor - West	0.5	Auto	Negative
162/159	52	Locked Room	Metal	Left Door Jamb	Beige	Fair	Wall "A" West	0.1	Auto	Negative
163/160	53	Room #111 - Lockers	Metal	Left Door Jamb	Beige	Fair	Wall "A" West	0.2	Auto	Negative
164/161	53	Room #111	Drywall	Wall	Beige	Fair	Wall "A" West	0.1	Auto	Negative
165/162	54	Unisex Restroom	Metal	Left Door Jamb	Beige	Intact	Wall "A" West	0.1	Auto	Negative
166/163	48	Kitchen - Gas Line	Metal	Vertical Pipe	Red	Fair	Center - West	0.1	Auto	Negative
167/164	55	Washroom Door to Kitchen	Metal	Left Door Jamb	Beige	Fair	Wall "B" East	0.2	Auto	Negative
168/165	55	Dishwash Room	Drywall	Wall	Ivory	Fair	Wall "B" East	0.1	Auto	Negative
169/166	55	Door to Cafeteria	Metal	Left Door Jamb	Charcoal	Intact	Wall "A" North	0.1	Auto	Negative
170/167	55	Dishwash Room	Ceramic Tile	Wall	White	Intact	Wall "C" South	0.2	Auto	Negative
171/168	55	Dishwash Room	Ceramic Tile	Wall	Green	Intact	Wall "C" South	0.2	Auto	Negative
172/169	55	Dishwash Room	Ceramic Tile	Wall	Blue	Intact	Wall "C" South	0.2	Auto	Negative
173/170	55	Dishwash Room	Ceramic Tile	Wall	Red	Intact	Wall "C" South	0.2	Auto	Negative
174/171	55	Dishwash Room	Ceramic Tile	Wall	Yellow	Intact	Wall "C" South	0.3	Auto	Negative
175/172	56	Connector Hallway	Drywall	Wall	Beige	Intact	Wall "A" East	0.1	Auto	Negative
176/173	56	Connector Hallway	Drywall	Ceiling	White	Intact	Ceiling - East	0.2	Auto	Negative
177/174	56	Access Panel	Metal	Cover	White	Intact	Ceiling - East	0.0	Auto	Negative
178/175	56	Window	Metal	Frame	Charcoal	Intact	Wall "D" North	0.1	Auto	Negative
179/176	56	Exit Doors	Metal	Left Door Jamb	Black	Intact	Wall "B" South	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM	
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		1st Floor School								
180/177	57	East/West Hall 1st Floor	Wood	Baseboard	Beige	Fair	Wall "A" North	0.1	Auto	**Negative**
181/178	57	Locker #31	Metal	Frame	Salmon	Fair	Wall "A" North	0.0	Auto	**Negative**
182/179	57	East / West Hall	Plaster	Wall	Beige	Intact	Wall "A" North	0.1	Auto	**Negative**
183/180	57	East / West Hall	Drywall	Wall	Beige	Intact	Wall "B" East	0.2	Auto	**Negative**
184/181	57	East / West Hall	Plaster	Wall	Beige	Intact	Wall "C" South	0.2	Auto	**Negative**
185/182	57	East / West Hall	Plaster	Wall	Beige	Intact	Wall "D" West	0.3	Auto	**Negative**
186/183	57	Windows	Wood	Frame	Brown	Fair	Wall "D" West	0.1	Auto	**Negative**
187/184	58	East North Entry	Metal	Left Door	Brown	Fair	Wall "A" North	0.1	Auto	**Negative**
188/185	58	East North Entry	Metal	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	**Negative**
189/186	58	East North Entry	Ceramic Tile	Floor	Beige	Intact	Floor - Center	0.1	Auto	**Negative**
190/187	58	Decorative	Ceramic Tile	Floor	Orange	Intact	Floor - Center	0.0	Auto	**Negative**
191/188	58	Decorative	Ceramic Tile	Floor	Gray	Intact	Floor - Center	0.1	Auto	**Negative**
192/189	58	East North Entry	Plaster	Wall	Beige	Intact	Wall "C" South	0.1	Auto	**Negative**
193/190	58	East North Entry	Plaster	Ceiling	White	Intact	Ceiling - Center	0.3	Auto	**Negative**
194/191	58	Light Fixture	Metal	Frame	Beige	Fair	Wall "C" South	0.2	Auto	**Negative**
195/192	58	East North Entry	Metal	Baseboard	Brown	Fair	Wall "C" South	0.6	Auto	**Negative**
196/193	59	South East Entry	Metal	Left Door	Brown	Fair	Wall "A" South	0.2	Auto	**Negative**
197/194	59	South East Entry	Metal	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	**Negative**
198/195	59	South East Foyer	Ceramic Tile	Floor	Beige	Intact	Floor - Center	0.2	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
199/196	59	South East Foyer	Plaster	Wall	Beige	Intact	Wall "A" South	0.5	Auto	Negative
200/197	59	South East Foyer	Plaster	Ceiling	White	Intact	Ceiling - South	0.5	Auto	Negative
201/198	57	East / West Hall	Wood	Frame	Beige	Intact	Wall "C" South	0.1	Auto	Negative
202/199	57	Decorative	Wood	Fascia	Brown	Intact	Wall "C" South	0.0	Auto	Negative
203/200	57	Wire Raceway	Metal	Cover	Beige	Intact	Wall "C" South	0.2	Auto	Negative
204/201	57	Light Fixture	Metal	Side	White	Intact	Ceiling - Center	0.2	Auto	Negative
208/202	60	Main Entry	Metal	Left Door	Brown	Fair	Wall "A" North	0.1	Auto	Negative
209/203	60	Main Entry	Metal	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	Negative
210/204	60	Foyer	Wood	Baseboard	Beige	Fair	Wall "B" East	0.1	Auto	Negative
211/205	60	Foyer	Plaster	Wall	Ivory	Intact	Wall "B" East	0.3	Auto	Negative
212/206	60	Foyer	Plaster	Ceiling	White	Intact	Ceiling - East	0.2	Auto	Negative
213/207	60	Foyer	Wood	Crown Molding	Beige	Intact	Wall "B" East	0.1	Auto	Negative
214/208	61	South West Entry	Metal	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	Negative
215/209	61	South West Entry	Metal	Left Door	Brown	Fair	Wall "A" South	0.0	Auto	Negative
216/210	61	South West Foyer	Ceramic Tile	Floor	Beige	Intact	Floor - Center	0.1	Auto	Negative
217/211	61	South West Foyer	Plaster	Wall	Beige	Intact	Wall "B" West	0.4	Auto	Negative
218/212	61	South West Foyer	Plaster	Ceiling	Beige	Intact	Ceiling - South	0.4	Auto	Negative
219/213	62	West North Entry	Metal	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	Negative
220/214	62	West North Entry	Metal	Left Door	Brown	Fair	Wall "A" North	0.0	Auto	Negative
221/215	62	West North Entry	Ceramic Tile	Floor	Beige	Intact	Floor - Center	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
222/216	62	West North Foyer	Plaster	Wall	Beige	Fair	Wall "B" East	0.3	Auto	Negative
223/217	62	West North Foyer	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
224/218	62	West North Foyer	Metal	Baseboard	Brown	Fair	Wall "C" South	0.2	Auto	Negative
225/219	63	Classroom #101	Wood	Door	Brown	Fair	Wall "A" South	0.0	Auto	Negative
226/220	63	Classroom #101	Wood	Baseboard	Brown	Fair	Wall "A" South	0.2	Auto	Negative
227/221	63	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
228/222	63	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
229/223	63	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.0	Auto	Negative
230/224	63	Classroom #101	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.3	Auto	Negative
231/225	63	Classroom #101	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	Negative
232/226	63	Classroom #101	Plaster	Wall	Beige	Intact	Wall "A" South	0.4	Auto	Negative
233/227	63	Classroom #101	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	Negative
234/228	63	Classroom #101	Plaster	Wall	Beige	Intact	Wall "C" North	0.5	Auto	Negative
235/229	63	Classroom #101	Plaster	Wall	Beige	Intact	Wall "D" East	0.1	Auto	Negative
236/230	63	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - South	0.0	Auto	Negative
237/231	63	Control Box	Metal	Cover	Beige	Intact	Wall "A" South	0.1	Auto	Negative
238/232	63	Surface Raceway	Metal	Side	Ivory	Intact	Wall "A" South	0.1	Auto	Negative
239/233	64	Girl's (Ladies) Restroom	Wood	Door	Brown	Fair	Wall "A" North	0.1	Auto	Negative
240/234	64	Girl's Restroom - Window	Wood	Left Frame	Ivory	Fair	Wall "B" East	0.9	Auto	Negative
241/235	64	Girl's Restroom - Window	Wood	Right Frame	Ivory	Intact	Wall "B" East	1.0	Auto	Positive

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
242/236	64	Girl's Restroom	Ceramic Tile	Wall	White	Intact	Wall "A" North	0.2	Auto	Negative
243/237	64	Girl's Restroom	Ceramic Tile	Red Wall	Red	Intact	Wall "A" North	0.2	Auto	Negative
244/238	64	Girl's Restroom	Ceramic Tile	Yellow Wall	Yellow	Intact	Wall "A" North	0.1	Auto	Negative
245/239	64	Girl's Restroom	Ceramic Tile	Blue Wall	Blue	Intact	Wall "A" North	0.2	Auto	Negative
246/240	64	Decorative	Ceramic Tile	Floor	Red	Intact	Floor - North	0.1	Auto	Negative
247/241	64	Girl's Restroom	Ceramic Tile	Floor	Gray	Intact	Floor - North	0.0	Auto	Negative
248/242	64	Girl's Restroom	Ceramic Tile	Floor	Beige	Intact	Floor - North	0.0	Auto	Negative
249/243	65	East North/South Hall	Wood	Baseboard	Beige	Fair	Wall "B" East	0.1	Auto	Negative
250/244	65	East North/South Hall	Wood	Crown Molding	Beige	Intact	Wall "B" East	0.2	Auto	Negative
251/245	65	East North/South Hall	Plaster	Wall	Beige	Intact	Wall "B" East	0.2	Auto	Negative
252/246	65	East North/South Hall	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	Negative
253/247	66	Classroom #100 - Hall	Plaster	Ceiling	White	Intact	Ceiling - North	0.1	Auto	Negative
254/248	66	Door to Hall	Wood	Transom	Beige	Intact	Wall "A" North	0.2	Auto	Negative
255/249	66	Classroom #100 - Hall	Wood	Baseboard	Beige	Fair	Wall "A" North	0.2	Auto	Negative
256/250	66	Classroom #100 - Hall	Wood	Chair Rail	Beige	Fair	Wall "A" North	0.1	Auto	Negative
257/251	66	Window	Wood	Frame	Ivory	Intact	Wall "D" West	0.2	Auto	Negative
258/252	66	Classroom #100 - Hall	Plaster	Wall	Beige	Intact	Wall "A" North	0.4	Auto	Negative
259/253	67	Workroom	Wood	Door	Beige	Intact	Wall "A" West	0.2	Auto	Negative
260/254	68	Classroom #100	Wood	Baseboard	Beige	Fair	Wall "A" North	0.2	Auto	Negative
261/255	68	Classroom #100	Wood	Chair Rail	Beige	Fair	Wall "A" North	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
262/256	68	Bulletin Board	Wood	Frame	Beige	Intact	Wall "A" North	0.3	Auto	Negative
263/257	68	Conduit	Metal	Horizontal Conduit	Beige	Intact	Wall "A" North	0.1	Auto	Negative
264/258	68	Heater Grate	Metal	Grate	Beige	Fair	Wall "A" North	0.5	Auto	Negative
265/259	68	Windows	Wood	Window Sill	Beige	Intact	Wall "D" West	0.4	Auto	Negative
266/260	68	Window	Wood	Frame	Ivory	Intact	Wall "D" West	0.2	Auto	Negative
267/261	68	Fireplace	Plaster	Hearth	Red	Intact	Wall "C" South	0.4	Auto	Negative
268/262	68	Bench	Wood	Seat	Beige	Fair	Wall "C" South	0.1	Auto	Negative
269/263	68	Classroom #100	Wood	Wainscot	Beige	Fair	Wall "C" South	0.1	Auto	Negative
270/264	68	Classroom #100	Wood	Crown Molding	Beige	Intact	Wall "D" West	0.3	Auto	Negative
271/265	68	Upper Wall	Plaster	Wall	White	Intact	Wall "D" West	0.1	Auto	Negative
272/266	68	Classroom #100	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
273/267	68	Classroom #100	Plaster	Wall	Beige	Intact	Wall "A" North	0.4	Auto	Negative
274/268	68	Classroom #100	Plaster	Wall	Beige	Intact	Wall "B" East	0.2	Auto	Negative
275/269	68	Classroom #100	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative
276/270	68	Classroom #100	Plaster	Wall	Beige	Intact	Wall "D" West	0.1	Auto	Negative
277/271	68	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - West	0.2	Auto	Negative
278/272	69	East Entry Foyer	Metal	Left Door Jamb	Brown	Fair	Wall "A" East	0.0	Auto	Negative
279/273	69	East Entry Foyer	Metal	Door	Brown	Fair	Wall "A" East	0.2	Auto	Negative
280/274	69	East Entry Foyer	Wood	Baseboard	Beige	Fair	Wall "A" East	0.1	Auto	Negative
281/275	69	East Entry Foyer	Wood	Chair Rail	Beige	Fair	Wall "A" East	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
282/276	69	East Entry Foyer	Plaster	Wall	Beige	Intact	Wall "A" East	0.3	Auto	Negative
283/277	69	East Entry Foyer	Plaster	Ceiling	White	Intact	Ceiling - Center	0.1	Auto	Negative
284/278	70	Coat Room	Wood	Top Door Jamb	Beige	Fair	Wall "A" East	0.1	Auto	Negative
285/279	70	Coat Room	Wood	Shelf	Beige	Intact	Wall "C" West	0.0	Auto	Negative
286/280	70	Coat Room	Wood	Baseboard	Beige	Intact	Wall "C" West	0.1	Auto	Negative
287/281	70	Coat Room	Plaster	Wall	Beige	Intact	Wall "C" West	0.2	Auto	Negative
288/282	70	Coat Room	Plaster	Ceiling	White	Intact	Ceiling - Center	0.2	Auto	Negative
289/283	71	Restroom	Wood	Door	Beige	Intact	Wall "A" South	0.2	Auto	Negative
290/284	71	Window	Wood	Frame	Beige	Intact	Wall "D" East	0.4	Auto	Negative
291/285	71	Restroom	Wood	Chair Rail	Beige	Intact	Wall "D" East	0.2	Auto	Negative
292/286	71	Restroom	Plaster	Wainscot	Beige	Poor	Wall "C" North	0.1	Auto	Negative
293/287	71	Restroom	Plaster	Wall	Ivory	Intact	Wall "A" South	0.2	Auto	Negative
294/288	71	Restroom	Plaster	Wall	Ivory	Intact	Wall "B" West	0.2	Auto	Negative
295/289	71	Restroom	Plaster	Wall	Ivory	Intact	Wall "C" North	0.1	Auto	Negative
296/290	71	Restroom	Plaster	Wall	Ivory	Intact	Wall "D" East	0.4	Auto	Negative
297/291	71	Restroom	Ceramic Tile	Floor	Green	Intact	Floor - South	0.1	Auto	Negative
298/292	71	E. Entry Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" South	**14.0**	Auto	**Caution**
299/293	72	Classroom #102	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	Negative
300/294	72	Classroom #102	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
301/295	72	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
302/296	72	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
303/297	72	Window	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
304/298	72	Classroom #102	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	Negative
305/299	72	Classroom #102	Plaster	Ceiling	White	Intact	Ceiling - South	0.2	Auto	Negative
306/300	72	Classroom #102	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	Negative
307/301	72	Classroom #102	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	Negative
308/302	72	Classroom #102	Plaster	Wall	Beige	Intact	Wall "C" North	0.4	Auto	Negative
309/303	72	Classroom #102	Plaster	Wall	Beige	Intact	Wall "D" East	0.1	Auto	Negative
310/304	72	Light Fixture	Metal	Side	Ivory	Intact	Ceiling - South	0.1	Auto	Negative
311/305	73	Classroom #112 - Light	Metal	Side	Ivory	Intact	Ceiling - North	0.1	Auto	Negative
312/306	73	Classroom #112	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
313/307	73	Classroom #112	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	Negative
314/308	73	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.0	Auto	Negative
315/309	73	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
316/310	73	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.0	Auto	Negative
317/311	73	Classroom #112	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.1	Auto	Negative
318/312	73	Classroom #112	Plaster	Ceiling	White	Intact	Ceiling - North	0.2	Auto	Negative
319/313	73	Classroom #112	Plaster	Wall	Beige	Intact	Wall "A" North	0.2	Auto	Negative
320/314	73	Classroom #112	Plaster	Wall	Beige	Intact	Wall "B" East	0.2	Auto	Negative
321/315	73	Classroom #112	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
322/316	73	Classroom #112	Plaster	Wall	Beige	Intact	Wall "D" West	0.4	Auto	**Negative**
323/317	74	Classroom #103	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**
324/318	74	Classroom #103	Wood	Baseboard	Brown	Fair	Wall "A" South	0.2	Auto	**Negative**
325/319	74	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**
326/320	74	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	**Negative**
327/321	74	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.0	Auto	**Negative**
328/322	74	Classroom #103	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.2	Auto	**Negative**
329/323	74	Classroom #103	Plaster	Ceiling	White	Intact	Ceiling - South	0.4	Auto	**Negative**
330/324	74	Classroom #103	Plaster	Wall	Beige	Intact	Wall "A" South	0.3	Auto	**Negative**
331/325	74	Classroom #103	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	**Negative**
332/326	74	Classroom #103	Plaster	Wall	Beige	Fair	Wall "C" North	0.4	Auto	**Negative**
333/327	74	Classroom #103	Plaster	Wall	Beige	Intact	Wall "D" East	0.2	Auto	**Negative**
334/328	74	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - South	0.0	Auto	**Negative**
335/329	74	Air Vent	Metal	Register	Silver	Poor	Wall "A" South	0.0	Auto	**Negative**
336/330	75	Classroom #111 - Light	Metal	Side	Ivory	Fair	Ceiling - North	0.0	Auto	**Negative**
337/331	75	Classroom #111	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	**Negative**
338/332	75	Classroom #111	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	**Negative**
339/333	75	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.0	Auto	**Negative**
340/334	75	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	**Negative**
341/335	75	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.1	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
342/336	75	Classroom #111	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.1	Auto	Negative
343/337	75	Classroom #111	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
344/338	75	Classroom #111	Plaster	Wall	Beige	Intact	Wall "A" North	0.3	Auto	Negative
345/339	75	Classroom #111	Plaster	Wall	Beige	Intact	Wall "B" East	0.3	Auto	Negative
346/340	75	Classroom #111	Plaster	Wall	Beige	Intact	Wall "C" South	0.5	Auto	Negative
347/341	75	Classroom #111	Plaster	Wall	Beige	Fair	Wall "D" West	0.2	Auto	Negative
348/342	76	Janitor Closet	Wood	Door	Ivory	Fair	Wall "A" North	0.1	Auto	Negative
349/343	76	Janitor Closet	Wood	Baseboard	Ivory	Fair	Wall "B" East	0.0	Auto	Negative
350/344	76	Janitor Closet	Plaster	Wall	Ivory	Fair	Wall "B" East	0.5	Auto	Negative
351/345	76	Power Panel	Metal	Cover	Gray	Poor	Wall "B" East	0.4	Auto	Negative
352/346	77	Boys' Restroom	Wood	Door	Brown	Fair	Wall "A" North	0.2	Auto	Negative
353/347	77	Boys' Restroom Windows	Wood	Frame	Ivory	Fair	Wall "C" South	1.1	Auto	Positive
354/348	77	Boys' Restroom	Ceramic Tile	Window Sill	Ivory	Intact	Wall "C" South	0.3	Auto	Negative
355/349	77	Decorative	Ceramic Tile	Wall	Red	Intact	Wall "B" East	0.3	Auto	Negative
356/350	77	Decorative	Ceramic Tile	Wall	Yellow	Intact	Wall "B" East	0.2	Auto	Negative
357/351	77	Decorative	Ceramic Tile	Wall	Blue	Intact	Wall "B" East	0.3	Auto	Negative
358/352	77	Decorative	Ceramic Tile	Floor	Blue	Intact	Floor - North	0.1	Auto	Negative
359/353	77	Decorative	Ceramic Tile	Floor	Gray	Intact	Floor - North	0.1	Auto	Negative
360/354	77	Decorative	Ceramic Tile	Floor	Beige	Intact	Floor - North	0.0	Auto	Negative
361/355	78	Classroom #104	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
362/356	78	Classroom #104	Wood	Baseboard	Brown	Fair	Wall "A" South	0.0	Auto	Negative
363/357	78	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
364/358	78	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
365/359	78	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.0	Auto	Negative
366/360	78	Classroom #104	Wood	Crown Molding	Beige	Intact	Wall "C" South	0.2	Auto	Negative
367/361	78	Classroom #104	Plaster	Ceiling	White	Intact	Ceiling - South	0.2	Auto	Negative
368/362	78	Classroom #104	Plaster	Wall	Beige	Intact	Wall "A" South	0.2	Auto	Negative
369/363	78	Classroom #104	Plaster	Wall	Beige	Intact	Wall "B" West	0.1	Auto	Negative
370/364	78	Classroom #104	Plaster	Wall	Beige	Intact	Wall "C" North	0.4	Auto	Negative
371/365	78	Classroom #104	Plaster	Wall	Beige	Intact	Wall "D" East	0.3	Auto	Negative
372/366	78	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - South	0.0	Auto	Negative
373/367	79	Room East of Office	Metal	Fixture Side	Ivory	Fair	Ceiling - South	0.1	Auto	Negative
374/368	79	Room East of Office	Wood	Left Door Jamb	Beige	Fair	Wall "A" East	0.1	Auto	Negative
375/369	79	Room East of Office	Wood	Baseboard	Beige	Fair	Wall "A" East	0.2	Auto	Negative
376/370	79	Window	Wood	Frame	Ivory	Intact	Wall "B" North	0.0	Auto	Negative
377/371	79	Outlets	Metal	Outlet Box	Beige	Intact	Wall "C" East	0.0	Auto	Negative
378/372	79	Cabinet / Hutch	Wood	Facing	Beige	Fair	Wall "D" South	0.3	Auto	Negative
379/373	79	Cabinets	Wood	Facing	Brown	Fair	Wall "D" South	0.1	Auto	Negative
380/374	79	Room East of Office	Plaster	Wall	Beige	Intact	Wall "A" West	0.1	Auto	Negative
381/375	79	Room East of Office	Plaster	Wall	Beige	Intact	Wall "B" North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Cafeteria	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 9:25 AM	
XRF INTERNAL REPORT NUMBER: 11/30/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 4:35 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
382/376	79	Room East of Office	Plaster	Wall	Beige	Intact	Wall "C" East	0.0	Auto	**Negative**
383/377	79	Room East of Office	Plaster	Wall	Beige	Intact	Wall "D" South	0.1	Auto	**Negative**
384/378	79	Room East of Office	Plaster	Ceiling	White	Intact	Ceiling - West	0.2	Auto	**Negative**
385/379	79	Room East of Office	Wood	Floor	Brown	Fair	Wall "A" West	0.1	Auto	**Negative**
386/380	79	Room East of Office	Metal	Cover	Ivory	Intact	Wall "A" West	0.1	Auto	**Negative**
		XRF Calibration								
1		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
2		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
3		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
205		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
206		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
207		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.9	Auto	
387		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.8	Auto	**RETEST**
388		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	**RETEST**
389		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	0.8	Auto	**RETEST**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Cafeteria
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 9:25 AM
XRF INTERNAL REPORT NUMBER: 11/30/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 4:35 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		XRF Calibration								
390		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
391		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
392		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
--END--	----------	--END OF UNIT--	----------	--END--	----------	--END--	----------	--END--	----------	--END--

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Audtrm	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 8:45 AM	
XRF INTERNAL REPORT NUMBER: 12/02/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:41 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
		1st Level - School								
4 / 1	80	Auditorium East Door	Wood	Left Door	Beige	Fair	Wall "A" North	0.1	Auto	**Negative**
5 / 2	80	Auditorium East Door	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	**Negative**
6 / 3	80	Auditorium East Door	Wood	Left Door Casing	Blue	Fair	Wall "A" North	0.2	Auto	**Negative**
7 / 4	80	Auditorium	Wood	Baseboard	Blue	Poor	Wall "A" North	0.2	Auto	**Negative**
8 / 5	80	Auditorium	Wood	Chair Rail	Blue	Fair	Wall "A" North	0.1	Auto	**Negative**
9 / 6	80	Auditorium	Wood	Wainscot	Blue	Intact	Wall "A" North	0.4	Auto	**Negative**
10 / 7	80	Auditorium	Plaster	Wall	Ivory	Fair	Wall "A" North	0.2	Auto	**Negative**
11 / 8	80	Auditorium	Plaster	Wall	Ivory	Fair	Wall "B" East	0.5	Auto	**Negative**
12 / 9	80	Windows	Wood	Window Sill	Blue	Poor	Wall "B" East	0.2	Auto	**Negative**
13 / 10	80	Windows	Wood	Frame	Blue	Fair	Wall "B" East	0.2	Auto	**Negative**
14 / 11	80	Stage	Plaster	Wall	Beige	Fair	Wall "C" South	0.1	Auto	**Negative**
15 / 12	80	West Exit Side	Plaster	Wall	Ivory	Poor	Wall "D" West	0.0	Auto	**Negative**
16 / 13	80	Windows	Wood	Frame	Blue	Fair	Wall "D" West	0.1	Auto	**Negative**
17 / 14	80	Balcony Supports	Plaster	Post	Blue	Fair	North / West	0.1	Auto	**Negative**
18 / 15	80	Last Row Center	Wood	Arm Rest	Brown	Fair	North / West	0.0	Auto	**Negative**
19 / 16	80	Last Row Center	Wood	Back	Brown	Fair	North / West	0.2	Auto	**Negative**
20 / 17	80	Last Row Center	Metal	Seat Bottom	Brown	Fair	North / West	0.1	Auto	**Negative**
21 / 18	80	Decorative	Metal	Side Plate	Brown	Fair	North / West	0.1	Auto	**Negative**
22 / 19	80	Connector	Metal	Frame	Brown	Fair	North / West	0.2	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
23 / 20	80	Air Diffuser	Metal	Vent	Beige	Fair	Ceiling - NWC	0.2	Auto	Negative
24 / 21	80	Auditorium	Plaster	Balcony Ceiling	White	Intact	Ceiling - West	0.3	Auto	Negative
25 / 22	80	Balcony	Wood	Lower Trim	Blue	Intact	Wall "A" North	0.2	Auto	Negative
26 / 23	80	Above Southwest Exit	Plaster	Above Door	Ivory	Intact	Wall "D" West	0.4	Auto	Negative
27 / 24	80	Air Return	Wood	Grate Frame	Ivory	Intact	Wall "D" West	0.3	Auto	Negative
28 / 25	80	Historic Speaker	Wood	Side	Brown	Intact	Wall "D" West	0.0	Auto	Negative
29 / 26	80-A	East Vestibule	Plaster	Ceiling	Blue	Intact	Ceiling - South	0.3	Auto	Negative
30 / 27	80-A	East Vestibule	Plaster	Wall	Blue	Intact	Wall "A" West	0.2	Auto	Negative
31 / 28	80-A	East Vestibule	Plaster	Wall	Blue	Fair	Wall "C" East	0.6	Auto	Negative
32 / 29	80-A	East Exit Door	Metal	Door	Brown	Fair	Wall "C" East	0.0	Auto	Negative
33 / 30	80-A	East Exit Door	Metal	Left Door Jamb	Brown	Fair	Wall "C" East	0.1	Auto	Negative
34 / 31	80-A	Door to Auditorium	Wood	Door	Beige	Fair	Wall "A" West	0.3	Auto	Negative
35 / 32	80-A	Door to Auditorium	Wood	Left Door Jamb	Blue	Fair	Wall "A" West	0.3	Auto	Negative
36 / 33	80-A	Steps to Stage	Wood	Stringer	White	Fair	Wall "A" West	0.2	Auto	Negative
37 / 34	80-A	Steps to Stage	Wood	Riser	White	Fair	Wall "C" South	0.1	Auto	Negative
38 / 35	80-A	Steps to Stage	Wood	Tread	Brown	Fair	Wall "C" South	0.1	Auto	Negative
39 / 36	80-A	Left Railing	Metal	Rail Cap	White	Fair	Wall "C" East	0.4	Auto	Negative
40 / 37	80-B	Stage - Steps	Wood	Frame	Blue	Fair	Wall "C" South	0.2	Auto	Negative
41 / 38	80-B	Stage Floor	Wood	Front Trim	Brown	Fair	Floor - North	0.1	Auto	Negative
42 / 39	80-B	Stage Floor	Wood	Floor	Brown	Fair	Floor - North	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
43 / 40	80-B	Trim Below Floor	Wood	Trim	Blue	Fair	Wall "C" South	0.2	Auto	Negative
44 / 41	80-B	Stage	Wood	East Trim	Blue	Intact	Wall "A" North	0.2	Auto	Negative
45 / 42	80-B	Stage	Plaster	East Side Wall	Beige	Fair	Wall "A" North	0.3	Auto	Negative
46 / 43	80-B	Stage	Wood	1/4 Round	Brown	Fair	Wall "A" North	0.3	Auto	Negative
47 / 44	80-B	Stage	Wood	Baseboard	Black	Poor	Wall "B" East	0.3	Auto	Negative
48 / 45	80-B	Stage	Wood	Crown Molding	Beige	Fair	Wall "B" East	0.0	Auto	Negative
49 / 46	80-B	Rope Peg Holder	Wood	Thick Plank	Brown	Fair	Wall "B" East	0.2	Auto	Negative
50 / 47	80-B	Pipe Holder	Metal	Rack	Bare	Rust	Wall "C" South	0.1	Auto	Negative
51 / 48	80-B	Stage by Closet	Fired Tile	Wall	Blue	Intact	Wall "C" South	0.0	Auto	Negative
52 / 49	80-B	Power Panel	Metal	Cover	Gray	Poor	Wall "C" South	0.1	Auto	Negative
53 / 50	80-B	East Closet	Wood	Door	Beige	Fair	Wall "A" West	0.1	Auto	Negative
54 / 51	80-B	East Closet	Wood	Shelf	Beige	Fair	Wall "C" East	0.1	Auto	Negative
55 / 52	80-B	East Closet	Wood	Wall	Beige	Fair	Wall "B" North	0.2	Auto	Negative
56 / 53	80-B	East Closet	Brick	Wall	Beige	Intact	Wall "C" East	0.0	Auto	Negative
57 / 54	80-B	Vertical Pipe	Metal	Pipe	Black	Fair	Wall "D" South	0.1	Auto	Negative
58 / 55	80-C	East Dressing Room	Wood	Door	Beige	Fair	Wall "A" West	0.2	Auto	Negative
59 / 56	80-C	East Dressing Room	Wood	Top Jamb	Black	Fair	Wall "A" West	0.1	Auto	Negative
60 / 57	80-C	East Dressing Room	Wood	Baseboard	Beige	Poor	Wall "C" East	0.3	Auto	Negative
61 / 58	80-C	Windows	Wood	Frame	Ivory	Fair	Wall "C" East	0.3	Auto	Negative
62 / 59	80-C	East Dressing Room	Wood	Crown Molding	Beige	Intact	Wall "A" West	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
63 / 60	80-C	East Dressing Room	Plaster	Ceiling	Ivory	Poor	Ceiling - West	0.4	Auto	Negative
64 / 61	80-C	East Dressing Room	Plaster	Wall	Beige	Fair	Wall "A" West	0.2	Auto	Negative
65 / 62	80-C	East Dressing Room	Plaster	Wall	Beige	Fair	Wall "B" North	0.2	Auto	Negative
66 / 63	80-C	East Dressing Room	Plaster	Wall	Beige	Poor	Wall "C" East	0.2	Auto	Negative
67 / 64	80-C	East Dressing Room	Plaster	Wall	Beige	Fair	Wall "D" West	0.3	Auto	Negative
68 / 65	80-C	Conduit	Metal	Outlet Box	Beige	Fair	Wall "B" North	0.2	Auto	Negative
69 / 66	80-C	Closet	Wood	Door	Beige	Fair	Wall "A" North	0.1	Auto	Negative
70 / 67	80-C	Closet	Wood	Baseboard	Beige	Fair	Wall "C" South	0.2	Auto	Negative
71 / 68	80-C	Closet	Wood	Floor	Brown	Poor	Floor - Center	0.1	Auto	Negative
72 / 69	80-C	Closet	Plaster	Wall	Ivory	Fair	Wall "C" South	0.4	Auto	Negative
73 / 70	80-D	Restroom	Plaster	Wall	Beige	Fair	Wall "A" North	0.3	Auto	Negative
74 / 71	80-D	Restroom	Plaster	Wall	Beige	Intact	Wall "B" East	0.3	Auto	Negative
75 / 72	80-D	Restroom	Plaster	Wall	Beige	Intact	Wall "C" South	0.2	Auto	Negative
76 / 73	80-D	Restroom	Plaster	Wall	Beige	Intact	Wall "D" West	0.2	Auto	Negative
77 / 74	80-D	Restroom	Plaster	Ceiling	Ivory	Fair	Ceiling - Center	0.1	Auto	Negative
78 / 75	80-D	Restroom	Wood	Door	Beige	Fair	Wall "A" North	0.1	Auto	Negative
79 / 76	80-D	Restroom	Wood	Threshold	Brown	Fair	Wall "A" North	0.5	Auto	Negative
80 / 77	80-D	Windows	Wood	Frame	Ivory	Fair	Wall "C" South	0.2	Auto	Negative
81 / 78	80-E	West Dressing Room	Wood	Top Door Jamb	Black	Fair	Wall "A" East	0.0	Auto	Negative
82 / 79	80-E	West Dressing Room	Wood	Floor	Light Brown	Fair	Floor - East	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
83 / 80	80-E	West Dressing Room	Wood	Baseboard	Beige	Fair	Wall "A" East	0.3	Auto	Negative
84 / 81	80-E	West Dressing Room	Wood	Crown Molding	Beige	Fair	Wall "A" East	0.3	Auto	Negative
85 / 82	80-E	Windows	Wood	Frame	Ivory	Poor	Wall "C" West	0.3	Auto	Negative
86 / 83	80-E	Air Vent	Metal	Register	Silver	Fair	Ceiling - NWC	0.1	Auto	Negative
87 / 84	80-E	Light Fixture	Metal	Side	White	Fair	Ceiling - Center	0.3	Auto	Negative
88 / 85	80-E	West Dressing Room	Plaster	Ceiling	Ivory	Poor	Ceiling - East	0.2	Auto	Negative
89 / 86	80-E	West Dressing Room	Plaster	Wall	Beige	Fair	Wall "A" East	0.2	Auto	Negative
90 / 87	80-E	West Dressing Room	Plaster	Wall	Beige	Fair	Wall "B" South	0.3	Auto	Negative
91 / 88	80-E	West Dressing Room	Plaster	Wall	Beige	Fair	Wall "C" West	0.4	Auto	Negative
92 / 89	80-E	West Dressing Room	Plaster	Wall	Beige	Fair	Wall "D" North	0.4	Auto	Negative
93 / 90	80-E	Small Closet	Plaster	Wall	Ivory	Fair	Wall "C" South	0.3	Auto	Negative
94 / 91	80-E	Small Closet	Wood	Shelf	Beige	Fair	Wall "C" South	0.1	Auto	Negative
95 / 92	80-E	Small Closet	Wood	Left Door Casing	Beige	Fair	Wall "A" North	0.2	Auto	Negative
96 / 93	80-E	Small Closet	Wood	Floor	Dark Brown	Fair	Floor - North	0.1	Auto	Negative
97 / 94	80-E	Large Closet	Wood	Shelf	Beige	Fair	Wall "C" North	0.0	Auto	Negative
98 / 95	80-E	Large Closet	Wood	Baseboard	Beige	Fair	Wall "C" North	0.2	Auto	Negative
99 / 96	80-E	Large Closet	Wood	Door	Beige	Fair	Wall "A" South	0.1	Auto	Negative
100 / 97	80-E	Large Closet	Plaster	Wall	Beige	Fair	Wall "C" North	0.3	Auto	Negative
101 / 98	80-F	Restroom	Wood	Door	Beige	Fair	Wall "A" North	0.1	Auto	Negative
102 / 99	80-F	Restroom	Wood	Threshold	Brown	Fair	Wall "A" North	0.3	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
103/100	80-F	Windows	Wood	Frame	Ivory	Fair	Wall "C" South	0.1	Auto	Negative
104/101	80-F	Restroom	Concrete	Floor	Brown	Poor	Floor - South	0.1	Auto	Negative
105/102	80-F	Restroom	Plaster	Wall	Beige	Fair	Wall "A" North	0.3	Auto	Negative
106/103	80-F	Restroom	Plaster	Wall	Beige	Fair	Wall "B" East	0.4	Auto	Negative
107/104	80-F	Restroom	Plaster	Wall	Beige	Fair	Wall "C" South	0.4	Auto	Negative
108/105	80-F	Restroom	Plaster	Wall	Beige	Fair	Wall "D" West	0.4	Auto	Negative
109/106	80-F	Restroom	Plaster	Ceiling	Beige	Fair	Ceiling - Center	0.3	Auto	Negative
110/107	80-G	West Exit Vestibule	Plaster	Ceiling	Blue	Intact	Ceiling - South	0.1	Auto	Negative
111/108	80-G	West Exit Vestibule	Plaster	Wall	Blue	Intact	Wall "C" West	0.6	Auto	Negative
112/109	80-G	West Exit Vestibule	Plaster	Wall	Blue	Intact	Wall "D" North	0.6	Auto	Negative
113/110	80-G	Door to Auditorium	Wood	Door	Beige	Fair	Wall "A" East	0.1	Auto	Negative
114/111	80-G	Door to Auditorium	Wood	Left Door Jamb	Blue	Fair	Wall "A" East	0.2	Auto	Negative
115/112	80-G	West Exit Door	Metal	Left Door Jamb	Brown	Fair	Wall "C" West	0.0	Auto	Negative
116/113	80-G	West Exit Door	Metal	Door	Brown	Fair	Wall "C" West	0.0	Auto	Negative
117/114	80-B	Steps to Stage	Metal	Handrail	Blue	Poor	Wall "C" West	0.5	Auto	Negative
118/115	80-B	Steps to Stage	Wood	Stringer	Blue	Fair	Wall "A" East	0.2	Auto	Negative
119/116	80-B	Steps to Stage	Wood	Riser	Blue	Fair	Wall "B" South	0.0	Auto	Negative
120/117	80-B	Steps to Stage	Wood	Tread	Brown	Fair	Wall "B" South	0.1	Auto	Negative
121/118	80-B	Steps to Stage	Fired Tile	Wall	Blue	Fair	Wall "B" South	0.0	Auto	Negative
122/119	80	Auditorium Entrance	Wood	Left Door	Beige	Fair	Wall "A" North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Audtrm	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 8:45 AM	
XRF INTERNAL REPORT NUMBER: 12/02/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:41 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
123/120	80	Auditorium Entrance	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
124/121	81	Office	Wood	Door	Brown	Fair	Wall "A" East	0.0	Auto	Negative
125/122	81	Office	Wood	Baseboard	Brown	Fair	Wall "D" North	0.2	Auto	Negative
126/123	81	Windows	Wood	Frame	Brown	Intact	Wall "D" North	0.1	Auto	Negative
127/124	81	Office	Wood	Crown Molding	Beige	Intact	Wall "B" South	0.2	Auto	Negative
128/125	81	Office	Plaster	Ceiling	White	Intact	Ceiling - South	0.3	Auto	Negative
129/126	81	Office	Plaster	Wall	Beige	Intact	Wall "A" East	0.3	Auto	Negative
130/127	81	Office	Plaster	Wall	Beige	Intact	Wall "B" South	0.4	Auto	Negative
131/128	81	Office	Plaster	Wall	Beige	Intact	Wall "C" West	0.3	Auto	Negative
132/129	81	Office	Plaster	Wall	Beige	Intact	Wall "D" North	0.4	Auto	Negative
133/130	81	Door to Next Office	Wood	Left Door Jamb	Brown	Fair	Wall "C" West	0.2	Auto	Negative
134/131	81	Closet	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
135/132	81	Closet	Wood	Baseboard	Brown	Fair	Wall "B" East	0.0	Auto	Negative
136/133	81	Closet	Plaster	Wall	Beige	Fair	Wall "B" East	0.2	Auto	Negative
137/134	82	Principal's Office	Wood	Door	Brown	Fair	Wall "A" South	0.0	Auto	Negative
138/135	82	Principal's Office	Wood	Baseboard	Brown	Fair	Wall "C" North	0.2	Auto	Negative
139/136	82	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.2	Auto	Negative
140/137	82	Door to Reception	Wood	Door	Brown	Fair	Wall "D" East	0.1	Auto	Negative
141/138	82	Door to Reception	Wood	Crown Molding	Beige	Intact	Wall "D" East	0.3	Auto	Negative
142/139	82	Principal's Office	Plaster	Ceiling	White	Intact	Ceiling - East	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
143/140	82	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - East	0.1	Auto	Negative
144/141	81	Office - Light Fixture	Metal	Side	Ivory	Fair	Ceiling - East	0.1	Auto	Negative
145/142	82	Principal's Office	Plaster	Wall	Ivory	Intact	Wall "A" South	0.2	Auto	Negative
146/143	82	Principal's Office	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	Negative
147/144	82	Principal's Office	Plaster	Wall	Beige	Intact	Wall "C" North	0.2	Auto	Negative
148/145	82	Principal's Office	Plaster	Wall	Beige	Intact	Wall "D" East	0.2	Auto	Negative
149/146	82	Closet	Plaster	Wall	Beige	Fair	Wall "C" South	0.1	Auto	Negative
150/147	82	Closet	Wood	Shelf	Beige	Fair	Wall "C" South	0.3	Auto	Negative
151/148	82	Closet	Wood	Baseboard	Ivory	Fair	Wall "C" South	0.1	Auto	Negative
152/149	82	Closet	Wood	Door	Brown	Fair	Wall "A" North	0.0	Auto	Negative
153/150	82-A	Safe	Metal	Door	Green	Fair	Wall "A" West	0.6	Auto	Negative
154/151	82-A	Safe	Metal	Threshold	Black	Poor	Floor - West	0.6	Auto	Negative
155/152	82-A	Safe	Metal	Top Jamb	Green	Intact	Wall "A" West	0.7	Auto	Negative
156/153	82-A	Safe	Plaster	Wall	Beige	Fair	Wall "B" North	0.2	Auto	Negative
157/154	82-B	Principal's Restroom	Plaster	Wall	Beige	Intact	Wall "A" East	0.5	Auto	Negative
158/155	82-B	Principal's Restroom	Plaster	Wall	Beige	Intact	Wall "B" South	0.5	Auto	Negative
159/156	82-B	Lower Wall	Plaster	Wall	Beige	Intact	Wall "C" West	0.4	Auto	Negative
160/157	82-B	Principal's Restroom	Plaster	Wall	Beige	Intact	Wall "D" North	0.5	Auto	Negative
161/158	82-B	Principal's Restroom	Plaster	Ceiling	Beige	Intact	Ceiling - Center	0.5	Auto	Negative
162/159	82-B	Air Vent	Metal	Register	Beige	Intact	Ceiling - West	0.3	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
163/160	82-B	Principal's Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" East	**14.4**	Auto	**Caution**
164/161	82-B	Principal's Restroom	Wood	Door	Brown	Fair	Wall "A" East	0.1	Auto	**Negative**
165/162	82-B	Principal's Restroom	Wood	Chair Rail	Beige	Intact	Wall "A" East	0.3	Auto	**Negative**
166/163	83	Assistant Principal's Office	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	**Negative**
167/164	83	Assistant Principal's Office	Wood	Baseboard	Beige	Intact	Wall "A" South	0.1	Auto	**Negative**
168/165	83	Windows	Wood	Frame	Ivory	Intact	Wall "C" North	0.5	Auto	**Negative**
169/166	83	Cabinet	Wood	Door	Beige	Intact	Wall "C" North	0.0	Auto	**Negative**
170/167	83	Wire Mold Structure	Metal	Cover	Ivory	Intact	Wall "D" East	0.3	Auto	**Negative**
171/168	83	Cabinet	Metal	Cover	Beige	Intact	Wall "A" South	0.0	Auto	**Negative**
172/169	83	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - East	0.1	Auto	**Negative**
173/170	83	Assistant Principal's Office	Wood	Crown Molding	Beige	Intact	Wall "D" East	0.7	Auto	**Negative**
174/171	83	Assistant Principal's Office	Plaster	Ceiling	White	Intact	Ceiling - East	0.3	Auto	**Negative**
175/172	83	Assistant Principal's Office	Plaster	Wall	Beige	Intact	Wall "A" South	0.3	Auto	**Negative**
176/173	83	Assistant Principal's Office	Plaster	Wall	Beige	Intact	Wall "B" West	0.3	Auto	**Negative**
177/174	83	Assistant Principal's Office	Plaster	Wall	Beige	Intact	Wall "C" North	0.3	Auto	**Negative**
178/175	83	Assistant Principal's Office	Plaster	Wall	Beige	Intact	Wall "D" East	0.5	Auto	**Negative**
179/176	83	Closet	Plaster	Wall	Ivory	Intact	Wall "C" West	0.2	Auto	**Negative**
180/177	83	Closet	Wood	Baseboard	Ivory	Intact	Wall "C" West	0.3	Auto	**Negative**
181/178	83	Closet	Wood	Door	Beige	Intact	Wall "A" East	0.2	Auto	**Negative**
182/179	83	Shower	Wood	Casing	Beige	Intact	Wall "A" West	0.3	Auto	**Negative**

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
183/180	83	Shower	Ceramic Tile	Threshold	Ivory	Fair	Floor - West	0.3	Auto	Negative
184/181	83	Asst. P. Shower / Closet	Ceramic Tile	Threshold	Black	Intact	Floor - West	**16.0**	Auto	**Caution**
185/182	83	Shower / Closet	Ceramic Tile	Floor	Beige	Intact	Floor - West	0.2	Auto	Negative
186/183	83	Wainscot	Ceramic Tile	Wall	Beige	Intact	Wall "C" East	0.3	Auto	Negative
187/184	83	Closet	Wood	Shelf	Beige	Intact	Wall "C" East	0.0	Auto	Negative
188/185	83	Upper Wall	Plaster	Wall	Beige	Intact	Wall "B" North	0.2	Auto	Negative
189/186	83	Closet	Plaster	Wall	Beige	Intact	Wall "C" East	0.2	Auto	Negative
190/187	83	Air Vent	Metal	Register	Beige	Intact	Ceiling - East	0.3	Auto	Negative
191/188	83	Closet	Plaster	Ceiling	Beige	Intact	Ceiling - Center	0.1	Auto	Negative
192/189	83	Asst. P. Shower Wainscot	Ceramic Tile	Top Trim	Black	Intact	Wall "A" West	**21.7**	Auto	**Caution**
193/190	84	Girls' Restroom	Ceramic Tile	Wall	White	Intact	Wall "D" West	0.3	Auto	Negative
194/191	84	Decorative	Ceramic Tile	Wall	Blue	Intact	Wall "D" West	0.4	Auto	Negative
195/192	84	Decorative	Ceramic Tile	Wall	Red	Intact	Wall "D" West	0.3	Auto	Negative
196/193	84	Decorative	Ceramic Tile	Wall	Yellow	Intact	Wall "D" West	0.3	Auto	Negative
197/194	84	Decorative	Ceramic Tile	Floor	Red	Intact	Floor - North	0.2	Auto	Negative
198/195	84	Decorative	Ceramic Tile	Floor	Gray	Intact	Floor - North	0.0	Auto	Negative
199/196	84	Girls' Restroom	Ceramic Tile	Floor	Beige	Intact	Floor - North	0.0	Auto	Negative
200/197	84	Girls' Restroom	Wood	Door	Brown	Fair	Wall "A" North	0.1	Auto	Negative
201/198	84	Windows	Wood	Frame	Ivory	Fair	Wall "C" South	0.1	Auto	Negative
205/199	85	Classroom #105	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
206/200	85	Classroom #105	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
207/201	85	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
208/202	85	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.1	Auto	Negative
209/203	85	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
210/204	85	Classroom #105	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.0	Auto	Negative
211/205	85	Classroom #105	Plaster	Ceiling	White	Intact	Ceiling - South	0.2	Auto	Negative
212/206	85	Classroom #105	Plaster	Wall	Beige	Intact	Wall "A" South	0.1	Auto	Negative
213/207	85	Classroom #105	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	Negative
214/208	85	Classroom #105	Plaster	Wall	Beige	Fair	Wall "C" North	0.5	Auto	Negative
215/209	85	Classroom #105	Plaster	Wall	Beige	Intact	Wall "D" East	0.4	Auto	Negative
216/210	85	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - South	0.1	Auto	Negative
217/211	86	Classroom #106 - Light	Metal	Side	Ivory	Fair	Ceiling - South	0.1	Auto	Negative
218/212	86	Classroom #106	Wood	Door	Brown	Fair	Wall "A" South	0.1	Auto	Negative
219/213	86	Classroom #106	Wood	Baseboard	Brown	Fair	Wall "A" South	0.2	Auto	Negative
220/214	86	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.0	Auto	Negative
221/215	86	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.1	Auto	Negative
222/216	86	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.1	Auto	Negative
223/217	86	Classroom #106	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.1	Auto	Negative
224/218	86	Classroom #106	Plaster	Ceiling	White	Intact	Ceiling - South	0.1	Auto	Negative
225/219	86	Classroom #106	Plaster	Wall	Beige	Intact	Wall "A" South	0.3	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:41 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
226/220	86	Classroom #106	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	Negative
227/221	86	Classroom #106	Metal	Vertical Pipe	Beige	Fair	Wall "B" West	0.0	Auto	Negative
228/222	86	Classroom #106	Plaster	Wall	Beige	Intact	Wall "C" North	0.3	Auto	Negative
229/223	86	Classroom #106	Plaster	Wall	Beige	Intact	Wall "D" East	0.4	Auto	Negative
230/224	87	Classroom #110	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.0	Auto	Negative
231/225	87	Classroom #110	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	Negative
232/226	87	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.0	Auto	Negative
233/227	87	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
234/228	87	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.0	Auto	Negative
235/229	87	Classroom #110	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.3	Auto	Negative
236/230	87	Classroom #110	Plaster	Ceiling	White	Intact	Ceiling - North	0.3	Auto	Negative
237/231	87	Classroom #110	Plaster	Wall	Beige	Intact	Wall "A" North	0.1	Auto	Negative
238/232	87	Classroom #110	Plaster	Wall	Beige	Intact	Wall "B" East	0.0	Auto	Negative
239/233	87	Classroom #110	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative
240/234	87	Classroom #110	Plaster	Wall	Beige	Intact	Wall "D" West	0.1	Auto	Negative
241/235	87	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - North	0.1	Auto	Negative
242/236	88	Classroom #109 - Light	Metal	Side	Ivory	Fair	Ceiling - North	0.1	Auto	Negative
243/237	88	Classroom #109	Wood	Door	Brown	Fair	Wall "A" North	0.1	Auto	Negative
244/238	88	Classroom #109	Wood	Baseboard	Brown	Fair	Wall "A" North	0.1	Auto	Negative
245/239	88	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" North	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
246/240	88	Chalkboard	Slate	Surface	Black	Fair	Wall "A" North	0.0	Auto	Negative
247/241	88	Windows	Wood	Frame	Brown	Fair	Wall "C" South	0.1	Auto	Negative
248/242	88	Classroom #109	Wood	Crown Molding	Beige	Intact	Wall "A" North	0.1	Auto	Negative
249/243	88	Classroom #109	Plaster	Ceiling	White	Intact	Ceiling - North	0.2	Auto	Negative
250/244	88	Classroom #109	Plaster	Wall	Beige	Intact	Wall "A" North	0.2	Auto	Negative
251/245	88	Classroom #109	Plaster	Wall	Beige	Intact	Wall "B" East	0.2	Auto	Negative
252/246	88	Classroom #109	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative
253/247	88	Classroom #109	Plaster	Wall	Beige	Intact	Wall "D" West	0.3	Auto	Negative
254/248	89	Classroom #107	Wood	Left Door Jamb	Brown	Fair	Wall "A" South	0.1	Auto	Negative
255/249	89	Classroom #107	Wood	Baseboard	Brown	Fair	Wall "A" South	0.1	Auto	Negative
256/250	89	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" South	0.1	Auto	Negative
257/251	89	Chalkboard	Slate	Surface	Black	Fair	Wall "A" South	0.0	Auto	Negative
258/252	89	Windows	Wood	Frame	Brown	Fair	Wall "C" North	0.0	Auto	Negative
259/253	89	Classroom #107	Wood	Crown Molding	Beige	Intact	Wall "A" South	0.3	Auto	Negative
260/254	89	Classroom #107	Plaster	Ceiling	White	Intact	Ceiling - South	0.2	Auto	Negative
261/255	89	Classroom #107	Plaster	Wall	Beige	Intact	Wall "A" South	0.0	Auto	Negative
262/256	89	Classroom #107	Plaster	Wall	Beige	Intact	Wall "B" West	0.2	Auto	Negative
263/257	89	Classroom #107	Plaster	Wall	Beige	Intact	Wall "C" North	0.3	Auto	Negative
264/258	89	Classroom #107	Plaster	Wall	Beige	Intact	Wall "D" East	0.4	Auto	Negative
265/259	89	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - South	0.1	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
266/260	89	Control Cabinet	Metal	Cover	Beige	Intact	Wall "A" South	0.1	Auto	Negative
267/261	90	Clinic	Wood	Door	White	Fair	Wall "A" North	0.0	Auto	Negative
268/262	90	Clinic	Wood	Left Door Jamb	Brown	Fair	Wall "A" North	0.1	Auto	Negative
269/263	90	Clinic	Wood	Baseboard	Beige	Intact	Wall "A" North	0.4	Auto	Negative
270/264	90	Window	Wood	Frame	Beige	Fair	Wall "D" West	0.7	Auto	Negative
271/265	90	Historic Speaker	Wood	Facing	Ivory	Intact	Wall "C" South	0.1	Auto	Negative
272/266	90	Clinic	Wood	Crown Molding	Beige	Intact	Wall "D" West	0.4	Auto	Negative
273/267	90	Air Vent	Metal	Register	Beige	Intact	Wall "D" West	0.3	Auto	Negative
274/268	90	Light Fixture	Metal	Side	White	Intact	Ceiling - Center	0.2	Auto	Negative
275/269	90	Clinic	Plaster	Ceiling	White	Intact	Ceiling - West	0.1	Auto	Negative
276/270	90	Clinic	Plaster	Wall	Beige	Intact	Wall "A" North	0.1	Auto	Negative
277/271	90	Clinic	Plaster	Wall	Beige	Intact	Wall "B" East	0.3	Auto	Negative
278/272	90	Clinic	Plaster	Wall	Brown	Intact	Wall "C" South	0.0	Auto	Negative
279/273	90	Clinic	Plaster	Wall	Beige	Intact	Wall "D" West	0.2	Auto	Negative
280/274	90-A	Restroom	Ceramic Tile	Floor	Green	Intact	Floor - West	0.1	Auto	Negative
281/275	90-A	Clinic Restroom	Ceramic Tile	Baseboard	Black	Intact	Wall "A" West	**14.6**	Auto	**Caution**
282/276	90-A	Restroom	Wood	Door	Beige	Fair	Wall "A" West	0.4	Auto	Negative
283/277	90-A	Restroom	Wood	Chair Rail	Beige	Intact	Wall "A" West	0.2	Auto	Negative
284/278	90-A	Shelves	Wood	Shelf	Beige	Intact	Wall "C" East	0.4	Auto	Negative
285/279	90-A	Air Vent	Metal	Register	Beige	Intact	Ceiling - North	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
286/280	90-A	Restroom	Plaster	Ceiling	Beige	Intact	Ceiling - Center	0.1	Auto	Negative
287/281	90-A	Restroom	Plaster	Wall	Beige	Intact	Wall "A" West	0.2	Auto	Negative
288/282	90-A	Restroom	Plaster	Wall	Beige	Intact	Wall "B" North	0.3	Auto	Negative
289/283	90-A	Restroom	Plaster	Wall	Beige	Intact	Wall "C" East	0.3	Auto	Negative
290/284	90-A	Restroom	Plaster	Wall	Beige	Intact	Wall "D" South	0.2	Auto	Negative
291/285	91	West North/South Hall	Plaster	Wall	Beige	Intact	Wall "B" East	0.4	Auto	Negative
292/286	91	West North/South Hall	Plaster	Wall	Beige	Intact	Wall "D" West	0.3	Auto	Negative
293/287	91	West North/South Hall	Drywall	Wall	Beige	Intact	Wall "C" South	0.2	Auto	Negative
294/288	91	West North/South Hall	Wood	Baseboard	Beige	Fair	Wall "B" East	0.0	Auto	Negative
295/289	91	Windows	Wood	Frame	Brown	Fair	Wall "B" East	0.2	Auto	Negative
296/290	91	Vertical Pipe	Metal	Larger Pipe	Beige	Intact	Wall "B" East	0.3	Auto	Negative
297/291	91	Light Fixture	Metal	Side	White	Intact	Ceiling - South	0.2	Auto	Negative
298/292	91	Lockers #81	Metal	Frame	Brown	Fair	Wall "D" West	0.2	Auto	Negative
299/293	92	End Room Lockers #81	Metal	Frame	Brown	Fair	Wall "D" West	0.1	Auto	Negative
300/294	92	Heater Unit	Metal	Side	Brown	Fair	Ceiling - Center	0.1	Auto	Negative
301/295	92	Light Fixture	Metal	Side	White	Intact	Ceiling - North	0.2	Auto	Negative
302/296	92	End Room	Wood	Door	Brown	Fair	Wall "A" North	0.1	Auto	Negative
303/297	92	End Room	Wood	Baseboard	Beige	Fair	Wall "B" East	0.1	Auto	Negative
304/298	92	Windows	Wood	Frame	Brown	Fair	Wall "B" East	0.1	Auto	Negative
305/299	92	Shelves	Wood	Shelf	Beige	Fair	Wall "D" West	0.2	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Audtrm	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started:	8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished:	3:41 PM
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
306/300	92	Vertical Pipe	Metal	Smaller Pipe	Beige	Fair	Wall "B" East	0.1	Auto	Negative
307/301	92	End Room	Drywall	Wall	Beige	Intact	Wall "A" North	0.3	Auto	Negative
308/302	92	End Room	Plaster	Wall	Beige	Intact	Wall "B" East	0.5	Auto	Negative
309/303	92	End Room	Plaster	Wall	Beige	Intact	Wall "C" South	0.3	Auto	Negative
310/304	92	End Room	Plaster	Wall	Beige	Intact	Wall "D" West	0.3	Auto	Negative
311/305	93	Classroom #108	Plaster	Wall	Beige	Fair	Wall "A" East	0.4	Auto	Negative
312/306	93	Classroom #108	Plaster	Wall	Beige	Fair	Wall "B" South	0.2	Auto	Negative
313/307	93	Classroom #108	Plaster	Wall	Beige	Intact	Wall "C" West	0.4	Auto	Negative
314/308	93	Classroom #108	Plaster	Wall	Beige	Intact	Wall "D" North	0.2	Auto	Negative
315/309	93	Classroom #108	Plaster	Ceiling	White	Intact	Ceiling - East	0.2	Auto	Negative
316/310	93	Classroom #108	Wood	Crown Molding	Beige	Intact	Wall "A" East	0.1	Auto	Negative
317/311	93	Classroom #108	Wood	Left Door Jamb	Brown	Fair	Wall "A" East	0.1	Auto	Negative
318/312	93	Classroom #108	Wood	Baseboard	Brown	Fair	Wall "A" East	0.1	Auto	Negative
319/313	93	Chalkboard	Wood	Chalk Sill	Brown	Fair	Wall "A" East	0.1	Auto	Negative
320/314	93	Chalkboard	Slate	Surface	Black	Fair	Wall "A" East	0.0	Auto	Negative
321/315	93	Windows	Wood	Frame	Brown	Fair	Wall "C" West	0.2	Auto	Negative
322/316	93	Light Fixture	Metal	Side	Ivory	Fair	Ceiling - East	0.0	Auto	Negative
323/317	94	Boys' Restroom	Wood	Door	Brown	Fair	Wall "A" East	0.2	Auto	Negative
324/318	94	Boys' Restroom Windows	Wood	Frame	Ivory	Fair	Wall "C" West	1.2	Auto	Positive
325/319	94	Boys' Restroom	Ceramic Tile	Window Sill	Ivory	Fair	Wall "C" West	0.3	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013	PROPERTY ID: 601 N. Lewis Street, Conroe, TX	Unit No. 1st FL School & Audtrm
RADIATION SOURCE ASSAY DATE: December 25, 2024	RISK ASSESSOR: T. Bazan (TDSHS # 2070001)	Job Started: 8:45 AM
XRF INTERNAL REPORT NUMBER: 12/02/2025	ABATEMENT LEVEL: 1.0 mg/cm2	Job Finished: 3:41 PM

XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
326/320	94	Decorative	Ceramic Tile	Wall	Red	Fair	Wall "B" South	0.2	Auto	Negative
327/321	94	Decorative	Ceramic Tile	Blue Wall	Blue	Intact	Wall "B" South	0.3	Auto	Negative
328/322	94	Decorative	Ceramic Tile	Yellow Wall	Yellow	Intact	Wall "B" South	0.4	Auto	Negative
329/323	94	Decorative	Ceramic Tile	Floor	Beige	Intact	Floor - East	0.0	Auto	Negative
330/324	94	Decorative	Ceramic Tile	Gray Floor	Gray	Intact	Floor - East	0.1	Auto	Negative
331/325	94	Decorative	Ceramic Tile	Blue Floor	Blue	Intact	Floor - East	0.1	Auto	Negative
332/326	95	Janitor Closet	Wood	Door	Ivory	Fair	Wall "A" East	0.0	Auto	Negative
333/327	95	Janitor Closet	Wood	Left Door Jamb	Brown	Fair	Wall "A" East	0.0	Auto	Negative
334/328	95	Janitor Closet	Plaster	Wall	Beige	Intact	Wall "C" West	0.2	Auto	Negative
335/329	Exterior	Roof	Metal	Frame	Gray	Poor	East of Center	0.1	Auto	Negative
336/330	Exterior	Roof	Metal	Cap	Beige	Fair	South	0.5	Auto	Negative
337/331	Exterior	School Roof	Metal	Vent Jack	Bare	-	South	55.0	Auto	Lead-Caution
338/332	Exterior	Roof	Stone	White Wash	Ivory	Fair	North	0.0	Auto	Negative
339/333	Exterior	Roof	Metal	Case	Beige	Poor	Center	0.1	Auto	Negative
340/334	Exterior	Auditorium Roof	Metal	Vent Cover	Brown	Poor	North	0.2	Auto	Negative
341/335	Exterior	Auditorium Roof	Metal	Pole	Beige	Poor	West	0.2	Auto	Negative
342/336	Exterior	Auditorium Roof	Metal	Pole	Beige	Fair	East	0.2	Auto	Negative
343/337	Exterior	Auditorium Roof	Metal	Scupper	Galvanized	Bare	East	0.4	Auto	Negative
344/338	Exterior	Auditorium Roof	Metal	Frame	Red	Poor	East	0.9	Auto	Negative
345/339	Exterior	Auditorium Roof	Metal	Opening	Gray	Poor	South	0.0	Auto	Negative

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

COPYRIGHT 1996-2025
HOUSTON, TEXAS

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

XRF SEQUENTIAL READING FIELD REPORT FORM FOR LEAD-BASED PAINT INSPECTIONS

XRF MANUFACTURER/SERIAL NUMBER: Viken Pb200e s/n #1013					PROPERTY ID: 601 N. Lewis Street, Conroe, TX				Unit No. 1st FL School & Audtrm	
RADIATION SOURCE ASSAY DATE: December 25, 2024					RISK ASSESSOR: T. Bazan (TDSHS # 2070001)				Job Started: 8:45 AM	
XRF INTERNAL REPORT NUMBER: 12/02/2025					ABATEMENT LEVEL: 1.0 mg/cm2				Job Finished: 3:41 PM	
XRF Reading Sample Number	Room Equivalent Number	Room Description Name	Substrate	Component	Paint Film Color	Paint Condition Intact / Fair or Poor	XRF Testing or Confirmatory Sampling Location	Indicated Lead Concentration (mg/cm2)	XRF Testing Mode	LBP Hazard Classification Positive / Negative or Inconclusive
346/340	Exterior	Auditorium Roof	Metal	Cover	Red	Rusted	SWC	0.2	Auto	**Negative**
		XRF Calibration								
1		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
2		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
3		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.1	Auto	
202		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
203		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
204		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
347		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
348		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
349		Calibration	Wood	Test Film	Red	Intact	NIST SRM 1.05	1.0	Auto	
--END--	----------	--END OF UNIT--	----------	--END--	----------	--END--	----------	--END--	----------	--END--

Negative = No LBP found
Lead concentration below
1.0 mg/cm2 or 0.5% by weight

Inconclusive = Lead concentration at or near 1.0 mg/cm2,
confirmatory laboratory sampling indicated

Positive = LBP present
See Lead Hazard Control Plan

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	10:17:10	0	0	T. Bazan	1.0	5	---	1	1	0.9	mg/cm2	0.1	Calibration
11/28/2025	10:17:28	0	0	T. Bazan	1.0	5	---	2	2	1.0	mg/cm2	0.1	Calibration
11/28/2025	10:17:45	0	0	T. Bazan	1.0	5	---	3	3	0.9	mg/cm2	0.1	Calibration
11/28/2025	10:20:48	0	0	T. Bazan	1.0	2	1	4	4	0.0	mg/cm2	0.2	Negative
11/28/2025	10:21:25	0	0	T. Bazan	1.0	2	2	5	5	0.3	mg/cm2	0.2	Negative
11/28/2025	10:21:54	0	0	T. Bazan	1.0	2	3	6	6	0.0	mg/cm2	0.2	Negative
11/28/2025	10:22:17	0	0	T. Bazan	1.0	2	4	7	7	0.0	mg/cm2	0.2	Negative
11/28/2025	10:22:34	30.3149	-95.46199	T. Bazan	1.0	2	5	8	8	0.1	mg/cm2	0.2	Negative
11/28/2025	10:25:23	30.3149	-95.46185	T. Bazan	1.0	2	6	9	9	0.2	mg/cm2	0.2	Negative
11/28/2025	10:25:35	30.3147	-95.46227	T. Bazan	1.0	2	7	10	10	0.1	mg/cm2	0.2	Negative
11/28/2025	10:27:21	30.3151	-95.46152	T. Bazan	1.0	2	8	11	11	0.0	mg/cm2	0.2	Negative
11/28/2025	10:27:49	30.3151	-95.46202	T. Bazan	1.0	2	9	12	12	0.0	mg/cm2	0.2	Negative
11/28/2025	10:28:23	30.3151	-95.46173	T. Bazan	1.0	2	10	13	13	0.1	mg/cm2	0.2	Negative
11/28/2025	10:29:04	30.315	-95.46189	T. Bazan	1.0	2	11	14	14	0.1	mg/cm2	0.2	Negative
11/28/2025	10:30:22	30.315	-95.46189	T. Bazan	1.0	2	12	15	15	0.1	mg/cm2	0.2	Negative
11/28/2025	10:30:52	30.315	-95.46189	T. Bazan	1.0	2	13	16	16	0.2	mg/cm2	0.2	Negative
11/28/2025	10:32:06	30.315	-95.46189	T. Bazan	1.0	2	14	17	17	0.4	mg/cm2	0.2	Negative
11/28/2025	10:33:09	30.315	-95.46189	T. Bazan	1.0	2	15	18	18	0.1	mg/cm2	0.2	Negative
11/28/2025	10:33:24	30.3152	-95.46172	T. Bazan	1.0	2	16	19	19	0.1	mg/cm2	0.2	Negative
11/28/2025	10:34:35	30.3152	-95.46172	T. Bazan	1.0	2	17	20	20	0.0	mg/cm2	0.2	Negative
11/28/2025	10:35:11	30.3149	-95.46212	T. Bazan	1.0	2	18	21	21	0.1	mg/cm2	0.2	Negative
11/28/2025	10:37:05	30.3152	-95.46214	T. Bazan	1.0	2	19	22	22	0.1	mg/cm2	0.2	Negative
11/28/2025	10:37:22	30.3151	-95.46178	T. Bazan	1.0	2	20	23	23	0.1	mg/cm2	0.2	Negative
11/28/2025	10:39:27	30.3151	-95.46142	T. Bazan	1.0	2	21	24	24	0.1	mg/cm2	0.2	Negative
11/28/2025	10:40:30	30.3146	-95.46271	T. Bazan	1.0	2	22	25	25	0.1	mg/cm2	0.2	Negative
11/28/2025	10:40:49	30.315	-95.46162	T. Bazan	1.0	2	23	26	26	0.0	mg/cm2	0.2	Negative
11/28/2025	10:41:25	30.3149	-95.46182	T. Bazan	1.0	2	24	27	27	0.5	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	10:42:22	30.3149	-95.46209	T. Bazan	1.0	2	25	28	28	0.1	mg/cm2	0.2	Negative
11/28/2025	10:43:08	30.3151	-95.46243	T. Bazan	1.0	2	26	29	29	0.0	mg/cm2	0.2	Negative
11/28/2025	10:43:40	30.3153	-95.46178	T. Bazan	1.0	2	27	30	30	0.2	mg/cm2	0.2	Negative
11/28/2025	10:51:07	30.3148	-95.46217	T. Bazan	1.0	2	28	31	31	0.2	mg/cm2	0.2	Negative
11/28/2025	10:51:46	30.3149	-95.46319	T. Bazan	1.0	2	29	32	32	0.0	mg/cm2	0.2	Negative
11/28/2025	10:52:51	30.3151	-95.46165	T. Bazan	1.0	2	30	33	33	0.1	mg/cm2	0.2	Negative
11/28/2025	11:01:30	30.3151	-95.46165	T. Bazan	1.0	2	1	34	34	0.1	mg/cm2	0.2	Negative
11/28/2025	11:01:43	30.3151	-95.46165	T. Bazan	1.0	2	2	35	35	0.4	mg/cm2	0.2	Negative
11/28/2025	11:02:58	30.3151	-95.46165	T. Bazan	1.0	2	3	36	36	0.1	mg/cm2	0.2	Negative
11/28/2025	11:03:46	30.3151	-95.46165	T. Bazan	1.0	2	4	37	37	0.0	mg/cm2	0.2	Negative
11/28/2025	11:03:58	30.3151	-95.46165	T. Bazan	1.0	2	5	38	38	0.2	mg/cm2	0.2	Negative
11/28/2025	11:09:09	30.3151	-95.46165	T. Bazan	1.0	2	6	39	39	0.2	mg/cm2	0.2	Negative
11/28/2025	11:09:18	30.3151	-95.46165	T. Bazan	1.0	2	7	40	40	0.4	mg/cm2	0.2	Negative
11/28/2025	11:09:36	30.3151	-95.46165	T. Bazan	1.0	2	8	41	41	0.3	mg/cm2	0.2	Negative
11/28/2025	11:10:19	30.3151	-95.46165	T. Bazan	1.0	2	9	42	42	0.2	mg/cm2	0.2	Negative
11/28/2025	11:10:30	30.3151	-95.46165	T. Bazan	1.0	2	10	43	43	0.1	mg/cm2	0.2	Negative
11/28/2025	11:12:19	30.3151	-95.46165	T. Bazan	1.0	2	11	44	44	0.1	mg/cm2	0.2	Negative
11/28/2025	11:12:54	30.3151	-95.46165	T. Bazan	1.0	2	12	45	45	0.2	mg/cm2	0.2	Negative
11/28/2025	11:13:48	30.3151	-95.46165	T. Bazan	1.0	2	13	46	46	0.1	mg/cm2	0.2	Negative
11/28/2025	11:14:01	30.3151	-95.46165	T. Bazan	1.0	2	14	47	47	0.0	mg/cm2	0.2	Negative
11/28/2025	11:16:05	30.3151	-95.46165	T. Bazan	1.0	2	15	48	48	0.2	mg/cm2	0.2	Negative
11/28/2025	11:16:46	30.3151	-95.46165	T. Bazan	1.0	2	16	49	49	0.1	mg/cm2	0.2	Negative
11/28/2025	11:16:54	30.3151	-95.46165	T. Bazan	1.0	2	17	50	50	0.2	mg/cm2	0.2	Negative
11/28/2025	11:17:38	30.3151	-95.46165	T. Bazan	1.0	2	18	51	51	0.1	mg/cm2	0.2	Negative
11/28/2025	11:17:48	30.3151	-95.46165	T. Bazan	1.0	2	19	52	52	0.5	mg/cm2	0.2	Negative
11/28/2025	11:19:21	30.3151	-95.46165	T. Bazan	1.0	2	20	53	53	0.1	mg/cm2	0.2	Negative
11/28/2025	11:22:53	30.3151	-95.46165	T. Bazan	1.0	2	21	54	54	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	11:23:05	30.3151	-95.46165	T. Bazan	1.0	2	22	55	55	0.0	mg/cm2	0.2	Negative
11/28/2025	11:23:24	30.3151	-95.46165	T. Bazan	1.0	2	23	56	56	0.5	mg/cm2	0.2	Negative
11/28/2025	11:23:52	30.3151	-95.46165	T. Bazan	1.0	2	24	57	57	0.5	mg/cm2	0.2	Negative
11/28/2025	11:24:31	30.3151	-95.46165	T. Bazan	1.0	2	25	58	58	0.5	mg/cm2	0.2	Negative
11/28/2025	11:25:23	30.3151	-95.46165	T. Bazan	1.0	2	26	59	59	0.5	mg/cm2	0.2	Negative
11/28/2025	11:26:00	0	0	T. Bazan	1.0	2	27	60	60	0.5	mg/cm2	0.2	Negative
11/28/2025	11:48:30	0	0	T. Bazan	1.0	2	28	61	61	0.5	mg/cm2	0.2	Negative
11/28/2025	11:48:57	0	0	T. Bazan	1.0	2	29	62	62	0.1	mg/cm2	0.2	Negative
11/28/2025	11:49:06	0	0	T. Bazan	1.0	2	30	63	63	0.2	mg/cm2	0.2	Negative
11/28/2025	11:53:10	0	0	T. Bazan	1.0	2	31	64	64	0.1	mg/cm2	0.2	Negative
11/28/2025	11:53:22	0	0	T. Bazan	1.0	2	32	65	65	0.4	mg/cm2	0.2	Negative
11/28/2025	11:54:27	0	0	T. Bazan	1.0	2	33	66	66	0.2	mg/cm2	0.2	Negative
11/28/2025	11:55:17	0	0	T. Bazan	1.0	2	34	67	67	0.1	mg/cm2	0.2	Negative
11/28/2025	11:57:56	0	0	T. Bazan	1.0	2	35	68	68	0.3	mg/cm2	0.2	Negative
11/28/2025	11:58:07	0	0	T. Bazan	1.0	2	36	69	69	0.1	mg/cm2	0.2	Negative
11/28/2025	11:59:07	0	0	T. Bazan	1.0	2	37	70	70	0.1	mg/cm2	0.2	Negative
11/28/2025	11:59:19	0	0	T. Bazan	1.0	2	38	71	71	0.2	mg/cm2	0.2	Negative
11/28/2025	12:01:14	0	0	T. Bazan	1.0	2	39	72	72	0.4	mg/cm2	0.2	Negative
11/28/2025	12:01:29	0	0	T. Bazan	1.0	2	40	73	73	0.5	mg/cm2	0.2	Negative
11/28/2025	12:01:48	0	0	T. Bazan	1.0	2	41	74	74	0.5	mg/cm2	0.2	Negative
11/28/2025	12:02:02	0	0	T. Bazan	1.0	2	42	75	75	0.1	mg/cm2	0.2	Negative
11/28/2025	12:02:25	0	0	T. Bazan	1.0	2	43	76	76	0.1	mg/cm2	0.2	Negative
11/28/2025	12:09:04	0	0	T. Bazan	1.0	2	44	77	77	0.1	mg/cm2	0.2	Negative
11/28/2025	12:10:10	0	0	T. Bazan	1.0	2	45	78	78	0.1	mg/cm2	0.2	Negative
11/28/2025	12:10:49	30.3149	-95.46156	T. Bazan	1.0	2	46	79	79	0.1	mg/cm2	0.2	Negative
11/28/2025	12:14:34	30.315	-95.46149	T. Bazan	1.0	2	1	80	80	0.0	mg/cm2	0.2	Negative
11/28/2025	12:15:29	30.315	-95.46149	T. Bazan	1.0	2	2	81	81	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	12:15:37	30.3145	-95.46169	T. Bazan	1.0	2	3	82	82	0.0	mg/cm2	0.2	Negative
11/28/2025	12:16:00	30.3151	-95.4614	T. Bazan	1.0	2	4	83	83	0.2	mg/cm2	0.2	Negative
11/28/2025	12:18:13	30.3152	-95.46143	T. Bazan	1.0	2	5	84	84	0.1	mg/cm2	0.2	Negative
11/28/2025	12:19:28	30.3152	-95.46138	T. Bazan	1.0	2	6	85	85	0.3	mg/cm2	0.2	Negative
11/28/2025	12:20:11	30.3151	-95.46143	T. Bazan	1.0	2	7	86	86	0.1	mg/cm2	0.2	Negative
11/28/2025	12:20:59	30.3151	-95.46146	T. Bazan	1.0	2	8	87	87	0.2	mg/cm2	0.2	Negative
11/28/2025	12:21:41	30.3152	-95.46142	T. Bazan	1.0	2	9	88	88	0.1	mg/cm2	0.2	Negative
11/28/2025	12:24:21	30.3152	-95.46138	T. Bazan	1.0	2	10	89	89	0.0	mg/cm2	0.2	Negative
11/28/2025	12:24:35	30.3152	-95.46135	T. Bazan	1.0	2	11	90	90	0.1	mg/cm2	0.2	Negative
11/28/2025	12:25:07	30.3152	-95.46153	T. Bazan	1.0	2	12	91	91	3.7	mg/cm2	0.2	Positive
11/28/2025	12:27:20	30.3152	-95.46153	T. Bazan	1.0	2	13	92	92	0.1	mg/cm2	0.2	Negative
11/28/2025	12:27:29	30.3152	-95.46153	T. Bazan	1.0	2	14	93	93	0.2	mg/cm2	0.2	Negative
11/28/2025	12:28:05	30.3148	-95.46151	T. Bazan	1.0	5	15	94	94	1.2	mg/cm2	0.1	Positive
11/28/2025	12:30:44	30.3148	-95.4615	T. Bazan	1.0	2	16	95	95	0.2	mg/cm2	0.2	Negative
11/28/2025	12:31:37	30.3162	-95.46111	T. Bazan	1.0	2	17	96	96	0.1	mg/cm2	0.2	Negative
11/28/2025	12:33:13	30.3152	-95.46184	T. Bazan	1.0	2	18	97	97	0.2	mg/cm2	0.2	Negative
11/28/2025	12:35:08	30.3155	-95.46175	T. Bazan	1.0	2	19	98	98	0.2	mg/cm2	0.2	Negative
11/28/2025	12:36:54	30.3156	-95.46174	T. Bazan	1.0	2	20	99	99	0.4	mg/cm2	0.2	Negative
11/28/2025	12:38:42	30.3155	-95.46165	T. Bazan	1.0	2	21	100	100	0.2	mg/cm2	0.2	Negative
11/28/2025	12:39:51	30.3155	-95.46162	T. Bazan	1.0	2	22	101	101	0.1	mg/cm2	0.2	Negative
11/28/2025	12:40:00	30.3155	-95.46162	T. Bazan	1.0	2	23	102	102	0.1	mg/cm2	0.2	Negative
11/28/2025	12:40:22	30.3156	-95.46132	T. Bazan	1.0	2	24	103	103	0.1	mg/cm2	0.2	Negative
11/28/2025	12:44:26	30.3156	-95.46131	T. Bazan	1.0	2	25	104	104	0.4	mg/cm2	0.2	Negative
11/28/2025	12:45:06	30.3157	-95.46117	T. Bazan	1.0	2	26	105	105	0.2	mg/cm2	0.2	Negative
11/28/2025	12:45:45	30.3157	-95.46114	T. Bazan	1.0	2	27	106	106	0.2	mg/cm2	0.2	Negative
11/28/2025	12:46:51	30.3155	-95.46132	T. Bazan	1.0	2	28	107	107	0.2	mg/cm2	0.2	Negative
11/28/2025	12:48:09	30.3154	-95.4613	T. Bazan	1.0	2	29	108	108	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	12:49:24	30.3154	-95.46137	T. Bazan	1.0	2	30	109	109	0.0	mg/cm2	0.2	Negative
11/28/2025	12:50:11	30.3152	-95.46133	T. Bazan	1.0	2	31	110	110	0.1	mg/cm2	0.2	Negative
11/28/2025	12:50:30	30.3149	-95.46127	T. Bazan	1.0	2	32	111	111	0.3	mg/cm2	0.2	Negative
11/28/2025	12:52:00	30.3152	-95.46095	T. Bazan	1.0	2	33	112	112	0.3	mg/cm2	0.2	Negative
11/28/2025	12:52:44	30.3152	-95.46095	T. Bazan	1.0	2	34	113	113	0.1	mg/cm2	0.2	Negative
11/28/2025	12:53:06	30.3153	-95.46128	T. Bazan	1.0	2	35	114	114	0.1	mg/cm2	0.2	Negative
11/28/2025	12:54:36	30.3155	-95.46123	T. Bazan	1.0	2	36	115	115	0.1	mg/cm2	0.2	Negative
11/28/2025	12:56:15	30.3155	-95.46093	T. Bazan	1.0	2	37	116	116	0.2	mg/cm2	0.2	Negative
11/28/2025	12:58:16	30.3155	-95.46092	T. Bazan	1.0	2	38	117	117	0.1	mg/cm2	0.2	Negative
11/28/2025	12:58:25	30.3155	-95.46092	T. Bazan	1.0	2	39	118	118	0.1	mg/cm2	0.2	Negative
11/28/2025	12:58:59	30.3155	-95.46094	T. Bazan	1.0	2	40	119	119	0.2	mg/cm2	0.2	Negative
11/28/2025	12:59:08	30.3155	-95.46053	T. Bazan	1.0	2	41	120	120	0.1	mg/cm2	0.2	Negative
11/28/2025	13:02:50	30.3155	-95.46055	T. Bazan	1.0	2	42	121	121	0.1	mg/cm2	0.2	Negative
11/28/2025	13:03:21	30.3155	-95.46062	T. Bazan	1.0	2	43	122	122	0.1	mg/cm2	0.2	Negative
11/28/2025	13:05:02	30.3153	-95.46031	T. Bazan	1.0	2	44	123	123	0.5	mg/cm2	0.2	Negative
11/28/2025	13:09:28	30.3153	-95.46035	T. Bazan	1.0	2	45	124	124	0.1	mg/cm2	0.2	Negative
11/28/2025	13:09:42	30.3152	-95.4604	T. Bazan	1.0	2	46	125	125	0.0	mg/cm2	0.2	Negative
11/28/2025	13:11:04	30.3153	-95.46031	T. Bazan	1.0	2	47	126	126	0.3	mg/cm2	0.2	Negative
11/28/2025	13:12:16	30.3149	-95.46038	T. Bazan	1.0	2	48	127	127	0.1	mg/cm2	0.2	Negative
11/28/2025	13:15:44	30.3149	-95.46037	T. Bazan	1.0	2	49	128	128	0.3	mg/cm2	0.2	Negative
11/28/2025	13:16:58	30.3148	-95.4604	T. Bazan	1.0	2	50	129	129	0.0	mg/cm2	0.2	Negative
11/28/2025	13:17:34	30.3151	-95.46058	T. Bazan	1.0	2	51	130	130	0.5	mg/cm2	0.2	Negative
11/28/2025	13:18:25	30.315	-95.46067	T. Bazan	1.0	2	52	131	131	0.4	mg/cm2	0.2	Negative
11/28/2025	13:19:39	30.3149	-95.46051	T. Bazan	1.0	2	53	132	132	0.1	mg/cm2	0.2	Negative
11/28/2025	13:20:09	30.3149	-95.46037	T. Bazan	1.0	2	54	133	133	0.3	mg/cm2	0.2	Negative
11/28/2025	13:21:16	30.315	-95.46053	T. Bazan	1.0	2	55	134	134	0.2	mg/cm2	0.2	Negative
11/28/2025	13:22:44	30.3149	-95.46052	T. Bazan	1.0	2	56	135	135	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	13:22:53	30.3147	-95.4602	T. Bazan	1.0	2	57	136	136	0.3	mg/cm2	0.2	Negative
11/28/2025	13:25:32	30.3146	-95.46019	T. Bazan	1.0	2	58	137	137	0.1	mg/cm2	0.2	Negative
11/28/2025	13:25:40	30.3145	-95.46022	T. Bazan	1.0	2	59	138	138	0.1	mg/cm2	0.2	Negative
11/28/2025	13:27:17	30.3145	-95.46022	T. Bazan	1.0	2	60	139	139	0.2	mg/cm2	0.2	Negative
11/28/2025	13:27:26	30.3145	-95.46022	T. Bazan	1.0	2	61	140	140	0.0	mg/cm2	0.2	Negative
11/28/2025	13:27:58	30.315	-95.4605	T. Bazan	1.0	2	62	141	141	0.1	mg/cm2	0.2	Negative
11/28/2025	13:30:17	30.315	-95.46071	T. Bazan	1.0	2	63	142	142	0.2	mg/cm2	0.2	Negative
11/28/2025	13:31:08	30.3151	-95.46072	T. Bazan	1.0	2	64	143	143	0.1	mg/cm2	0.2	Negative
11/28/2025	13:35:39	30.315	-95.46097	T. Bazan	1.0	2	65	144	144	0.4	mg/cm2	0.2	Negative
11/28/2025	13:36:45	30.315	-95.46096	T. Bazan	1.0	2	66	145	145	0.3	mg/cm2	0.2	Negative
11/28/2025	13:37:04	30.315	-95.46095	T. Bazan	1.0	2	67	146	146	0.5	mg/cm2	0.2	Negative
11/28/2025	13:37:13	30.3151	-95.46071	T. Bazan	1.0	2	68	147	147	0.2	mg/cm2	0.2	Negative
11/28/2025	13:38:57	30.3151	-95.46061	T. Bazan	1.0	2	69	148	148	0.1	mg/cm2	0.2	Negative
11/28/2025	13:39:31	30.3152	-95.46064	T. Bazan	1.0	2	70	149	149	0.4	mg/cm2	0.2	Negative
11/28/2025	13:39:50	30.3149	-95.46077	T. Bazan	1.0	2	71	150	150	0.0	mg/cm2	0.2	Negative
11/28/2025	13:40:45	30.3151	-95.46086	T. Bazan	1.0	2	72	151	151	0.3	mg/cm2	0.2	Negative
11/28/2025	13:42:26	30.3152	-95.46062	T. Bazan	1.0	2	73	152	152	0.0	mg/cm2	0.2	Negative
11/28/2025	13:45:34	30.3152	-95.4606	T. Bazan	1.0	2	74	153	153	0.0	mg/cm2	0.2	Negative
11/28/2025	13:45:44	30.3153	-95.46068	T. Bazan	1.0	2	75	154	154	0.1	mg/cm2	0.2	Negative
11/28/2025	13:46:10	30.3153	-95.46072	T. Bazan	1.0	2	76	155	155	3.6	mg/cm2	0.2	Positive
11/28/2025	13:47:00	30.3154	-95.46092	T. Bazan	1.0	2	77	156	156	0.2	mg/cm2	0.2	Negative
11/28/2025	13:49:04	30.3153	-95.46137	T. Bazan	1.0	2	78	157	157	0.2	mg/cm2	0.2	Negative
11/28/2025	13:51:06	30.3153	-95.46142	T. Bazan	1.0	2	79	158	158	0.1	mg/cm2	0.2	Negative
11/28/2025	13:51:15	30.3153	-95.46144	T. Bazan	1.0	2	80	159	159	0.0	mg/cm2	0.2	Negative
11/28/2025	13:51:32	30.3151	-95.46108	T. Bazan	1.0	2	81	160	160	1.6	mg/cm2	0.2	Positive
11/28/2025	13:53:34	30.3151	-95.46109	T. Bazan	1.0	2	82	161	161	0.1	mg/cm2	0.2	Negative
11/28/2025	13:53:48	30.3151	-95.46109	T. Bazan	1.0	2	83	162	162	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	13:54:30	30.3151	-95.46133	T. Bazan	1.0	2	84	163	163	0.2	mg/cm2	0.2	Negative
11/28/2025	14:00:40	0	0	T. Bazan	1.0	2	---	164	164	1.3	mg/cm2	0.2	Calibration
11/28/2025	14:05:30	0	0	T. Bazan	1.0	5	---	165	165	1.0	mg/cm2	0.1	Calibration
11/28/2025	14:05:47	0	0	T. Bazan	1.0	5	---	166	166	1.0	mg/cm2	0.1	Calibration
11/28/2025	14:06:05	0	0	T. Bazan	1.0	5	---	167	167	1.0	mg/cm2	0.1	Calibration
11/28/2025	14:12:47	0	0	T. Bazan	1.0	2	85	168	168	0.2	mg/cm2	0.2	Negative
11/28/2025	14:12:56	0	0	T. Bazan	1.0	2	86	169	169	0.1	mg/cm2	0.2	Negative
11/28/2025	14:14:02	0	0	T. Bazan	1.0	2	87	170	170	0.1	mg/cm2	0.2	Negative
11/28/2025	14:14:12	0	0	T. Bazan	1.0	2	88	171	171	0.2	mg/cm2	0.2	Negative
11/28/2025	14:15:17	0	0	T. Bazan	1.0	2	89	172	172	0.5	mg/cm2	0.2	Negative
11/28/2025	14:15:32	0	0	T. Bazan	1.0	2	90	173	173	0.1	mg/cm2	0.2	Negative
11/28/2025	14:17:25	0	0	T. Bazan	1.0	2	91	174	174	0.6	mg/cm2	0.2	Negative
11/28/2025	14:17:39	0	0	T. Bazan	1.0	2	92	175	175	0.3	mg/cm2	0.2	Negative
11/28/2025	14:18:55	0	0	T. Bazan	1.0	2	93	176	176	0.0	mg/cm2	0.2	Negative
11/28/2025	14:19:24	0	0	T. Bazan	1.0	2	94	177	177	0.0	mg/cm2	0.2	Negative
11/28/2025	14:19:51	0	0	T. Bazan	1.0	2	95	178	178	0.2	mg/cm2	0.2	Negative
11/28/2025	14:20:05	0	0	T. Bazan	1.0	2	96	179	179	0.1	mg/cm2	0.2	Negative
11/28/2025	14:20:39	0	0	T. Bazan	1.0	2	97	180	180	0.1	mg/cm2	0.2	Negative
11/28/2025	14:21:36	0	0	T. Bazan	1.0	2	98	181	181	0.4	mg/cm2	0.2	Negative
11/28/2025	14:22:21	0	0	T. Bazan	1.0	2	99	182	182	0.1	mg/cm2	0.2	Negative
11/28/2025	14:23:06	0	0	T. Bazan	1.0	2	100	183	183	0.5	mg/cm2	0.2	Negative
11/28/2025	14:23:15	0	0	T. Bazan	1.0	2	101	184	184	0.0	mg/cm2	0.2	Negative
11/28/2025	14:24:16	0	0	T. Bazan	1.0	3	102	185	185	0.7	mg/cm2	0.2	Negative
11/28/2025	14:25:32	0	0	T. Bazan	1.0	2	103	186	186	0.3	mg/cm2	0.2	Negative
11/28/2025	14:25:53	0	0	T. Bazan	1.0	2	104	187	187	0.2	mg/cm2	0.2	Negative
11/28/2025	14:28:10	0	0	T. Bazan	1.0	2	105	188	188	0.1	mg/cm2	0.2	Negative
11/28/2025	14:28:57	0	0	T. Bazan	1.0	2	106	189	189	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	14:29:18	0	0	T. Bazan	1.0	2	107	190	190	0.1	mg/cm2	0.2	Negative
11/28/2025	14:30:11	0	0	T. Bazan	1.0	2	108	191	191	0.0	mg/cm2	0.2	Negative
11/28/2025	14:33:14	0	0	T. Bazan	1.0	2	109	192	192	0.1	mg/cm2	0.2	Negative
11/28/2025	14:35:54	0	0	T. Bazan	1.0	2	110	193	193	0.1	mg/cm2	0.2	Negative
11/28/2025	14:36:05	0	0	T. Bazan	1.0	2	111	194	194	0.1	mg/cm2	0.2	Negative
11/28/2025	14:36:36	0	0	T. Bazan	1.0	2	112	195	195	0.2	mg/cm2	0.2	Negative
11/28/2025	14:37:00	0	0	T. Bazan	1.0	2	113	196	196	0.2	mg/cm2	0.2	Negative
11/28/2025	14:37:26	0	0	T. Bazan	1.0	2	114	197	197	0.0	mg/cm2	0.2	Negative
11/28/2025	14:38:15	0	0	T. Bazan	1.0	2	115	198	198	0.0	mg/cm2	0.2	Negative
11/28/2025	14:38:38	0	0	T. Bazan	1.0	2	116	199	199	0.0	mg/cm2	0.2	Negative
11/28/2025	14:38:58	0	0	T. Bazan	1.0	2	117	200	200	0.1	mg/cm2	0.2	Negative
11/28/2025	14:39:17	0	0	T. Bazan	1.0	2	118	201	201	0.1	mg/cm2	0.2	Negative
11/28/2025	14:39:34	0	0	T. Bazan	1.0	2	119	202	202	0.2	mg/cm2	0.2	Negative
11/28/2025	14:39:49	0	0	T. Bazan	1.0	2	120	203	203	0.0	mg/cm2	0.2	Negative
11/28/2025	14:41:51	0	0	T. Bazan	1.0	2	121	204	204	0.3	mg/cm2	0.2	Negative
11/28/2025	14:42:34	0	0	T. Bazan	1.0	2	122	205	205	0.1	mg/cm2	0.2	Negative
11/28/2025	14:42:57	0	0	T. Bazan	1.0	2	123	206	206	0.2	mg/cm2	0.2	Negative
11/28/2025	14:43:45	0	0	T. Bazan	1.0	2	124	207	207	0.6	mg/cm2	0.2	Negative
11/28/2025	14:46:29	0	0	T. Bazan	1.0	2	125	208	208	0.0	mg/cm2	0.2	Negative
11/28/2025	14:47:20	0	0	T. Bazan	1.0	2	126	209	209	0.3	mg/cm2	0.2	Negative
11/28/2025	14:47:44	0	0	T. Bazan	1.0	2	127	210	210	0.1	mg/cm2	0.2	Negative
11/28/2025	14:47:56	0	0	T. Bazan	1.0	2	128	211	211	0.1	mg/cm2	0.2	Negative
11/28/2025	14:49:04	0	0	T. Bazan	1.0	2	129	212	212	0.3	mg/cm2	0.2	Negative
11/28/2025	14:49:32	0	0	T. Bazan	1.0	2	130	213	213	0.3	mg/cm2	0.2	Negative
11/28/2025	14:49:45	0	0	T. Bazan	1.0	2	131	214	214	0.2	mg/cm2	0.2	Negative
11/28/2025	14:50:08	0	0	T. Bazan	1.0	2	132	215	215	0.2	mg/cm2	0.2	Negative
11/28/2025	14:50:48	0	0	T. Bazan	1.0	2	133	216	216	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	14:52:02	0	0	T. Bazan	1.0	2	134	217	217	0.2	mg/cm2	0.2	Negative
11/28/2025	14:52:39	0	0	T. Bazan	1.0	2	135	218	218	0.0	mg/cm2	0.2	Negative
11/28/2025	14:53:03	0	0	T. Bazan	1.0	2	136	219	219	0.3	mg/cm2	0.2	Negative
11/28/2025	14:53:18	0	0	T. Bazan	1.0	2	137	220	220	0.1	mg/cm2	0.2	Negative
11/28/2025	14:53:34	0	0	T. Bazan	1.0	2	138	221	221	0.0	mg/cm2	0.2	Negative
11/28/2025	14:53:55	0	0	T. Bazan	1.0	2	139	222	222	0.4	mg/cm2	0.2	Negative
11/28/2025	14:54:24	0	0	T. Bazan	1.0	2	140	223	223	0.2	mg/cm2	0.2	Negative
11/28/2025	14:55:04	0	0	T. Bazan	1.0	2	141	224	224	0.4	mg/cm2	0.2	Negative
11/28/2025	14:55:21	0	0	T. Bazan	1.0	2	142	225	225	0.1	mg/cm2	0.2	Negative
11/28/2025	14:56:03	0	0	T. Bazan	1.0	2	143	226	226	0.1	mg/cm2	0.2	Negative
11/28/2025	14:56:39	0	0	T. Bazan	1.0	2	144	227	227	0.3	mg/cm2	0.2	Negative
11/28/2025	14:58:51	0	0	T. Bazan	1.0	2	145	228	228	0.0	mg/cm2	0.2	Negative
11/28/2025	14:59:03	0	0	T. Bazan	1.0	2	146	229	229	0.3	mg/cm2	0.2	Negative
11/28/2025	15:00:12	0	0	T. Bazan	1.0	2	147	230	230	0.1	mg/cm2	0.2	Negative
11/28/2025	15:00:38	0	0	T. Bazan	1.0	2	148	231	231	0.1	mg/cm2	0.2	Negative
11/28/2025	15:01:09	0	0	T. Bazan	1.0	2	149	232	232	0.3	mg/cm2	0.2	Negative
11/28/2025	15:02:53	0	0	T. Bazan	1.0	2	150	233	233	0.1	mg/cm2	0.2	Negative
11/28/2025	15:03:11	0	0	T. Bazan	1.0	2	151	234	234	0.2	mg/cm2	0.2	Negative
11/28/2025	15:03:21	0	0	T. Bazan	1.0	2	152	235	235	0.6	mg/cm2	0.2	Negative
11/28/2025	15:03:33	0	0	T. Bazan	1.0	2	153	236	236	0.1	mg/cm2	0.2	Negative
11/28/2025	15:05:09	0	0	T. Bazan	1.0	2	154	237	237	0.1	mg/cm2	0.2	Negative
11/28/2025	15:07:47	0	0	T. Bazan	1.0	2	155	238	238	0.2	mg/cm2	0.2	Negative
11/28/2025	15:07:58	0	0	T. Bazan	1.0	2	156	239	239	0.3	mg/cm2	0.2	Negative
11/28/2025	15:08:48	0	0	T. Bazan	1.0	2	157	240	240	0.2	mg/cm2	0.2	Negative
11/28/2025	15:08:57	0	0	T. Bazan	1.0	2	158	241	241	0.1	mg/cm2	0.2	Negative
11/28/2025	15:10:12	0	0	T. Bazan	1.0	2	159	242	242	0.1	mg/cm2	0.2	Negative
11/28/2025	15:10:21	0	0	T. Bazan	1.0	2	160	243	243	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/28/2025	15:11:54	0	0	T. Bazan	1.0	2	161	244	244	0.1	mg/cm2	0.2	Negative
11/28/2025	15:12:04	0	0	T. Bazan	1.0	2	162	245	245	0.2	mg/cm2	0.2	Negative
11/28/2025	15:12:49	0	0	T. Bazan	1.0	2	163	246	246	0.2	mg/cm2	0.2	Negative
11/28/2025	15:13:40	0	0	T. Bazan	1.0	2	164	247	247	0.0	mg/cm2	0.2	Negative
11/28/2025	15:16:43	0	0	T. Bazan	1.0	3	165	248	248	0.0	mg/cm2	0.2	Negative
11/28/2025	15:16:56	0	0	T. Bazan	1.0	2	166	249	249	0.2	mg/cm2	0.2	Negative
11/28/2025	15:17:34	0	0	T. Bazan	1.0	2	167	250	250	0.0	mg/cm2	0.2	Negative
11/28/2025	15:17:42	0	0	T. Bazan	1.0	2	168	251	251	0.2	mg/cm2	0.2	Negative
11/28/2025	15:18:16	0	0	T. Bazan	1.0	2	169	252	252	0.5	mg/cm2	0.2	Negative
11/28/2025	15:20:11	0	0	T. Bazan	1.0	2	170	253	253	0.1	mg/cm2	0.2	Negative
11/28/2025	15:21:54	0	0	T. Bazan	1.0	2	171	254	254	0.1	mg/cm2	0.2	Negative
11/28/2025	15:23:00	0	0	T. Bazan	1.0	2	172	255	255	0.0	mg/cm2	0.2	Negative
11/28/2025	15:23:14	0	0	T. Bazan	1.0	2	173	256	256	0.3	mg/cm2	0.2	Negative
11/28/2025	15:24:44	0	0	T. Bazan	1.0	2	174	257	257	0.1	mg/cm2	0.2	Negative
11/28/2025	15:26:20	0	0	T. Bazan	1.0	2	175	258	258	0.0	mg/cm2	0.2	Negative
11/28/2025	15:27:22	0	0	T. Bazan	1.0	2	176	259	259	0.1	mg/cm2	0.2	Negative
11/28/2025	15:27:31	0	0	T. Bazan	1.0	2	177	260	260	0.2	mg/cm2	0.2	Negative
11/28/2025	15:31:41	0	0	T. Bazan	1.0	5	---	261	261	1.0	mg/cm2	0.1	Calibration
11/28/2025	15:31:59	0	0	T. Bazan	1.0	5	---	262	262	1.0	mg/cm2	0.1	Calibration
11/28/2025	15:32:16	0	0	T. Bazan	1.0	5	---	263	263	1.0	mg/cm2	0.1	Calibration
DAY TWO													
11/29/2025	9:11:46	0	0	T. Bazan	1.0	5	---	1	264	1.0	mg/cm2	0.1	Calibration
11/29/2025	9:12:04	0	0	T. Bazan	1.0	5	---	2	265	1.0	mg/cm2	0.1	Calibration
11/29/2025	9:12:24	0	0	T. Bazan	1.0	5	---	3	266	1.0	mg/cm2	0.1	Calibration
11/29/2025	9:16:56	0	0	T. Bazan	1.0	2	1	4	267	0.3	mg/cm2	0.2	Negative
11/29/2025	9:18:40	0	0	T. Bazan	1.0	2	2	5	268	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	9:19:02	0	0	T. Bazan	1.0	2	3	6	269	0.0	mg/cm2	0.2	Negative
11/29/2025	9:19:14	0	0	T. Bazan	1.0	2	4	7	270	0.3	mg/cm2	0.2	Negative
11/29/2025	9:20:14	0	0	T. Bazan	1.0	2	5	8	271	0.0	mg/cm2	0.2	Negative
11/29/2025	9:21:06	0	0	T. Bazan	1.0	2	6	9	272	0.1	mg/cm2	0.2	Negative
11/29/2025	9:22:30	0	0	T. Bazan	1.0	2	7	10	273	0.1	mg/cm2	0.2	Negative
11/29/2025	9:22:40	0	0	T. Bazan	1.0	2	8	11	274	0.2	mg/cm2	0.2	Negative
11/29/2025	9:23:37	0	0	T. Bazan	1.0	2	9	12	275	0.1	mg/cm2	0.2	Negative
11/29/2025	9:23:46	0	0	T. Bazan	1.0	2	10	13	276	0.0	mg/cm2	0.2	Negative
11/29/2025	9:24:27	0	0	T. Bazan	1.0	2	11	14	277	0.3	mg/cm2	0.2	Negative
11/29/2025	9:26:34	0	0	T. Bazan	1.0	2	12	15	278	0.0	mg/cm2	0.2	Negative
11/29/2025	9:27:16	0	0	T. Bazan	1.0	2	13	16	279	0.2	mg/cm2	0.2	Negative
11/29/2025	9:28:27	0	0	T. Bazan	1.0	2	14	17	280	0.2	mg/cm2	0.2	Negative
11/29/2025	9:29:27	0	0	T. Bazan	1.0	2	15	18	281	0.2	mg/cm2	0.2	Negative
11/29/2025	9:30:11	0	0	T. Bazan	1.0	2	16	19	282	0.1	mg/cm2	0.2	Negative
11/29/2025	9:30:35	0	0	T. Bazan	1.0	2	17	20	283	0.2	mg/cm2	0.2	Negative
11/29/2025	9:32:40	0	0	T. Bazan	1.0	2	18	21	284	0.3	mg/cm2	0.2	Negative
11/29/2025	9:33:00	0	0	T. Bazan	1.0	2	19	22	285	0.1	mg/cm2	0.2	Negative
11/29/2025	9:33:51	0	0	T. Bazan	1.0	2	20	23	286	0.1	mg/cm2	0.2	Negative
11/29/2025	9:42:43	0	0	T. Bazan	1.0	2	21	24	287	0.1	mg/cm2	0.2	Negative
11/29/2025	9:46:19	0	0	T. Bazan	1.0	2	22	25	288	0.3	mg/cm2	0.2	Negative
11/29/2025	9:47:00	0	0	T. Bazan	1.0	2	23	26	289	0.0	mg/cm2	0.2	Negative
11/29/2025	9:49:49	0	0	T. Bazan	1.0	2	24	27	290	0.2	mg/cm2	0.2	Negative
11/29/2025	9:51:19	0	0	T. Bazan	1.0	2	25	28	291	0.1	mg/cm2	0.2	Negative
11/29/2025	9:52:42	0	0	T. Bazan	1.0	2	26	29	292	0.1	mg/cm2	0.2	Negative
11/29/2025	9:57:04	0	0	T. Bazan	1.0	2	27	30	293	0.0	mg/cm2	0.2	Negative
11/29/2025	9:57:14	0	0	T. Bazan	1.0	2	28	31	294	0.3	mg/cm2	0.2	Negative
11/29/2025	9:58:35	0	0	T. Bazan	1.0	2	29	32	295	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	9:58:46	0	0	T. Bazan	1.0	2	30	33	296	0.0	mg/cm2	0.2	Negative
11/29/2025	9:59:03	0	0	T. Bazan	1.0	2	31	34	297	0.1	mg/cm2	0.2	Negative
11/29/2025	10:01:38	0	0	T. Bazan	1.0	2	32	35	298	0.2	mg/cm2	0.2	Negative
11/29/2025	10:01:51	0	0	T. Bazan	1.0	2	33	36	299	0.2	mg/cm2	0.2	Negative
11/29/2025	10:02:00	0	0	T. Bazan	1.0	2	34	37	300	0.1	mg/cm2	0.2	Negative
11/29/2025	10:02:53	0	0	T. Bazan	1.0	2	35	38	301	0.0	mg/cm2	0.2	Negative
11/29/2025	10:03:36	0	0	T. Bazan	1.0	2	36	39	302	0.1	mg/cm2	0.2	Negative
11/29/2025	10:05:26	0	0	T. Bazan	1.0	2	37	40	303	0.1	mg/cm2	0.2	Negative
11/29/2025	10:05:42	0	0	T. Bazan	1.0	2	38	41	304	0.1	mg/cm2	0.2	Negative
11/29/2025	10:07:45	0	0	T. Bazan	1.0	2	39	42	305	0.1	mg/cm2	0.2	Negative
11/29/2025	10:08:14	0	0	T. Bazan	1.0	2	40	43	306	0.3	mg/cm2	0.2	Negative
11/29/2025	10:10:50	0	0	T. Bazan	1.0	2	41	44	307	0.4	mg/cm2	0.2	Negative
11/29/2025	10:11:18	0	0	T. Bazan	1.0	2	42	45	308	0.3	mg/cm2	0.2	Negative
11/29/2025	10:11:39	0	0	T. Bazan	1.0	2	43	46	309	0.5	mg/cm2	0.2	Negative
11/29/2025	10:11:51	0	0	T. Bazan	1.0	2	44	47	310	0.4	mg/cm2	0.2	Negative
11/29/2025	10:17:37	0	0	T. Bazan	1.0	2	45	48	311	0.1	mg/cm2	0.2	Negative
11/29/2025	10:19:57	0	0	T. Bazan	1.0	2	46	49	312	0.0	mg/cm2	0.2	Negative
11/29/2025	10:20:14	0	0	T. Bazan	1.0	2	47	50	313	0.1	mg/cm2	0.2	Negative
11/29/2025	10:20:38	0	0	T. Bazan	1.0	2	48	51	314	0.1	mg/cm2	0.2	Negative
11/29/2025	10:20:47	0	0	T. Bazan	1.0	2	49	52	315	0.0	mg/cm2	0.2	Negative
11/29/2025	10:22:19	0	0	T. Bazan	1.0	2	50	53	316	0.5	mg/cm2	0.2	Negative
11/29/2025	10:22:53	0	0	T. Bazan	1.0	2	51	54	317	0.1	mg/cm2	0.2	Negative
11/29/2025	10:23:08	0	0	T. Bazan	1.0	2	52	55	318	0.5	mg/cm2	0.2	Negative
11/29/2025	10:23:48	0	0	T. Bazan	1.0	2	53	56	319	0.2	mg/cm2	0.2	Negative
11/29/2025	10:26:17	0	0	T. Bazan	1.0	2	54	57	320	0.5	mg/cm2	0.2	Negative
11/29/2025	10:26:28	0	0	T. Bazan	1.0	2	55	58	321	0.1	mg/cm2	0.2	Negative
11/29/2025	10:26:45	0	0	T. Bazan	1.0	2	56	59	322	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	10:28:45	0	0	T. Bazan	1.0	2	57	60	323	0.1	mg/cm2	0.2	Negative
11/29/2025	10:29:04	0	0	T. Bazan	1.0	2	58	61	324	0.1	mg/cm2	0.2	Negative
11/29/2025	10:29:34	0	0	T. Bazan	1.0	2	59	62	325	0.2	mg/cm2	0.2	Negative
11/29/2025	10:30:03	0	0	T. Bazan	1.0	2	60	63	326	0.1	mg/cm2	0.2	Negative
11/29/2025	10:32:24	0	0	T. Bazan	1.0	2	61	64	327	0.2	mg/cm2	0.2	Negative
11/29/2025	10:32:34	0	0	T. Bazan	1.0	2	62	65	328	0.1	mg/cm2	0.2	Negative
11/29/2025	10:33:28	0	0	T. Bazan	1.0	2	63	66	329	0.0	mg/cm2	0.2	Negative
11/29/2025	10:33:37	0	0	T. Bazan	1.0	2	64	67	330	0.1	mg/cm2	0.2	Negative
11/29/2025	10:38:26	0	0	T. Bazan	1.0	2	65	68	331	0.0	mg/cm2	0.2	Negative
11/29/2025	10:38:42	0	0	T. Bazan	1.0	2	66	69	332	0.1	mg/cm2	0.2	Negative
11/29/2025	10:39:00	0	0	T. Bazan	1.0	2	67	70	333	0.1	mg/cm2	0.2	Negative
11/29/2025	10:39:43	0	0	T. Bazan	1.0	2	68	71	334	0.1	mg/cm2	0.2	Negative
11/29/2025	10:40:39	0	0	T. Bazan	1.0	2	69	72	335	0.2	mg/cm2	0.2	Negative
11/29/2025	10:41:28	0	0	T. Bazan	1.0	2	70	73	336	0.1	mg/cm2	0.2	Negative
11/29/2025	10:41:39	0	0	T. Bazan	1.0	2	71	74	337	0.2	mg/cm2	0.2	Negative
11/29/2025	10:42:38	0	0	T. Bazan	1.0	2	72	75	338	0.1	mg/cm2	0.2	Negative
11/29/2025	10:42:54	0	0	T. Bazan	1.0	2	73	76	339	0.1	mg/cm2	0.2	Negative
11/29/2025	10:43:10	0	0	T. Bazan	1.0	2	74	77	340	0.1	mg/cm2	0.2	Negative
11/29/2025	10:43:20	0	0	T. Bazan	1.0	2	75	78	341	0.1	mg/cm2	0.2	Negative
11/29/2025	10:46:21	0	0	T. Bazan	1.0	2	76	79	342	0.2	mg/cm2	0.2	Negative
11/29/2025	10:46:29	0	0	T. Bazan	1.0	2	77	80	343	0.1	mg/cm2	0.2	Negative
11/29/2025	10:47:12	0	0	T. Bazan	1.0	2	78	81	344	0.2	mg/cm2	0.2	Negative
11/29/2025	10:48:29	0	0	T. Bazan	1.0	2	79	82	345	0.2	mg/cm2	0.2	Negative
11/29/2025	10:48:50	0	0	T. Bazan	1.0	2	80	83	346	0.1	mg/cm2	0.2	Negative
11/29/2025	10:51:43	0	0	T. Bazan	1.0	2	81	84	347	0.2	mg/cm2	0.2	Negative
11/29/2025	10:51:53	0	0	T. Bazan	1.0	2	82	85	348	0.0	mg/cm2	0.2	Negative
11/29/2025	10:52:13	0	0	T. Bazan	1.0	2	83	86	349	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	10:52:30	0	0	T. Bazan	1.0	2	84	87	350	0.1	mg/cm2	0.2	Negative
11/29/2025	10:52:54	0	0	T. Bazan	1.0	2	85	88	351	0.1	mg/cm2	0.2	Negative
11/29/2025	10:53:07	0	0	T. Bazan	1.0	2	86	89	352	0.1	mg/cm2	0.2	Negative
11/29/2025	10:53:32	0	0	T. Bazan	1.0	2	87	90	353	0.4	mg/cm2	0.2	Negative
11/29/2025	10:55:06	0	0	T. Bazan	1.0	2	88	91	354	0.2	mg/cm2	0.2	Negative
11/29/2025	10:55:15	0	0	T. Bazan	1.0	2	89	92	355	0.0	mg/cm2	0.2	Negative
11/29/2025	10:55:32	0	0	T. Bazan	1.0	2	90	93	356	0.0	mg/cm2	0.2	Negative
11/29/2025	10:55:53	0	0	T. Bazan	1.0	2	91	94	357	0.1	mg/cm2	0.2	Negative
11/29/2025	10:56:03	0	0	T. Bazan	1.0	2	92	95	358	0.1	mg/cm2	0.2	Negative
11/29/2025	11:01:27	0	0	T. Bazan	1.0	2	93	96	359	0.1	mg/cm2	0.2	Negative
11/29/2025	11:01:41	0	0	T. Bazan	1.0	2	94	97	360	0.0	mg/cm2	0.2	Negative
11/29/2025	11:02:33	0	0	T. Bazan	1.0	2	95	98	361	0.1	mg/cm2	0.2	Negative
11/29/2025	11:04:05	0	0	T. Bazan	1.0	2	96	99	362	0.2	mg/cm2	0.2	Negative
11/29/2025	11:04:14	0	0	T. Bazan	1.0	2	97	100	363	0.2	mg/cm2	0.2	Negative
11/29/2025	11:05:12	0	0	T. Bazan	1.0	2	98	101	364	0.3	mg/cm2	0.2	Negative
11/29/2025	11:05:52	0	0	T. Bazan	1.0	2	99	102	365	0.2	mg/cm2	0.2	Negative
11/29/2025	11:06:01	30.3099	-95.46864	T. Bazan	1.0	2	100	103	366	0.2	mg/cm2	0.2	Negative
11/29/2025	11:07:27	30.31	-95.46858	T. Bazan	1.0	2	101	104	367	0.2	mg/cm2	0.2	Negative
11/29/2025	11:07:36	30.3099	-95.46928	T. Bazan	1.0	2	102	105	368	0.1	mg/cm2	0.2	Negative
11/29/2025	11:08:28	30.31	-95.46957	T. Bazan	1.0	2	103	106	369	0.1	mg/cm2	0.2	Negative
11/29/2025	11:08:39	30.3108	-95.4736	T. Bazan	1.0	2	104	107	370	0.0	mg/cm2	0.2	Negative
11/29/2025	11:09:32	30.3111	-95.47416	T. Bazan	1.0	2	105	108	371	0.2	mg/cm2	0.2	Negative
11/29/2025	11:10:01	30.311	-95.47457	T. Bazan	1.0	2	106	109	372	0.1	mg/cm2	0.2	Negative
11/29/2025	11:10:09	30.3111	-95.47522	T. Bazan	1.0	2	107	110	373	0.1	mg/cm2	0.2	Negative
11/29/2025	11:10:31	30.3111	-95.47522	T. Bazan	1.0	2	108	111	374	0.1	mg/cm2	0.2	Negative
11/29/2025	11:10:43	30.3111	-95.47587	T. Bazan	1.0	2	109	112	375	0.0	mg/cm2	0.2	Negative
11/29/2025	11:11:05	30.3114	-95.47618	T. Bazan	1.0	2	110	113	376	0.3	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	11:12:22	30.3114	-95.47618	T. Bazan	1.0	2	111	114	377	0.1	mg/cm2	0.2	Negative
11/29/2025	11:12:30	30.3111	-95.47613	T. Bazan	1.0	2	112	115	378	0.0	mg/cm2	0.2	Negative
11/29/2025	11:12:51	30.3129	-95.48217	T. Bazan	1.0	2	113	116	379	0.1	mg/cm2	0.2	Negative
11/29/2025	11:14:26	30.313	-95.48223	T. Bazan	1.0	2	114	117	380	0.2	mg/cm2	0.2	Negative
11/29/2025	11:14:41	30.3142	-95.48589	T. Bazan	1.0	2	115	118	381	0.2	mg/cm2	0.2	Negative
11/29/2025	11:15:00	30.3143	-95.48757	T. Bazan	1.0	2	116	119	382	0.2	mg/cm2	0.2	Negative
11/29/2025	11:15:09	30.3145	-95.48747	T. Bazan	1.0	2	117	120	383	0.2	mg/cm2	0.2	Negative
11/29/2025	11:17:12	30.3144	-95.48731	T. Bazan	1.0	2	118	121	384	0.1	mg/cm2	0.2	Negative
11/29/2025	11:17:22	30.3143	-95.48721	T. Bazan	1.0	2	119	122	385	0.3	mg/cm2	0.2	Negative
11/29/2025	11:17:40	30.3141	-95.4831	T. Bazan	1.0	2	120	123	386	0.1	mg/cm2	0.2	Negative
11/29/2025	11:20:00	30.3141	-95.4831	T. Bazan	1.0	2	121	124	387	0.1	mg/cm2	0.2	Negative
11/29/2025	11:20:08	30.3149	-95.48025	T. Bazan	1.0	2	122	125	388	0.5	mg/cm2	0.2	Negative
11/29/2025	11:20:29	30.315	-95.47988	T. Bazan	1.0	2	123	126	389	0.5	mg/cm2	0.2	Negative
11/29/2025	11:20:38	30.315	-95.47988	T. Bazan	1.0	2	124	127	390	0.0	mg/cm2	0.2	Negative
11/29/2025	11:21:39	30.315	-95.47988	T. Bazan	1.0	2	125	128	391	0.0	mg/cm2	0.2	Negative
11/29/2025	11:21:47	30.315	-95.47988	T. Bazan	1.0	2	126	129	392	0.4	mg/cm2	0.2	Negative
11/29/2025	11:22:03	30.315	-95.47988	T. Bazan	1.0	2	127	130	393	0.0	mg/cm2	0.2	Negative
11/29/2025	11:22:13	30.315	-95.47988	T. Bazan	1.0	2	128	131	394	0.0	mg/cm2	0.2	Negative
11/29/2025	11:22:47	30.315	-95.47988	T. Bazan	1.0	2	129	132	395	0.3	mg/cm2	0.2	Negative
11/29/2025	11:22:56	30.315	-95.47988	T. Bazan	1.0	2	130	133	396	0.1	mg/cm2	0.2	Negative
11/29/2025	11:23:59	30.315	-95.47988	T. Bazan	1.0	2	131	134	397	0.0	mg/cm2	0.2	Negative
11/29/2025	11:24:08	30.3148	-95.4612	T. Bazan	1.0	2	132	135	398	0.2	mg/cm2	0.2	Negative
11/29/2025	11:25:28	30.3147	-95.46118	T. Bazan	1.0	2	133	136	399	0.1	mg/cm2	0.2	Negative
11/29/2025	11:25:58	30.3147	-95.4612	T. Bazan	1.0	2	134	137	400	0.0	mg/cm2	0.2	Negative
11/29/2025	11:26:40	30.3147	-95.4612	T. Bazan	1.0	2	135	138	401	0.1	mg/cm2	0.2	Negative
11/29/2025	11:26:50	30.3147	-95.4612	T. Bazan	1.0	2	136	139	402	0.1	mg/cm2	0.2	Negative
11/29/2025	11:27:04	30.3147	-95.4612	T. Bazan	1.0	2	137	140	403	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	11:27:12	30.3147	-95.4612	T. Bazan	1.0	2	138	141	404	0.1	mg/cm2	0.2	Negative
11/29/2025	11:28:41	30.3147	-95.4612	T. Bazan	1.0	2	139	142	405	0.2	mg/cm2	0.2	Negative
11/29/2025	11:28:50	30.3147	-95.4612	T. Bazan	1.0	2	140	143	406	0.1	mg/cm2	0.2	Negative
11/29/2025	11:32:07	30.3147	-95.4612	T. Bazan	1.0	2	141	144	407	0.1	mg/cm2	0.2	Negative
11/29/2025	11:32:17	30.3147	-95.4612	T. Bazan	1.0	2	142	145	408	0.1	mg/cm2	0.2	Negative
11/29/2025	11:32:34	30.3147	-95.4612	T. Bazan	1.0	2	143	146	409	0.1	mg/cm2	0.2	Negative
11/29/2025	11:32:53	30.3151	-95.46109	T. Bazan	1.0	2	144	147	410	0.2	mg/cm2	0.2	Negative
11/29/2025	11:43:28	30.3151	-95.46109	T. Bazan	1.0	2	145	148	411	0.1	mg/cm2	0.2	Negative
11/29/2025	11:43:37	30.3151	-95.46109	T. Bazan	1.0	2	146	149	412	0.3	mg/cm2	0.2	Negative
11/29/2025	11:43:50	30.3151	-95.46109	T. Bazan	1.0	2	147	150	413	0.2	mg/cm2	0.2	Negative
11/29/2025	11:44:18	30.3151	-95.46109	T. Bazan	1.0	2	148	151	414	0.1	mg/cm2	0.2	Negative
11/29/2025	11:44:27	30.3159	-95.46098	T. Bazan	1.0	2	149	152	415	0.2	mg/cm2	0.2	Negative
11/29/2025	11:46:38	30.3159	-95.46098	T. Bazan	1.0	2	150	153	416	0.0	mg/cm2	0.2	Negative
11/29/2025	11:46:48	30.3159	-95.46098	T. Bazan	1.0	2	151	154	417	0.2	mg/cm2	0.2	Negative
11/29/2025	11:47:14	30.3159	-95.46098	T. Bazan	1.0	2	152	155	418	0.0	mg/cm2	0.2	Negative
11/29/2025	11:48:20	30.3159	-95.46098	T. Bazan	1.0	2	153	156	419	0.1	mg/cm2	0.2	Negative
11/29/2025	11:48:32	30.3155	-95.46072	T. Bazan	1.0	2	154	157	420	0.0	mg/cm2	0.2	Negative
11/29/2025	11:52:08	30.3153	-95.46087	T. Bazan	1.0	2	155	158	421	0.0	mg/cm2	0.2	Negative
11/29/2025	11:52:32	30.3153	-95.46087	T. Bazan	1.0	2	156	159	422	0.2	mg/cm2	0.2	Negative
11/29/2025	11:52:50	30.3153	-95.46087	T. Bazan	1.0	2	157	160	423	0.1	mg/cm2	0.2	Negative
11/29/2025	11:53:24	30.3153	-95.46087	T. Bazan	1.0	2	158	161	424	0.1	mg/cm2	0.2	Negative
11/29/2025	11:53:41	30.3153	-95.46087	T. Bazan	1.0	2	159	162	425	0.1	mg/cm2	0.2	Negative
11/29/2025	11:53:59	30.3154	-95.46115	T. Bazan	1.0	2	160	163	426	0.0	mg/cm2	0.2	Negative
11/29/2025	11:57:31	30.3153	-95.46037	T. Bazan	1.0	2	161	164	427	0.4	mg/cm2	0.2	Negative
11/29/2025	11:57:57	30.3154	-95.46134	T. Bazan	1.0	2	162	165	428	0.2	mg/cm2	0.2	Negative
11/29/2025	11:58:08	30.3152	-95.46143	T. Bazan	1.0	2	163	166	429	0.5	mg/cm2	0.2	Negative
11/29/2025	11:58:30	30.3153	-95.46325	T. Bazan	1.0	2	164	167	430	0.5	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	11:59:12	30.3152	-95.46071	T. Bazan	1.0	2	165	168	431	0.2	mg/cm2	0.2	Negative
11/29/2025	12:03:58	30.3153	-95.4608	T. Bazan	1.0	2	166	169	432	0.1	mg/cm2	0.2	Negative
11/29/2025	12:04:50	30.3153	-95.4609	T. Bazan	1.0	2	167	170	433	0.1	mg/cm2	0.2	Negative
11/29/2025	12:05:02	30.3152	-95.46091	T. Bazan	1.0	2	168	171	434	0.1	mg/cm2	0.2	Negative
11/29/2025	12:05:18	30.3151	-95.46104	T. Bazan	1.0	2	169	172	435	0.1	mg/cm2	0.2	Negative
11/29/2025	12:05:50	30.3151	-95.46104	T. Bazan	1.0	2	170	173	436	0.1	mg/cm2	0.2	Negative
11/29/2025	12:06:21	30.3151	-95.46121	T. Bazan	1.0	2	171	174	437	0.0	mg/cm2	0.2	Negative
11/29/2025	12:06:53	30.3153	-95.46049	T. Bazan	1.0	2	172	175	438	0.0	mg/cm2	0.2	Negative
11/29/2025	12:08:56	30.3148	-95.46056	T. Bazan	1.0	2	173	176	439	0.2	mg/cm2	0.2	Negative
11/29/2025	12:09:48	30.3148	-95.46056	T. Bazan	1.0	2	174	177	440	0.2	mg/cm2	0.2	Negative
11/29/2025	12:09:57	30.3154	-95.46129	T. Bazan	1.0	2	175	178	441	0.1	mg/cm2	0.2	Negative
11/29/2025	12:10:41	30.3151	-95.46029	T. Bazan	1.0	2	176	179	442	0.1	mg/cm2	0.2	Negative
11/29/2025	12:11:35	30.3151	-95.46024	T. Bazan	1.0	2	177	180	443	0.4	mg/cm2	0.2	Negative
11/29/2025	12:12:29	30.3151	-95.46024	T. Bazan	1.0	2	178	181	444	0.2	mg/cm2	0.2	Negative
11/29/2025	12:13:19	30.3154	-95.46086	T. Bazan	1.0	2	179	182	445	0.4	mg/cm2	0.2	Negative
11/29/2025	12:13:28	30.3147	-95.46082	T. Bazan	1.0	2	180	183	446	0.3	mg/cm2	0.2	Negative
11/29/2025	12:27:24	30.3147	-95.46082	T. Bazan	1.0	2	181	184	447	0.1	mg/cm2	0.2	Negative
11/29/2025	12:27:34	30.3147	-95.46082	T. Bazan	1.0	2	182	185	448	0.2	mg/cm2	0.2	Negative
11/29/2025	12:27:43	30.3147	-95.46082	T. Bazan	1.0	2	183	186	449	0.1	mg/cm2	0.2	Negative
11/29/2025	12:27:53	30.3147	-95.46082	T. Bazan	1.0	2	184	187	450	0.2	mg/cm2	0.2	Negative
11/29/2025	12:28:10	30.3147	-95.46082	T. Bazan	1.0	2	185	188	451	0.1	mg/cm2	0.2	Negative
11/29/2025	12:28:48	30.3147	-95.46082	T. Bazan	1.0	2	186	189	452	0.1	mg/cm2	0.2	Negative
11/29/2025	12:28:57	30.3147	-95.46082	T. Bazan	1.0	2	187	190	453	0.2	mg/cm2	0.2	Negative
11/29/2025	12:29:06	30.3147	-95.46082	T. Bazan	1.0	2	188	191	454	0.0	mg/cm2	0.2	Negative
11/29/2025	12:29:41	30.3147	-95.46082	T. Bazan	1.0	2	189	192	455	0.1	mg/cm2	0.2	Negative
11/29/2025	12:30:00	30.3147	-95.46082	T. Bazan	1.0	2	190	193	456	0.5	mg/cm2	0.2	Negative
11/29/2025	12:30:21	30.3147	-95.46082	T. Bazan	1.0	2	191	194	457	0.4	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	12:30:53	30.3165	-95.45913	T. Bazan	1.0	2	192	195	458	0.2	mg/cm2	0.2	Negative
11/29/2025	12:36:47	30.3165	-95.45913	T. Bazan	1.0	2	193	196	459	0.1	mg/cm2	0.2	Negative
11/29/2025	12:37:19	30.3165	-95.45913	T. Bazan	1.0	2	194	197	460	0.1	mg/cm2	0.2	Negative
11/29/2025	12:37:43	30.3165	-95.45913	T. Bazan	1.0	2	195	198	461	0.1	mg/cm2	0.2	Negative
11/29/2025	12:37:55	30.3165	-95.45913	T. Bazan	1.0	2	196	199	462	0.1	mg/cm2	0.2	Negative
11/29/2025	12:38:12	30.3165	-95.45913	T. Bazan	1.0	2	197	200	463	0.0	mg/cm2	0.2	Negative
11/29/2025	12:38:47	30.3165	-95.45913	T. Bazan	1.0	2	198	201	464	0.1	mg/cm2	0.2	Negative
11/29/2025	12:39:29	30.3165	-95.45913	T. Bazan	1.0	2	199	202	465	0.2	mg/cm2	0.2	Negative
11/29/2025	12:39:39	30.3165	-95.45913	T. Bazan	1.0	2	200	203	466	0.1	mg/cm2	0.2	Negative
11/29/2025	12:39:48	30.3165	-95.45913	T. Bazan	1.0	2	201	204	467	0.1	mg/cm2	0.2	Negative
11/29/2025	12:40:29	30.3165	-95.45913	T. Bazan	1.0	2	202	205	468	0.2	mg/cm2	0.2	Negative
11/29/2025	12:43:13	30.3165	-95.45913	T. Bazan	1.0	2	203	206	469	0.4	mg/cm2	0.2	Negative
11/29/2025	12:43:25	30.3167	-95.4624	T. Bazan	1.0	2	204	207	470	0.4	mg/cm2	0.2	Negative
11/29/2025	12:47:27	30.3167	-95.4624	T. Bazan	1.0	2	205	208	471	0.0	mg/cm2	0.2	Negative
11/29/2025	12:47:38	30.3167	-95.4624	T. Bazan	1.0	2	206	209	472	0.0	mg/cm2	0.2	Negative
11/29/2025	12:47:51	30.3167	-95.4624	T. Bazan	1.0	2	207	210	473	0.3	mg/cm2	0.2	Negative
11/29/2025	12:48:03	30.3115	-95.46285	T. Bazan	1.0	2	208	211	474	0.2	mg/cm2	0.2	Negative
11/29/2025	12:49:32	30.3157	-95.46027	T. Bazan	1.0	2	209	212	475	0.3	mg/cm2	0.2	Negative
11/29/2025	12:49:59	0	0	T. Bazan	1.0	2	210	213	476	0.4	mg/cm2	0.2	Negative
11/29/2025	12:59:19	0	0	T. Bazan	1.0	2	211	214	477	0.3	mg/cm2	0.2	Negative
11/29/2025	12:59:35	0	0	T. Bazan	1.0	2	212	215	478	0.4	mg/cm2	0.2	Negative
11/29/2025	12:59:52	0	0	T. Bazan	1.0	2	213	216	479	0.1	mg/cm2	0.2	Negative
11/29/2025	13:01:06	0	0	T. Bazan	1.0	4	214	217	480	0.8	mg/cm2	0.1	Negative
11/29/2025	13:03:41	0	0	T. Bazan	1.0	2	215	218	481	0.2	mg/cm2	0.2	Negative
11/29/2025	13:04:41	0	0	T. Bazan	1.0	2	216	219	482	0.3	mg/cm2	0.2	Negative
11/29/2025	13:05:16	0	0	T. Bazan	1.0	2	217	220	483	0.2	mg/cm2	0.2	Negative
11/29/2025	13:06:29	0	0	T. Bazan	1.0	2	218	221	484	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	13:06:38	0	0	T. Bazan	1.0	2	219	222	485	0.2	mg/cm2	0.2	Negative
11/29/2025	13:06:47	0	0	T. Bazan	1.0	2	220	223	486	0.0	mg/cm2	0.2	Negative
11/29/2025	13:08:17	0	0	T. Bazan	1.0	5	---	224	487	0.9	mg/cm2	0.1	Calibration
11/29/2025	13:08:34	0	0	T. Bazan	1.0	5	---	225	488	1.0	mg/cm2	0.1	Calibration
11/29/2025	13:08:53	0	0	T. Bazan	1.0	5	---	226	489	1.0	mg/cm2	0.1	Calibration
11/29/2025	13:14:53	0	0	T. Bazan	1.0	2	221	227	490	0.3	mg/cm2	0.2	Negative
11/29/2025	13:15:35	0	0	T. Bazan	1.0	2	222	228	491	0.1	mg/cm2	0.2	Negative
11/29/2025	13:15:54	0	0	T. Bazan	1.0	2	223	229	492	0.3	mg/cm2	0.2	Negative
11/29/2025	13:16:32	0	0	T. Bazan	1.0	2	224	230	493	0.1	mg/cm2	0.2	Negative
11/29/2025	13:17:15	0	0	T. Bazan	1.0	2	225	231	494	0.0	mg/cm2	0.2	Negative
11/29/2025	13:18:15	0	0	T. Bazan	1.0	2	226	232	495	0.2	mg/cm2	0.2	Negative
11/29/2025	13:19:06	0	0	T. Bazan	1.0	2	227	233	496	0.0	mg/cm2	0.2	Negative
11/29/2025	13:19:16	0	0	T. Bazan	1.0	2	228	234	497	0.3	mg/cm2	0.2	Negative
11/29/2025	13:20:16	0	0	T. Bazan	1.0	2	229	235	498	0.1	mg/cm2	0.2	Negative
11/29/2025	13:25:38	0	0	T. Bazan	1.0	2	230	236	499	0.6	mg/cm2	0.2	Negative
11/29/2025	13:25:48	0	0	T. Bazan	1.0	2	231	237	500	0.2	mg/cm2	0.2	Negative
11/29/2025	13:26:31	0	0	T. Bazan	1.0	2	232	238	501	0.1	mg/cm2	0.2	Negative
11/29/2025	13:26:47	0	0	T. Bazan	1.0	2	233	239	502	0.5	mg/cm2	0.2	Negative
11/29/2025	13:27:10	0	0	T. Bazan	1.0	2	234	240	503	0.1	mg/cm2	0.2	Negative
11/29/2025	13:27:53	0	0	T. Bazan	1.0	2	235	241	504	0.2	mg/cm2	0.2	Negative
11/29/2025	13:28:14	0	0	T. Bazan	1.0	2	236	242	505	0.3	mg/cm2	0.2	Negative
11/29/2025	13:29:09	0	0	T. Bazan	1.0	2	237	243	506	0.2	mg/cm2	0.2	Negative
11/29/2025	13:29:48	0	0	T. Bazan	1.0	2	238	244	507	0.4	mg/cm2	0.2	Negative
11/29/2025	13:29:58	0	0	T. Bazan	1.0	2	239	245	508	0.2	mg/cm2	0.2	Negative
11/29/2025	13:31:07	0	0	T. Bazan	1.0	2	240	246	509	0.0	mg/cm2	0.2	Negative
11/29/2025	13:31:20	0	0	T. Bazan	1.0	2	241	247	510	0.3	mg/cm2	0.2	Negative
11/29/2025	13:33:29	0	0	T. Bazan	1.0	2	242	248	511	0.3	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	13:35:13	0	0	T. Bazan	1.0	2	243	249	512	0.5	mg/cm2	0.2	Negative
11/29/2025	13:35:59	0	0	T. Bazan	1.0	2	244	250	513	0.2	mg/cm2	0.2	Negative
11/29/2025	13:37:20	0	0	T. Bazan	1.0	2	245	251	514	0.2	mg/cm2	0.2	Negative
11/29/2025	13:37:30	0	0	T. Bazan	1.0	2	246	252	515	0.2	mg/cm2	0.2	Negative
11/29/2025	13:38:13	0	0	T. Bazan	1.0	2	247	253	516	0.3	mg/cm2	0.2	Negative
11/29/2025	13:40:40	0	0	T. Bazan	1.0	2	248	254	517	0.1	mg/cm2	0.2	Negative
11/29/2025	13:40:49	0	0	T. Bazan	1.0	2	249	255	518	0.1	mg/cm2	0.2	Negative
11/29/2025	13:41:07	0	0	T. Bazan	1.0	2	250	256	519	0.1	mg/cm2	0.2	Negative
11/29/2025	13:41:26	0	0	T. Bazan	1.0	2	251	257	520	0.1	mg/cm2	0.2	Negative
11/29/2025	13:54:30	0	0	T. Bazan	1.0	2	252	258	521	0.2	mg/cm2	0.2	Negative
11/29/2025	13:54:39	0	0	T. Bazan	1.0	2	253	259	522	0.2	mg/cm2	0.2	Negative
11/29/2025	13:56:48	0	0	T. Bazan	1.0	2	254	260	523	0.0	mg/cm2	0.2	Negative
11/29/2025	13:58:27	0	0	T. Bazan	1.0	2	255	261	524	0.1	mg/cm2	0.2	Negative
11/29/2025	13:58:37	0	0	T. Bazan	1.0	2	256	262	525	0.1	mg/cm2	0.2	Negative
11/29/2025	13:59:40	0	0	T. Bazan	1.0	2	257	263	526	0.2	mg/cm2	0.2	Negative
11/29/2025	14:00:37	0	0	T. Bazan	1.0	2	258	264	527	0.1	mg/cm2	0.2	Negative
11/29/2025	14:00:56	0	0	T. Bazan	1.0	2	259	265	528	0.1	mg/cm2	0.2	Negative
11/29/2025	14:01:46	0	0	T. Bazan	1.0	2	260	266	529	0.2	mg/cm2	0.2	Negative
11/29/2025	14:03:51	0	0	T. Bazan	1.0	2	261	267	530	0.1	mg/cm2	0.2	Negative
11/29/2025	14:04:24	0	0	T. Bazan	1.0	2	262	268	531	0.7	mg/cm2	0.2	Negative
11/29/2025	14:04:52	0	0	T. Bazan	1.0	2	263	269	532	0.0	mg/cm2	0.2	Negative
11/29/2025	14:07:56	0	0	T. Bazan	1.0	2	264	270	533	0.3	mg/cm2	0.2	Negative
11/29/2025	14:08:05	0	0	T. Bazan	1.0	2	265	271	534	0.2	mg/cm2	0.2	Negative
11/29/2025	14:08:24	0	0	T. Bazan	1.0	2	266	272	535	0.3	mg/cm2	0.2	Negative
11/29/2025	14:08:41	0	0	T. Bazan	1.0	2	267	273	536	0.1	mg/cm2	0.2	Negative
11/29/2025	14:08:49	0	0	T. Bazan	1.0	2	268	274	537	0.1	mg/cm2	0.2	Negative
11/29/2025	14:09:05	0	0	T. Bazan	1.0	2	269	275	538	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	14:14:32	0	0	T. Bazan	1.0	2	270	276	539	0.1	mg/cm2	0.2	Negative
11/29/2025	14:14:44	0	0	T. Bazan	1.0	2	271	277	540	0.1	mg/cm2	0.2	Negative
11/29/2025	14:14:54	0	0	T. Bazan	1.0	2	272	278	541	0.0	mg/cm2	0.2	Negative
11/29/2025	14:15:04	0	0	T. Bazan	1.0	2	273	279	542	0.0	mg/cm2	0.2	Negative
11/29/2025	14:15:27	0	0	T. Bazan	1.0	2	274	280	543	0.1	mg/cm2	0.2	Negative
11/29/2025	14:16:04	0	0	T. Bazan	1.0	2	275	281	544	0.2	mg/cm2	0.2	Negative
11/29/2025	14:16:14	0	0	T. Bazan	1.0	2	276	282	545	0.3	mg/cm2	0.2	Negative
11/29/2025	14:16:35	0	0	T. Bazan	1.0	2	277	283	546	0.4	mg/cm2	0.2	Negative
11/29/2025	14:17:17	0	0	T. Bazan	1.0	2	278	284	547	0.2	mg/cm2	0.2	Negative
11/29/2025	14:17:35	0	0	T. Bazan	1.0	2	279	285	548	0.3	mg/cm2	0.2	Negative
11/29/2025	14:17:43	0	0	T. Bazan	1.0	2	280	286	549	0.4	mg/cm2	0.2	Negative
11/29/2025	14:18:15	0	0	T. Bazan	1.0	2	281	287	550	0.1	mg/cm2	0.2	Negative
11/29/2025	14:27:00	0	0	T. Bazan	1.0	2	282	288	551	0.0	mg/cm2	0.2	Negative
11/29/2025	14:27:34	0	0	T. Bazan	1.0	2	283	289	552	0.2	mg/cm2	0.2	Negative
11/29/2025	14:27:47	0	0	T. Bazan	1.0	2	284	290	553	0.1	mg/cm2	0.2	Negative
11/29/2025	14:27:59	0	0	T. Bazan	1.0	2	285	291	554	0.1	mg/cm2	0.2	Negative
11/29/2025	14:28:12	0	0	T. Bazan	1.0	2	286	292	555	0.0	mg/cm2	0.2	Negative
11/29/2025	14:28:31	0	0	T. Bazan	1.0	2	287	293	556	0.1	mg/cm2	0.2	Negative
11/29/2025	14:29:08	0	0	T. Bazan	1.0	2	288	294	557	0.2	mg/cm2	0.2	Negative
11/29/2025	14:29:19	0	0	T. Bazan	1.0	2	289	295	558	0.0	mg/cm2	0.2	Negative
11/29/2025	14:29:28	0	0	T. Bazan	1.0	2	290	296	559	0.3	mg/cm2	0.2	Negative
11/29/2025	14:30:04	0	0	T. Bazan	1.0	2	291	297	560	0.3	mg/cm2	0.2	Negative
11/29/2025	14:30:25	0	0	T. Bazan	1.0	2	292	298	561	0.5	mg/cm2	0.2	Negative
11/29/2025	14:30:33	0	0	T. Bazan	1.0	2	293	299	562	0.2	mg/cm2	0.2	Negative
11/29/2025	14:33:26	0	0	T. Bazan	1.0	2	294	300	563	0.4	mg/cm2	0.2	Negative
11/29/2025	14:33:47	0	0	T. Bazan	1.0	2	295	301	564	0.2	mg/cm2	0.2	Negative
11/29/2025	14:35:49	0	0	T. Bazan	1.0	2	296	302	565	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	14:36:01	0	0	T. Bazan	1.0	2	297	303	566	0.1	mg/cm2	0.2	Negative
11/29/2025	14:36:17	0	0	T. Bazan	1.0	2	298	304	567	0.0	mg/cm2	0.2	Negative
11/29/2025	14:36:40	0	0	T. Bazan	1.0	2	299	305	568	0.2	mg/cm2	0.2	Negative
11/29/2025	14:37:44	0	0	T. Bazan	1.0	2	300	306	569	0.1	mg/cm2	0.2	Negative
11/29/2025	14:41:53	0	0	T. Bazan	1.0	2	301	307	570	0.0	mg/cm2	0.2	Negative
11/29/2025	14:42:04	0	0	T. Bazan	1.0	2	302	308	571	0.2	mg/cm2	0.2	Negative
11/29/2025	14:42:21	0	0	T. Bazan	1.0	2	303	309	572	0.1	mg/cm2	0.2	Negative
11/29/2025	14:42:31	0	0	T. Bazan	1.0	2	304	310	573	0.0	mg/cm2	0.2	Negative
11/29/2025	14:42:55	0	0	T. Bazan	1.0	2	305	311	574	0.3	mg/cm2	0.2	Negative
11/29/2025	14:43:06	0	0	T. Bazan	1.0	2	306	312	575	0.3	mg/cm2	0.2	Negative
11/29/2025	14:43:23	0	0	T. Bazan	1.0	2	307	313	576	0.1	mg/cm2	0.2	Negative
11/29/2025	14:48:32	0	0	T. Bazan	1.0	2	308	314	577	0.1	mg/cm2	0.2	Negative
11/29/2025	14:48:52	0	0	T. Bazan	1.0	2	309	315	578	0.1	mg/cm2	0.2	Negative
11/29/2025	14:49:07	0	0	T. Bazan	1.0	2	310	316	579	0.2	mg/cm2	0.2	Negative
11/29/2025	14:49:17	0	0	T. Bazan	1.0	2	311	317	580	0.0	mg/cm2	0.2	Negative
11/29/2025	14:49:31	0	0	T. Bazan	1.0	2	312	318	581	0.1	mg/cm2	0.2	Negative
11/29/2025	14:49:49	0	0	T. Bazan	1.0	2	313	319	582	0.1	mg/cm2	0.2	Negative
11/29/2025	14:50:28	0	0	T. Bazan	1.0	2	314	320	583	0.3	mg/cm2	0.2	Negative
11/29/2025	14:50:39	0	0	T. Bazan	1.0	2	315	321	584	0.2	mg/cm2	0.2	Negative
11/29/2025	14:50:48	0	0	T. Bazan	1.0	2	316	322	585	0.3	mg/cm2	0.2	Negative
11/29/2025	14:51:23	0	0	T. Bazan	1.0	2	317	323	586	0.2	mg/cm2	0.2	Negative
11/29/2025	14:51:45	0	0	T. Bazan	1.0	2	318	324	587	0.5	mg/cm2	0.2	Negative
11/29/2025	14:51:54	0	0	T. Bazan	1.0	2	319	325	588	0.4	mg/cm2	0.2	Negative
11/29/2025	14:55:53	0	0	T. Bazan	1.0	2	320	326	589	0.0	mg/cm2	0.2	Negative
11/29/2025	15:00:05	0	0	T. Bazan	1.0	2	321	327	590	0.1	mg/cm2	0.2	Negative
11/29/2025	15:00:25	0	0	T. Bazan	1.0	2	322	328	591	0.0	mg/cm2	0.2	Negative
11/29/2025	15:00:34	0	0	T. Bazan	1.0	2	323	329	592	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/29/2025	15:00:52	0	0	T. Bazan	1.0	2	324	330	593	0.1	mg/cm2	0.2	Negative
11/29/2025	15:01:32	0	0	T. Bazan	1.0	2	325	331	594	0.2	mg/cm2	0.2	Negative
11/29/2025	15:01:41	0	0	T. Bazan	1.0	2	326	332	595	0.0	mg/cm2	0.2	Negative
11/29/2025	15:01:50	0	0	T. Bazan	1.0	2	327	333	596	0.2	mg/cm2	0.2	Negative
11/29/2025	15:02:25	0	0	T. Bazan	1.0	2	328	334	597	0.1	mg/cm2	0.2	Negative
11/29/2025	15:02:49	0	0	T. Bazan	1.0	2	329	335	598	0.5	mg/cm2	0.2	Negative
11/29/2025	15:02:58	0	0	T. Bazan	1.0	2	330	336	599	0.3	mg/cm2	0.2	Negative
11/29/2025	15:03:30	0	0	T. Bazan	1.0	2	331	337	600	0.0	mg/cm2	0.2	Negative
11/29/2025	15:04:31	0	0	T. Bazan	1.0	5	---	338	601	0.9	mg/cm2	0.1	Calibration
11/29/2025	15:04:50	0	0	T. Bazan	1.0	5	---	339	602	1.0	mg/cm2	0.1	Calibration
11/29/2025	15:05:10	0	0	T. Bazan	1.0	5	---	340	603	0.9	mg/cm2	0.1	Calibration
DAY THREE													
11/30/2025	9:25:23	0	0	T. Bazan	1.0	5	---	1	604	1.1	mg/cm2	0.1	Calibration
11/30/2025	9:25:44	0	0	T. Bazan	1.0	5	---	2	605	1.0	mg/cm2	0.1	Calibration
11/30/2025	9:26:02	0	0	T. Bazan	1.0	5	---	3	606	1.0	mg/cm2	0.1	Calibration
11/30/2025	9:29:50	0	0	T. Bazan	1.0	2	1	4	607	0.0	mg/cm2	0.2	Negative
11/30/2025	9:30:05	0	0	T. Bazan	1.0	2	2	5	608	0.0	mg/cm2	0.2	Negative
11/30/2025	9:30:22	0	0	T. Bazan	1.0	2	3	6	609	0.0	mg/cm2	0.2	Negative
11/30/2025	9:30:31	0	0	T. Bazan	1.0	2	4	7	610	0.0	mg/cm2	0.2	Negative
11/30/2025	9:30:48	0	0	T. Bazan	1.0	2	5	8	611	0.2	mg/cm2	0.2	Negative
11/30/2025	9:32:53	0	0	T. Bazan	1.0	2	6	9	612	0.2	mg/cm2	0.2	Negative
11/30/2025	9:33:02	0	0	T. Bazan	1.0	2	7	10	613	0.1	mg/cm2	0.2	Negative
11/30/2025	9:33:12	0	0	T. Bazan	1.0	2	8	11	614	0.1	mg/cm2	0.2	Negative
11/30/2025	9:33:42	0	0	T. Bazan	1.0	2	9	12	615	0.3	mg/cm2	0.2	Negative
11/30/2025	9:34:03	0	0	T. Bazan	1.0	2	10	13	616	0.5	mg/cm2	0.2	Negative
11/30/2025	9:34:12	0	0	T. Bazan	1.0	2	11	14	617	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	9:34:41	0	0	T. Bazan	1.0	2	12	15	618	0.1	mg/cm2	0.2	Negative
11/30/2025	9:40:54	0	0	T. Bazan	1.0	2	13	16	619	0.3	mg/cm2	0.2	Negative
11/30/2025	9:41:03	0	0	T. Bazan	1.0	2	14	17	620	0.2	mg/cm2	0.2	Negative
11/30/2025	9:41:24	0	0	T. Bazan	1.0	2	15	18	621	0.1	mg/cm2	0.2	Negative
11/30/2025	9:42:21	0	0	T. Bazan	1.0	2	16	19	622	0.2	mg/cm2	0.2	Negative
11/30/2025	9:42:41	0	0	T. Bazan	1.0	2	17	20	623	0.1	mg/cm2	0.2	Negative
11/30/2025	9:42:55	0	0	T. Bazan	1.0	2	18	21	624	0.1	mg/cm2	0.2	Negative
11/30/2025	9:44:06	0	0	T. Bazan	1.0	2	19	22	625	0.1	mg/cm2	0.2	Negative
11/30/2025	9:44:16	0	0	T. Bazan	1.0	2	20	23	626	0.1	mg/cm2	0.2	Negative
11/30/2025	9:46:06	0	0	T. Bazan	1.0	2	21	24	627	0.0	mg/cm2	0.2	Negative
11/30/2025	9:53:08	0	0	T. Bazan	1.0	2	22	25	628	0.0	mg/cm2	0.2	Negative
11/30/2025	9:53:21	0	0	T. Bazan	1.0	2	23	26	629	0.0	mg/cm2	0.2	Negative
11/30/2025	9:53:40	0	0	T. Bazan	1.0	2	24	27	630	0.1	mg/cm2	0.2	Negative
11/30/2025	9:53:49	0	0	T. Bazan	1.0	2	25	28	631	0.2	mg/cm2	0.2	Negative
11/30/2025	9:54:05	0	0	T. Bazan	1.0	2	26	29	632	0.2	mg/cm2	0.2	Negative
11/30/2025	9:54:41	0	0	T. Bazan	1.0	2	27	30	633	0.1	mg/cm2	0.2	Negative
11/30/2025	9:54:51	0	0	T. Bazan	1.0	2	28	31	634	0.1	mg/cm2	0.2	Negative
11/30/2025	9:55:00	0	0	T. Bazan	1.0	2	29	32	635	0.1	mg/cm2	0.2	Negative
11/30/2025	9:55:30	0	0	T. Bazan	1.0	2	30	33	636	0.3	mg/cm2	0.2	Negative
11/30/2025	9:55:51	0	0	T. Bazan	1.0	2	31	34	637	0.4	mg/cm2	0.2	Negative
11/30/2025	9:55:59	0	0	T. Bazan	1.0	2	32	35	638	0.4	mg/cm2	0.2	Negative
11/30/2025	9:56:26	0	0	T. Bazan	1.0	2	33	36	639	0.1	mg/cm2	0.2	Negative
11/30/2025	10:04:05	0	0	T. Bazan	1.0	2	34	37	640	0.0	mg/cm2	0.2	Negative
11/30/2025	10:04:19	0	0	T. Bazan	1.0	2	35	38	641	0.1	mg/cm2	0.2	Negative
11/30/2025	10:04:30	0	0	T. Bazan	1.0	2	36	39	642	0.0	mg/cm2	0.2	Negative
11/30/2025	10:04:40	0	0	T. Bazan	1.0	2	37	40	643	0.0	mg/cm2	0.2	Negative
11/30/2025	10:04:57	0	0	T. Bazan	1.0	2	38	41	644	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	10:05:39	0	0	T. Bazan	1.0	2	39	42	645	0.2	mg/cm2	0.2	Negative
11/30/2025	10:05:49	0	0	T. Bazan	1.0	2	40	43	646	0.2	mg/cm2	0.2	Negative
11/30/2025	10:06:00	0	0	T. Bazan	1.0	2	41	44	647	0.3	mg/cm2	0.2	Negative
11/30/2025	10:07:31	0	0	T. Bazan	1.0	2	42	45	648	0.3	mg/cm2	0.2	Negative
11/30/2025	10:07:49	0	0	T. Bazan	1.0	2	43	46	649	0.3	mg/cm2	0.2	Negative
11/30/2025	10:07:57	0	0	T. Bazan	1.0	2	44	47	650	0.2	mg/cm2	0.2	Negative
11/30/2025	10:08:39	0	0	T. Bazan	1.0	2	45	48	651	0.2	mg/cm2	0.2	Negative
11/30/2025	10:09:13	0	0	T. Bazan	1.0	2	46	49	652	0.1	mg/cm2	0.2	Negative
11/30/2025	10:19:39	0	0	T. Bazan	1.0	2	47	50	653	0.1	mg/cm2	0.2	Negative
11/30/2025	10:20:04	0	0	T. Bazan	1.0	2	48	51	654	0.1	mg/cm2	0.2	Negative
11/30/2025	10:20:14	0	0	T. Bazan	1.0	2	49	52	655	0.1	mg/cm2	0.2	Negative
11/30/2025	10:20:27	0	0	T. Bazan	1.0	2	50	53	656	0.4	mg/cm2	0.2	Negative
11/30/2025	10:20:36	0	0	T. Bazan	1.0	2	51	54	657	0.0	mg/cm2	0.2	Negative
11/30/2025	10:20:56	0	0	T. Bazan	1.0	2	52	55	658	0.1	mg/cm2	0.2	Negative
11/30/2025	10:21:43	0	0	T. Bazan	1.0	2	53	56	659	0.2	mg/cm2	0.2	Negative
11/30/2025	10:21:53	0	0	T. Bazan	1.0	2	54	57	660	0.5	mg/cm2	0.2	Negative
11/30/2025	10:22:02	0	0	T. Bazan	1.0	2	55	58	661	0.1	mg/cm2	0.2	Negative
11/30/2025	10:22:47	0	0	T. Bazan	1.0	2	56	59	662	0.2	mg/cm2	0.2	Negative
11/30/2025	10:22:56	0	0	T. Bazan	1.0	2	57	60	663	0.4	mg/cm2	0.2	Negative
11/30/2025	10:23:16	0	0	T. Bazan	1.0	2	58	61	664	0.0	mg/cm2	0.2	Negative
11/30/2025	10:23:30	0	0	T. Bazan	1.0	2	59	62	665	0.1	mg/cm2	0.2	Negative
11/30/2025	10:23:46	0	0	T. Bazan	1.0	2	60	63	666	0.1	mg/cm2	0.2	Negative
11/30/2025	10:33:23	0	0	T. Bazan	1.0	2	61	64	667	0.1	mg/cm2	0.2	Negative
11/30/2025	10:33:37	0	0	T. Bazan	1.0	2	62	65	668	0.2	mg/cm2	0.2	Negative
11/30/2025	10:33:47	0	0	T. Bazan	1.0	2	63	66	669	0.0	mg/cm2	0.2	Negative
11/30/2025	10:33:57	0	0	T. Bazan	1.0	5	64	67	670	0.8	mg/cm2	0.1	Negative
11/30/2025	10:34:53	0	0	T. Bazan	1.0	5	65	68	671	1.0	mg/cm2	0.1	Positive

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	10:36:46	0	0	T. Bazan	1.0	2	66	69	672	0.7	mg/cm2	0.2	Negative
11/30/2025	10:37:32	0	0	T. Bazan	1.0	4	67	70	673	0.8	mg/cm2	0.2	Negative
11/30/2025	10:38:06	0	0	T. Bazan	1.0	2	68	71	674	0.1	mg/cm2	0.2	Negative
11/30/2025	10:38:19	0	0	T. Bazan	1.0	2	69	72	675	0.1	mg/cm2	0.2	Negative
11/30/2025	10:38:34	0	0	T. Bazan	1.0	2	70	73	676	0.1	mg/cm2	0.2	Negative
11/30/2025	10:39:28	0	0	T. Bazan	1.0	2	71	74	677	0.1	mg/cm2	0.2	Negative
11/30/2025	10:40:09	0	0	T. Bazan	1.0	2	72	75	678	0.1	mg/cm2	0.2	Negative
11/30/2025	10:40:47	0	0	T. Bazan	1.0	2	73	76	679	0.2	mg/cm2	0.2	Negative
11/30/2025	10:47:30	0	0	T. Bazan	1.0	2	74	77	680	0.0	mg/cm2	0.2	Negative
11/30/2025	10:47:41	0	0	T. Bazan	1.0	2	75	78	681	0.1	mg/cm2	0.2	Negative
11/30/2025	10:47:59	0	0	T. Bazan	1.0	2	76	79	682	0.1	mg/cm2	0.2	Negative
11/30/2025	10:48:18	0	0	T. Bazan	1.0	2	77	80	683	0.1	mg/cm2	0.2	Negative
11/30/2025	10:48:59	0	0	T. Bazan	1.0	2	78	81	684	0.2	mg/cm2	0.2	Negative
11/30/2025	10:49:08	0	0	T. Bazan	1.0	2	79	82	685	0.0	mg/cm2	0.2	Negative
11/30/2025	10:49:57	0	0	T. Bazan	1.0	2	80	83	686	0.1	mg/cm2	0.2	Negative
11/30/2025	10:51:04	0	0	T. Bazan	1.0	2	81	84	687	0.2	mg/cm2	0.2	Negative
11/30/2025	10:51:13	0	0	T. Bazan	1.0	2	82	85	688	0.2	mg/cm2	0.2	Negative
11/30/2025	10:51:31	0	0	T. Bazan	1.0	2	83	86	689	0.3	mg/cm2	0.2	Negative
11/30/2025	10:51:40	0	0	T. Bazan	1.0	2	84	87	690	0.0	mg/cm2	0.2	Negative
11/30/2025	10:51:56	0	0	T. Bazan	1.0	2	85	88	691	0.2	mg/cm2	0.2	Negative
11/30/2025	10:58:51	0	0	T. Bazan	1.0	2	86	89	692	0.0	mg/cm2	0.2	Negative
11/30/2025	10:59:04	0	0	T. Bazan	1.0	2	87	90	693	0.2	mg/cm2	0.2	Negative
11/30/2025	10:59:15	0	0	T. Bazan	1.0	2	88	91	694	0.1	mg/cm2	0.2	Negative
11/30/2025	10:59:30	0	0	T. Bazan	1.0	2	89	92	695	0.0	mg/cm2	0.2	Negative
11/30/2025	10:59:49	0	0	T. Bazan	1.0	2	90	93	696	0.2	mg/cm2	0.2	Negative
11/30/2025	11:00:28	0	0	T. Bazan	1.0	2	91	94	697	0.0	mg/cm2	0.2	Negative
11/30/2025	11:00:38	0	0	T. Bazan	1.0	2	92	95	698	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	11:00:48	0	0	T. Bazan	1.0	2	93	96	699	0.1	mg/cm2	0.2	Negative
11/30/2025	11:01:29	30.4007	-95.46018	T. Bazan	1.0	2	94	97	700	0.4	mg/cm2	0.2	Negative
11/30/2025	11:01:50	30.3333	-95.46181	T. Bazan	1.0	2	95	98	701	0.3	mg/cm2	0.2	Negative
11/30/2025	11:02:19	30.3325	-95.46204	T. Bazan	1.0	2	96	99	702	0.5	mg/cm2	0.2	Negative
11/30/2025	11:03:00	30.3092	-95.46063	T. Bazan	1.0	2	97	100	703	0.1	mg/cm2	0.2	Negative
11/30/2025	11:11:31	30.3092	-95.46063	T. Bazan	1.0	2	98	101	704	0.1	mg/cm2	0.2	Negative
11/30/2025	11:11:41	30.3075	-95.46096	T. Bazan	1.0	2	99	102	705	0.1	mg/cm2	0.2	Negative
11/30/2025	11:11:52	30.3075	-95.46104	T. Bazan	1.0	2	100	103	706	0.0	mg/cm2	0.2	Negative
11/30/2025	11:12:02	30.31	-95.46111	T. Bazan	1.0	2	101	104	707	0.0	mg/cm2	0.2	Negative
11/30/2025	11:12:18	30.3109	-95.46073	T. Bazan	1.0	2	102	105	708	0.1	mg/cm2	0.2	Negative
11/30/2025	11:12:58	30.3107	-95.46076	T. Bazan	1.0	2	103	106	709	0.1	mg/cm2	0.2	Negative
11/30/2025	11:13:07	30.3105	-95.46079	T. Bazan	1.0	2	104	107	710	0.3	mg/cm2	0.2	Negative
11/30/2025	11:13:17	30.3118	-95.46064	T. Bazan	1.0	2	105	108	711	0.3	mg/cm2	0.2	Negative
11/30/2025	11:14:00	30.313	-95.46059	T. Bazan	1.0	2	106	109	712	0.3	mg/cm2	0.2	Negative
11/30/2025	11:14:23	30.3131	-95.46057	T. Bazan	1.0	2	107	110	713	0.2	mg/cm2	0.2	Negative
11/30/2025	11:14:38	30.3131	-95.46058	T. Bazan	1.0	2	108	111	714	0.3	mg/cm2	0.2	Negative
11/30/2025	11:15:11	0	0	T. Bazan	1.0	2	109	112	715	0.0	mg/cm2	0.2	Negative
11/30/2025	11:34:20	0	0	T. Bazan	1.0	2	110	113	716	0.4	mg/cm2	0.2	Negative
11/30/2025	11:34:52	0	0	T. Bazan	1.0	2	111	114	717	0.2	mg/cm2	0.2	Negative
11/30/2025	11:35:01	0	0	T. Bazan	1.0	2	112	115	718	0.1	mg/cm2	0.2	Negative
11/30/2025	11:35:47	0	0	T. Bazan	1.0	2	113	116	719	0.1	mg/cm2	0.2	Negative
11/30/2025	11:36:30	0	0	T. Bazan	1.0	2	114	117	720	0.1	mg/cm2	0.2	Negative
11/30/2025	11:37:11	0	0	T. Bazan	1.0	2	115	118	721	0.4	mg/cm2	0.2	Negative
11/30/2025	11:38:23	0	0	T. Bazan	1.0	2	116	119	722	0.3	mg/cm2	0.2	Negative
11/30/2025	11:39:07	0	0	T. Bazan	1.0	2	117	120	723	0.1	mg/cm2	0.2	Negative
11/30/2025	11:41:26	0	0	T. Bazan	1.0	2	118	121	724	0.1	mg/cm2	0.2	Negative
11/30/2025	11:42:06	0	0	T. Bazan	1.0	2	119	122	725	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	11:42:21	0	0	T. Bazan	1.0	2	120	123	726	0.1	mg/cm2	0.2	Negative
11/30/2025	11:43:21	0	0	T. Bazan	1.0	2	121	124	727	0.1	mg/cm2	0.2	Negative
11/30/2025	11:43:47	0	0	T. Bazan	1.0	2	122	125	728	0.1	mg/cm2	0.2	Negative
11/30/2025	11:44:34	0	0	T. Bazan	1.0	2	123	126	729	0.0	mg/cm2	0.2	Negative
11/30/2025	11:45:24	0	0	T. Bazan	1.0	2	124	127	730	0.1	mg/cm2	0.2	Negative
11/30/2025	11:45:56	0	0	T. Bazan	1.0	2	125	128	731	0.1	mg/cm2	0.2	Negative
11/30/2025	11:46:54	0	0	T. Bazan	1.0	2	126	129	732	0.1	mg/cm2	0.2	Negative
11/30/2025	11:47:03	0	0	T. Bazan	1.0	2	127	130	733	0.3	mg/cm2	0.2	Negative
11/30/2025	11:47:59	0	0	T. Bazan	1.0	2	128	131	734	0.1	mg/cm2	0.2	Negative
11/30/2025	11:48:08	0	0	T. Bazan	1.0	2	129	132	735	0.2	mg/cm2	0.2	Negative
11/30/2025	11:49:41	0	0	T. Bazan	1.0	2	130	133	736	0.2	mg/cm2	0.2	Negative
11/30/2025	11:49:58	0	0	T. Bazan	1.0	2	131	134	737	0.1	mg/cm2	0.2	Negative
11/30/2025	11:50:22	0	0	T. Bazan	1.0	2	132	135	738	0.1	mg/cm2	0.2	Negative
11/30/2025	11:50:40	0	0	T. Bazan	1.0	2	133	136	739	0.2	mg/cm2	0.2	Negative
11/30/2025	11:58:21	0	0	T. Bazan	1.0	2	134	137	740	0.2	mg/cm2	0.2	Negative
11/30/2025	12:00:07	0	0	T. Bazan	1.0	2	135	138	741	0.4	mg/cm2	0.2	Negative
11/30/2025	12:00:22	0	0	T. Bazan	1.0	2	136	139	742	0.2	mg/cm2	0.2	Negative
11/30/2025	12:01:32	0	0	T. Bazan	1.0	2	137	140	743	0.1	mg/cm2	0.2	Negative
11/30/2025	12:04:14	0	0	T. Bazan	1.0	2	138	141	744	0.2	mg/cm2	0.2	Negative
11/30/2025	12:04:23	0	0	T. Bazan	1.0	2	139	142	745	0.2	mg/cm2	0.2	Negative
11/30/2025	12:04:31	0	0	T. Bazan	1.0	2	140	143	746	0.3	mg/cm2	0.2	Negative
11/30/2025	12:04:48	0	0	T. Bazan	1.0	2	141	144	747	0.2	mg/cm2	0.2	Negative
11/30/2025	12:06:59	0	0	T. Bazan	1.0	2	142	145	748	0.4	mg/cm2	0.2	Negative
11/30/2025	12:07:08	0	0	T. Bazan	1.0	2	143	146	749	0.3	mg/cm2	0.2	Negative
11/30/2025	12:07:17	0	0	T. Bazan	1.0	2	144	147	750	0.1	mg/cm2	0.2	Negative
11/30/2025	12:07:35	0	0	T. Bazan	1.0	2	145	148	751	0.2	mg/cm2	0.2	Negative
11/30/2025	12:07:46	0	0	T. Bazan	1.0	2	146	149	752	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	12:08:41	0	0	T. Bazan	1.0	2	147	150	753	0.1	mg/cm2	0.2	Negative
11/30/2025	12:10:16	0	0	T. Bazan	1.0	2	148	151	754	0.1	mg/cm2	0.2	Negative
11/30/2025	12:10:24	0	0	T. Bazan	1.0	2	149	152	755	0.2	mg/cm2	0.2	Negative
11/30/2025	12:10:39	0	0	T. Bazan	1.0	2	150	153	756	0.1	mg/cm2	0.2	Negative
11/30/2025	12:12:00	0	0	T. Bazan	1.0	2	151	154	757	0.1	mg/cm2	0.2	Negative
11/30/2025	12:12:20	0	0	T. Bazan	1.0	2	152	155	758	0.1	mg/cm2	0.2	Negative
11/30/2025	12:13:10	0	0	T. Bazan	1.0	2	153	156	759	0.1	mg/cm2	0.2	Negative
11/30/2025	12:13:45	0	0	T. Bazan	1.0	2	154	157	760	0.2	mg/cm2	0.2	Negative
11/30/2025	12:13:57	0	0	T. Bazan	1.0	2	155	158	761	0.2	mg/cm2	0.2	Negative
11/30/2025	12:14:18	0	0	T. Bazan	1.0	2	156	159	762	0.1	mg/cm2	0.2	Negative
11/30/2025	12:15:42	0	0	T. Bazan	1.0	2	157	160	763	0.1	mg/cm2	0.2	Negative
11/30/2025	12:18:31	0	0	T. Bazan	1.0	2	158	161	764	0.5	mg/cm2	0.2	Negative
11/30/2025	12:19:50	0	0	T. Bazan	1.0	2	159	162	765	0.1	mg/cm2	0.2	Negative
11/30/2025	12:21:19	0	0	T. Bazan	1.0	2	160	163	766	0.2	mg/cm2	0.2	Negative
11/30/2025	12:21:31	0	0	T. Bazan	1.0	2	161	164	767	0.1	mg/cm2	0.2	Negative
11/30/2025	12:22:14	0	0	T. Bazan	1.0	2	162	165	768	0.1	mg/cm2	0.2	Negative
11/30/2025	12:23:59	0	0	T. Bazan	1.0	2	163	166	769	0.1	mg/cm2	0.2	Negative
11/30/2025	12:25:18	0	0	T. Bazan	1.0	2	164	167	770	0.2	mg/cm2	0.2	Negative
11/30/2025	12:25:27	0	0	T. Bazan	1.0	2	165	168	771	0.1	mg/cm2	0.2	Negative
11/30/2025	12:25:45	0	0	T. Bazan	1.0	2	166	169	772	0.1	mg/cm2	0.2	Negative
11/30/2025	12:26:20	0	0	T. Bazan	1.0	2	167	170	773	0.2	mg/cm2	0.2	Negative
11/30/2025	12:29:56	0	0	T. Bazan	1.0	2	168	171	774	0.2	mg/cm2	0.2	Negative
11/30/2025	12:30:14	0	0	T. Bazan	1.0	2	169	172	775	0.2	mg/cm2	0.2	Negative
11/30/2025	12:30:24	0	0	T. Bazan	1.0	2	170	173	776	0.2	mg/cm2	0.2	Negative
11/30/2025	12:30:33	0	0	T. Bazan	1.0	2	171	174	777	0.3	mg/cm2	0.2	Negative
11/30/2025	12:33:45	0	0	T. Bazan	1.0	2	172	175	778	0.1	mg/cm2	0.2	Negative
11/30/2025	12:33:58	0	0	T. Bazan	1.0	2	173	176	779	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	12:34:08	0	0	T. Bazan	1.0	2	174	177	780	0.0	mg/cm2	0.2	Negative
11/30/2025	12:34:37	0	0	T. Bazan	1.0	2	175	178	781	0.1	mg/cm2	0.2	Negative
11/30/2025	12:35:07	0	0	T. Bazan	1.0	2	176	179	782	0.2	mg/cm2	0.2	Negative
11/30/2025	12:40:41	0	0	T. Bazan	1.0	2	177	180	783	0.1	mg/cm2	0.2	Negative
11/30/2025	12:41:02	0	0	T. Bazan	1.0	2	178	181	784	0.0	mg/cm2	0.2	Negative
11/30/2025	12:41:31	0	0	T. Bazan	1.0	2	179	182	785	0.1	mg/cm2	0.2	Negative
11/30/2025	12:42:20	0	0	T. Bazan	1.0	2	180	183	786	0.2	mg/cm2	0.2	Negative
11/30/2025	12:42:30	0	0	T. Bazan	1.0	2	181	184	787	0.2	mg/cm2	0.2	Negative
11/30/2025	12:47:23	0	0	T. Bazan	1.0	2	182	185	788	0.3	mg/cm2	0.2	Negative
11/30/2025	12:47:39	0	0	T. Bazan	1.0	2	183	186	789	0.1	mg/cm2	0.2	Negative
11/30/2025	12:52:03	0	0	T. Bazan	1.0	2	184	187	790	0.1	mg/cm2	0.2	Negative
11/30/2025	12:52:13	0	0	T. Bazan	1.0	2	185	188	791	0.0	mg/cm2	0.2	Negative
11/30/2025	12:54:11	0	0	T. Bazan	1.0	2	186	189	792	0.1	mg/cm2	0.2	Negative
11/30/2025	12:54:21	0	0	T. Bazan	1.0	2	187	190	793	0.0	mg/cm2	0.2	Negative
11/30/2025	12:54:56	0	0	T. Bazan	1.0	2	188	191	794	0.1	mg/cm2	0.2	Negative
11/30/2025	12:55:20	0	0	T. Bazan	1.0	2	189	192	795	0.1	mg/cm2	0.2	Negative
11/30/2025	12:56:00	0	0	T. Bazan	1.0	2	190	193	796	0.3	mg/cm2	0.2	Negative
11/30/2025	12:56:20	0	0	T. Bazan	1.0	2	191	194	797	0.2	mg/cm2	0.2	Negative
11/30/2025	12:57:54	0	0	T. Bazan	1.0	2	192	195	798	0.6	mg/cm2	0.2	Negative
11/30/2025	13:00:49	0	0	T. Bazan	1.0	2	193	196	799	0.2	mg/cm2	0.2	Negative
11/30/2025	13:00:58	0	0	T. Bazan	1.0	2	194	197	800	0.0	mg/cm2	0.2	Negative
11/30/2025	13:01:32	0	0	T. Bazan	1.0	2	195	198	801	0.2	mg/cm2	0.2	Negative
11/30/2025	13:02:35	0	0	T. Bazan	1.0	2	196	199	802	0.5	mg/cm2	0.2	Negative
11/30/2025	13:03:18	0	0	T. Bazan	1.0	2	197	200	803	0.5	mg/cm2	0.2	Negative
11/30/2025	13:08:25	0	0	T. Bazan	1.0	2	198	201	804	0.1	mg/cm2	0.2	Negative
11/30/2025	13:08:36	0	0	T. Bazan	1.0	2	199	202	805	0.0	mg/cm2	0.2	Negative
11/30/2025	13:09:10	0	0	T. Bazan	1.0	2	200	203	806	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	13:11:29	0	0	T. Bazan	1.0	2	201	204	807	0.2	mg/cm2	0.2	Negative
11/30/2025	13:14:45	0	0	T. Bazan	1.0	5	---	205	808	0.9	mg/cm2	0.1	Calibration
11/30/2025	13:15:03	0	0	T. Bazan	1.0	5	---	206	809	0.9	mg/cm2	0.1	Calibration
11/30/2025	13:15:21	0	0	T. Bazan	1.0	5	---	207	810	0.9	mg/cm2	0.1	Calibration
11/30/2025	13:17:12	0	0	T. Bazan	1.0	2	202	208	811	0.1	mg/cm2	0.2	Negative
11/30/2025	13:17:26	0	0	T. Bazan	1.0	2	203	209	812	0.0	mg/cm2	0.2	Negative
11/30/2025	13:19:07	0	0	T. Bazan	1.0	2	204	210	813	0.1	mg/cm2	0.2	Negative
11/30/2025	13:19:31	0	0	T. Bazan	1.0	2	205	211	814	0.3	mg/cm2	0.2	Negative
11/30/2025	13:20:03	0	0	T. Bazan	1.0	2	206	212	815	0.2	mg/cm2	0.2	Negative
11/30/2025	13:20:13	0	0	T. Bazan	1.0	2	207	213	816	0.1	mg/cm2	0.2	Negative
11/30/2025	13:24:14	0	0	T. Bazan	1.0	2	208	214	817	0.0	mg/cm2	0.2	Negative
11/30/2025	13:24:24	0	0	T. Bazan	1.0	2	209	215	818	0.0	mg/cm2	0.2	Negative
11/30/2025	13:24:40	0	0	T. Bazan	1.0	2	210	216	819	0.1	mg/cm2	0.2	Negative
11/30/2025	13:25:01	0	0	T. Bazan	1.0	2	211	217	820	0.4	mg/cm2	0.2	Negative
11/30/2025	13:26:20	0	0	T. Bazan	1.0	2	212	218	821	0.4	mg/cm2	0.2	Negative
11/30/2025	13:31:23	0	0	T. Bazan	1.0	2	213	219	822	0.0	mg/cm2	0.2	Negative
11/30/2025	13:31:32	0	0	T. Bazan	1.0	2	214	220	823	0.0	mg/cm2	0.2	Negative
11/30/2025	13:31:54	0	0	T. Bazan	1.0	2	215	221	824	0.0	mg/cm2	0.2	Negative
11/30/2025	13:32:12	0	0	T. Bazan	1.0	2	216	222	825	0.3	mg/cm2	0.2	Negative
11/30/2025	13:33:03	0	0	T. Bazan	1.0	2	217	223	826	0.3	mg/cm2	0.2	Negative
11/30/2025	13:33:42	0	0	T. Bazan	1.0	2	218	224	827	0.2	mg/cm2	0.2	Negative
11/30/2025	13:40:01	0	0	T. Bazan	1.0	2	219	225	828	0.0	mg/cm2	0.2	Negative
11/30/2025	13:40:18	0	0	T. Bazan	1.0	2	220	226	829	0.2	mg/cm2	0.2	Negative
11/30/2025	13:44:12	0	0	T. Bazan	1.0	2	221	227	830	0.0	mg/cm2	0.2	Negative
11/30/2025	13:44:21	0	0	T. Bazan	1.0	2	222	228	831	0.0	mg/cm2	0.2	Negative
11/30/2025	13:44:38	0	0	T. Bazan	1.0	2	223	229	832	0.0	mg/cm2	0.2	Negative
11/30/2025	13:45:18	0	0	T. Bazan	1.0	2	224	230	833	0.3	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	13:45:29	0	0	T. Bazan	1.0	2	225	231	834	0.1	mg/cm2	0.2	Negative
11/30/2025	13:45:38	0	0	T. Bazan	1.0	2	226	232	835	0.4	mg/cm2	0.2	Negative
11/30/2025	13:46:17	0	0	T. Bazan	1.0	2	227	233	836	0.2	mg/cm2	0.2	Negative
11/30/2025	13:46:54	0	0	T. Bazan	1.0	2	228	234	837	0.5	mg/cm2	0.2	Negative
11/30/2025	13:47:14	0	0	T. Bazan	1.0	2	229	235	838	0.1	mg/cm2	0.2	Negative
11/30/2025	13:48:33	0	0	T. Bazan	1.0	2	230	236	839	0.0	mg/cm2	0.2	Negative
11/30/2025	13:49:08	0	0	T. Bazan	1.0	2	231	237	840	0.1	mg/cm2	0.2	Negative
11/30/2025	13:49:18	0	0	T. Bazan	1.0	2	232	238	841	0.1	mg/cm2	0.2	Negative
11/30/2025	13:55:50	0	0	T. Bazan	1.0	2	233	239	842	0.1	mg/cm2	0.2	Negative
11/30/2025	13:56:15	0	0	T. Bazan	1.0	5	234	240	843	0.9	mg/cm2	0.1	Negative
11/30/2025	13:57:19	0	0	T. Bazan	1.0	5	235	241	844	1.0	mg/cm2	0.1	Positive
11/30/2025	13:59:49	0	0	T. Bazan	1.0	2	236	242	845	0.2	mg/cm2	0.2	Negative
11/30/2025	13:59:58	0	0	T. Bazan	1.0	2	237	243	846	0.2	mg/cm2	0.2	Negative
11/30/2025	14:00:09	0	0	T. Bazan	1.0	2	238	244	847	0.1	mg/cm2	0.2	Negative
11/30/2025	14:00:19	0	0	T. Bazan	1.0	2	239	245	848	0.2	mg/cm2	0.2	Negative
11/30/2025	14:00:57	0	0	T. Bazan	1.0	2	240	246	849	0.1	mg/cm2	0.2	Negative
11/30/2025	14:01:07	0	0	T. Bazan	1.0	2	241	247	850	0.0	mg/cm2	0.2	Negative
11/30/2025	14:01:15	0	0	T. Bazan	1.0	2	242	248	851	0.0	mg/cm2	0.2	Negative
11/30/2025	14:09:16	0	0	T. Bazan	1.0	2	243	249	852	0.1	mg/cm2	0.2	Negative
11/30/2025	14:10:05	0	0	T. Bazan	1.0	2	244	250	853	0.2	mg/cm2	0.2	Negative
11/30/2025	14:10:14	0	0	T. Bazan	1.0	2	245	251	854	0.2	mg/cm2	0.2	Negative
11/30/2025	14:10:29	0	0	T. Bazan	1.0	2	246	252	855	0.1	mg/cm2	0.2	Negative
11/30/2025	14:13:12	0	0	T. Bazan	1.0	2	247	253	856	0.1	mg/cm2	0.2	Negative
11/30/2025	14:13:24	0	0	T. Bazan	1.0	2	248	254	857	0.2	mg/cm2	0.2	Negative
11/30/2025	14:15:32	0	0	T. Bazan	1.0	2	249	255	858	0.2	mg/cm2	0.2	Negative
11/30/2025	14:15:42	0	0	T. Bazan	1.0	2	250	256	859	0.1	mg/cm2	0.2	Negative
11/30/2025	14:16:02	0	0	T. Bazan	1.0	2	251	257	860	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	14:16:32	0	0	T. Bazan	1.0	2	252	258	861	0.4	mg/cm2	0.2	Negative
11/30/2025	14:17:22	0	0	T. Bazan	1.0	2	253	259	862	0.2	mg/cm2	0.2	Negative
11/30/2025	14:20:04	0	0	T. Bazan	1.0	2	254	260	863	0.2	mg/cm2	0.2	Negative
11/30/2025	14:20:15	0	0	T. Bazan	1.0	2	255	261	864	0.0	mg/cm2	0.2	Negative
11/30/2025	14:20:34	0	0	T. Bazan	1.0	2	256	262	865	0.3	mg/cm2	0.2	Negative
11/30/2025	14:21:05	0	0	T. Bazan	1.0	2	257	263	866	0.1	mg/cm2	0.2	Negative
11/30/2025	14:21:48	0	0	T. Bazan	1.0	2	258	264	867	0.5	mg/cm2	0.2	Negative
11/30/2025	14:22:05	0	0	T. Bazan	1.0	2	259	265	868	0.4	mg/cm2	0.2	Negative
11/30/2025	14:22:27	0	0	T. Bazan	1.0	2	260	266	869	0.2	mg/cm2	0.2	Negative
11/30/2025	14:24:55	0	0	T. Bazan	1.0	2	261	267	870	0.4	mg/cm2	0.2	Negative
11/30/2025	14:25:30	0	0	T. Bazan	1.0	2	262	268	871	0.1	mg/cm2	0.2	Negative
11/30/2025	14:25:45	0	0	T. Bazan	1.0	2	263	269	872	0.1	mg/cm2	0.2	Negative
11/30/2025	14:28:09	0	0	T. Bazan	1.0	2	264	270	873	0.3	mg/cm2	0.2	Negative
11/30/2025	14:28:19	0	0	T. Bazan	1.0	2	265	271	874	0.1	mg/cm2	0.2	Negative
11/30/2025	14:28:34	0	0	T. Bazan	1.0	2	266	272	875	0.3	mg/cm2	0.2	Negative
11/30/2025	14:29:22	0	0	T. Bazan	1.0	2	267	273	876	0.4	mg/cm2	0.2	Negative
11/30/2025	14:29:38	0	0	T. Bazan	1.0	2	268	274	877	0.2	mg/cm2	0.2	Negative
11/30/2025	14:29:56	0	0	T. Bazan	1.0	2	269	275	878	0.3	mg/cm2	0.2	Negative
11/30/2025	14:30:08	0	0	T. Bazan	1.0	2	270	276	879	0.1	mg/cm2	0.2	Negative
11/30/2025	14:31:52	0	0	T. Bazan	1.0	2	271	277	880	0.2	mg/cm2	0.2	Negative
11/30/2025	14:33:33	0	0	T. Bazan	1.0	2	272	278	881	0.0	mg/cm2	0.2	Negative
11/30/2025	14:33:42	0	0	T. Bazan	1.0	2	273	279	882	0.2	mg/cm2	0.2	Negative
11/30/2025	14:34:21	0	0	T. Bazan	1.0	2	274	280	883	0.1	mg/cm2	0.2	Negative
11/30/2025	14:34:34	0	0	T. Bazan	1.0	2	275	281	884	0.0	mg/cm2	0.2	Negative
11/30/2025	14:34:47	0	0	T. Bazan	1.0	2	276	282	885	0.3	mg/cm2	0.2	Negative
11/30/2025	14:35:35	0	0	T. Bazan	1.0	2	277	283	886	0.1	mg/cm2	0.2	Negative
11/30/2025	14:37:54	0	0	T. Bazan	1.0	2	278	284	887	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	14:38:10	0	0	T. Bazan	1.0	2	279	285	888	0.0	mg/cm2	0.2	Negative
11/30/2025	14:38:35	0	0	T. Bazan	1.0	2	280	286	889	0.1	mg/cm2	0.2	Negative
11/30/2025	14:40:53	0	0	T. Bazan	1.0	2	281	287	890	0.2	mg/cm2	0.2	Negative
11/30/2025	14:41:24	0	0	T. Bazan	1.0	2	282	288	891	0.2	mg/cm2	0.2	Negative
11/30/2025	14:43:19	0	0	T. Bazan	1.0	2	283	289	892	0.2	mg/cm2	0.2	Negative
11/30/2025	14:43:30	0	0	T. Bazan	1.0	2	284	290	893	0.4	mg/cm2	0.2	Negative
11/30/2025	14:43:39	0	0	T. Bazan	1.0	2	285	291	894	0.2	mg/cm2	0.2	Negative
11/30/2025	14:44:19	0	0	T. Bazan	1.0	2	286	292	895	0.1	mg/cm2	0.2	Negative
11/30/2025	14:45:43	0	0	T. Bazan	1.0	2	287	293	896	0.2	mg/cm2	0.2	Negative
11/30/2025	14:45:53	0	0	T. Bazan	1.0	2	288	294	897	0.2	mg/cm2	0.2	Negative
11/30/2025	14:46:02	0	0	T. Bazan	1.0	2	289	295	898	0.1	mg/cm2	0.2	Negative
11/30/2025	14:46:10	0	0	T. Bazan	1.0	2	290	296	899	0.4	mg/cm2	0.2	Negative
11/30/2025	14:46:28	0	0	T. Bazan	1.0	2	291	297	900	0.1	mg/cm2	0.2	Negative
11/30/2025	14:46:37	0	0	T. Bazan	1.0	2	292	298	901	**14.0**	mg/cm2	0.2	**Caution**
11/30/2025	14:56:38	0	0	T. Bazan	1.0	2	293	299	902	0.1	mg/cm2	0.2	Negative
11/30/2025	14:56:48	0	0	T. Bazan	1.0	2	294	300	903	0.1	mg/cm2	0.2	Negative
11/30/2025	14:56:59	0	0	T. Bazan	1.0	2	295	301	904	0.0	mg/cm2	0.2	Negative
11/30/2025	14:57:08	0	0	T. Bazan	1.0	2	296	302	905	0.0	mg/cm2	0.2	Negative
11/30/2025	14:57:26	0	0	T. Bazan	1.0	2	297	303	906	0.1	mg/cm2	0.2	Negative
11/30/2025	14:58:11	0	0	T. Bazan	1.0	2	298	304	907	0.2	mg/cm2	0.2	Negative
11/30/2025	14:58:21	0	0	T. Bazan	1.0	2	299	305	908	0.2	mg/cm2	0.2	Negative
11/30/2025	14:58:31	0	0	T. Bazan	1.0	2	300	306	909	0.1	mg/cm2	0.2	Negative
11/30/2025	14:59:28	0	0	T. Bazan	1.0	2	301	307	910	0.3	mg/cm2	0.2	Negative
11/30/2025	14:59:47	0	0	T. Bazan	1.0	2	302	308	911	0.4	mg/cm2	0.2	Negative
11/30/2025	14:59:56	0	0	T. Bazan	1.0	2	303	309	912	0.1	mg/cm2	0.2	Negative
11/30/2025	15:00:33	0	0	T. Bazan	1.0	2	304	310	913	0.1	mg/cm2	0.2	Negative
11/30/2025	15:21:55	0	0	T. Bazan	1.0	2	305	311	914	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	15:22:19	0	0	T. Bazan	1.0	2	306	312	915	0.1	mg/cm2	0.2	Negative
11/30/2025	15:22:29	0	0	T. Bazan	1.0	2	307	313	916	0.1	mg/cm2	0.2	Negative
11/30/2025	15:22:40	0	0	T. Bazan	1.0	2	308	314	917	0.0	mg/cm2	0.2	Negative
11/30/2025	15:22:49	0	0	T. Bazan	1.0	2	309	315	918	0.0	mg/cm2	0.2	Negative
11/30/2025	15:23:06	0	0	T. Bazan	1.0	2	310	316	919	0.0	mg/cm2	0.2	Negative
11/30/2025	15:23:40	0	0	T. Bazan	1.0	2	311	317	920	0.1	mg/cm2	0.2	Negative
11/30/2025	15:23:57	0	0	T. Bazan	1.0	2	312	318	921	0.2	mg/cm2	0.2	Negative
11/30/2025	15:24:07	0	0	T. Bazan	1.0	2	313	319	922	0.2	mg/cm2	0.2	Negative
11/30/2025	15:24:39	0	0	T. Bazan	1.0	2	314	320	923	0.2	mg/cm2	0.2	Negative
11/30/2025	15:24:59	0	0	T. Bazan	1.0	2	315	321	924	0.3	mg/cm2	0.2	Negative
11/30/2025	15:25:08	0	0	T. Bazan	1.0	2	316	322	925	0.4	mg/cm2	0.2	Negative
11/30/2025	15:32:21	0	0	T. Bazan	1.0	2	317	323	926	0.1	mg/cm2	0.2	Negative
11/30/2025	15:32:32	0	0	T. Bazan	1.0	2	318	324	927	0.2	mg/cm2	0.2	Negative
11/30/2025	15:32:43	0	0	T. Bazan	1.0	2	319	325	928	0.1	mg/cm2	0.2	Negative
11/30/2025	15:32:52	0	0	T. Bazan	1.0	2	320	326	929	0.0	mg/cm2	0.2	Negative
11/30/2025	15:33:16	0	0	T. Bazan	1.0	2	321	327	930	0.0	mg/cm2	0.2	Negative
11/30/2025	15:33:55	0	0	T. Bazan	1.0	2	322	328	931	0.2	mg/cm2	0.2	Negative
11/30/2025	15:34:05	0	0	T. Bazan	1.0	2	323	329	932	0.4	mg/cm2	0.2	Negative
11/30/2025	15:34:16	0	0	T. Bazan	1.0	2	324	330	933	0.3	mg/cm2	0.2	Negative
11/30/2025	15:35:26	0	0	T. Bazan	1.0	2	325	331	934	0.2	mg/cm2	0.2	Negative
11/30/2025	15:35:44	0	0	T. Bazan	1.0	2	326	332	935	0.4	mg/cm2	0.2	Negative
11/30/2025	15:35:53	0	0	T. Bazan	1.0	2	327	333	936	0.2	mg/cm2	0.2	Negative
11/30/2025	15:36:34	0	0	T. Bazan	1.0	2	328	334	937	0.0	mg/cm2	0.2	Negative
11/30/2025	15:37:11	0	0	T. Bazan	1.0	2	329	335	938	0.0	mg/cm2	0.2	Negative
11/30/2025	15:45:15	0	0	T. Bazan	1.0	2	330	336	939	0.0	mg/cm2	0.2	Negative
11/30/2025	15:45:41	0	0	T. Bazan	1.0	2	331	337	940	0.0	mg/cm2	0.2	Negative
11/30/2025	15:45:51	0	0	T. Bazan	1.0	2	332	338	941	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	15:46:01	0	0	T. Bazan	1.0	2	333	339	942	0.0	mg/cm2	0.2	Negative
11/30/2025	15:46:11	0	0	T. Bazan	1.0	2	334	340	943	0.0	mg/cm2	0.2	Negative
11/30/2025	15:46:55	0	0	T. Bazan	1.0	2	335	341	944	0.1	mg/cm2	0.2	Negative
11/30/2025	15:47:38	0	0	T. Bazan	1.0	2	336	342	945	0.1	mg/cm2	0.2	Negative
11/30/2025	15:47:48	0	0	T. Bazan	1.0	2	337	343	946	0.3	mg/cm2	0.2	Negative
11/30/2025	15:47:57	0	0	T. Bazan	1.0	2	338	344	947	0.3	mg/cm2	0.2	Negative
11/30/2025	15:48:35	0	0	T. Bazan	1.0	2	339	345	948	0.3	mg/cm2	0.2	Negative
11/30/2025	15:48:58	0	0	T. Bazan	1.0	2	340	346	949	0.5	mg/cm2	0.2	Negative
11/30/2025	15:49:29	0	0	T. Bazan	1.0	2	341	347	950	0.2	mg/cm2	0.2	Negative
11/30/2025	15:52:23	0	0	T. Bazan	1.0	2	342	348	951	0.1	mg/cm2	0.2	Negative
11/30/2025	15:52:39	0	0	T. Bazan	1.0	2	343	349	952	0.0	mg/cm2	0.2	Negative
11/30/2025	15:52:57	0	0	T. Bazan	1.0	2	344	350	953	0.5	mg/cm2	0.2	Negative
11/30/2025	15:53:15	0	0	T. Bazan	1.0	2	345	351	954	0.4	mg/cm2	0.2	Negative
11/30/2025	15:57:51	0	0	T. Bazan	1.0	2	346	352	955	0.2	mg/cm2	0.2	Negative
11/30/2025	15:58:15	0	0	T. Bazan	1.0	5	347	353	956	1.1	mg/cm2	0.1	Positive
11/30/2025	15:59:28	0	0	T. Bazan	1.0	2	348	354	957	0.3	mg/cm2	0.2	Negative
11/30/2025	16:00:15	0	0	T. Bazan	1.0	2	349	355	958	0.3	mg/cm2	0.2	Negative
11/30/2025	16:00:25	0	0	T. Bazan	1.0	2	350	356	959	0.2	mg/cm2	0.2	Negative
11/30/2025	16:00:34	0	0	T. Bazan	1.0	2	351	357	960	0.3	mg/cm2	0.2	Negative
11/30/2025	16:01:28	0	0	T. Bazan	1.0	2	352	358	961	0.1	mg/cm2	0.2	Negative
11/30/2025	16:01:38	0	0	T. Bazan	1.0	2	353	359	962	0.1	mg/cm2	0.2	Negative
11/30/2025	16:01:47	0	0	T. Bazan	1.0	2	354	360	963	0.0	mg/cm2	0.2	Negative
11/30/2025	16:07:14	0	0	T. Bazan	1.0	2	355	361	964	0.0	mg/cm2	0.2	Negative
11/30/2025	16:07:26	0	0	T. Bazan	1.0	2	356	362	965	0.0	mg/cm2	0.2	Negative
11/30/2025	16:07:39	0	0	T. Bazan	1.0	2	357	363	966	0.0	mg/cm2	0.2	Negative
11/30/2025	16:07:51	0	0	T. Bazan	1.0	2	358	364	967	0.0	mg/cm2	0.2	Negative
11/30/2025	16:08:10	0	0	T. Bazan	1.0	2	359	365	968	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
11/30/2025	16:08:48	0	0	T. Bazan	1.0	2	360	366	969	0.2	mg/cm2	0.2	Negative
11/30/2025	16:08:58	0	0	T. Bazan	1.0	2	361	367	970	0.2	mg/cm2	0.2	Negative
11/30/2025	16:09:07	0	0	T. Bazan	1.0	2	362	368	971	0.2	mg/cm2	0.2	Negative
11/30/2025	16:09:57	0	0	T. Bazan	1.0	2	363	369	972	0.1	mg/cm2	0.2	Negative
11/30/2025	16:10:18	0	0	T. Bazan	1.0	2	364	370	973	0.4	mg/cm2	0.2	Negative
11/30/2025	16:10:27	0	0	T. Bazan	1.0	2	365	371	974	0.3	mg/cm2	0.2	Negative
11/30/2025	16:11:00	0	0	T. Bazan	1.0	2	366	372	975	0.0	mg/cm2	0.2	Negative
11/30/2025	16:21:04	0	0	T. Bazan	1.0	2	367	373	976	0.1	mg/cm2	0.2	Negative
11/30/2025	16:21:51	0	0	T. Bazan	1.0	2	368	374	977	0.1	mg/cm2	0.2	Negative
11/30/2025	16:22:05	0	0	T. Bazan	1.0	2	369	375	978	0.2	mg/cm2	0.2	Negative
11/30/2025	16:22:28	0	0	T. Bazan	1.0	2	370	376	979	0.0	mg/cm2	0.2	Negative
11/30/2025	16:22:46	0	0	T. Bazan	1.0	2	371	377	980	0.0	mg/cm2	0.2	Negative
11/30/2025	16:23:03	0	0	T. Bazan	1.0	2	372	378	981	0.3	mg/cm2	0.2	Negative
11/30/2025	16:23:20	0	0	T. Bazan	1.0	2	373	379	982	0.1	mg/cm2	0.2	Negative
11/30/2025	16:23:37	0	0	T. Bazan	1.0	2	374	380	983	0.1	mg/cm2	0.2	Negative
11/30/2025	16:23:52	0	0	T. Bazan	1.0	2	375	381	984	0.2	mg/cm2	0.2	Negative
11/30/2025	16:24:02	0	0	T. Bazan	1.0	2	376	382	985	0.0	mg/cm2	0.2	Negative
11/30/2025	16:24:20	0	0	T. Bazan	1.0	2	377	383	986	0.1	mg/cm2	0.2	Negative
11/30/2025	16:25:04	0	0	T. Bazan	1.0	2	378	384	987	0.2	mg/cm2	0.2	Negative
11/30/2025	16:25:41	0	0	T. Bazan	1.0	2	379	385	988	0.1	mg/cm2	0.2	Negative
11/30/2025	16:26:04	0	0	T. Bazan	1.0	2	380	386	989	0.1	mg/cm2	0.2	Negative
11/30/2025	16:27:10	0	0	T. Bazan	1.0	3	---	387	990	0.8	mg/cm2	0.2	Calibration
11/30/2025	16:30:11	0	0	T. Bazan	1.0	5	---	388	991	1.0	mg/cm2	0.1	Calibration
11/30/2025	16:30:31	0	0	T. Bazan	1.0	5	---	389	992	0.8	mg/cm2	0.1	Calibration
11/30/2025	16:33:59	0	0	T. Bazan	1.0	5	---	390	993	1.0	mg/cm2	0.1	Calibration
11/30/2025	16:34:18	0	0	T. Bazan	1.0	5	---	391	994	1.1	mg/cm2	0.1	Calibration
11/30/2025	16:34:40	0	0	T. Bazan	1.0	5	---	392	995	1.1	mg/cm2	0.1	Calibration

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
DAY FOUR													
12/2/2025	8:45:17	0	0	T. Bazan	1.0	5	---	1	996	1.1	mg/cm2	0.1	Calibration
12/2/2025	8:45:35	0	0	T. Bazan	1.0	5	---	2	997	1.1	mg/cm2	0.1	Calibration
12/2/2025	8:45:56	0	0	T. Bazan	1.0	5	---	3	998	1.1	mg/cm2	0.1	Calibration
12/2/2025	8:49:57	0	0	T. Bazan	1.0	2	1	4	999	0.1	mg/cm2	0.2	Negative
12/2/2025	8:50:25	0	0	T. Bazan	1.0	2	2	5	1000	0.0	mg/cm2	0.2	Negative
12/2/2025	8:50:39	0	0	T. Bazan	1.0	2	3	6	1001	0.2	mg/cm2	0.2	Negative
12/2/2025	8:51:00	0	0	T. Bazan	1.0	2	4	7	1002	0.2	mg/cm2	0.2	Negative
12/2/2025	8:51:15	0	0	T. Bazan	1.0	2	5	8	1003	0.1	mg/cm2	0.2	Negative
12/2/2025	8:51:38	0	0	T. Bazan	1.0	2	6	9	1004	0.4	mg/cm2	0.2	Negative
12/2/2025	8:52:46	0	0	T. Bazan	1.0	2	7	10	1005	0.2	mg/cm2	0.2	Negative
12/2/2025	8:53:28	0	0	T. Bazan	1.0	2	8	11	1006	0.5	mg/cm2	0.2	Negative
12/2/2025	8:53:56	0	0	T. Bazan	1.0	2	9	12	1007	0.2	mg/cm2	0.2	Negative
12/2/2025	8:54:24	0	0	T. Bazan	1.0	2	10	13	1008	0.2	mg/cm2	0.2	Negative
12/2/2025	8:56:19	0	0	T. Bazan	1.0	2	11	14	1009	0.1	mg/cm2	0.2	Negative
12/2/2025	9:10:38	0	0	T. Bazan	1.0	2	12	15	1010	0.0	mg/cm2	0.2	Negative
12/2/2025	9:11:15	0	0	T. Bazan	1.0	2	13	16	1011	0.1	mg/cm2	0.2	Negative
12/2/2025	9:12:50	0	0	T. Bazan	1.0	2	14	17	1012	0.1	mg/cm2	0.2	Negative
12/2/2025	9:14:54	0	0	T. Bazan	1.0	2	15	18	1013	0.0	mg/cm2	0.2	Negative
12/2/2025	9:15:05	0	0	T. Bazan	1.0	2	16	19	1014	0.2	mg/cm2	0.2	Negative
12/2/2025	9:15:23	0	0	T. Bazan	1.0	2	17	20	1015	0.1	mg/cm2	0.2	Negative
12/2/2025	9:15:40	0	0	T. Bazan	1.0	2	18	21	1016	0.1	mg/cm2	0.2	Negative
12/2/2025	9:15:51	0	0	T. Bazan	1.0	2	19	22	1017	0.2	mg/cm2	0.2	Negative
12/2/2025	9:19:00	0	0	T. Bazan	1.0	2	20	23	1018	0.2	mg/cm2	0.2	Negative
12/2/2025	9:19:44	0	0	T. Bazan	1.0	2	21	24	1019	0.3	mg/cm2	0.2	Negative
12/2/2025	9:20:12	0	0	T. Bazan	1.0	2	22	25	1020	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	9:26:39	0	0	T. Bazan	1.0	2	23	26	1021	0.4	mg/cm2	0.2	Negative
12/2/2025	9:28:54	0	0	T. Bazan	1.0	2	24	27	1022	0.3	mg/cm2	0.2	Negative
12/2/2025	9:29:28	0	0	T. Bazan	1.0	2	25	28	1023	0.0	mg/cm2	0.2	Negative
12/2/2025	9:31:30	0	0	T. Bazan	1.0	2	26	29	1024	0.3	mg/cm2	0.2	Negative
12/2/2025	9:32:18	0	0	T. Bazan	1.0	2	27	30	1025	0.2	mg/cm2	0.2	Negative
12/2/2025	9:32:37	0	0	T. Bazan	1.0	2	28	31	1026	0.6	mg/cm2	0.2	Negative
12/2/2025	9:33:01	0	0	T. Bazan	1.0	2	29	32	1027	0.0	mg/cm2	0.2	Negative
12/2/2025	9:33:13	0	0	T. Bazan	1.0	2	30	33	1028	0.1	mg/cm2	0.2	Negative
12/2/2025	9:33:44	0	0	T. Bazan	1.0	2	31	34	1029	0.3	mg/cm2	0.2	Negative
12/2/2025	9:34:14	0	0	T. Bazan	1.0	2	32	35	1030	0.3	mg/cm2	0.2	Negative
12/2/2025	9:36:59	0	0	T. Bazan	1.0	2	33	36	1031	0.2	mg/cm2	0.2	Negative
12/2/2025	9:37:08	0	0	T. Bazan	1.0	2	34	37	1032	0.1	mg/cm2	0.2	Negative
12/2/2025	9:37:16	0	0	T. Bazan	1.0	2	35	38	1033	0.1	mg/cm2	0.2	Negative
12/2/2025	9:37:26	0	0	T. Bazan	1.0	2	36	39	1034	0.4	mg/cm2	0.2	Negative
12/2/2025	9:38:14	0	0	T. Bazan	1.0	2	37	40	1035	0.2	mg/cm2	0.2	Negative
12/2/2025	9:38:48	0	0	T. Bazan	1.0	2	38	41	1036	0.1	mg/cm2	0.2	Negative
12/2/2025	9:39:32	0	0	T. Bazan	1.0	2	39	42	1037	0.0	mg/cm2	0.2	Negative
12/2/2025	9:39:49	0	0	T. Bazan	1.0	2	40	43	1038	0.2	mg/cm2	0.2	Negative
12/2/2025	9:42:12	0	0	T. Bazan	1.0	2	41	44	1039	0.2	mg/cm2	0.2	Negative
12/2/2025	9:42:24	0	0	T. Bazan	1.0	2	42	45	1040	0.3	mg/cm2	0.2	Negative
12/2/2025	9:43:58	0	0	T. Bazan	1.0	2	43	46	1041	0.3	mg/cm2	0.2	Negative
12/2/2025	9:44:32	0	0	T. Bazan	1.0	2	44	47	1042	0.3	mg/cm2	0.2	Negative
12/2/2025	9:45:49	0	0	T. Bazan	1.0	2	45	48	1043	0.0	mg/cm2	0.2	Negative
12/2/2025	9:46:54	0	0	T. Bazan	1.0	2	46	49	1044	0.2	mg/cm2	0.2	Negative
12/2/2025	9:51:12	0	0	T. Bazan	1.0	2	47	50	1045	0.1	mg/cm2	0.2	Negative
12/2/2025	9:53:14	0	0	T. Bazan	1.0	2	48	51	1046	0.0	mg/cm2	0.2	Negative
12/2/2025	9:53:27	0	0	T. Bazan	1.0	2	49	52	1047	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	9:54:59	0	0	T. Bazan	1.0	2	50	53	1048	0.1	mg/cm2	0.2	Negative
12/2/2025	9:55:19	0	0	T. Bazan	1.0	2	51	54	1049	0.1	mg/cm2	0.2	Negative
12/2/2025	9:55:37	0	0	T. Bazan	1.0	2	52	55	1050	0.2	mg/cm2	0.2	Negative
12/2/2025	9:56:00	0	0	T. Bazan	1.0	2	53	56	1051	0.0	mg/cm2	0.2	Negative
12/2/2025	9:57:06	0	0	T. Bazan	1.0	2	54	57	1052	0.1	mg/cm2	0.2	Negative
12/2/2025	9:58:50	0	0	T. Bazan	1.0	2	55	58	1053	0.2	mg/cm2	0.2	Negative
12/2/2025	9:59:24	0	0	T. Bazan	1.0	2	56	59	1054	0.1	mg/cm2	0.2	Negative
12/2/2025	10:00:25	0	0	T. Bazan	1.0	2	57	60	1055	0.3	mg/cm2	0.2	Negative
12/2/2025	10:00:36	0	0	T. Bazan	1.0	2	58	61	1056	0.3	mg/cm2	0.2	Negative
12/2/2025	10:02:36	0	0	T. Bazan	1.0	2	59	62	1057	0.2	mg/cm2	0.2	Negative
12/2/2025	10:02:46	0	0	T. Bazan	1.0	2	60	63	1058	0.4	mg/cm2	0.2	Negative
12/2/2025	10:05:21	0	0	T. Bazan	1.0	2	61	64	1059	0.2	mg/cm2	0.2	Negative
12/2/2025	10:05:32	0	0	T. Bazan	1.0	2	62	65	1060	0.2	mg/cm2	0.2	Negative
12/2/2025	10:05:47	0	0	T. Bazan	1.0	2	63	66	1061	0.2	mg/cm2	0.2	Negative
12/2/2025	10:05:58	0	0	T. Bazan	1.0	2	64	67	1062	0.3	mg/cm2	0.2	Negative
12/2/2025	10:06:26	0	0	T. Bazan	1.0	2	65	68	1063	0.2	mg/cm2	0.2	Negative
12/2/2025	10:08:03	0	0	T. Bazan	1.0	2	66	69	1064	0.1	mg/cm2	0.2	Negative
12/2/2025	10:08:21	0	0	T. Bazan	1.0	2	67	70	1065	0.2	mg/cm2	0.2	Negative
12/2/2025	10:08:30	0	0	T. Bazan	1.0	2	68	71	1066	0.1	mg/cm2	0.2	Negative
12/2/2025	10:08:49	0	0	T. Bazan	1.0	2	69	72	1067	0.4	mg/cm2	0.2	Negative
12/2/2025	10:11:12	0	0	T. Bazan	1.0	2	70	73	1068	0.3	mg/cm2	0.2	Negative
12/2/2025	10:11:28	0	0	T. Bazan	1.0	2	71	74	1069	0.3	mg/cm2	0.2	Negative
12/2/2025	10:11:37	0	0	T. Bazan	1.0	2	72	75	1070	0.2	mg/cm2	0.2	Negative
12/2/2025	10:11:47	0	0	T. Bazan	1.0	2	73	76	1071	0.2	mg/cm2	0.2	Negative
12/2/2025	10:12:25	0	0	T. Bazan	1.0	2	74	77	1072	0.1	mg/cm2	0.2	Negative
12/2/2025	10:12:57	0	0	T. Bazan	1.0	2	75	78	1073	0.1	mg/cm2	0.2	Negative
12/2/2025	10:13:12	0	0	T. Bazan	1.0	2	76	79	1074	0.5	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	10:13:28	0	0	T. Bazan	1.0	2	77	80	1075	0.2	mg/cm2	0.2	Negative
12/2/2025	10:16:50	0	0	T. Bazan	1.0	2	78	81	1076	0.0	mg/cm2	0.2	Negative
12/2/2025	10:17:04	0	0	T. Bazan	1.0	2	79	82	1077	0.1	mg/cm2	0.2	Negative
12/2/2025	10:17:14	0	0	T. Bazan	1.0	2	80	83	1078	0.3	mg/cm2	0.2	Negative
12/2/2025	10:22:19	0	0	T. Bazan	1.0	2	81	84	1079	0.3	mg/cm2	0.2	Negative
12/2/2025	10:22:46	0	0	T. Bazan	1.0	2	82	85	1080	0.3	mg/cm2	0.2	Negative
12/2/2025	10:23:01	0	0	T. Bazan	1.0	2	83	86	1081	0.1	mg/cm2	0.2	Negative
12/2/2025	10:23:22	0	0	T. Bazan	1.0	2	84	87	1082	0.3	mg/cm2	0.2	Negative
12/2/2025	10:23:32	0	0	T. Bazan	1.0	2	85	88	1083	0.2	mg/cm2	0.2	Negative
12/2/2025	10:23:48	0	0	T. Bazan	1.0	2	86	89	1084	0.2	mg/cm2	0.2	Negative
12/2/2025	10:23:59	0	0	T. Bazan	1.0	2	87	90	1085	0.3	mg/cm2	0.2	Negative
12/2/2025	10:24:12	0	0	T. Bazan	1.0	2	88	91	1086	0.4	mg/cm2	0.2	Negative
12/2/2025	10:24:22	0	0	T. Bazan	1.0	2	89	92	1087	0.4	mg/cm2	0.2	Negative
12/2/2025	10:24:58	0	0	T. Bazan	1.0	2	90	93	1088	0.3	mg/cm2	0.2	Negative
12/2/2025	10:25:35	0	0	T. Bazan	1.0	2	91	94	1089	0.1	mg/cm2	0.2	Negative
12/2/2025	10:25:45	0	0	T. Bazan	1.0	2	92	95	1090	0.2	mg/cm2	0.2	Negative
12/2/2025	10:26:05	0	0	T. Bazan	1.0	2	93	96	1091	0.1	mg/cm2	0.2	Negative
12/2/2025	10:28:17	0	0	T. Bazan	1.0	2	94	97	1092	0.0	mg/cm2	0.2	Negative
12/2/2025	10:28:29	0	0	T. Bazan	1.0	2	95	98	1093	0.2	mg/cm2	0.2	Negative
12/2/2025	10:28:45	0	0	T. Bazan	1.0	2	96	99	1094	0.1	mg/cm2	0.2	Negative
12/2/2025	10:28:56	0	0	T. Bazan	1.0	2	97	100	1095	0.3	mg/cm2	0.2	Negative
12/2/2025	10:30:10	0	0	T. Bazan	1.0	2	98	101	1096	0.1	mg/cm2	0.2	Negative
12/2/2025	10:30:23	0	0	T. Bazan	1.0	2	99	102	1097	0.3	mg/cm2	0.2	Negative
12/2/2025	10:30:42	0	0	T. Bazan	1.0	2	100	103	1098	0.1	mg/cm2	0.2	Negative
12/2/2025	10:34:18	0	0	T. Bazan	1.0	2	101	104	1099	0.1	mg/cm2	0.2	Negative
12/2/2025	10:34:30	0	0	T. Bazan	1.0	2	102	105	1100	0.3	mg/cm2	0.2	Negative
12/2/2025	10:34:42	0	0	T. Bazan	1.0	2	103	106	1101	0.4	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	10:34:52	0	0	T. Bazan	1.0	2	104	107	1102	0.4	mg/cm2	0.2	Negative
12/2/2025	10:35:07	0	0	T. Bazan	1.0	2	105	108	1103	0.4	mg/cm2	0.2	Negative
12/2/2025	10:35:27	0	0	T. Bazan	1.0	2	106	109	1104	0.3	mg/cm2	0.2	Negative
12/2/2025	10:37:12	0	0	T. Bazan	1.0	2	107	110	1105	0.1	mg/cm2	0.2	Negative
12/2/2025	10:37:42	0	0	T. Bazan	1.0	2	108	111	1106	0.6	mg/cm2	0.2	Negative
12/2/2025	10:38:06	0	0	T. Bazan	1.0	2	109	112	1107	0.6	mg/cm2	0.2	Negative
12/2/2025	10:38:55	0	0	T. Bazan	1.0	2	110	113	1108	0.1	mg/cm2	0.2	Negative
12/2/2025	10:39:05	0	0	T. Bazan	1.0	2	111	114	1109	0.2	mg/cm2	0.2	Negative
12/2/2025	10:39:21	0	0	T. Bazan	1.0	2	112	115	1110	0.0	mg/cm2	0.2	Negative
12/2/2025	10:39:31	0	0	T. Bazan	1.0	2	113	116	1111	0.0	mg/cm2	0.2	Negative
12/2/2025	10:41:43	0	0	T. Bazan	1.0	2	114	117	1112	0.5	mg/cm2	0.2	Negative
12/2/2025	10:41:58	0	0	T. Bazan	1.0	2	115	118	1113	0.2	mg/cm2	0.2	Negative
12/2/2025	10:42:07	0	0	T. Bazan	1.0	2	116	119	1114	0.0	mg/cm2	0.2	Negative
12/2/2025	10:42:16	0	0	T. Bazan	1.0	2	117	120	1115	0.1	mg/cm2	0.2	Negative
12/2/2025	10:42:58	0	0	T. Bazan	1.0	2	118	121	1116	0.0	mg/cm2	0.2	Negative
12/2/2025	10:49:00	0	0	T. Bazan	1.0	2	119	122	1117	0.2	mg/cm2	0.2	Negative
12/2/2025	10:49:23	0	0	T. Bazan	1.0	2	120	123	1118	0.1	mg/cm2	0.2	Negative
12/2/2025	11:07:44	0	0	T. Bazan	1.0	2	121	124	1119	0.0	mg/cm2	0.2	Negative
12/2/2025	11:08:02	0	0	T. Bazan	1.0	2	122	125	1120	0.2	mg/cm2	0.2	Negative
12/2/2025	11:08:16	0	0	T. Bazan	1.0	2	123	126	1121	0.1	mg/cm2	0.2	Negative
12/2/2025	11:08:50	0	0	T. Bazan	1.0	2	124	127	1122	0.2	mg/cm2	0.2	Negative
12/2/2025	11:09:01	0	0	T. Bazan	1.0	2	125	128	1123	0.3	mg/cm2	0.2	Negative
12/2/2025	11:09:29	0	0	T. Bazan	1.0	2	126	129	1124	0.3	mg/cm2	0.2	Negative
12/2/2025	11:09:41	0	0	T. Bazan	1.0	2	127	130	1125	0.4	mg/cm2	0.2	Negative
12/2/2025	11:09:50	0	0	T. Bazan	1.0	2	128	131	1126	0.3	mg/cm2	0.2	Negative
12/2/2025	11:10:06	0	0	T. Bazan	1.0	2	129	132	1127	0.4	mg/cm2	0.2	Negative
12/2/2025	11:10:19	0	0	T. Bazan	1.0	2	130	133	1128	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	11:11:08	0	0	T. Bazan	1.0	2	131	134	1129	0.1	mg/cm2	0.2	Negative
12/2/2025	11:11:47	0	0	T. Bazan	1.0	2	132	135	1130	0.0	mg/cm2	0.2	Negative
12/2/2025	11:11:57	0	0	T. Bazan	1.0	2	133	136	1131	0.2	mg/cm2	0.2	Negative
12/2/2025	11:15:30	0	0	T. Bazan	1.0	2	134	137	1132	0.0	mg/cm2	0.2	Negative
12/2/2025	11:16:26	0	0	T. Bazan	1.0	2	135	138	1133	0.2	mg/cm2	0.2	Negative
12/2/2025	11:16:39	0	0	T. Bazan	1.0	2	136	139	1134	0.2	mg/cm2	0.2	Negative
12/2/2025	11:16:56	0	0	T. Bazan	1.0	2	137	140	1135	0.1	mg/cm2	0.2	Negative
12/2/2025	11:19:07	0	0	T. Bazan	1.0	2	138	141	1136	0.3	mg/cm2	0.2	Negative
12/2/2025	11:19:17	0	0	T. Bazan	1.0	2	139	142	1137	0.2	mg/cm2	0.2	Negative
12/2/2025	11:19:46	0	0	T. Bazan	1.0	2	140	143	1138	0.1	mg/cm2	0.2	Negative
12/2/2025	11:22:01	0	0	T. Bazan	1.0	2	141	144	1139	0.1	mg/cm2	0.2	Negative
12/2/2025	11:24:04	0	0	T. Bazan	1.0	2	142	145	1140	0.2	mg/cm2	0.2	Negative
12/2/2025	11:24:14	0	0	T. Bazan	1.0	2	143	146	1141	0.3	mg/cm2	0.2	Negative
12/2/2025	11:24:29	0	0	T. Bazan	1.0	2	144	147	1142	0.2	mg/cm2	0.2	Negative
12/2/2025	11:24:41	0	0	T. Bazan	1.0	2	145	148	1143	0.2	mg/cm2	0.2	Negative
12/2/2025	11:26:03	0	0	T. Bazan	1.0	2	146	149	1144	0.1	mg/cm2	0.2	Negative
12/2/2025	11:26:13	0	0	T. Bazan	1.0	2	147	150	1145	0.3	mg/cm2	0.2	Negative
12/2/2025	11:26:43	0	0	T. Bazan	1.0	2	148	151	1146	0.1	mg/cm2	0.2	Negative
12/2/2025	11:26:58	0	0	T. Bazan	1.0	2	149	152	1147	0.0	mg/cm2	0.2	Negative
12/2/2025	11:28:46	0	0	T. Bazan	1.0	2	150	153	1148	0.6	mg/cm2	0.2	Negative
12/2/2025	11:29:01	0	0	T. Bazan	1.0	2	151	154	1149	0.6	mg/cm2	0.2	Negative
12/2/2025	11:29:14	0	0	T. Bazan	1.0	2	152	155	1150	0.7	mg/cm2	0.2	Negative
12/2/2025	11:29:37	0	0	T. Bazan	1.0	2	153	156	1151	0.2	mg/cm2	0.2	Negative
12/2/2025	11:47:37	0	0	T. Bazan	1.0	2	154	157	1152	0.5	mg/cm2	0.2	Negative
12/2/2025	11:47:47	0	0	T. Bazan	1.0	2	155	158	1153	0.5	mg/cm2	0.2	Negative
12/2/2025	11:47:59	0	0	T. Bazan	1.0	2	156	159	1154	0.4	mg/cm2	0.2	Negative
12/2/2025	11:48:17	0	0	T. Bazan	1.0	2	157	160	1155	0.5	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	11:49:08	0	0	T. Bazan	1.0	2	158	161	1156	0.5	mg/cm2	0.2	Negative
12/2/2025	11:49:20	0	0	T. Bazan	1.0	2	159	162	1157	0.3	mg/cm2	0.2	Negative
12/2/2025	11:50:00	0	0	T. Bazan	1.0	2	160	163	1158	14.4	mg/cm2	0.2	Caution
12/2/2025	11:52:39	0	0	T. Bazan	1.0	2	161	164	1159	0.1	mg/cm2	0.2	Negative
12/2/2025	11:52:54	0	0	T. Bazan	1.0	2	162	165	1160	0.3	mg/cm2	0.2	Negative
12/2/2025	11:55:23	0	0	T. Bazan	1.0	2	163	166	1161	0.1	mg/cm2	0.2	Negative
12/2/2025	11:55:37	0	0	T. Bazan	1.0	2	164	167	1162	0.1	mg/cm2	0.2	Negative
12/2/2025	11:56:01	0	0	T. Bazan	1.0	2	165	168	1163	0.5	mg/cm2	0.2	Negative
12/2/2025	11:56:16	0	0	T. Bazan	1.0	2	166	169	1164	0.0	mg/cm2	0.2	Negative
12/2/2025	11:57:13	0	0	T. Bazan	1.0	2	167	170	1165	0.3	mg/cm2	0.2	Negative
12/2/2025	11:59:19	0	0	T. Bazan	1.0	2	168	171	1166	0.0	mg/cm2	0.2	Negative
12/2/2025	12:05:36	0	0	T. Bazan	1.0	2	169	172	1167	0.1	mg/cm2	0.2	Negative
12/2/2025	12:05:53	0	0	T. Bazan	1.0	2	170	173	1168	0.7	mg/cm2	0.2	Negative
12/2/2025	12:06:05	0	0	T. Bazan	1.0	2	171	174	1169	0.3	mg/cm2	0.2	Negative
12/2/2025	12:06:52	0	0	T. Bazan	1.0	2	172	175	1170	0.3	mg/cm2	0.2	Negative
12/2/2025	12:07:08	0	0	T. Bazan	1.0	2	173	176	1171	0.3	mg/cm2	0.2	Negative
12/2/2025	12:07:18	0	0	T. Bazan	1.0	2	174	177	1172	0.3	mg/cm2	0.2	Negative
12/2/2025	12:07:34	0	0	T. Bazan	1.0	2	175	178	1173	0.5	mg/cm2	0.2	Negative
12/2/2025	12:13:47	0	0	T. Bazan	1.0	2	176	179	1174	0.2	mg/cm2	0.2	Negative
12/2/2025	12:14:35	0	0	T. Bazan	1.0	2	177	180	1175	0.3	mg/cm2	0.2	Negative
12/2/2025	12:14:47	0	0	T. Bazan	1.0	2	178	181	1176	0.2	mg/cm2	0.2	Negative
12/2/2025	12:15:01	0	0	T. Bazan	1.0	2	179	182	1177	0.3	mg/cm2	0.2	Negative
12/2/2025	12:16:19	0	0	T. Bazan	1.0	2	180	183	1178	0.3	mg/cm2	0.2	Negative
12/2/2025	12:18:57	0	0	T. Bazan	1.0	2	181	184	1179	16.0	mg/cm2	0.2	Caution
12/2/2025	12:19:58	0	0	T. Bazan	1.0	2	182	185	1180	0.2	mg/cm2	0.2	Negative
12/2/2025	12:20:29	0	0	T. Bazan	1.0	2	183	186	1181	0.3	mg/cm2	0.2	Negative
12/2/2025	12:20:51	0	0	T. Bazan	1.0	2	184	187	1182	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	12:21:04	0	0	T. Bazan	1.0	2	185	188	1183	0.2	mg/cm2	0.2	Negative
12/2/2025	12:22:21	0	0	T. Bazan	1.0	2	186	189	1184	0.2	mg/cm2	0.2	Negative
12/2/2025	12:22:41	0	0	T. Bazan	1.0	2	187	190	1185	0.3	mg/cm2	0.2	Negative
12/2/2025	12:22:53	0	0	T. Bazan	1.0	2	188	191	1186	0.1	mg/cm2	0.2	Negative
12/2/2025	12:27:32	0	0	T. Bazan	1.0	2	189	192	1187	21.7	mg/cm2	0.2	Caution
12/2/2025	12:30:59	0	0	T. Bazan	1.0	2	190	193	1188	0.3	mg/cm2	0.2	Negative
12/2/2025	12:31:07	0	0	T. Bazan	1.0	2	191	194	1189	0.4	mg/cm2	0.2	Negative
12/2/2025	12:31:20	0	0	T. Bazan	1.0	2	192	195	1190	0.3	mg/cm2	0.2	Negative
12/2/2025	12:31:30	0	0	T. Bazan	1.0	2	193	196	1191	0.3	mg/cm2	0.2	Negative
12/2/2025	12:31:47	0	0	T. Bazan	1.0	2	194	197	1192	0.2	mg/cm2	0.2	Negative
12/2/2025	12:31:56	0	0	T. Bazan	1.0	2	195	198	1193	0.0	mg/cm2	0.2	Negative
12/2/2025	12:32:06	0	0	T. Bazan	1.0	2	196	199	1194	0.0	mg/cm2	0.2	Negative
12/2/2025	12:32:39	0	0	T. Bazan	1.0	2	197	200	1195	0.1	mg/cm2	0.2	Negative
12/2/2025	12:33:03	0	0	T. Bazan	1.0	2	198	201	1196	0.1	mg/cm2	0.2	Negative
12/2/2025	12:41:25	0	0	T. Bazan	1.0	5	---	202	1197	1.0	mg/cm2	0.1	Calibration
12/2/2025	12:42:18	0	0	T. Bazan	1.0	5	---	203	1198	1.0	mg/cm2	0.1	Calibration
12/2/2025	12:42:37	0	0	T. Bazan	1.0	5	---	204	1199	1.0	mg/cm2	0.1	Calibration
12/2/2025	12:46:23	0	0	T. Bazan	1.0	2	199	205	1200	0.1	mg/cm2	0.2	Negative
12/2/2025	12:46:37	0	0	T. Bazan	1.0	2	200	206	1201	0.1	mg/cm2	0.2	Negative
12/2/2025	12:46:49	0	0	T. Bazan	1.0	2	201	207	1202	0.0	mg/cm2	0.2	Negative
12/2/2025	12:50:59	0	0	T. Bazan	1.0	2	202	208	1203	0.1	mg/cm2	0.2	Negative
12/2/2025	12:51:15	0	0	T. Bazan	1.0	2	203	209	1204	0.1	mg/cm2	0.2	Negative
12/2/2025	12:52:01	0	0	T. Bazan	1.0	2	204	210	1205	0.0	mg/cm2	0.2	Negative
12/2/2025	12:52:12	0	0	T. Bazan	1.0	2	205	211	1206	0.2	mg/cm2	0.2	Negative
12/2/2025	12:52:22	0	0	T. Bazan	1.0	2	206	212	1207	0.1	mg/cm2	0.2	Negative
12/2/2025	12:53:17	0	0	T. Bazan	1.0	2	207	213	1208	0.2	mg/cm2	0.2	Negative
12/2/2025	12:53:37	0	0	T. Bazan	1.0	2	208	214	1209	0.5	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	12:53:55	0	0	T. Bazan	1.0	2	209	215	1210	0.4	mg/cm2	0.2	Negative
12/2/2025	12:54:39	0	0	T. Bazan	1.0	2	210	216	1211	0.1	mg/cm2	0.2	Negative
12/2/2025	13:01:18	0	0	T. Bazan	1.0	2	211	217	1212	0.1	mg/cm2	0.2	Negative
12/2/2025	13:01:42	0	0	T. Bazan	1.0	2	212	218	1213	0.1	mg/cm2	0.2	Negative
12/2/2025	13:01:56	0	0	T. Bazan	1.0	2	213	219	1214	0.2	mg/cm2	0.2	Negative
12/2/2025	13:07:05	0	0	T. Bazan	1.0	2	214	220	1215	0.0	mg/cm2	0.2	Negative
12/2/2025	13:07:41	0	0	T. Bazan	1.0	2	215	221	1216	0.1	mg/cm2	0.2	Negative
12/2/2025	13:07:58	0	0	T. Bazan	1.0	2	216	222	1217	0.1	mg/cm2	0.2	Negative
12/2/2025	13:08:49	0	0	T. Bazan	1.0	2	217	223	1218	0.1	mg/cm2	0.2	Negative
12/2/2025	13:09:00	0	0	T. Bazan	1.0	2	218	224	1219	0.1	mg/cm2	0.2	Negative
12/2/2025	13:09:09	0	0	T. Bazan	1.0	2	219	225	1220	0.3	mg/cm2	0.2	Negative
12/2/2025	13:09:47	0	0	T. Bazan	1.0	2	220	226	1221	0.2	mg/cm2	0.2	Negative
12/2/2025	13:13:02	0	0	T. Bazan	1.0	2	221	227	1222	0.0	mg/cm2	0.2	Negative
12/2/2025	13:13:20	0	0	T. Bazan	1.0	2	222	228	1223	0.3	mg/cm2	0.2	Negative
12/2/2025	13:13:29	0	0	T. Bazan	1.0	2	223	229	1224	0.4	mg/cm2	0.2	Negative
12/2/2025	13:17:53	0	0	T. Bazan	1.0	2	224	230	1225	0.0	mg/cm2	0.2	Negative
12/2/2025	13:18:05	0	0	T. Bazan	1.0	2	225	231	1226	0.1	mg/cm2	0.2	Negative
12/2/2025	13:18:16	0	0	T. Bazan	1.0	2	226	232	1227	0.0	mg/cm2	0.2	Negative
12/2/2025	13:18:26	0	0	T. Bazan	1.0	2	227	233	1228	0.0	mg/cm2	0.2	Negative
12/2/2025	13:18:43	0	0	T. Bazan	1.0	2	228	234	1229	0.0	mg/cm2	0.2	Negative
12/2/2025	13:19:24	0	0	T. Bazan	1.0	2	229	235	1230	0.3	mg/cm2	0.2	Negative
12/2/2025	13:19:34	0	0	T. Bazan	1.0	2	230	236	1231	0.3	mg/cm2	0.2	Negative
12/2/2025	13:19:43	0	0	T. Bazan	1.0	2	231	237	1232	0.1	mg/cm2	0.2	Negative
12/2/2025	13:20:28	0	0	T. Bazan	1.0	2	232	238	1233	0.0	mg/cm2	0.2	Negative
12/2/2025	13:20:48	0	0	T. Bazan	1.0	2	233	239	1234	0.3	mg/cm2	0.2	Negative
12/2/2025	13:20:56	0	0	T. Bazan	1.0	2	234	240	1235	0.1	mg/cm2	0.2	Negative
12/2/2025	13:21:29	0	0	T. Bazan	1.0	2	235	241	1236	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	13:30:46	0	0	T. Bazan	1.0	2	236	242	1237	0.1	mg/cm2	0.2	Negative
12/2/2025	13:31:06	0	0	T. Bazan	1.0	2	237	243	1238	0.1	mg/cm2	0.2	Negative
12/2/2025	13:31:24	0	0	T. Bazan	1.0	2	238	244	1239	0.1	mg/cm2	0.2	Negative
12/2/2025	13:31:33	0	0	T. Bazan	1.0	2	239	245	1240	0.0	mg/cm2	0.2	Negative
12/2/2025	13:31:42	0	0	T. Bazan	1.0	2	240	246	1241	0.0	mg/cm2	0.2	Negative
12/2/2025	13:32:09	0	0	T. Bazan	1.0	2	241	247	1242	0.1	mg/cm2	0.2	Negative
12/2/2025	13:32:48	0	0	T. Bazan	1.0	2	242	248	1243	0.1	mg/cm2	0.2	Negative
12/2/2025	13:32:58	0	0	T. Bazan	1.0	2	243	249	1244	0.2	mg/cm2	0.2	Negative
12/2/2025	13:33:08	0	0	T. Bazan	1.0	2	244	250	1245	0.2	mg/cm2	0.2	Negative
12/2/2025	13:33:50	0	0	T. Bazan	1.0	2	245	251	1246	0.2	mg/cm2	0.2	Negative
12/2/2025	13:34:11	0	0	T. Bazan	1.0	2	246	252	1247	0.3	mg/cm2	0.2	Negative
12/2/2025	13:34:20	0	0	T. Bazan	1.0	2	247	253	1248	0.3	mg/cm2	0.2	Negative
12/2/2025	13:46:03	0	0	T. Bazan	1.0	2	248	254	1249	0.1	mg/cm2	0.2	Negative
12/2/2025	13:46:19	0	0	T. Bazan	1.0	2	249	255	1250	0.1	mg/cm2	0.2	Negative
12/2/2025	13:46:32	0	0	T. Bazan	1.0	2	250	256	1251	0.1	mg/cm2	0.2	Negative
12/2/2025	13:46:42	0	0	T. Bazan	1.0	2	251	257	1252	0.0	mg/cm2	0.2	Negative
12/2/2025	13:47:00	0	0	T. Bazan	1.0	2	252	258	1253	0.0	mg/cm2	0.2	Negative
12/2/2025	13:48:17	0	0	T. Bazan	1.0	2	253	259	1254	0.3	mg/cm2	0.2	Negative
12/2/2025	13:48:29	0	0	T. Bazan	1.0	2	254	260	1255	0.2	mg/cm2	0.2	Negative
12/2/2025	13:48:39	0	0	T. Bazan	1.0	2	255	261	1256	0.0	mg/cm2	0.2	Negative
12/2/2025	13:49:16	0	0	T. Bazan	1.0	2	256	262	1257	0.2	mg/cm2	0.2	Negative
12/2/2025	13:49:38	0	0	T. Bazan	1.0	2	257	263	1258	0.3	mg/cm2	0.2	Negative
12/2/2025	13:49:48	0	0	T. Bazan	1.0	2	258	264	1259	0.4	mg/cm2	0.2	Negative
12/2/2025	13:50:23	0	0	T. Bazan	1.0	2	259	265	1260	0.1	mg/cm2	0.2	Negative
12/2/2025	13:50:54	0	0	T. Bazan	1.0	2	260	266	1261	0.1	mg/cm2	0.2	Negative
12/2/2025	13:59:25	0	0	T. Bazan	1.0	2	261	267	1262	0.0	mg/cm2	0.2	Negative
12/2/2025	13:59:41	0	0	T. Bazan	1.0	2	262	268	1263	0.1	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	13:59:57	0	0	T. Bazan	1.0	2	263	269	1264	0.4	mg/cm2	0.2	Negative
12/2/2025	14:00:12	0	0	T. Bazan	1.0	3	264	270	1265	0.7	mg/cm2	0.2	Negative
12/2/2025	14:00:35	0	0	T. Bazan	1.0	2	265	271	1266	0.1	mg/cm2	0.2	Negative
12/2/2025	14:01:37	0	0	T. Bazan	1.0	2	266	272	1267	0.4	mg/cm2	0.2	Negative
12/2/2025	14:01:47	0	0	T. Bazan	1.0	2	267	273	1268	0.3	mg/cm2	0.2	Negative
12/2/2025	14:02:30	0	0	T. Bazan	1.0	2	268	274	1269	0.2	mg/cm2	0.2	Negative
12/2/2025	14:02:44	0	0	T. Bazan	1.0	2	269	275	1270	0.1	mg/cm2	0.2	Negative
12/2/2025	14:03:20	0	0	T. Bazan	1.0	2	270	276	1271	0.1	mg/cm2	0.2	Negative
12/2/2025	14:03:38	0	0	T. Bazan	1.0	2	271	277	1272	0.3	mg/cm2	0.2	Negative
12/2/2025	14:03:47	0	0	T. Bazan	1.0	2	272	278	1273	0.0	mg/cm2	0.2	Negative
12/2/2025	14:04:04	0	0	T. Bazan	1.0	2	273	279	1274	0.2	mg/cm2	0.2	Negative
12/2/2025	14:05:04	0	0	T. Bazan	1.0	2	274	280	1275	0.1	mg/cm2	0.2	Negative
12/2/2025	14:05:17	0	0	T. Bazan	1.0	2	275	281	1276	14.6	mg/cm2	0.2	Caution
12/2/2025	14:07:09	0	0	T. Bazan	1.0	2	276	282	1277	0.4	mg/cm2	0.2	Negative
12/2/2025	14:07:20	0	0	T. Bazan	1.0	2	277	283	1278	0.2	mg/cm2	0.2	Negative
12/2/2025	14:07:32	0	0	T. Bazan	1.0	2	278	284	1279	0.4	mg/cm2	0.2	Negative
12/2/2025	14:09:01	0	0	T. Bazan	1.0	2	279	285	1280	0.2	mg/cm2	0.2	Negative
12/2/2025	14:09:12	0	0	T. Bazan	1.0	2	280	286	1281	0.1	mg/cm2	0.2	Negative
12/2/2025	14:14:59	0	0	T. Bazan	1.0	2	281	287	1282	0.2	mg/cm2	0.2	Negative
12/2/2025	14:15:08	0	0	T. Bazan	1.0	2	282	288	1283	0.3	mg/cm2	0.2	Negative
12/2/2025	14:15:31	0	0	T. Bazan	1.0	2	283	289	1284	0.3	mg/cm2	0.2	Negative
12/2/2025	14:15:40	0	0	T. Bazan	1.0	2	284	290	1285	0.2	mg/cm2	0.2	Negative
12/2/2025	14:16:56	0	0	T. Bazan	1.0	2	285	291	1286	0.4	mg/cm2	0.2	Negative
12/2/2025	14:17:07	0	0	T. Bazan	1.0	2	286	292	1287	0.3	mg/cm2	0.2	Negative
12/2/2025	14:17:39	0	0	T. Bazan	1.0	2	287	293	1288	0.2	mg/cm2	0.2	Negative
12/2/2025	14:19:18	0	0	T. Bazan	1.0	2	288	294	1289	0.0	mg/cm2	0.2	Negative
12/2/2025	14:19:32	0	0	T. Bazan	1.0	2	289	295	1290	0.2	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	14:20:03	0	0	T. Bazan	1.0	2	290	296	1291	0.3	mg/cm2	0.2	Negative
12/2/2025	14:20:25	0	0	T. Bazan	1.0	2	291	297	1292	0.2	mg/cm2	0.2	Negative
12/2/2025	14:21:10	0	0	T. Bazan	1.0	2	292	298	1293	0.2	mg/cm2	0.2	Negative
12/2/2025	14:22:25	0	0	T. Bazan	1.0	2	293	299	1294	0.1	mg/cm2	0.2	Negative
12/2/2025	14:23:02	0	0	T. Bazan	1.0	2	294	300	1295	0.1	mg/cm2	0.2	Negative
12/2/2025	14:23:48	0	0	T. Bazan	1.0	2	295	301	1296	0.2	mg/cm2	0.2	Negative
12/2/2025	14:25:49	0	0	T. Bazan	1.0	2	296	302	1297	0.1	mg/cm2	0.2	Negative
12/2/2025	14:26:04	0	0	T. Bazan	1.0	2	297	303	1298	0.1	mg/cm2	0.2	Negative
12/2/2025	14:26:17	0	0	T. Bazan	1.0	2	298	304	1299	0.1	mg/cm2	0.2	Negative
12/2/2025	14:26:35	0	0	T. Bazan	1.0	2	299	305	1300	0.2	mg/cm2	0.2	Negative
12/2/2025	14:26:48	0	0	T. Bazan	1.0	2	300	306	1301	0.1	mg/cm2	0.2	Negative
12/2/2025	14:29:34	0	0	T. Bazan	1.0	2	301	307	1302	0.3	mg/cm2	0.2	Negative
12/2/2025	14:30:39	0	0	T. Bazan	1.0	2	302	308	1303	0.5	mg/cm2	0.2	Negative
12/2/2025	14:30:48	0	0	T. Bazan	1.0	2	303	309	1304	0.3	mg/cm2	0.2	Negative
12/2/2025	14:30:59	0	0	T. Bazan	1.0	2	304	310	1305	0.3	mg/cm2	0.2	Negative
12/2/2025	14:34:09	0	0	T. Bazan	1.0	2	305	311	1306	0.4	mg/cm2	0.2	Negative
12/2/2025	14:34:30	0	0	T. Bazan	1.0	2	306	312	1307	0.2	mg/cm2	0.2	Negative
12/2/2025	14:35:01	0	0	T. Bazan	1.0	2	307	313	1308	0.4	mg/cm2	0.2	Negative
12/2/2025	14:35:10	0	0	T. Bazan	1.0	2	308	314	1309	0.2	mg/cm2	0.2	Negative
12/2/2025	14:36:06	0	0	T. Bazan	1.0	2	309	315	1310	0.2	mg/cm2	0.2	Negative
12/2/2025	14:36:16	0	0	T. Bazan	1.0	2	310	316	1311	0.1	mg/cm2	0.2	Negative
12/2/2025	14:37:33	0	0	T. Bazan	1.0	2	311	317	1312	0.1	mg/cm2	0.2	Negative
12/2/2025	14:38:15	0	0	T. Bazan	1.0	2	312	318	1313	0.1	mg/cm2	0.2	Negative
12/2/2025	14:38:32	0	0	T. Bazan	1.0	2	313	319	1314	0.1	mg/cm2	0.2	Negative
12/2/2025	14:38:42	0	0	T. Bazan	1.0	2	314	320	1315	0.0	mg/cm2	0.2	Negative
12/2/2025	14:39:01	0	0	T. Bazan	1.0	2	315	321	1316	0.2	mg/cm2	0.2	Negative
12/2/2025	14:39:54	0	0	T. Bazan	1.0	2	316	322	1317	0.0	mg/cm2	0.2	Negative

XRF ASSAYS - Proposed 601 Landmark, 601 N. Lewis St., Conroe, Montgomery Co., TX- Job No. 202511026
VIKEN (HEURESIS) Detection; Pb200i/e XRF Lead Paint Analyzer s/n 1013 App Version 5.3.1
T. Bazan [TDSHS R/A #2070001]

Date	Time	Latitude	Longitude	Operator	Action Level	Nominal Seconds	Reading Number	XRF Assay	Running Total XRF	Pb	Units	Pb +/-	Classification
12/2/2025	14:44:38	0	0	T. Bazan	1.0	2	317	323	1318	0.2	mg/cm2	0.2	Negative
12/2/2025	14:45:06	0	0	T. Bazan	1.0	5	318	324	1319	1.2	mg/cm2	0.1	Positive
12/2/2025	14:46:34	0	0	T. Bazan	1.0	2	319	325	1320	0.3	mg/cm2	0.2	Negative
12/2/2025	14:47:17	0	0	T. Bazan	1.0	2	320	326	1321	0.2	mg/cm2	0.2	Negative
12/2/2025	14:50:27	0	0	T. Bazan	1.0	2	321	327	1322	0.3	mg/cm2	0.2	Negative
12/2/2025	14:50:37	0	0	T. Bazan	1.0	2	322	328	1323	0.4	mg/cm2	0.2	Negative
12/2/2025	14:51:02	0	0	T. Bazan	1.0	2	323	329	1324	0.0	mg/cm2	0.2	Negative
12/2/2025	14:51:11	0	0	T. Bazan	1.0	2	324	330	1325	0.1	mg/cm2	0.2	Negative
12/2/2025	14:51:25	0	0	T. Bazan	1.0	2	325	331	1326	0.1	mg/cm2	0.2	Negative
12/2/2025	14:53:10	0	0	T. Bazan	1.0	2	326	332	1327	0.0	mg/cm2	0.2	Negative
12/2/2025	14:53:19	0	0	T. Bazan	1.0	2	327	333	1328	0.0	mg/cm2	0.2	Negative
12/2/2025	14:53:31	0	0	T. Bazan	1.0	2	328	334	1329	0.2	mg/cm2	0.2	Negative
12/2/2025	15:08:06	30.31546	-95.461296	T. Bazan	1.0	2	329	335	1330	0.1	mg/cm2	0.2	Negative
12/2/2025	15:09:36	30.31541	-95.461235	T. Bazan	1.0	2	330	336	1331	0.5	mg/cm2	0.2	Negative
12/2/2025	15:10:52	30.31546	-95.461258	T. Bazan	1.0	2	331	337	1332	55.0	mg/cm2	0	Lead-Caution
12/2/2025	15:12:57	30.3154	-95.461411	T. Bazan	1.0	2	332	338	1333	0.0	mg/cm2	0.2	Negative
12/2/2025	15:13:24	30.31535	-95.461342	T. Bazan	1.0	2	333	339	1334	0.1	mg/cm2	0.2	Negative
12/2/2025	15:15:18	30.31529	-95.461433	T. Bazan	1.0	2	334	340	1335	0.2	mg/cm2	0.2	Negative
12/2/2025	15:16:14	30.3153	-95.461266	T. Bazan	1.0	2	335	341	1336	0.2	mg/cm2	0.2	Negative
12/2/2025	15:26:20	30.31529	-95.46125	T. Bazan	1.0	2	336	342	1337	0.2	mg/cm2	0.2	Negative
12/2/2025	15:26:45	30.31511	-95.461304	T. Bazan	1.0	2	337	343	1338	0.4	mg/cm2	0.2	Negative
12/2/2025	15:27:44	30.3151	-95.461334	T. Bazan	1.0	5	338	344	1339	0.9	mg/cm2	0.1	Negative
12/2/2025	15:28:50	30.31508	-95.461433	T. Bazan	1.0	2	339	345	1340	0.0	mg/cm2	0.2	Negative
12/2/2025	15:29:50	30.31506	-95.461113	T. Bazan	1.0	2	340	346	1341	0.2	mg/cm2	0.2	Negative
12/2/2025	15:40:45	30.31506	-95.461113	T. Bazan	1.0	5	---	347	1342	1.0	mg/cm2	0.1	Calibration
12/2/2025	15:41:03	30.31506	-95.461113	T. Bazan	1.0	5	---	348	1343	1.0	mg/cm2	0.1	Calibration
12/2/2025	15:41:22	0	0	T. Bazan	1.0	5	---	349	1344	1.0	mg/cm2	0.1	Calibration

Attachment 2: Site Plans

DEMOLITION SITE PLAN NOTES

GENERAL

1. GENERAL CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS & DIMENSIONS.
2. CONTRACTOR SHALL COORDINATE ALL WORK WITH THE REQUIREMENTS OF THE UTILITY COMPANIES AND THE CITY OF CONROE, TEXAS.
3. WHERE EXISTING BLDG. & SITE COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXIST. UNLESS NOTED OTHERWISE.
4. REMOVE EXIST. BLDG. & SITE COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
5. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
6. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
7. DEMOLITION PLAN IS SCHEMATIC AND FOR REFERENCE PURPOSES. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION, REMOVAL OF ITEMS, PATCHING, AS REQUIRED FOR NEW CONSTRUCTION. CONTRACTOR SHALL VISIT AND BECOME FAMILIAR WITH THE SITE PRIOR TO BIDDING AND INCLUDE IN HIS BID ALL DEMOLITION PLANS.
8. REFERENCE COMPLETE CONSTRUCTION DOCUMENTS FOR ADDITIONAL SPECIFIC DEMOLITION REQUIREMENTS.
9. REFERENCE SURVEY, MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL SITE DEMOLITION AND SITE ELEMENTS.
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.

SPECIFIC


1. REMOVE EXIST. CONCRETE DRIVE AND CURBS. AREA TO RECEIVE NEW CURB AND GUTTER. REFERENCE SHEET A1.1
2. REMOVE ANY EXISTING PARKING STRIPES & DRIVE DESIGNATIONS. ENTIRE PARKING LOT TO BE RE-SURFACED AND RE-STRIPED. REFERENCE SHEET A1.1
3. REMOVE EXISTING DRIVE/CURBS AND GUTTERS AND SIDEWALK. APPROACH/DRIVE TO BE RE-CONFIGURED. REFERENCE SHEET A1.1
4. REMOVE ALL ASPHALT & GRAVEL HARD SURFACE TO ROUGH GRADE DIRT.
5. REMOVE SECTION OF EXISTING SIDEWALK.
6. SAWCUT EXISTING DRIVE, CURBS, GUTTERS, FOR NEW PARKING LOT AND DRIVE CONNECTION.
7. REMOVE EXISTING LIGHT POLE & BASE. REF. ME PLANS FOR ELECTRICAL DEMO/RE-USE & CONDUIT

Demolish. Ref. keynotes

Demo Asphalt, Gravel, Paving Ref. Keynote #1 #4 #5



SITE AERIAL
NTS



A SITE DEMOLITION PLAN
1/32"=1'-0"

JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

LANDMARK 601
601. W LEWIS
CONROE, TEXAS

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

REVISION:

DATE: 10-31-2025
JOB: 25-3385
SHEET NO.:

D1.1

COPYRIGHTED ©

HISTORIC PRESERVATION NOTES

STRUCTURE, MASONRY AND EXTERIOR WALLS

1. WORK SHALL NOT DAMAGE ANY EXISTING MASONRY, ORNAMENT OR CHARACTER-DEFINING FEATURES. CONTRACTOR TO PROTECT DURING CONSTRUCTION.
2. MASONRY REHABILITATION SHALL CONSIST OF SPOT REPOINTING AND REPAIR/REPLACEMENT OF ISOLATED DETERIORATION. ALL WORK SHALL CONFORM TO PRESERVATION STANDARDS OUTLINED IN THE NATIONAL PARK SERVICE PRESERVATION BRIEFS 1,2 & 6. DETERIORATED MORTAR SHOULD BE REMOVED TO SOUND MORTAR. NEW MORTAR SHOULD MATCH EXISTING IN COLOR, TEXTURE, COMPOSITION, AND JOINT PROFILE. OLD MORTAR SHOULD BE ANALYZED, AS A HEAVILY CONCENTRATED PORTLAND CEMENT MORTAR CAN CAUSE BRICKS TO BREAK APART IF IT DOES NOT ALLOW FOR EXPANSION AND CONTRACTION.
3. NATIONAL PARK SERVICE BRIEF 2 SPECIFIES THE RECOMMENDED COMPOSITION OF MORTARS USED IN HISTORIC BUILDINGS.
4. IF ANY WALL SECTIONS MUST BE REBUILT, THE EXISTING STONE SHOULD BE SALVAGED FOR REUSE. IF EXISTING STONE IS DAMAGED BEYOND REPAIR, NEW MATERIAL MUST MATCH THE HISTORIC/EXISTING IN SIZE, COLOR, AND TEXTURE.
5. IF IT IS NECESSARY TO REMOVE PAINT, SOILING, OR BIO GROWTH FROM EXTERIOR STONE CLADDING, IT SHOULD BE ACCOMPLISHED USING THE GENTLEST MEANS POSSIBLE TO AVOID DAMAGING THE HISTORIC MASONRY. CONTACT AND REFER TO HISTORIC CONSULTANTS/SPECIALISTS FOR TREATMENT OPTIONS.
6. BRICK SHOULD NOT BE PAINTED.
7. CORDOVA LIMESTONE MUST REMAIN AND BE REPAIRED.
8. SMALL HOLES OR DAMAGE MAY BE REPAIRED WITH A PATCHING MORTAR. CONTACT HISTORICAL CONSULTANT FOR REFERENCE TYPES AND APPROVALS.
9. LIMESTONE SHOULD NOT BE PAINTED.
10. METAL DECORATIVE ELEMENTS MUST BE RETAINED, CLEANED, AND/OR REPLACED IN KIND IF DAMAGED.
11. METAL ELEMENTS SHOULD NOT BE PAINTED.

ENTRANCES

1. LIMESTONE MUST BE RETAINED IN ACCORDANCE WITH THE ABOVE GUIDANCE.
2. THE METAL CANOPIES SHOULD BE RETAINED AND REPAIRED WITH ANY MISSING OR DETERIORATED ELEMENTS REPLACED IN KIND. THEY SHOULD NOT BE PAINTED.
3. EXISTING DOORS MAY REMAIN OR NEW DOORS MAY REPLACE EXISTING WITHIN THE EXISTING OPENING. THESE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING. NEW DOORS MAY BE WOOD, CLAD WOOD, OR METAL BUT SHOULD HAVE THE THICKER RAILS AND STILES TYPICAL OF DOORS FROM THIS TIME PERIOD. GLASS IN NEW DOORS MAY BE INSULATED AND/OR LOW-E BUT MUST BE CLEAR, COLORLESS AND NON-REFLECTIVE WITH NO LESS THAN 69% VLT AND NO GREATER THAN 11% VLR.
4. TERRAZZO MUST REMAIN AND BE REPAIRED AS NEEDED. TERRAZZO CAN BE CLEANED PER THE GSA TECHNICAL REFERENCE ON CLEANING TERRAZZO. DO NOT SEAL, WAX, OIL OR COAT TERRAZZO IN ANY NEW MATERIAL. TERRAZZO WITH MINOR DAMAGE CAN BE PATCHED WITH A REPAIR KIT TO MATCH EXISTING.
5. EXISTING STAIRS SHOULD REMAIN AND BE REPAIRED AS NEEDED.
6. NEW RAILINGS CAN REPLACE EXISTING BUT MUST BE COMPATIBLE WITH MODERNE CHARACTER OF BUILDING & SIMPLE.

WINDOWS

1. EXISTING NON-HISTORIC REPLACEMENT WINDOWS MAY REMAIN.
2. IF NEW WINDOWS ARE PROPOSED, THEY SHOULD MATCH WINDOWS VISIBLE IN HISTORIC IMAGES. ORIGINAL WINDOWS APPEAR TO BE STEEL, 3 OVER 3, HUNG, WITH HORIZONTAL SASHES AND THICK MULLIONS.

ROOF

1. THE EXISTING ROOF MAY REMAIN OR BE REPLACED.
2. NEW ROOFTOP FEATURES OR AMENITIES (HVAC EQUIPMENT ETC.) SHOULD BE HELD TOWARDS THE CENTER OR REAR OF THE ROOF TO MINIMIZE VISIBILITY FROM THE STREET.

INTERIOR

1. THE CONFIGURATION OF PRIMARY DOUBLE LOADED CORRIDOR MUST REMAIN. CLASSROOM DOORS ARE TO REMAIN AND BE USED FOR NEW UNITS AS POSSIBLE. IF DOORS ARE NOT TO BE USED, THEY SHOULD REMAIN AND BE FIXED IN PLACE.
2. NEW PARTITIONS SHOULD NOT INTERSECT WITH OR RUN IN FRONT OF WINDOWS. ANY WALL JOGS MUST BE HELD AT LEAST 3' BACK FROM WINDOWS.
3. FURRED OUT WALLS WITH LOCKERS SHOULD REMAIN.
4. NEW FLOORING MAY REPLACE CARPET. CARPET, LVT, OR OTHER FINISHED MATERIAL IS SUFFICIENT. WOOD-LOOK LVT IS NOT ACCEPTABLE.
5. CURVED PLASTER CORNERS, PLASTER WALLS, AND WOOD BASE TRIM SHOULD REMAIN. ANY DAMAGED OR MISSING TRIM SHOULD BE REPLACED IN KIND. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
6. THE EXISTING DROPPED GRID CEILING MAY REMAIN. IF IT IS TO BE REPLACED, THE NEW CEILING SHOULD BE HIGHER, CLOSER TO THE HISTORIC HEIGHT. NEW CEILING SHOULD BE A HARD CEILING OR A SPINELESS DROPPED CEILING.
7. WHERE POSSIBLE, EXISTING BUILT-IN CABINETS AND CHALKBOARD FRAMES SHOULD REMAIN AND BE INCORPORATED INTO THE NEW UNIT DESIGN. MILLWORK SHOULD REMAIN, BE REPAIRED, OR REPLACED WHERE DETERIORATED.
8. BRICK WINDOW SILLS SHOULD REMAIN AND BE REPAIRED IN ACCORDANCE WITH MASONRY GUIDANCE ABOVE. BRICK SHOULD NOT BE PAINTED .
9. THE FIREPLACE AS NOTED ON PLANS, MUST REMAIN.
10. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
11. EXISTING DOORS INTO CLASSROOMS AND TRANSOMS SHOULD REMAIN AND BE REPAIRED AS NEEDED. UNPAINTED DOORS SHOULD NOT BE PAINTED, BUT MAY BE REFINISHED.

AUDITORIUM

1. THE AUDITORIUM SHOULD REMAIN ITS OPEN VOLUME TO THE GREATEST EXTENT POSSIBLE.
2. THE AUDITORIUM'S HISTORIC FINISHES INCLUDING PLASTER WALLS AND CEILINGS, MILLWORK, TRIM, WOOD STAGE FLOORING, AND THE PROSCENIUM MUST REMAIN AND BE REPAIRED.
3. FLAT PLASTER SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21 AND DECORATIVE PLASTER IN ACCORDANCE WITH PRESERVATION BRIEF 23.
4. AUDITORIUM SEATING SHOULD BE RETAINED IN PLACE AND REPAIRED.
5. HISTORIC FLOORING IS LIKELY PRESENT BENEATH THE NON HISTORIC FINISHES IN AREAS NOTED WITH DEMOLITION NOTE 16. REMOVE NON-HISTORIC FINISHES IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC FLOORING BENEATH.
6. HISTORIC PLASTER CEILINGS & TRIM ARE LIKELY PRESENT ABOVE THE NON HISTORIC CEILINGS IN AREAS NOTED WITH DEMOLITION NOTE [A]. REMOVE NON-HISTORIC CEILINGS IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC PLASTER ABOVE.
7. IF ANY HISTORIC FINISHES NOT PREVIOUSLY NOTED, CONTACT THE ARCHITECT.

BASEMENT

1. THE TERRAZZO MUST REMAIN AND BE REPAIRED.
2. THE CAFETERIA SHOULD REMAIN AS OPEN AS POSSIBLE.

VERTICAL CIRCULATION

1. STAIRS MUST REMAIN, AND IF POSSIBLE, REMAIN OPEN
2. CONCRETE SHOULD BE VISIBLE
3. TILE MUST REMAIN. DAMAGED OR MISSING TILE SHOULD BE REPLACED IN KIND.
4. PLASTER WALLS MUST REMAIN AND SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21.
5. MILLWORK INCLUDING RAILINGS SHOULD REMAIN, AND ANY NEW RAILINGS SHOULD AUGMENT THE HISTORIC FEATURES INSTEAD OF REPLACE.

MECHANICAL, ELECTRICAL, PLUMBING

1. NEW HVAC SHALL BE CONCEALED THROUGHOUT BUILDING.
2. ROOFTOP EQUIPMENT SHALL NOT BE VISIBLE FROM GROUND.
3. SOFFITS AND DROPPED CEILINGS SHALL NOT DROP BELOW WINDOWS.
4. NEW PLUMBING SHALL NOT BE EXPOSED.
5. AUDITORIUM VENTS SHOULD BE REMAIN AND BE REUSED.
6. WHERE POSSIBLE ELECTRICAL SHOULD BE CONCEALED WITHIN WALLS AND CEILINGS. ANY SURFACE MOUNTED CONDUIT SHOULD BE LOCATED AS INCONSPICUOUSLY AS POSSIBLE.

LIGHTING

1. ANY SURFACE MOUNTED EXTERIOR FIXTURES SHOULD BE ANCHORED INTO THE MORTAR RATHER THAN THE MASONRY UNITS.
2. EXISTING INTERIOR AUDITORIUM LIGHTING SHOULD REMAIN AND BE REPAIRED WHERE POSSIBLE.

SIGNAGE

1. ETCHED SIGNAGE ABOVE FRONT ENTRY DOORS MUST REMAIN AND BE REPAIRED.
2. NEW SIGNAGE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING.
3. INTERIOR SIGNAGE SHOULD BE RETAINED WHERE POSSIBLE.


GENERAL DEMOLITION NOTES

1. WHERE EXISTING BLDG. COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXISTING FINISH, UNLESS NEW FINISHES ARE CALLED FOR IN THE FINISH SCHEDULE.
2. REMOVE EXISTING BLDG. COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
3. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
4. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. SHORING OF EXISTING STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
6. NOTIFY ARCHITECT IMMEDIATELY IF ASBESTOS IS SUSPECTED ON SITE. DO NOT DISTURB UNLESS DIRECTED.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE THE DEMOLITION BY DIFFERING TRADES.
8. CONTRACTOR COORDINATE SCHEDULE & LOCATION OF ANY OR ALL EXISTING RECEPTACLES, SWITCHES, DEVICES, ETC. PRIOR TO DEMOLITION, RELOCATE OR ABANDON ACCORDINGLY.
9. COORDINATE & REFERENCE MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS AND DETAILS
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.



C **HISTORIC DOOR/TRANSOM**
N.T.S.

**EVALUATE HISTORIC WOOD CABINETS TO DETERMINE METHOD AND POSSIBILITY OF SEPARATING INTO 3 SECTIONS. TWO SECTIONS TO BE REMOVED, AND ONE SECTION TO REMAIN.



B **HISTORIC CABINETS**
N.T.S.

SPECIFIC DEMOLITION NOTES

01 REMOVE EXISTING WALLS AS SHOWN SCHEMATICALLY BY DASHED LINES. PATCH AND REPAIR EXISTING CEILING, ADJACENT WALLS, AND FLOOR AS NEEDED. REPAIR AS INSTRUCTED BY THE HISTORIC MEMO IF REQUIRED.

02 HISTORIC DOOR & FRAME TO REMAIN AND SECURED CLOSED. REPAIR & REFINISH PER HISTORIC MEMO NOTES. REMOVE DOOR HARDWARE & COVER HOLES WITH APPROVED METHOD.

03 NON-HISTORIC DOOR: REMOVE EXISTING DOOR AND FRAME.

04 REMOVE & SALVAGE SECTIONS OF EXISTING WOOD BUILT INS. AS SHOWN. REF. HISTORIC PRESERVATION NOTES. REF. CABINETS PHOTO B/D2.1. **SEE NOTE

05 REMOVE & SALVAGE EXISTING CABINET. RE-INSTALL OR USE AT DIRECTION OF OWNER.

06 REMOVE EXISTING CABINET

07 REMOVE EXISTING PLUMBING FIXTURE(S). REFERENCE ALL PROPOSED MEP PLANS AND NOTES FOR PROPER DEMO AND NEW WORK PREP.

08 EXISTING WINDOWS TO REMAIN. PROTECT AND REPAIR WHERE NECESSARY.

09 SAWCUT & REMOVE PORTION OF MASONRY, PLASTER, BRICK WALL FOR NEW WINDOW. PREP FOR NEW WINDOW UNIT INSTALLATION

10 PROTECT HISTORIC LOCKERS DURING DEMOLITION PROCESS. LOCKERS WILL REMAIN & BE REFINISHED AS DIRECTED.

11 PROTECT HISTORIC FIREPLACE FEATURE DURING DEMOLITION PROCESS. WILL REMAIN.

12 REMOVE PORTION OF WALL & PREP FOR DOOR INSTALLATION

13 REMOVE ELECTRICAL PANEL. REFERENCE ELECTRICAL PLANS FOR OTHER DEMO AND PROPOSED INSTALLATION

14 PROTECT HISTORIC TRANSOM WINDOW OVER DOOR, TO REMAIN FIXED & SECURED CLOSED. REF. PHOTO C/D2.1

15 PROTECT HISTORIC FLOOR/WALL FINISH (AS SHOWN BY FINISH KEY A9.1) DURING DEMOLITION PROCESS

16 REMOVE NON HISTORIC FINISH: CARPET


17 REMOVE NON HISTORIC FINISH: VT TILE/BATHROOM TILE


18 EXISTING TERRAZZO TO BE PROTECTED DURING CONSTRUCTION. AT TERRAZZO SAWCUT/GRIND ANY RAISED AREAS AT REMOVED WALLS. PROTECT, CLEAN, PATCH AND REPAIR AS NEEDED.

19 EXISTING AUDITORIUM SEATING TO REMAIN. PROTECT AND REPAIR.

20 EXISTING WOOD HANDRAILS TO REMAIN. NEW CODE COMPLIANT HANDRAIL SECTIONS SHALL BE ADDED PER PLANS/DETAILS.

21 ENTRY STEPS, RAMP, & ALL CONCRETE TO REMAIN.





-------- Demolish. Ref. keynotes

A **PARTIAL FIRST FLOOR DEMOLITION PLAN**
3/32"=1'-0"

JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

JGR

LANDMARK 601
601. W LEWIS
CONROE, TEXAS

PRELIMINARY DRAWING
NOT FOR CONSTRUCTION

REVISION:

DATE: 10-31-2025
JOB: 25-3385
SHEET NO.:

D2.1

COPYRIGHTED ©

HISTORIC PRESERVATION NOTES

STRUCTURE, MASONRY AND EXTERIOR WALLS

1. WORK SHALL NOT DAMAGE ANY EXISTING MASONRY, ORNAMENT OR CHARACTER–DEFINING FEATURES. CONTRACTOR TO PROTECT DURING CONSTRUCTION.
2. MASONRY REHABILITATION SHALL CONSIST OF SPOT REPOINTING AND REPAIR/REPLACEMENT OF ISOLATED DETERIORATION. ALL WORK SHALL CONFORM TO PRESERVATION STANDARDS OUTLINED IN THE NATIONAL PARK SERVICE PRESERVATION BRIEFS 1,2 & 6. DETERIORATED MORTAR SHOULD BE REMOVED TO SOUND MORTAR. NEW MORTAR SHOULD MATCH EXISTING IN COLOR, TEXTURE, COMPOSITION, AND JOINT PROFILE. OLD MORTAR SHOULD BE ANALYZED, AS A HEAVILY CONCENTRATED PORTLAND CEMENT MORTAR CAN CAUSE BRICKS TO BREAK APART IF IT DOES NOT ALLOW FOR EXPANSION AND CONTRACTION.
3. NATIONAL PARK SERVICE BRIEF 2 SPECIFIES THE RECOMMENDED COMPOSITION OF MORTARS USED IN HISTORIC BUILDINGS.
4. IF ANY WALL SECTIONS MUST BE REBUILT, THE EXISTING STONE SHOULD BE SALVAGED FOR REUSE. IF EXISTING STONE IS DAMAGED BEYOND REPAIR, NEW MATERIAL MUST MATCH THE HISTORIC/EXISTING IN SIZE, COLOR, AND TEXTURE.
5. IF IT IS NECESSARY TO REMOVE PAINT, SOILING, OR BIO GROWTH FROM EXTERIOR STONE CLADDING, IT SHOULD BE ACCOMPLISHED USING THE GENTLEST MEANS POSSIBLE TO AVOID DAMAGING THE HISTORIC MASONRY. CONTACT AND REFER TO HISTORIC CONSULTANTS/SPECIALISTS FOR TREATMENT OPTIONS.
6. BRICK SHOULD NOT BE PAINTED.
7. CORDOVA LIMESTONE MUST REMAIN AND BE REPAIRED.
8. SMALL HOLES OR DAMAGE MAY BE REPAIRED WITH A PATCHING MORTAR. CONTACT HISTORICAL CONSULTANT FOR REFERENCE TYPES AND APPROVALS.
9. LIMESTONE SHOULD NOT BE PAINTED.
10. METAL DECORATIVE ELEMENTS MUST BE RETAINED, CLEANED, AND/OR REPLACED IN KIND IF DAMAGED.
11. METAL ELEMENTS SHOULD NOT BE PAINTED.

ENTRANCES

1. LIMESTONE MUST BE RETAINED IN ACCORDANCE WITH THE ABOVE GUIDANCE.
2. THE METAL CANOPIES SHOULD BE RETAINED AND REPAIRED WITH ANY MISSING OR DETERIORATED ELEMENTS REPLACED IN KIND. THEY SHOULD NOT BE PAINTED.
3. EXISTING DOORS MAY REMAIN OR NEW DOORS MAY REPLACE EXISTING WITHIN THE EXISTING OPENING. THESE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING. NEW DOORS MAY BE WOOD, CLAD WOOD, OR METAL BUT SHOULD HAVE THE THICKER RAILS AND STILES TYPICAL OF DOORS FROM THIS TIME PERIOD. GLASS IN NEW DOORS MAY BE INSULATED AND/OR LOW–E BUT MUST BE CLEAR, COLORLESS AND NON–REFLECTIVE WITH NO LESS THAN 69% VLT AND NO GREATER THAN 11% VLR.
4. TERRAZZO MUST REMAIN AND BE REPAIRED AS NEEDED. TERRAZZO CAN BE CLEANED PER THE GSA TECHNICAL REFERENCE ON CLEANING TERRAZZO. DO NOT SEAL, WAX, OIL OR COAT TERRAZZO IN ANY NEW MATERIAL. TERRAZZO WITH MINOR DAMAGE CAN BE PATCHED WITH A REPAIR KIT TO MATCH EXISTING.
5. EXISTING STAIRS SHOULD REMAIN AND BE REPAIRED AS NEEDED.
6. NEW RAILINGS CAN REPLACE EXISTING BUT MUST BE COMPATIBLE WITH MODERNE CHARACTER OF BUILDING & SIMPLE.

WINDOWS

1. EXISTING NON–HISTORIC REPLACEMENT WINDOWS MAY REMAIN.
2. IF NEW WINDOWS ARE PROPOSED, THEY SHOULD MATCH WINDOWS VISIBLE IN HISTORIC IMAGES. ORIGINAL WINDOWS APPEAR TO BE STEEL, 3 OVER 3, HUNG, WITH HORIZONTAL SASHES AND THICK MULLIONS.

ROOF

1. THE EXISTING ROOF MAY REMAIN OR BE REPLACED.
2. NEW ROOFTOP FEATURES OR AMENITIES (HVAC EQUIPMENT ETC.) SHOULD BE HELD TOWARDS THE CENTER OR REAR OF THE ROOF TO MINIMIZE VISIBILITY FROM THE STREET.

INTERIOR

1. THE CONFIGURATION OF PRIMARY DOUBLE LOADED CORRIDOR MUST REMAIN. CLASSROOM DOORS ARE TO REMAIN AND BE USED FOR NEW UNITS AS POSSIBLE. IF DOORS ARE NOT TO BE USED, THEY SHOULD REMAIN AND BE FIXED IN PLACE.
2. NEW PARTITIONS SHOULD NOT INTERSECT WITH OR RUN IN FRONT OF WINDOWS. ANY WALL JOGS MUST BE HELD AT LEAST 3' BACK FROM WINDOWS.
3. FURRED OUT WALLS WITH LOCKERS SHOULD REMAIN.
4. NEW FLOORING MAY REPLACE CARPET. CARPET, LVT, OR OTHER FINISHED MATERIAL IS SUFFICIENT. WOOD–LOOK LVT IS NOT ACCEPTABLE.
5. CURVED PLASTER CORNERS, PLASTER WALLS, AND WOOD BASE TRIM SHOULD REMAIN. ANY DAMAGED OR MISSING TRIM SHOULD BE REPLACED IN KIND. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
6. THE EXISTING DROPPED GRID CEILING MAY REMAIN. IF IT IS TO BE REPLACED, THE NEW CEILING SHOULD BE HIGHER, CLOSER TO THE HISTORIC HEIGHT. NEW CEILING SHOULD BE A HARD CEILING OR A SPINELESS DROPPED CEILING.
7. WHERE POSSIBLE, EXISTING BUILT–IN CABINETS AND CHALKBOARD FRAMES SHOULD REMAIN AND BE INCORPORATED INTO THE NEW UNIT DESIGN. MILLWORK SHOULD REMAIN, BE REPAIRED, OR REPLACED WHERE DETERIORATED.
8. BRICK WINDOW SILLS SHOULD REMAIN AND BE REPAIRED IN ACCORDANCE WITH MASONRY GUIDANCE ABOVE. BRICK SHOULD NOT BE PAINTED .
9. THE FIREPLACE AS NOTED ON PLANS, MUST REMAIN.
10. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
11. EXISTING DOORS INTO CLASSROOMS AND TRANSOMS SHOULD REMAIN AND BE REPAIRED AS NEEDED. UNPAINTED DOORS SHOULD NOT BE PAINTED, BUT MAY BE REFINISHED.

AUDITORIUM

1. THE AUDITORIUM SHOULD REMAIN ITS OPEN VOLUME TO THE GREATEST EXTENT POSSIBLE.
2. THE AUDITORIUM'S HISTORIC FINISHES INCLUDING PLASTER WALLS AND CEILINGS, MILLWORK, TRIM, WOOD STAGE FLOORING, AND THE PROSCENIUM MUST REMAIN AND BE REPAIRED.
3. FLAT PLASTER SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21 AND DECORATIVE PLASTER IN ACCORDANCE WITH PRESERVATION BRIEF 23.
4. AUDITORIUM SEATING SHOULD BE RETAINED IN PLACE AND REPAIRED.
5. HISTORIC FLOORING IS LIKELY PRESENT BENEATH THE NON HISTORIC FINISHES IN AREAS NOTED WITH DEMOLITION NOTE 16. REMOVE NON–HISTORIC FINISHES IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC FLOORING BENEATH.
6. HISTORIC PLASTER CEILINGS & TRIM ARE LIKELY PRESENT ABOVE THE NON HISTORIC CEILINGS IN AREAS NOTED WITH DEMOLITION NOTE [A]. REMOVE NON–HISTORIC CEILINGS IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC PLASTER ABOVE.
7. IF ANY HISTORIC FINISHES NOT PREVIOUSLY NOTED, CONTACT THE ARCHITECT.

BASEMENT

1. THE TERRAZZO MUST REMAIN AND BE REPAIRED.
2. THE CAFETERIA SHOULD REMAIN AS OPEN AS POSSIBLE.

VERTICAL CIRCULATION

1. STAIRS MUST REMAIN, AND IF POSSIBLE, REMAIN OPEN
2. CONCRETE SHOULD BE VISIBLE
3. TILE MUST REMAIN. DAMAGED OR MISSING TILE SHOULD BE REPLACED IN KIND.
4. PLASTER WALLS MUST REMAIN AND SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21.
5. MILLWORK INCLUDING RAILINGS SHOULD REMAIN, AND ANY NEW RAILINGS SHOULD AUGMENT THE HISTORIC FEATURES INSTEAD OF REPLACE.

MECHANICAL, ELECTRICAL, PLUMBING

1. NEW HVAC SHALL BE CONCEALED THROUGHOUT BUILDING.
2. ROOFTOP EQUIPMENT SHALL NOT BE VISIBLE FROM GROUND.
3. SOFFITS AND DROPPED CEILINGS SHALL NOT DROP BELOW WINDOWS.
4. NEW PLUMBING SHALL NOT BE EXPOSED.
5. AUDITORIUM VENTS SHOULD BE REMAIN AND BE REUSED.
6. WHERE POSSIBLE ELECTRICAL SHOULD BE CONCEALED WITHIN WALLS AND CEILINGS. ANY SURFACE MOUNTED CONDUIT SHOULD BE LOCATED AS INCONSPICUOUSLY AS POSSIBLE.

LIGHTING

1. ANY SURFACE MOUNTED EXTERIOR FIXTURES SHOULD BE ANCHORED INTO THE MORTAR RATHER THAN THE MASONRY UNITS.
2. EXISTING INTERIOR AUDITORIUM LIGHTING SHOULD REMAIN AND BE REPAIRED WHERE POSSIBLE.

SIGNAGE

1. ETCHED SIGNAGE ABOVE FRONT ENTRY DOORS MUST REMAIN AND BE REPAIRED.
2. NEW SIGNAGE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING.
3. INTERIOR SIGNAGE SHOULD BE RETAINED WHERE POSSIBLE.

SPECIFIC DEMOLITION NOTES

01 REMOVE EXISTING WALLS AS SHOWN SCHEMATICALLY BY DASHED LINES. PATCH AND REPAIR EXISTING CEILING, ADJACENT WALLS, AND FLOOR AS NEEDED. REPAIR AS INSTRUCTED BY THE HISTORIC MEMO IF REQUIRED.

02 HISTORIC DOOR & FRAME TO REMAIN AND SECURED CLOSED. REPAIR & REFINISH PER HISTORIC MEMO NOTES. REMOVE DOOR HARDWARE & COVER HOLES WITH APPROVED METHOD.

03 NON–HISTORIC DOOR: REMOVE EXISTING DOOR AND FRAME.

04 REMOVE & SALVAGE SECTIONS OF EXISTING WOOD BUILT INS. AS SHOWN. REF. HISTORIC PRESERVATION NOTES. REF. CABINETS PHOTO B/D2.1. **SEE NOTE

05 REMOVE & SALVAGE EXISTING CABINET. RE–INSTALL OR USE AT DIRECTION OF OWNER.

06 REMOVE EXISTING CABINET

07 REMOVE EXISTING PLUMBING FIXTURE(S). REFERENCE ALL PROPOSED MEP PLANS AND NOTES FOR PROPER DEMO AND NEW WORK PREP.

08 EXISTING WINDOWS TO REMAIN. PROTECT AND REPAIR WHERE NECESSARY.

09 SAWCUT & REMOVE PORTION OF MASONRY, PLASTER, BRICK WALL FOR NEW WINDOW. PREP FOR NEW WINDOW UNIT INSTALLATION

10 PROTECT HISTORIC LOCKERS DURING DEMOLITION PROCESS. LOCKERS WILL REMAIN & BE REFINISHED AS DIRECTED.

11 PROTECT HISTORIC FIREPLACE FEATURE DURING DEMOLITION PROCESS. WILL REMAIN.

12 REMOVE PORTION OF WALL & PREP FOR DOOR INSTALLATION

13 REMOVE ELECTRICAL PANEL. REFERENCE ELECTRICAL PLANS FOR OTHER DEMO AND PROPOSED INSTALLATION

14 PROTECT HISTORIC TRANSOM WINDOW OVER DOOR, TO REMAIN FIXED & SECURED CLOSED. REF. PHOTO C/D2.1

15 PROTECT HISTORIC FLOOR/WALL FINISH (AS SHOWN BY FINISH KEY A9.1) DURING DEMOLITION PROCESS

16 REMOVE NON HISTORIC FINISH: CARPET

17 REMOVE NON HISTORIC FINISH: VT TILE/BATHROOM TILE

18 EXISTING TERRAZZO TO BE PROTECTED DURING CONSTRUCTION. AT TERRAZZO SAWCUT/GRIND ANY RAISED AREAS AT REMOVED WALLS. PROTECT, CLEAN, PATCH AND REPAIR AS NEEDED.


19 EXISTING AUDITORIUM SEATING TO REMAIN. PROTECT AND REPAIR.

20 EXISTING WOOD HANDRAILS TO REMAIN. NEW CODE COMPLIANT HANDRAIL SECTIONS SHALL BE ADDED PER PLANS/DETAILS.


21 ENTRY STEPS, RAMP, & ALL CONCRETE TO REMAIN.

GENERAL DEMOLITION NOTES

1. WHERE EXISTING BLDG. COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXISTING FINISH, UNLESS NEW FINISHES ARE CALLED FOR IN THE FINISH SCHEDULE.
2. REMOVE EXISTING BLDG. COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
3. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
4. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. SHORING OF EXISTING STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
6. NOTIFY ARCHITECT IMMEDIATELY IF ASBESTOS IS SUSPECTED ON SITE. DO NOT DISTURB UNLESS DIRECTED.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE THE DEMOLITION BY DIFFERING TRADES.
8. CONTRACTOR COORDINATE SCHEDULE & LOCATION OF ANY OR ALL EXISTING RECEPTACLES, SWITCHES, DEVICES, ETC. PRIOR TO DEMOLITION, RELOCATE OR ABANDON ACCORDINGLY.
9. COORDINATE & REFERENCE MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS AND DETAILS
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.




B **HISTORIC TRANSOM & LOCKERS**
N.T.S.



-------- Demolish. Ref. keynotes

A **PARTIAL FIRST FLOOR DEMOLITION PLAN**
3/32"=1'-0"



JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

LANDMARK
601. W LEWIS
CONROE, TEXAS

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

REVISION:

DATE: 10–31–2025
JOB: 25–3385
SHEET NO.:

D2.2

COPYRIGHTED ©

HISTORIC PRESERVATION NOTES

STRUCTURE, MASONRY AND EXTERIOR WALLS

1. WORK SHALL NOT DAMAGE ANY EXISTING MASONRY, ORNAMENT OR CHARACTER-DEFINING FEATURES. CONTRACTOR TO PROTECT DURING CONSTRUCTION.
2. MASONRY REHABILITATION SHALL CONSIST OF SPOT REPOINTING AND REPAIR/REPLACEMENT OF ISOLATED DETERIORATION. ALL WORK SHALL CONFORM TO PRESERVATION STANDARDS OUTLINED IN THE NATIONAL PARK SERVICE PRESERVATION BRIEFS 1,2 & 6. DETERIORATED MORTAR SHOULD BE REMOVED TO SOUND MORTAR. NEW MORTAR SHOULD MATCH EXISTING IN COLOR, TEXTURE, COMPOSITION, AND JOINT PROFILE. OLD MORTAR SHOULD BE ANALYZED, AS A HEAVILY CONCENTRATED PORTLAND CEMENT MORTAR CAN CAUSE BRICKS TO BREAK APART IF IT DOES NOT ALLOW FOR EXPANSION AND CONTRACTION.
3. NATIONAL PARK SERVICE BRIEF 2 SPECIFIES THE RECOMMENDED COMPOSITION OF MORTARS USED IN HISTORIC BUILDINGS.
4. IF ANY WALL SECTIONS MUST BE REBUILT, THE EXISTING STONE SHOULD BE SALVAGED FOR REUSE. IF EXISTING STONE IS DAMAGED BEYOND REPAIR, NEW MATERIAL MUST MATCH THE HISTORIC/EXISTING IN SIZE, COLOR, AND TEXTURE.
5. IF IT IS NECESSARY TO REMOVE PAINT, SOILING, OR BIO GROWTH FROM EXTERIOR STONE CLADDING, IT SHOULD BE ACCOMPLISHED USING THE GENTLEST MEANS POSSIBLE TO AVOID DAMAGING THE HISTORIC MASONRY. CONTACT AND REFER TO HISTORIC CONSULTANTS/SPECIALISTS FOR TREATMENT OPTIONS.
6. BRICK SHOULD NOT BE PAINTED.
7. CORDOVA LIMESTONE MUST REMAIN AND BE REPAIRED.
8. SMALL HOLES OR DAMAGE MAY BE REPAIRED WITH A PATCHING MORTAR. CONTACT HISTORICAL CONSULTANT FOR REFERENCE TYPES AND APPROVALS.
9. LIMESTONE SHOULD NOT BE PAINTED.
10. METAL DECORATIVE ELEMENTS MUST BE RETAINED, CLEANED, AND/OR REPLACED IN KIND IF DAMAGED.
11. METAL ELEMENTS SHOULD NOT BE PAINTED.

ENTRANCES

1. LIMESTONE MUST BE RETAINED IN ACCORDANCE WITH THE ABOVE GUIDANCE.
2. THE METAL CANOPIES SHOULD BE RETAINED AND REPAIRED WITH ANY MISSING OR DETERIORATED ELEMENTS REPLACED IN KIND. THEY SHOULD NOT BE PAINTED.
3. EXISTING DOORS MAY REMAIN OR NEW DOORS MAY REPLACE EXISTING WITHIN THE EXISTING OPENING. THESE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING. NEW DOORS MAY BE WOOD, CLAD WOOD, OR METAL BUT SHOULD HAVE THE THICKER RAILS AND STILES TYPICAL OF DOORS FROM THIS TIME PERIOD. GLASS IN NEW DOORS MAY BE INSULATED AND/OR LOW-E BUT MUST BE CLEAR, COLORLESS AND NON-REFLECTIVE WITH NO LESS THAN 69% VLT AND NO GREATER THAN 11% VLR.
4. TERRAZZO MUST REMAIN AND BE REPAIRED AS NEEDED. TERRAZZO CAN BE CLEANED PER THE GSA TECHNICAL REFERENCE ON CLEANING TERRAZZO. DO NOT SEAL, WAX, OIL OR COAT TERRAZZO IN ANY NEW MATERIAL. TERRAZZO WITH MINOR DAMAGE CAN BE PATCHED WITH A REPAIR KIT TO MATCH EXISTING.
5. EXISTING STAIRS SHOULD REMAIN AND BE REPAIRED AS NEEDED.
6. NEW RAILINGS CAN REPLACE EXISTING BUT MUST BE COMPATIBLE WITH MODERNE CHARACTER OF BUILDING & SIMPLE.

WINDOWS

1. EXISTING NON-HISTORIC REPLACEMENT WINDOWS MAY REMAIN.
2. IF NEW WINDOWS ARE PROPOSED, THEY SHOULD MATCH WINDOWS VISIBLE IN HISTORIC IMAGES. ORIGINAL WINDOWS APPEAR TO BE STEEL, 3 OVER 3, HUNG, WITH HORIZONTAL SASHES AND THICK MULLIONS.

ROOF

1. THE EXISTING ROOF MAY REMAIN OR BE REPLACED.
2. NEW ROOFTOP FEATURES OR AMENITIES (HVAC EQUIPMENT ETC.) SHOULD BE HELD TOWARDS THE CENTER OR REAR OF THE ROOF TO MINIMIZE VISIBILITY FROM THE STREET.

INTERIOR

1. THE CONFIGURATION OF PRIMARY DOUBLE LOADED CORRIDOR MUST REMAIN. CLASSROOM DOORS ARE TO REMAIN AND BE USED FOR NEW UNITS AS POSSIBLE. IF DOORS ARE NOT TO BE USED, THEY SHOULD REMAIN AND BE FIXED IN PLACE.
2. NEW PARTITIONS SHOULD NOT INTERSECT WITH OR RUN IN FRONT OF WINDOWS. ANY WALL JOGS MUST BE HELD AT LEAST 3' BACK FROM WINDOWS.
3. FURRED OUT WALLS WITH LOCKERS SHOULD REMAIN.
4. NEW FLOORING MAY REPLACE CARPET. CARPET, LVT, OR OTHER FINISHED MATERIAL IS SUFFICIENT. WOOD-LOOK LVT IS NOT ACCEPTABLE.
5. CURVED PLASTER CORNERS, PLASTER WALLS, AND WOOD BASE TRIM SHOULD REMAIN. ANY DAMAGED OR MISSING TRIM SHOULD BE REPLACED IN KIND. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
6. THE EXISTING DROPPED GRID CEILING MAY REMAIN. IF IT IS TO BE REPLACED, THE NEW CEILING SHOULD BE HIGHER, CLOSER TO THE HISTORIC HEIGHT. NEW CEILING SHOULD BE A HARD CEILING OR A SPINELESS DROPPED CEILING.
7. WHERE POSSIBLE, EXISTING BUILT-IN CABINETS AND CHALKBOARD FRAMES SHOULD REMAIN AND BE INCORPORATED INTO THE NEW UNIT DESIGN. MILLWORK SHOULD REMAIN, BE REPAIRED, OR REPLACED WHERE DETERIORATED.
8. BRICK WINDOW SILLS SHOULD REMAIN AND BE REPAIRED IN ACCORDANCE WITH MASONRY GUIDANCE ABOVE. BRICK SHOULD NOT BE PAINTED .
9. THE FIREPLACE AS NOTED ON PLANS, MUST REMAIN.
10. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
11. EXISTING DOORS INTO CLASSROOMS AND TRANSOMS SHOULD REMAIN AND BE REPAIRED AS NEEDED. UNPAINTED DOORS SHOULD NOT BE PAINTED, BUT MAY BE REFINISHED.

AUDITORIUM

1. THE AUDITORIUM SHOULD REMAIN ITS OPEN VOLUME TO THE GREATEST EXTENT POSSIBLE.
2. THE AUDITORIUM'S HISTORIC FINISHES INCLUDING PLASTER WALLS AND CEILINGS, MILLWORK, TRIM, WOOD STAGE FLOORING, AND THE PROSCENIUM MUST REMAIN AND BE REPAIRED.
3. FLAT PLASTER SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21 AND DECORATIVE PLASTER IN ACCORDANCE WITH PRESERVATION BRIEF 23.
4. AUDITORIUM SEATING SHOULD BE RETAINED IN PLACE AND REPAIRED.
5. HISTORIC FLOORING IS LIKELY PRESENT BENEATH THE NON HISTORIC FINISHES IN AREAS NOTED WITH DEMOLITION NOTE 16. REMOVE NON-HISTORIC FINISHES IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC FLOORING BENEATH.
6. HISTORIC PLASTER CEILINGS & TRIM ARE LIKELY PRESENT ABOVE THE NON HISTORIC CEILINGS IN AREAS NOTED WITH DEMOLITION NOTE [A]. REMOVE NON-HISTORIC CEILINGS IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC PLASTER ABOVE.
7. IF ANY HISTORIC FINISHES NOT PREVIOUSLY NOTED, CONTACT THE ARCHITECT.

BASEMENT

1. THE TERRAZZO MUST REMAIN AND BE REPAIRED.
2. THE CAFETERIA SHOULD REMAIN AS OPEN AS POSSIBLE.

VERTICAL CIRCULATION

1. STAIRS MUST REMAIN, AND IF POSSIBLE, REMAIN OPEN
2. CONCRETE SHOULD BE VISIBLE
3. TILE MUST REMAIN. DAMAGED OR MISSING TILE SHOULD BE REPLACED IN KIND.
4. PLASTER WALLS MUST REMAIN AND SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21.
5. MILLWORK INCLUDING RAILINGS SHOULD REMAIN, AND ANY NEW RAILINGS SHOULD AUGMENT THE HISTORIC FEATURES INSTEAD OF REPLACE.

MECHANICAL, ELECTRICAL, PLUMBING

1. NEW HVAC SHALL BE CONCEALED THROUGHOUT BUILDING.
2. ROOFTOP EQUIPMENT SHALL NOT BE VISIBLE FROM GROUND.
3. SOFFITS AND DROPPED CEILINGS SHALL NOT DROP BELOW WINDOWS.
4. NEW PLUMBING SHALL NOT BE EXPOSED.
5. AUDITORIUM VENTS SHOULD BE REMAIN AND BE REUSED.
6. WHERE POSSIBLE ELECTRICAL SHOULD BE CONCEALED WITHIN WALLS AND CEILINGS. ANY SURFACE MOUNTED CONDUIT SHOULD BE LOCATED AS INCONSPICUOUSLY AS POSSIBLE.

LIGHTING

1. ANY SURFACE MOUNTED EXTERIOR FIXTURES SHOULD BE ANCHORED INTO THE MORTAR RATHER THAN THE MASONRY UNITS.
2. EXISTING INTERIOR AUDITORIUM LIGHTING SHOULD REMAIN AND BE REPAIRED WHERE POSSIBLE.

SIGNAGE

1. ETCHED SIGNAGE ABOVE FRONT ENTRY DOORS MUST REMAIN AND BE REPAIRED.
2. NEW SIGNAGE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING.
3. INTERIOR SIGNAGE SHOULD BE RETAINED WHERE POSSIBLE.

GENERAL DEMOLITION NOTES

1. WHERE EXISTING BLDG. COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXISTING FINISH, UNLESS NEW FINISHES ARE CALLED FOR IN THE FINISH SCHEDULE.
2. REMOVE EXISTING BLDG. COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
3. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
4. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. SHORING OF EXISTING STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
6. NOTIFY ARCHITECT IMMEDIATELY IF ASBESTOS IS SUSPECTED ON SITE. DO NOT DISTURB UNLESS DIRECTED.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE THE DEMOLITION BY DIFFERING TRADES.
8. CONTRACTOR COORDINATE SCHEDULE & LOCATION OF ANY OR ALL EXISTING RECEPTACLES, SWITCHES, DEVICES, ETC. PRIOR TO DEMOLITION, RELOCATE OR ABANDON ACCORDINGLY.
9. COORDINATE & REFERENCE MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS AND DETAILS
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.

SPECIFIC DEMOLITION NOTES

01 REMOVE EXISTING WALLS AS SHOWN SCHEMATICALLY BY DASHED LINES. PATCH AND REPAIR EXISTING CEILING, ADJACENT WALLS, AND FLOOR AS NEEDED. REPAIR AS INSTRUCTED BY THE HISTORIC MEMO IF REQUIRED.

02 HISTORIC DOOR & FRAME TO REMAIN AND SECURED CLOSED. REPAIR & REFINISH PER HISTORIC MEMO NOTES. REMOVE DOOR HARDWARE & COVER HOLES WITH APPROVED METHOD.

03 NON-HISTORIC DOOR: REMOVE EXISTING DOOR AND FRAME.

04 REMOVE & SALVAGE SECTIONS OF EXISTING WOOD BUILT INS. AS SHOWN. REF. HISTORIC PRESERVATION NOTES. REF. CABINETS PHOTO B/D2.1. **SEE NOTE

05 REMOVE & SALVAGE EXISTING CABINET. RE-INSTALL OR USE AT DIRECTION OF OWNER.

06 REMOVE EXISTING CABINET

07 REMOVE EXISTING PLUMBING FIXTURE(S). REFERENCE ALL PROPOSED MEP PLANS AND NOTES FOR PROPER DEMO AND NEW WORK PREP.

08 EXISTING WINDOWS TO REMAIN. PROTECT AND REPAIR WHERE NECESSARY.

09 SAWCUT & REMOVE PORTION OF MASONRY, PLASTER, BRICK WALL FOR NEW WINDOW. PREP FOR NEW WINDOW UNIT INSTALLATION

10 PROTECT HISTORIC LOCKERS DURING DEMOLITION PROCESS. LOCKERS WILL REMAIN & BE REFINISHED AS DIRECTED.

11 PROTECT HISTORIC FIREPLACE FEATURE DURING DEMOLITION PROCESS. WILL REMAIN.

12 REMOVE PORTION OF WALL & PREP FOR DOOR INSTALLATION

13 REMOVE ELECTRICAL PANEL. REFERENCE ELECTRICAL PLANS FOR OTHER DEMO AND PROPOSED INSTALLATION

14 PROTECT HISTORIC TRANSOM WINDOW OVER DOOR, TO REMAIN FIXED & SECURED CLOSED. REF. PHOTO C/D2.1

15 PROTECT HISTORIC FLOOR/WALL FINISH (AS SHOWN BY FINISH KEY A9.1) DURING DEMOLITION PROCESS

16 REMOVE NON HISTORIC FINISH: CARPET


17 REMOVE NON HISTORIC FINISH: VT TILE/BATHROOM TILE


18 EXISTING TERRAZZO TO BE PROTECTED DURING CONSTRUCTION. AT TERRAZZO SAWCUT/GRIND ANY RAISED AREAS AT REMOVED WALLS. PROTECT, CLEAN, PATCH AND REPAIR AS NEEDED.

19 EXISTING AUDITORIUM SEATING TO REMAIN. PROTECT AND REPAIR.

20 EXISTING WOOD HANDRAILS TO REMAIN. NEW CODE COMPLIANT HANDRAIL SECTIONS SHALL BE ADDED PER PLANS/DETAILS.

21 ENTRY STEPS, RAMP, & ALL CONCRETE TO REMAIN.





--------- Demolish. Ref. keynotes

A

PARTIAL SECOND FLOOR DEMOLITION PLAN

3/32"=1'-0"

JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

JGR

LANDMARK 601

601. W LEWIS

CONROE, TEXAS

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

REVISION:

DATE: 10-31-2025
JOB: 25-3385
SHEET NO.:

D2.3

COPYRIGHTED ©

HISTORIC PRESERVATION NOTES

STRUCTURE, MASONRY AND EXTERIOR WALLS

1. WORK SHALL NOT DAMAGE ANY EXISTING MASONRY, ORNAMENT OR CHARACTER-DEFINING FEATURES. CONTRACTOR TO PROTECT DURING CONSTRUCTION.
2. MASONRY REHABILITATION SHALL CONSIST OF SPOT REPOINTING AND REPAIR/REPLACEMENT OF ISOLATED DETERIORATION. ALL WORK SHALL CONFORM TO PRESERVATION STANDARDS OUTLINED IN THE NATIONAL PARK SERVICE PRESERVATION BRIEFS 1,2 & 6. DETERIORATED MORTAR SHOULD BE REMOVED TO SOUND MORTAR. NEW MORTAR SHOULD MATCH EXISTING IN COLOR, TEXTURE, COMPOSITION, AND JOINT PROFILE. OLD MORTAR SHOULD BE ANALYZED, AS A HEAVILY CONCENTRATED PORTLAND CEMENT MORTAR CAN CAUSE BRICKS TO BREAK APART IF IT DOES NOT ALLOW FOR EXPANSION AND CONTRACTION.
3. NATIONAL PARK SERVICE BRIEF 2 SPECIFIES THE RECOMMENDED COMPOSITION OF MORTARS USED IN HISTORIC BUILDINGS.
4. IF ANY WALL SECTIONS MUST BE REBUILT, THE EXISTING STONE SHOULD BE SALVAGED FOR REUSE. IF EXISTING STONE IS DAMAGED BEYOND REPAIR, NEW MATERIAL MUST MATCH THE HISTORIC/EXISTING IN SIZE, COLOR, AND TEXTURE.
5. IF IT IS NECESSARY TO REMOVE PAINT, SOILING, OR BIO GROWTH FROM EXTERIOR STONE CLADDING, IT SHOULD BE ACCOMPLISHED USING THE GENTLEST MEANS POSSIBLE TO AVOID DAMAGING THE HISTORIC MASONRY. CONTACT AND REFER TO HISTORIC CONSULTANTS/SPECIALISTS FOR TREATMENT OPTIONS.
6. BRICK SHOULD NOT BE PAINTED.
7. CORDOVA LIMESTONE MUST REMAIN AND BE REPAIRED.
8. SMALL HOLES OR DAMAGE MAY BE REPAIRED WITH A PATCHING MORTAR. CONTACT HISTORICAL CONSULTANT FOR REFERENCE TYPES AND APPROVALS.
9. LIMESTONE SHOULD NOT BE PAINTED.
10. METAL DECORATIVE ELEMENTS MUST BE RETAINED, CLEANED, AND/OR REPLACED IN KIND IF DAMAGED.
11. METAL ELEMENTS SHOULD NOT BE PAINTED.

ENTRANCES

1. LIMESTONE MUST BE RETAINED IN ACCORDANCE WITH THE ABOVE GUIDANCE.
2. THE METAL CANOPIES SHOULD BE RETAINED AND REPAIRED WITH ANY MISSING OR DETERIORATED ELEMENTS REPLACED IN KIND. THEY SHOULD NOT BE PAINTED.
3. EXISTING DOORS MAY REMAIN OR NEW DOORS MAY REPLACE EXISTING WITHIN THE EXISTING OPENING. THESE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING. NEW DOORS MAY BE WOOD, CLAD WOOD, OR METAL BUT SHOULD HAVE THE THICKER RAILS AND STILES TYPICAL OF DOORS FROM THIS TIME PERIOD. GLASS IN NEW DOORS MAY BE INSULATED AND/OR LOW-E BUT MUST BE CLEAR, COLORLESS AND NON-REFLECTIVE WITH NO LESS THAN 69% VLT AND NO GREATER THAN 11% VLR.
4. TERRAZZO MUST REMAIN AND BE REPAIRED AS NEEDED. TERRAZZO CAN BE CLEANED PER THE GSA TECHNICAL REFERENCE ON CLEANING TERRAZZO. DO NOT SEAL, WAX, OIL OR COAT TERRAZZO IN ANY NEW MATERIAL. TERRAZZO WITH MINOR DAMAGE CAN BE PATCHED WITH A REPAIR KIT TO MATCH EXISTING.
5. EXISTING STAIRS SHOULD REMAIN AND BE REPAIRED AS NEEDED.
6. NEW RAILINGS CAN REPLACE EXISTING BUT MUST BE COMPATIBLE WITH MODERNE CHARACTER OF BUILDING & SIMPLE.

WINDOWS

1. EXISTING NON-HISTORIC REPLACEMENT WINDOWS MAY REMAIN.
2. IF NEW WINDOWS ARE PROPOSED, THEY SHOULD MATCH WINDOWS VISIBLE IN HISTORIC IMAGES. ORIGINAL WINDOWS APPEAR TO BE STEEL, 3 OVER 3, HUNG, WITH HORIZONTAL SASHES AND THICK MULLIONS.

ROOF

1. THE EXISTING ROOF MAY REMAIN OR BE REPLACED.
2. NEW ROOFTOP FEATURES OR AMENITIES (HVAC EQUIPMENT ETC.) SHOULD BE HELD TOWARDS THE CENTER OR REAR OF THE ROOF TO MINIMIZE VISIBILITY FROM THE STREET.

INTERIOR

1. THE CONFIGURATION OF PRIMARY DOUBLE LOADED CORRIDOR MUST REMAIN. CLASSROOM DOORS ARE TO REMAIN AND BE USED FOR NEW UNITS AS POSSIBLE. IF DOORS ARE NOT TO BE USED, THEY SHOULD REMAIN AND BE FIXED IN PLACE.
2. NEW PARTITIONS SHOULD NOT INTERSECT WITH OR RUN IN FRONT OF WINDOWS. ANY WALL JOGS MUST BE HELD AT LEAST 3' BACK FROM WINDOWS.
3. FURRED OUT WALLS WITH LOCKERS SHOULD REMAIN.
4. NEW FLOORING MAY REPLACE CARPET. CARPET, LVT, OR OTHER FINISHED MATERIAL IS SUFFICIENT. WOOD-LOOK LVT IS NOT ACCEPTABLE.
5. CURVED PLASTER CORNERS, PLASTER WALLS, AND WOOD BASE TRIM SHOULD REMAIN. ANY DAMAGED OR MISSING TRIM SHOULD BE REPLACED IN KIND. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
6. THE EXISTING DROPPED GRID CEILING MAY REMAIN. IF IT IS TO BE REPLACED, THE NEW CEILING SHOULD BE HIGHER, CLOSER TO THE HISTORIC HEIGHT. NEW CEILING SHOULD BE A HARD CEILING OR A SPINELESS DROPPED CEILING.
7. WHERE POSSIBLE, EXISTING BUILT-IN CABINETS AND CHALKBOARD FRAMES SHOULD REMAIN AND BE INCORPORATED INTO THE NEW UNIT DESIGN. MILLWORK SHOULD REMAIN, BE REPAIRED, OR REPLACED WHERE DETERIORATED.
8. BRICK WINDOW SILLS SHOULD REMAIN AND BE REPAIRED IN ACCORDANCE WITH MASONRY GUIDANCE ABOVE. BRICK SHOULD NOT BE PAINTED .
9. THE FIREPLACE AS NOTED ON PLANS, MUST REMAIN.
10. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
11. EXISTING DOORS INTO CLASSROOMS AND TRANSOMS SHOULD REMAIN AND BE REPAIRED AS NEEDED. UNPAINTED DOORS SHOULD NOT BE PAINTED, BUT MAY BE REFINISHED.

AUDITORIUM

1. THE AUDITORIUM SHOULD REMAIN ITS OPEN VOLUME TO THE GREATEST EXTENT POSSIBLE.
2. THE AUDITORIUM'S HISTORIC FINISHES INCLUDING PLASTER WALLS AND CEILINGS, MILLWORK, TRIM, WOOD STAGE FLOORING, AND THE PROSCENIUM MUST REMAIN AND BE REPAIRED.
3. FLAT PLASTER SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21 AND DECORATIVE PLASTER IN ACCORDANCE WITH PRESERVATION BRIEF 23.
4. AUDITORIUM SEATING SHOULD BE RETAINED IN PLACE AND REPAIRED.
5. HISTORIC FLOORING IS LIKELY PRESENT BENEATH THE NON HISTORIC FINISHES IN AREAS NOTED WITH DEMOLITION NOTE 16. REMOVE NON-HISTORIC FINISHES IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC FLOORING BENEATH.
6. HISTORIC PLASTER CEILINGS & TRIM ARE LIKELY PRESENT ABOVE THE NON HISTORIC CEILINGS IN AREAS NOTED WITH DEMOLITION NOTE [A]. REMOVE NON-HISTORIC CEILINGS IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC PLASTER ABOVE.
7. IF ANY HISTORIC FINISHES NOT PREVIOUSLY NOTED, CONTACT THE ARCHITECT.

BASEMENT

1. THE TERRAZZO MUST REMAIN AND BE REPAIRED.
2. THE CAFETERIA SHOULD REMAIN AS OPEN AS POSSIBLE.

VERTICAL CIRCULATION

1. STAIRS MUST REMAIN, AND IF POSSIBLE, REMAIN OPEN
2. CONCRETE SHOULD BE VISIBLE
3. TILE MUST REMAIN. DAMAGED OR MISSING TILE SHOULD BE REPLACED IN KIND.
4. PLASTER WALLS MUST REMAIN AND SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21.
5. MILLWORK INCLUDING RAILINGS SHOULD REMAIN, AND ANY NEW RAILINGS SHOULD AUGMENT THE HISTORIC FEATURES INSTEAD OF REPLACE.

MECHANICAL, ELECTRICAL, PLUMBING

1. NEW HVAC SHALL BE CONCEALED THROUGHOUT BUILDING.
2. ROOFTOP EQUIPMENT SHALL NOT BE VISIBLE FROM GROUND.
3. SOFFITS AND DROPPED CEILINGS SHALL NOT DROP BELOW WINDOWS.
4. NEW PLUMBING SHALL NOT BE EXPOSED.
5. AUDITORIUM VENTS SHOULD BE REMAIN AND BE REUSED.
6. WHERE POSSIBLE ELECTRICAL SHOULD BE CONCEALED WITHIN WALLS AND CEILINGS. ANY SURFACE MOUNTED CONDUIT SHOULD BE LOCATED AS INCONSPICUOUSLY AS POSSIBLE.

LIGHTING

1. ANY SURFACE MOUNTED EXTERIOR FIXTURES SHOULD BE ANCHORED INTO THE MORTAR RATHER THAN THE MASONRY UNITS.
2. EXISTING INTERIOR AUDITORIUM LIGHTING SHOULD REMAIN AND BE REPAIRED WHERE POSSIBLE.

SIGNAGE

1. ETCHED SIGNAGE ABOVE FRONT ENTRY DOORS MUST REMAIN AND BE REPAIRED.
2. NEW SIGNAGE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING.
3. INTERIOR SIGNAGE SHOULD BE RETAINED WHERE POSSIBLE.

SPECIFIC DEMOLITION NOTES

01 REMOVE EXISTING WALLS AS SHOWN SCHEMATICALLY BY DASHED LINES. PATCH AND REPAIR EXISTING CEILING, ADJACENT WALLS, AND FLOOR AS NEEDED. REPAIR AS INSTRUCTED BY THE HISTORIC MEMO IF REQUIRED.

02 HISTORIC DOOR & FRAME TO REMAIN AND SECURED CLOSED. REPAIR & REFINISH PER HISTORIC MEMO NOTES. REMOVE DOOR HARDWARE & COVER HOLES WITH APPROVED METHOD.

03 NON-HISTORIC DOOR: REMOVE EXISTING DOOR AND FRAME.

04 REMOVE & SALVAGE SECTIONS OF EXISTING WOOD BUILT INS. AS SHOWN. REF. HISTORIC PRESERVATION NOTES. REF. CABINETS PHOTO B/D2.1. **SEE NOTE

05 REMOVE & SALVAGE EXISTING CABINET. RE-INSTALL OR USE AT DIRECTION OF OWNER.

06 REMOVE EXISTING CABINET

07 REMOVE EXISTING PLUMBING FIXTURE(S). REFERENCE ALL PROPOSED MEP PLANS AND NOTES FOR PROPER DEMO AND NEW WORK PREP.

08 EXISTING WINDOWS TO REMAIN. PROTECT AND REPAIR WHERE NECESSARY.

09 SAWCUT & REMOVE PORTION OF MASONRY, PLASTER, BRICK WALL FOR NEW WINDOW. PREP FOR NEW WINDOW UNIT INSTALLATION

10 PROTECT HISTORIC LOCKERS DURING DEMOLITION PROCESS. LOCKERS WILL REMAIN & BE REFINISHED AS DIRECTED.

11 PROTECT HISTORIC FIREPLACE FEATURE DURING DEMOLITION PROCESS. WILL REMAIN.

12 REMOVE PORTION OF WALL & PREP FOR DOOR INSTALLATION

13 REMOVE ELECTRICAL PANEL. REFERENCE ELECTRICAL PLANS FOR OTHER DEMO AND PROPOSED INSTALLATION

14 PROTECT HISTORIC TRANSOM WINDOW OVER DOOR, TO REMAIN FIXED & SECURED CLOSED. REF. PHOTO C/D2.1

15 PROTECT HISTORIC FLOOR/WALL FINISH (AS SHOWN BY FINISH KEY A9.1) DURING DEMOLITION PROCESS

16 REMOVE NON HISTORIC FINISH: CARPET

17 REMOVE NON HISTORIC FINISH: VT TILE/BATHROOM TILE

18 EXISTING TERRAZZO TO BE PROTECTED DURING CONSTRUCTION. AT TERRAZZO SAWCUT/GRIND ANY RAISED AREAS AT REMOVED WALLS. PROTECT, CLEAN, PATCH AND REPAIR AS NEEDED.


19 EXISTING AUDITORIUM SEATING TO REMAIN. PROTECT AND REPAIR.

20 EXISTING WOOD HANDRAILS TO REMAIN. NEW CODE COMPLIANT HANDRAIL SECTIONS SHALL BE ADDED PER PLANS/DETAILS.

21 ENTRY STEPS, RAMP, & ALL CONCRETE TO REMAIN.

GENERAL DEMOLITION NOTES

1. WHERE EXISTING BLDG. COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXISTING FINISH, UNLESS NEW FINISHES ARE CALLED FOR IN THE FINISH SCHEDULE.
2. REMOVE EXISTING BLDG. COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
3. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
4. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. SHORING OF EXISTING STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
6. NOTIFY ARCHITECT IMMEDIATELY IF ASBESTOS IS SUSPECTED ON SITE. DO NOT DISTURB UNLESS DIRECTED.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE THE DEMOLITION BY DIFFERING TRADES.
8. CONTRACTOR COORDINATE SCHEDULE & LOCATION OF ANY OR ALL EXISTING RECEPTACLES, SWITCHES, DEVICES, ETC. PRIOR TO DEMOLITION, RELOCATE OR ABANDON ACCORDINGLY.
9. COORDINATE & REFERENCE MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS AND DETAILS
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.




Demolish. Ref. keynotes

A

PARTIAL SECOND FLOOR DEMOLITION PLAN

3/32"=1'-0"



EASTSIDE 2ND LEVEL SHOWN

JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

LANDMARK 601

601. W LEWIS

CONROE, TEXAS

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

REVISION:

DATE: 10-31-2025
JOB: 25-3385
SHEET NO.:

D2.4

COPYRIGHTED©

HISTORIC PRESERVATION NOTES

STRUCTURE, MASONRY AND EXTERIOR WALLS

1. WORK SHALL NOT DAMAGE ANY EXISTING MASONRY, ORNAMENT OR CHARACTER-DEFINING FEATURES. CONTRACTOR TO PROTECT DURING CONSTRUCTION.
2. MASONRY REHABILITATION SHALL CONSIST OF SPOT REPOINTING AND REPAIR/REPLACEMENT OF ISOLATED DETERIORATION. ALL WORK SHALL CONFORM TO PRESERVATION STANDARDS OUTLINED IN THE NATIONAL PARK SERVICE PRESERVATION BRIEFS 1,2 & 6. DETERIORATED MORTAR SHOULD BE REMOVED TO SOUND MORTAR. NEW MORTAR SHOULD MATCH EXISTING IN COLOR, TEXTURE, COMPOSITION, AND JOINT PROFILE. OLD MORTAR SHOULD BE ANALYZED, AS A HEAVILY CONCENTRATED PORTLAND CEMENT MORTAR CAN CAUSE BRICKS TO BREAK APART IF IT DOES NOT ALLOW FOR EXPANSION AND CONTRACTION.
3. NATIONAL PARK SERVICE BRIEF 2 SPECIFIES THE RECOMMENDED COMPOSITION OF MORTARS USED IN HISTORIC BUILDINGS.
4. IF ANY WALL SECTIONS MUST BE REBUILT, THE EXISTING STONE SHOULD BE SALVAGED FOR REUSE. IF EXISTING STONE IS DAMAGED BEYOND REPAIR, NEW MATERIAL MUST MATCH THE HISTORIC/EXISTING IN SIZE, COLOR, AND TEXTURE.
5. IF IT IS NECESSARY TO REMOVE PAINT, SOILING, OR BIO GROWTH FROM EXTERIOR STONE CLADDING, IT SHOULD BE ACCOMPLISHED USING THE GENTLEST MEANS POSSIBLE TO AVOID DAMAGING THE HISTORIC MASONRY. CONTACT AND REFER TO HISTORIC CONSULTANTS/SPECIALISTS FOR TREATMENT OPTIONS.
6. BRICK SHOULD NOT BE PAINTED.
7. CORDOVA LIMESTONE MUST REMAIN AND BE REPAIRED.
8. SMALL HOLES OR DAMAGE MAY BE REPAIRED WITH A PATCHING MORTAR. CONTACT HISTORICAL CONSULTANT FOR REFERENCE TYPES AND APPROVALS.
9. LIMESTONE SHOULD NOT BE PAINTED.
10. METAL DECORATIVE ELEMENTS MUST BE RETAINED, CLEANED, AND/OR REPLACED IN KIND IF DAMAGED.
11. METAL ELEMENTS SHOULD NOT BE PAINTED.

ENTRANCES

1. LIMESTONE MUST BE RETAINED IN ACCORDANCE WITH THE ABOVE GUIDANCE.
2. THE METAL CANOPIES SHOULD BE RETAINED AND REPAIRED WITH ANY MISSING OR DETERIORATED ELEMENTS REPLACED IN KIND. THEY SHOULD NOT BE PAINTED.
3. EXISTING DOORS MAY REMAIN OR NEW DOORS MAY REPLACE EXISTING WITHIN THE EXISTING OPENING. THESE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING. NEW DOORS MAY BE WOOD, CLAD WOOD, OR METAL BUT SHOULD HAVE THE THICKER RAILS AND STILES TYPICAL OF DOORS FROM THIS TIME PERIOD. GLASS IN NEW DOORS MAY BE INSULATED AND/OR LOW-E BUT MUST BE CLEAR, COLORLESS AND NON-REFLECTIVE WITH NO LESS THAN 69% VLT AND NO GREATER THAN 11% VLR.
4. TERRAZZO MUST REMAIN AND BE REPAIRED AS NEEDED. TERRAZZO CAN BE CLEANED PER THE GSA TECHNICAL REFERENCE ON CLEANING TERRAZZO. DO NOT SEAL, WAX, OIL OR COAT TERRAZZO IN ANY NEW MATERIAL. TERRAZZO WITH MINOR DAMAGE CAN BE PATCHED WITH A REPAIR KIT TO MATCH EXISTING.
5. EXISTING STAIRS SHOULD REMAIN AND BE REPAIRED AS NEEDED.
6. NEW RAILINGS CAN REPLACE EXISTING BUT MUST BE COMPATIBLE WITH MODERNE CHARACTER OF BUILDING & SIMPLE.

WINDOWS

1. EXISTING NON-HISTORIC REPLACEMENT WINDOWS MAY REMAIN.
2. IF NEW WINDOWS ARE PROPOSED, THEY SHOULD MATCH WINDOWS VISIBLE IN HISTORIC IMAGES. ORIGINAL WINDOWS APPEAR TO BE STEEL, 3 OVER 3, HUNG, WITH HORIZONTAL SASHES AND THICK MULLIONS.

ROOF

1. THE EXISTING ROOF MAY REMAIN OR BE REPLACED.
2. NEW ROOFTOP FEATURES OR AMENITIES (HVAC EQUIPMENT ETC.) SHOULD BE HELD TOWARDS THE CENTER OR REAR OF THE ROOF TO MINIMIZE VISIBILITY FROM THE STREET.

INTERIOR

1. THE CONFIGURATION OF PRIMARY DOUBLE LOADED CORRIDOR MUST REMAIN. CLASSROOM DOORS ARE TO REMAIN AND BE USED FOR NEW UNITS AS POSSIBLE. IF DOORS ARE NOT TO BE USED, THEY SHOULD REMAIN AND BE FIXED IN PLACE.
2. NEW PARTITIONS SHOULD NOT INTERSECT WITH OR RUN IN FRONT OF WINDOWS. ANY WALL JOGS MUST BE HELD AT LEAST 3' BACK FROM WINDOWS.
3. FURRED OUT WALLS WITH LOCKERS SHOULD REMAIN.
4. NEW FLOORING MAY REPLACE CARPET. CARPET, LVT, OR OTHER FINISHED MATERIAL IS SUFFICIENT. WOOD-LOOK LVT IS NOT ACCEPTABLE.
5. CURVED PLASTER CORNERS, PLASTER WALLS, AND WOOD BASE TRIM SHOULD REMAIN. ANY DAMAGED OR MISSING TRIM SHOULD BE REPLACED IN KIND. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
6. THE EXISTING DROPPED GRID CEILING MAY REMAIN. IF IT IS TO BE REPLACED, THE NEW CEILING SHOULD BE HIGHER, CLOSER TO THE HISTORIC HEIGHT. NEW CEILING SHOULD BE A HARD CEILING OR A SPINELESS DROPPED CEILING.
7. WHERE POSSIBLE, EXISTING BUILT-IN CABINETS AND CHALKBOARD FRAMES SHOULD REMAIN AND BE INCORPORATED INTO THE NEW UNIT DESIGN. MILLWORK SHOULD REMAIN, BE REPAIRED, OR REPLACED WHERE DETERIORATED.
8. BRICK WINDOW SILLS SHOULD REMAIN AND BE REPAIRED IN ACCORDANCE WITH MASONRY GUIDANCE ABOVE. BRICK SHOULD NOT BE PAINTED .
9. THE FIREPLACE AS NOTED ON PLANS, MUST REMAIN.
10. PLASTER WALLS SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21
11. EXISTING DOORS INTO CLASSROOMS AND TRANSOMS SHOULD REMAIN AND BE REPAIRED AS NEEDED. UNPAINTED DOORS SHOULD NOT BE PAINTED, BUT MAY BE REFINISHED.

AUDITORIUM

1. THE AUDITORIUM SHOULD REMAIN ITS OPEN VOLUME TO THE GREATEST EXTENT POSSIBLE.
2. THE AUDITORIUM'S HISTORIC FINISHES INCLUDING PLASTER WALLS AND CEILINGS, MILLWORK, TRIM, WOOD STAGE FLOORING, AND THE PROSCENIUM MUST REMAIN AND BE REPAIRED.
3. FLAT PLASTER SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21 AND DECORATIVE PLASTER IN ACCORDANCE WITH PRESERVATION BRIEF 23.
4. AUDITORIUM SEATING SHOULD BE RETAINED IN PLACE AND REPAIRED.
5. HISTORIC FLOORING IS LIKELY PRESENT BENEATH THE NON HISTORIC FINISHES IN AREAS NOTED WITH DEMOLITION NOTE 16. REMOVE NON-HISTORIC FINISHES IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC FLOORING BENEATH.
6. HISTORIC PLASTER CEILINGS & TRIM ARE LIKELY PRESENT ABOVE THE NON HISTORIC CEILINGS IN AREAS NOTED WITH DEMOLITION NOTE [A]. REMOVE NON-HISTORIC CEILINGS IN A FASHION APPROPRIATE FOR THE PROTECTION OF HISTORIC PLASTER ABOVE.
7. IF ANY HISTORIC FINISHES NOT PREVIOUSLY NOTED, CONTACT THE ARCHITECT.

BASEMENT

1. THE TERRAZZO MUST REMAIN AND BE REPAIRED.
2. THE CAFETERIA SHOULD REMAIN AS OPEN AS POSSIBLE.

VERTICAL CIRCULATION

1. STAIRS MUST REMAIN, AND IF POSSIBLE, REMAIN OPEN
2. CONCRETE SHOULD BE VISIBLE
3. TILE MUST REMAIN. DAMAGED OR MISSING TILE SHOULD BE REPLACED IN KIND.
4. PLASTER WALLS MUST REMAIN AND SHOULD BE REPAIRED IN ACCORDANCE WITH PRESERVATION BRIEF 21.
5. MILLWORK INCLUDING RAILINGS SHOULD REMAIN, AND ANY NEW RAILINGS SHOULD AUGMENT THE HISTORIC FEATURES INSTEAD OF REPLACE.

MECHANICAL, ELECTRICAL, PLUMBING

1. NEW HVAC SHALL BE CONCEALED THROUGHOUT BUILDING.
2. ROOFTOP EQUIPMENT SHALL NOT BE VISIBLE FROM GROUND.
3. SOFFITS AND DROPPED CEILINGS SHALL NOT DROP BELOW WINDOWS.
4. NEW PLUMBING SHALL NOT BE EXPOSED.
5. AUDITORIUM VENTS SHOULD BE REMAIN AND BE REUSED.
6. WHERE POSSIBLE ELECTRICAL SHOULD BE CONCEALED WITHIN WALLS AND CEILINGS. ANY SURFACE MOUNTED CONDUIT SHOULD BE LOCATED AS INCONSPICUOUSLY AS POSSIBLE.

LIGHTING

1. ANY SURFACE MOUNTED EXTERIOR FIXTURES SHOULD BE ANCHORED INTO THE MORTAR RATHER THAN THE MASONRY UNITS.
2. EXISTING INTERIOR AUDITORIUM LIGHTING SHOULD REMAIN AND BE REPAIRED WHERE POSSIBLE.

SIGNAGE

1. ETCHED SIGNAGE ABOVE FRONT ENTRY DOORS MUST REMAIN AND BE REPAIRED.
2. NEW SIGNAGE SHOULD BE COMPATIBLE WITH THE CHARACTER OF THE BUILDING.
3. INTERIOR SIGNAGE SHOULD BE RETAINED WHERE POSSIBLE.

GENERAL DEMOLITION NOTES

1. WHERE EXISTING BLDG. COMPONENTS ARE TO BE REMOVED; PATCH & REPAIR THE SURFACES TO MATCH EXISTING FINISH, UNLESS NEW FINISHES ARE CALLED FOR IN THE FINISH SCHEDULE.
2. REMOVE EXISTING BLDG. COMPONENTS AS INDICATED, IMPLIED OR AS REQUIRED SCHEMATICALLY SHOWN AS DASHED LINES. FIELD VERIFY ALL LOCATIONS.
3. THE ELECTRICAL & MECHANICAL CONTRACTORS SHALL BE RESPONSIBLE FOR ALL CORE DRILLING FOR PIPING & CONDUIT INSTALLATION.
4. ALL OTHER CUTTING, PATCHING & FINISHING, U.N.O. SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. SHORING OF EXISTING STRUCTURE SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
6. NOTIFY ARCHITECT IMMEDIATELY IF ASBESTOS IS SUSPECTED ON SITE. DO NOT DISTURB UNLESS DIRECTED.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE THE DEMOLITION BY DIFFERING TRADES.
8. CONTRACTOR COORDINATE SCHEDULE & LOCATION OF ANY OR ALL EXISTING RECEPTACLES, SWITCHES, DEVICES, ETC. PRIOR TO DEMOLITION, RELOCATE OR ABANDON ACCORDINGLY.
9. COORDINATE & REFERENCE MECHANICAL & ELECTRICAL DRAWINGS FOR ADDITIONAL DEMOLITION ITEMS AND DETAILS
10. REVIEW HISTORIC PRESERVATION NOTES ON A2.1 FOR BUILDING FEATURES THAT SHOULD BE PROTECTED AND SHALL NOT BE DEMOLISHED OR DAMAGED. NOTIFY ARCHITECT PRIOR TO WORK THAT MAY IMPACT THESE REFERENCED ITEMS.

SPECIFIC DEMOLITION NOTES

01 REMOVE EXISTING WALLS AS SHOWN SCHEMATICALLY BY DASHED LINES. PATCH AND REPAIR EXISTING CEILING, ADJACENT WALLS, AND FLOOR AS NEEDED. REPAIR AS INSTRUCTED BY THE HISTORIC MEMO IF REQUIRED.

02 HISTORIC DOOR & FRAME TO REMAIN AND SECURED CLOSED. REPAIR & REFINISH PER HISTORIC MEMO NOTES. REMOVE DOOR HARDWARE & COVER HOLES WITH APPROVED METHOD.

03 NON-HISTORIC DOOR: REMOVE EXISTING DOOR AND FRAME.

04 REMOVE & SALVAGE SECTIONS OF EXISTING WOOD BUILT INS. AS SHOWN. REF. HISTORIC PRESERVATION NOTES. REF. CABINETS PHOTO B/D2.1. **SEE NOTE

05 REMOVE & SALVAGE EXISTING CABINET. RE-INSTALL OR USE AT DIRECTION OF OWNER.

06 REMOVE EXISTING CABINET

07 REMOVE EXISTING PLUMBING FIXTURE(S). REFERENCE ALL PROPOSED MEP PLANS AND NOTES FOR PROPER DEMO AND NEW WORK PREP.

08 EXISTING WINDOWS TO REMAIN. PROTECT AND REPAIR WHERE NECESSARY.

09 SAWCUT & REMOVE PORTION OF MASONRY, PLASTER, BRICK WALL FOR NEW WINDOW. PREP FOR NEW WINDOW UNIT INSTALLATION

10 PROTECT HISTORIC LOCKERS DURING DEMOLITION PROCESS. LOCKERS WILL REMAIN & BE REFINISHED AS DIRECTED.

11 PROTECT HISTORIC FIREPLACE FEATURE DURING DEMOLITION PROCESS. WILL REMAIN.

12 REMOVE PORTION OF WALL & PREP FOR DOOR INSTALLATION

13 REMOVE ELECTRICAL PANEL. REFERENCE ELECTRICAL PLANS FOR OTHER DEMO AND PROPOSED INSTALLATION

14 PROTECT HISTORIC TRANSOM WINDOW OVER DOOR, TO REMAIN FIXED & SECURED CLOSED. REF. PHOTO C/D2.1

15 PROTECT HISTORIC FLOOR/WALL FINISH (AS SHOWN BY FINISH KEY A9.1) DURING DEMOLITION PROCESS

16 REMOVE NON HISTORIC FINISH: CARPET


17 REMOVE NON HISTORIC FINISH: VT TILE/BATHROOM TILE


18 EXISTING TERRAZZO TO BE PROTECTED DURING CONSTRUCTION. AT TERRAZZO SAWCUT/GRIND ANY RAISED AREAS AT REMOVED WALLS. PROTECT, CLEAN, PATCH AND REPAIR AS NEEDED.

19 EXISTING AUDITORIUM SEATING TO REMAIN. PROTECT AND REPAIR.

20 EXISTING WOOD HANDRAILS TO REMAIN. NEW CODE COMPLIANT HANDRAIL SECTIONS SHALL BE ADDED PER PLANS/DETAILS.

21 ENTRY STEPS, RAMP, & ALL CONCRETE TO REMAIN.





-------- Demolish. Ref. keynotes

A **BASEMENT DEMOLITION PLAN**
1/8"=1'-0"

JonesGillamRenz
730 N. Ninth 1881 Main Street, Suite 301
Salina, KS 67401 Kansas City, MO 64108
785.827.0386 jgr@jgrarchitects.com

LANDMARK 601
601. W LEWIS
CONROE, TEXAS

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

REVISION:

DATE: 10-31-2025
JOB: 25-3385
SHEET NO.:

D2.5

COPYRIGHTED ©

Attachment 3: Licenses / Certifications

Texas Department of State Health Services

BE IT KNOWN THAT

PHASE ENGINEERING LLC

is certified to perform as a

Lead Firm

in the State of Texas and is hereby governed by the rights, privileges and responsibilities set forth in Texas Occupations Code, Chapter 1955 and Title 25, Texas Administrative Code, Chapter 295 relating to Texas Environmental Lead Reduction, as long as this license is not suspended or revoked.

Certification Number: 2110073

Expiration Date: 01/27/2026

Jennifer Shuford, MD, MPH, Commissioner of Health

Control Number: 7525

(Void After Expiration Date)

VOID IF ALTERED NON-TRANSFERABLE

SEE BACK

Texas Department of State Health Services

BE IT KNOWN THAT

THOMAS A BAZAN

is certified to perform as a

Lead Risk Assessor

in the State of Texas and is hereby governed by the rights, privileges and responsibilities set forth in Texas Occupations Code, Chapter 1955 and Title 25, Texas Administrative Code, Chapter 295 relating to Texas Environmental Lead Reduction, as long as this license is not suspended or revoked.

Certification Number: 2070001

Expiration Date: 08/05/2027

Jennifer Shuford, MD

Jennifer Shuford, MD, MPH, Commissioner of Health

Control Number: 8383

(Void After Expiration Date)

VOID IF ALTERED NON-TRANSFERABLE

SEE BACK

AEHS, INC.

DSHS Lead Training Provider Certification # 20439

CERTIFIES THAT

THOMAS BAZAN

has successfully completed

Lead Inspector Refresher

IN ACCORDANCE WITH ALL REQUIREMENTS OF TEXAS ENVIRONMENTAL LEAD REDUCTION RULES

Certification Number	0625-5377F
Course Completion Date	18 June 2025

Marcie Sinclair

Marcie Sinclair, MS, REM
Training Manager

AEHS, Inc.
4402 Centergate St.
San Antonio, TX 78217
(210) 656-9300
www.aehs-sa.com

Kelly N Brown

Kelly Brown, IAC
Instructor

AEHS, INC.

DSHS Lead Training Provider Certification # 20439

CERTIFIES THAT

THOMAS BAZAN

has successfully completed

Lead Risk Assessor Refresher

IN ACCORDANCE WITH ALL REQUIREMENTS OF TEXAS ENVIRONMENTAL LEAD REDUCTION RULES

Certification Number	0625-5378C
Course Completion Date	19 June 2025

Marcie Sinclair

Marcie Sinclair, MS, REM
Training Manager

AEHS, Inc.
4402 Centergate St.
San Antonio, TX 78217
(210) 656-9300
www.aehs-sa.com

Kelly N Brown

Kelly Brown, IAC
Instructor

Texas Department of State Health Services

BE IT KNOWN THAT

THOMAS A BAZAN

is certified to perform as a

Lead Abatement Supervisor

in the State of Texas and is hereby governed by the rights, privileges and responsibilities set forth in Texas Occupations Code, Chapter 1955 and Title 25, Texas Administrative Code, Chapter 295 relating to Texas Environmental Lead Reduction, as long as this license is not suspended or revoked.

Certification Number: 2080131

Expiration Date: 12/07/2025

Jennifer Shuford, MD, MPH, Commissioner of Health

Control Number: 6835

(Void After Expiration Date)

VOID IF ALTERED NON-TRANSFERABLE

SEE BACK

AEHS, INC.

DSHS Lead Training Provider Certification # 20439

CERTIFIES THAT

THOMAS BAZAN

has successfully completed

Lead Supervisor Refresher

IN ACCORDANCE WITH ALL REQUIREMENTS OF TEXAS ENVIRONMENTAL LEAD REDUCTION RULES

Certification Number	0625-5379D
Course Completion Date	20 June 2025

Marcie Sinclair

Marcie Sinclair, MS, REM
Training Manager

AEHS, Inc.
4402 Centergate St.
San Antonio, TX 78217
(210) 656-9300
www.aehs-sa.com

Kelly N Brown

Kelly Brown, IAC
Instructor

CONGRATULATIONS

Thomas Bazan

has successfully completed the U.S. Department

of Housing and Urban Development,

Office of Healthy Homes and Lead Hazard Control's

VISUAL ASSESSMENT COURSE

pursuant to 24 Code of Federal Regulations Part 35

Jonnette G. Hawkins
Director, Program Management and Assurance Division
Office of Healthy Homes and Lead Hazard Control

U.S. Department of Housing and Urban Development

Environmental Assessment Association

ENVIRONMENTAL ASSESSMENT ASSOCIATION SEAL 1991

EAA
ENVIRONMENTAL
Assessment Association

hereby certifies that

LOYAL MEMBER 20+ YEARS

LOYAL MEMBER 10+ YEARS

Thomas A. Bazan

has been qualified for membership in the

ENVIRONMENTAL ASSESSMENT ASSOCIATION

and has been admitted by its Board of Directors and declared to be a

Certified Remediation Specialist
Certified Environmental Inspector

and is hereby granted this certificate under the conditions presented in its by-laws.

Brent Felstead

Executive Director

Member Since: September 1, 1991 ***ID # 7210***

Expiration Date: February 28, 2025

Certificate of Training

Thomas Bazan

Has completed the Viken Detection Corporation training materials presented on the topic of Instrument Operator Training, Pb200i, with regards to the materials licensed by the Commonwealth of Massachusetts and the Nuclear Regulatory Commission.

Instrument Operator Training
Viken Detection Corporation, Pb200i

I confirm that the above named individual has received the training listed on this certificate.

Deblyn Palella — April 1st 2020

Name — Date

XRF Sales, Rentals, Training and Consulting

Title



I certify that I have received the stated training and understand the content presented. I understand that I can follow up this training with questions from Viken Detection Corporation.

_____ — April 1, 2020

Name — Date

Certificate of Training

Thomas Bazan

Has completed the Heuresis Corporation training materials presented on the topic of Instrument Operator Training, Pb200i, with regards to the materials licensed by the Commonwealth of Massachusetts and the Nuclear Regulatory

Instrument Operator Training
Heuresis Corporation, Pb200i

I confirm that the above named individual has received the training listed on this certificate.

Raymond Lindee — 01/18/2016

Name — Date

Regional Representative for Heuresis

Title

I certify that I have received the stated training and understand the content presented. I understand that I can follow up this training with questions from Heuresis Corporation.

01/18/2016

Name — Date

Caution:
radioactive material

Co-57	SN:X5-468
Activity:	5 mCi
Reference Date:	12/25/24
Model Pb200e:	SN:1013

Viken Detection Burlington, MA
+1-617-467-5526

12/16/2024 10:05

Send all kits and requests to:

SUNTRAC Services, Inc.
1818 East Main Street
League City, TX 77573
(281) 338-2133

ATTN: SIT-KIT

CAUTION: Conduct a survey on the outside of each package placed in the U.S. Mails. Any reading over 0.5 mR/hr at contact with the envelope or package shall not be mailed.

LEAK TEST INVENTORY/REPORT FORM

Company Name: Thomas A. Bazan (14539)

Address: 14722 Wind Cave Lane City: Houston State: TX Zip Code: 77040

Isotope: Co 57 Activity: 5 mCi

Source Serial No: X5-468

Device Serial No: 1013

Manufacturer: Eckert & Ziegler Model No.: Pb200i/e

Smear Taken By: T. Bazan Leak Test Date: 10/07/25

--- --- --- --- --- --- --- --- --- --- DO NOT WRITE BELOW THIS LINE --- --- --- --- --- --- --- --- --- ---

This is to certify that the above described smear/swab has been assayed at our facilities for indication of source leakage.

Our findings show the leakage to be:

ALPHA	BETA-GAMMA
-----	<.0001

µCi (Wet)

Presley Solliday

Certified By: _____ Date: 10/08/25

Presley Solliday

Register Number: 2377625

Texas Radioactive License No. L03062

Send all kits and requests to:

SUNTRAC Services, Inc.
1818 East Main Street
League City, TX 77573
(281) 338-2133

ATTN: SIT-KIT

CAUTION: Conduct a survey on the outside of each package placed in the U.S. Mails. Any reading over 0.5 mR/hr at contact with the envelope or package shall not be mailed.

LEAK TEST INVENTORY/REPORT FORM

Company Name: Thomas A. Bazan (14539)

Address: 14722 Wind Cave Lane City: Houston State: TX Zip Code: 77040

Isotope: Co 57 Activity: 5 mCi

Source Serial No: X5-468

Device Serial No: 1013

Manufacturer: Eckert & Ziegler Model No.: Pb200i/e

Smear Taken By: T. Bazan Leak Test Date: 04/18/25

--- --- --- --- --- --- --- --- --- --- **DO NOT WRITE BELOW THIS LINE** --- --- --- --- --- --- --- --- --- ---

This is to certify that the above described smear/swab has been assayed at our facilities for indication of source leakage.

Our findings show the leakage to be:

ALPHA	BETA-GAMMA
-----	<.0001

µCi (Wet)

Certified By: _____ Date: 04/25/25

SUNTRAC Services, Inc. Representative
(Texas Radioactive License No. L03062)

2262025

VSSA

Valley Safety Services Associates, Inc.

330 Old Enfield Road, Belchertown, MA 01007
http://www.vssa-inc.com
Tel/Fax: (413)323-9571

Leak Test Data/Certificate

Complete the data requested on the top part of this form and return it with your leak test to the address in the above heading. Following our analysis of your leak test specimen we will return this form to you for your record of the test and results.

Source/Device Description

Device: Source **Model:** Pb200i/e **Serial #:** 1013 **Manufacturer:** Viken

Radioisotope Co - 57 **Activity (mCi)** 6 mci

Source model: A3901 - 2 **Source # :** X5-468 **Manufacturer:** Eckert & Ziegler

The leak testing of this source/device was performed as indicated in manufacturer recommendations or LT-952 kit instructions using kit # 888317

By: Seth Martin Date: 10/15/24

Company: Viken Detection Corporation Telephone: 617-467-5526

Address: 21 North Avenue Email:
Burlington, MA 01803

Do Not Write Below This Line

Leak Test Analysis Result

Analysis of the above test on 16 Oct 24 yielded the following;

☒ Statistical analysis of the radioactive count data of this leak test specimen indicated any activity present is less than 0.005 μCi. The source may be used as authorized.

☐ Statistical analysis of the radioactive count data of this leak test specimen indicated there is greater than 0.005 microcuries of activity present. This source should be considered leaking. Consult your device operations manual; place this unit in storage and make the required notification to your regulatory agency.

REMINDER: YOUR NEXT REQUIRED LEAK TEST FOR THIS DEVICE/SOURCE IS DUE ON OR BEFORE (Exemptions*)

16 Oct 25 N/A

***Model Pb200i is approved under SSDR# MA-1397-D-101-B for a leak testing frequency not to exceed 12months. Model Pb200e does not require leak tesing by end users (SSDR# NR-1397-D-102-E). (Please ensure to check for the requirements of your state.)**

THIS CERTIFICATE IS AN ESSENTIAL RECORD AND SHOULD BE MAINTAINED FOR INSPECTION BY THE REGULATORY AGENCY.

CERTIFICATE #: 888317 **BY:** S R **DATE :** 16 Oct 24

VIKEN
DETECTION

Conversion to PB200e


This document confirms that the unit listed below has been converted to the PB200e. All appropriate labels have been applied.

Date: 12-13-2024

Customer: Thomas Bazan

Serial number: 1013

Signature of Authorized Service Representative:



Revision A 5/1/2023

21 North Avenue Burlington, MA 01803 / 617.467.5526 / vikendetection.com

VIKEN
DETECTION
One Sense Ahead

Service Report for Ticket #:
00016383
Date: December 13, 2024

21 North Ave
Burlington, MA 01803

Prepared For: Thomas Bazan

Account: Thomas Andrew Bazan
Billing Address: 14772 Wind Cave Lane
Houston, Texas 77040
United States

Service Representative: Juliann Lipski
Phone: 617-467-5526
Email: jlipski@vikendetection.com

Phone: +1 617-467-5526
Fax: +1 617-467-5024
Email: technicalservice@vikendetection.com

Service Ticket Number	00016383

Service Ticket Info			
Date Issue Reported	December 05, 2024	Covered Under Warranty	No
Description of Issue	Customer would like unit resourced and converted to the PB200e.		

Date Received In	December 05, 2024	Software Version After Repair	5.3.1

Root Cause	

Corrective Action	Resourced Co57 source. Also replaced several parts as part of the resourcing upgrade. Updated software. Unit was put through a calibration validation process and all tests passed. Unit has been converted to a PB200e.

Affected Asset			
Asset Name	Product Code	Product Name	Serial Number
12-100327	12-100327	Pb200e - Lead Paint Analyzer with Accessory Kit	1013

RMA Items				
Part Number	Asset Name	Serial Number	Shipment Status	Asset Quantity
5-000039	Co-57 Source / 5mCi	V6-215	Removed	1
5-002047	Co-57 Source / 6mCi	X5-468	Installed	1

Required Materials and Services				
Product Code	Description	QTY	Unit Price	Extended
10-000003	Domestic 2 Day Shipping	1	$100.00	$100.00
8-100421	Pb200i/e Service - Type i-to-e Conversion	1	$350.00	$0.00
8-100482	Standard Resourcing Service, Pb200	1	$3,950.00	$3,950.00

Products and Services Subtotal	**$4,300.00**
Shipping and Handling Subtotal	**$100.00**
Warranty Subtotal	**$0.00**
Total Discount	**$350.00**
Total Price	**$4,050.00**

Performance Characteristic Sheet

EFFECTIVE DATE: **September 1, 2022**

MANUFACTURER AND MODEL:

Make: ***Heuresis***
Models: ***Model Pb200i, Pb200e***
Source: ***^{57}Co, 5 mCi (nominal – new source)***

FIELD OPERATION GUIDANCE

OPERATING PARAMETERS:

Action Level 1.0 mg/cm^2

XRF CALIBRATION CHECK LIMITS:

0.8 to 1.2 mg/cm^2 (inclusive)

SUBSTRATE CORRECTION:

Not applicable

INCONCLUSIVE RANGE OR THRESHOLD:

ACTION LEVEL MODE READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm^2)
Results not corrected for substrate bias on any substrate	Brick Concrete Drywall Metal Plaster Wood	1.0 1.0 1.0 1.0 1.0 1.0

BACKGROUND INFORMATION

EVALUATION DATA SOURCE AND DATE:

This sheet is supplemental information to be used in conjunction with Chapter 7 of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing* ("HUD Guidelines"). Performance parameters shown on this sheet are calculated using test results on building components in the HUD archive. Testing was conducted on 146 test samples in November 2015, with two separate instruments running software version 2.1-2 in Action Level test mode. The actual source strength of each instrument on the day of testing was approximately 2.0 mCi; source ages were approximately one year.

OPERATING PARAMETERS

Performance parameters shown in this sheet are applicable only when properly operating the instrument using the manufacturer's instructions and procedures described in Chapter 7 of the HUD Guidelines.

XRF CALIBRATION CHECK:

The calibration of the XRF instrument should be checked using the paint film nearest 1.0 mg/cm^2 in the NIST Standard Reference Material (SRM) used (e.g., for NIST SRM 2579, use the 1.02 mg/cm^2 film).

If the average (rounded to 1 decimal place) of three readings is outside the acceptable calibration check range, follow the manufacturer's instructions to bring the instrument into control before XRF testing proceeds.

SUBSTRATE CORRECTION VALUE COMPUTATION:

Chapter 7 of the HUD Guidelines provides guidance on correcting XRF results for substrate bias. Supplemental guidance for using the paint film nearest 1.0 mg/cm^2 for substrate correction is provided:

XRF results are corrected for substrate bias by subtracting from each XRF result a correction value determined separately in each house for single-family housing or in each development for multifamily housing, for each substrate. The correction value is an average of XRF readings taken over the NIST SRM paint film nearest to 1.0 mg/cm^2 at test locations that have been scraped bare of their paint covering. Compute the correction values as follows:

> Using the same XRF instrument, take three readings on a bare substrate area covered with the NIST SRM paint film nearest 1 mg/cm^2. Repeat this procedure by taking three more readings on a second bare substrate area of the same substrate covered with the NIST SRM.
>
> Compute the correction value for each substrate type where XRF readings indicate substrate correction is needed by computing the average of all six readings as shown below.
>
> <u>For each substrate type</u> (the 1.02 mg/cm^2 NIST SRM is shown in this example; use the actual lead loading of the NIST SRM used for substrate correction):
>
> Correction value = (1st + 2nd + 3rd + 4th + 5th + 6th *Reading*)/6 - 1.02 mg/cm^2
>
> Repeat this procedure for each substrate requiring substrate correction in the house or housing development.

EVALUATING THE QUALITY OF XRF TESTING:

Randomly select ten testing combinations for retesting from each house or from two randomly selected units in multifamily housing.

Conduct XRF re-testing at the ten testing combinations selected for retesting.

Determine if the XRF testing in the units or house passed or failed the test by applying the steps below. Compute the Retest Tolerance Limit by the following steps:

Determine XRF results for the original and retest XRF readings. Do not correct the original or retest results for substrate bias. In single-family and multi-family housing, a result is defined as a single reading. Therefore, there will be ten original and ten retest XRF results for each house or for the two selected units.

Calculate the average of the original XRF result and the retest XRF result for each testing combination.

Square the average for each testing combination.

Add the ten squared averages together. Call this quantity C.

Multiply the number C by 0.0072. Call this quantity D.

Add the number 0.032 to D. Call this quantity E.

Take the square root of E. Call this quantity F.

Multiply F by 1.645. The result is the Retest Tolerance Limit.

Compute the average of all ten original XRF readings.

Compute the average of all ten re-test XRF readings.

Find the absolute difference of the two averages.

If the difference is less than the Retest Tolerance Limit, the inspection has passed the retest. If the difference of the overall averages equals or exceeds the Retest Tolerance Limit, this procedure should be repeated with ten new testing combinations. If the difference of the overall averages is equal to or greater than the Retest Tolerance Limit a second time, then the inspection should be considered deficient.

Use of this procedure is estimated to produce a spurious result approximately 1% of the time. That is, results of this procedure will call for further examination when no examination is warranted in approximately 1 out of 100 dwelling units tested.

TESTING TIMES:

In the Action Level paint test mode, the instrument takes the longest time to complete readings close to the Federal standard of 1.0 mg/cm^2. The table below shows the mean and standard deviation of actual reading times by reading level for paint samples during the November 2015 archive testing. The tested instruments reported readings to one decimal place. No significant differences in reading times by substrate were observed. These times apply only to instruments with the same source strength as those tested (2.0 mCi). Instruments with stronger sources will have shorter reading times and those with weaker sources, longer reading times, than those in the table.

Mean and Standard Deviation of Reading Times in Action Level Mode by Reading Level		
Reading (mg/cm^2)	**Mean Reading Time (seconds)**	**Standard Deviation (seconds)**
< 0.7	3.48	0.47
0.7	7.29	1.92
0.8	13.95	1.78
0.9 – 1.2	15.25	0.66
1.3 – 1.4	6.08	2.50
$\geq$ 1.5	3.32	0.05

CLASSIFICATION OF RESULTS:

XRF results are classified as **positive** if they are **greater than or equal** to the stated threshold for the instrument (1.0 mg/cm^2), and *negative* if they are *less than* the threshold.

DOCUMENTATION:

A report titled *Methodology for XRF Performance Characteristic Sheets* (EPA 747-R-95-008) provides an explanation of the statistical methodology used to construct the data in the sheets, and provides empirical results from using the recommended inconclusive ranges or thresholds for specific XRF instruments. The report may be downloaded at http://www2.epa.gov/lead/methodology-xrf-performance-characteristic-sheets-epa-747-r-95-008-september-1997.

This XRF Performance Characteristic Sheet (PCS) was developed by QuanTech, Inc., under a contract with the XRF manufacturer.

A Nonparametric Method for Estimating the 5th and 95th Percentile Curves of Variable-Time XRF Readings Based on Monotone Regression

Prepared for the
HUD Office of Healthy Homes and Lead Hazard Control
by
QuanTech, Inc.

October 24, 2000

For some newer XRF instruments, readings are typically taken in a “variable-time” mode where the reading time depends on the lead level in the paint. As detailed in Appendix B of *Methodology for XRF Performance Characteristic Sheets*(EPA 747-R-95-008, September 1997), it is not appropriate to apply the parametric XRF measurement model to such readings.

Since the underlying distribution is unknown and suspected to be nonnormal, a nonparametric method, based on monotone regression, was developed to obtain estimates of the 5th and 95th percentile XRF readings, as functions of the true lead level. This method applies the assumption that the percentiles are increasing functions of the lead level. Monotone regression is the solution to a quadratic programming problem, and is obtained with the "pool adjacent violators" (PAV) algorithm. The solution takes the form of a step function, formed by percentiles of the data over subgroups in a way that the percentiles do not decrease. Although a monotone regression cannot be "smooth" in appearance, it will approximate the true response if the sample is large, and if the true response is itself a nondecreasing function. A full treatment of monotone regression can be found in *Statistical Inference Under Order Restrictions* (Barlow, Bartholomew, Bremner, and Brunk, Wiley 1972). The nonparametric 5th and 95th percentile curves are applied to determine the threshold/inconclusive range for the PCS for an instrument with variable-time readings. Because the method is nonparametric, there is typically insufficient data to develop thresholds/inconclusive ranges separately by substrate.

November 21, 2025

Caroline Hurst
Overland Property Group
254 North Santa Fe Ave, Suite A
Salina, Kansas 67401

Re: Noise Assessment; **Landmark 601**, **601 West Lewis Street, Conroe, Montgomery County, Texas 77301; PE 202511026**

Dear Ms. Hurst:

Phase Engineering, LLC has completed a Noise Assessment for the proposed Landmark 601 multifamily development to be located at 601 West Lewis Street, Conroe, Texas 77301. The Noise Assessment Guidelines provided by the US Department of Housing and Urban Development (HUD) were used to complete this report.

Noise Assessment

According to HUD, all properties considered for federal funding must be assessed for excessive noise levels. HUD's Noise Assessment Guidelines define noise generating features as: all major civil or military airports within 15 miles, major roadways within 1,000 feet, and railroads within 3,000 feet of the subject property. If any of these features are identified within the minimum search distance, the proposed project must be evaluated for excessive noise exposure.

Four major roads were identified near the subject property, W. Lewis Street, S. Frazier Street, W. Phillips Street and W. Davis Street. TXDOT's traffic data treats W. Phillips Street and W. Davis Street as a single thoroughfare due to these roads having unidirectional travel. Therefore, the AADTs are combined and distance to each NAL was measured to the mid-way point between the lanes of travel. No other roadways within 1,000 feet of the property meet the minimum annual/daily traffic count of 8,000 vehicles; thus, they are not considered 'major'. Two railroads are located within 3,000 feet of the subject property, a Union Pacific line to the easy and a BNSF line to the south. No major civil airports or military airfields are located within 15-miles of the subject property. All airports within this range are considered minor with less than 9,000 annual enplanements. Therefore, impacts from aircraft were not included in the assessment.

Noise Assessment Locations (NALs) were selected on the property based on closest proximity of noise sensitive areas to each noise generating feature. The combined Day/Night Noise Level (DNL) for each NAL was calculated based on the effective distance from each of the noise sources and provided in the below table. A 10-year projected DNL is provided based on a 2% annual growth in traffic counts.

Noise Assessment Location (NAL)	Combined Projected DNL (dB)
NAL 1 - NW Corner of Main Building	66
NAL 2 - SW Corner of Main Building	66

Noise Assessment Location (NAL)	Combined Projected DNL (dB)
NAL 3 - NE Corner of Main Building	64
NAL 4 - SE Corner of Proposed Building	64
NAL 5 - Dog Park	65

Two of the calculated noise values for the selected NALs fall within the range of 65 – 75 dB, which is considered “Normally Unacceptable” based on the HUD guidelines. Indoor residential areas should meet HUD’s goal of 45 dB or less, based on the assumption that standard construction materials will provide a minimum of 20 dBA of noise reduction from outdoor noise environments. When the outdoor noise environment is within the normally unacceptable range, special building construction may be necessary to meet the indoor noise goal.

In order to confirm the proposed building materials will provide sufficient noise attenuation, the project architect will need to perform an analysis using HUD’s Sound Transmission Classification Assessment Tool (STraCAT). The STraCAT tool needs to confirm a minimum of 21 dB of attenuation will occur, sufficient to ensure an interior noise environment of at least 45 dB.

The Noise Assessment confirmed the dog park area falls within HUD’s *Acceptable* noise range and therefore is in compliance with noise requirements.

If you should have any questions or comments concerning this letter, please call 832-485-2227 or email Tracy@phaseengineering.com. We appreciate you using Phase Engineering, LLC professional environmental services and look forward to serving you again in the near future.

Prepared by:




Ryan Starr
Special Projects Manager

Phase Engineering, LLC

APPENDIX I

Noise Documentation



Note: Property location and boundary are representative only.


Copyright ©2023 Phase Engineering, LLC

Noise Sources Map

Subject Property **1000 foot radius** **3000 foot radius**

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

PE Project No: 202511026



Sources: Federal Aviation Administration, Department of Defense, National Transportation Atlas, TxDOT, ESRI, HERE, (c) OpenStreetMap contributors, and the GIS user community

Property boundary and locations are representative only.

0 1.25 2.5 5 7.5 10 Miles

1:300,000

Copyright © 2025 Phase Engineering, LLC

Airport Noise Map

- Subject Property
- 15 Mile Radius

- Airport Boundary
- Runway
- Spaceport
- Airport
- Ballonport
- Gliderport
- Heliport
- Seaplane Base
- Ultralight Field

2023-2027 NPIAS Airports


- Major Airport - This category includes all civil airports with a minimum of 9,000 emplanements annually
- Minor Airport - Includes all nonprimary public airports which are not considered as a major noise source

Military Installations, Ranges and Training Areas

- Air Force Active
- Air Force Reserve
- Air National Guard
- Army Active
- Army Reserve
- Army National Guard
- Marine Corps Active
- Marine Corps Reserve
- Navy Active
- Other Federal Administration

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

PE Project No: 202511026



Note: Property location and boundary are representative only.

0 130 260 520 Feet

Copyright © 2025 Phase Engineering, LLC


NORTH

Noise Assessment Location (NAL) Map - Roads

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

- Subject Property
- NAL
- Noise Sources

PE Project No: 202511026



Note: Property location and boundary are representative only.

0 260 520 1,040 Feet

Copyright © 2025 Phase Engineering, LLC

NORTH

Noise Assessment Location (NAL) Map - Railways

PHASE
TRUSTED ENVIRONMENTAL SOLUTIONS

Subject Property
NAL
Noise Sources

PE Project No: 202511026

Landmark 601: Noise Calculation Data

			Projected 2% Annual Growth										10-Year
Road		Percent	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
W. Lewis Street	Gross Total ADT		1923	1961	2001	2041	2082	2123	2166	2209	2253	2298	2344
30 mph	Total Cars	96.5%	1856	1893	1931	1969	2009	2049	2090	2132	2174	2218	2262
Truck Traffic[1] =	Total Medium Trucks	ALL TRUCK TRAFFIC IS CONSIDERED "HEAVY"											
3.5%	Total Heavy Trucks	3.5%	67	69	70	71	73	74	76	77	79	80	82

			Projected 2% Annual Growth										10-Year
Road		Percent	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
S. Frazier Street	Gross Total ADT		13188	13452	13721	13995	14275	14561	14852	15149	15452	15761	16076
55 mph	Total Cars	93.5%	12331	12577	12829	13086	13347	13614	13886	14164	14447	14736	15031
Truck Traffic[1] =	Total Medium Trucks	ALL TRUCK TRAFFIC IS CONSIDERED "HEAVY"											
6.5%	Total Heavy Trucks	6.5%	857	874	892	910	928	946	965	985	1004	1024	1045

			Projected 2% Annual Growth										10-Year
Road		Percent	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035
W. Phillips St & W. Davis St	Gross Total ADT		28187	28751	29326	29912	30511	31121	31743	32378	33026	33686	34360
30 mph	Total Cars	95.3%	26862	27399	27947	28506	29077	29658	30251	30856	31473	32103	32745
Truck Traffic[1] =	Total Medium Trucks	ALL TRUCK TRAFFIC IS CONSIDERED "HEAVY"											
4.7%	Total Heavy Trucks	4.7%	1325	1351	1378	1406	1434	1463	1492	1522	1552	1583	1615

Railroad	Train ATO	% Night Traffic	Typical Speed Over Crossing	Within 1/4 Mile of At-Grade Crossing?	Bolted Tracks?							
Union Pacific	7	43%	30	yes	yes							
BNSF	5	40%	49	yes	yes							

Airport		Distance	Outside Noise Countours									
None												

Noise Assement Locations (NAL)

	NAL 1 - NW Corner of Main Building		NAL 2 - SW Corner of Main Building		NAL 3 - NE Corner of Main Building		NAL 4 - SE Corner of Proposed Bldg		NAL 5 - Dog Park	
Noise Sources	Effective Distance (feet)	DNL	Distance	10-year DNL	Distance	DNL	Distance	DNL	Distance	DNL
W. Lewis Street	120	58	225	54	125	58	450	50	310	52
S. Frazier Street	325	64	290	65	705	59	650	60	465	62
W. Phillips St & W. Davis St	1,060	57	955	58	1,030	57	710	60	855	58
Union Pacific	1,895	56	1,900	56	1,490	58	1,450	58	1,685	57
BNSF	2,785	50	2,690	51	2,590	51	2,280	52	2,515	51
NAL Combined DNL:		**66**		**66**		**64**		**64**		**65**

ADT = Average Daily Traffic Count
DNL = Day/Night Noise Level
1 = Percent of Truck Traffic is obtained from the TxDOT Statewide Planning Map

Criteria
Acceptable: 65 or less
Normally Not Acceptable: 66-75
Not Acceptable: greater than 75

Day/Night Noise Level (DNL) Calculator

The Day/Night Noise Level Calculator is an electronic assessment tool that calculates the Day/Night Noise Level (DNL) from roadway and railway traffic. For more information on using the DNL calculator, view the **Day/Night Noise Level Calculator Electronic Assessment Tool Overview (/programs/environmental-review/daynight-noise-level-electronic-assessment-tool/)**.

Guidelines

- To display the Road and/or Rail DNL calculator(s), click on the "Add Road Source" and/or "Add Rail Source" button(s) below.
- All Road and Rail input values must be positive non-decimal numbers.
- All Road and/or Rail DNL value(s) must be calculated separately before calculating the Site DNL.
- All checkboxes that apply must be checked for vehicles and trains in the tables' headers.
- **Note #1:** Tooltips, containing field specific information, have been added in this tool and may be accessed by hovering over all the respective data fields (site identification, roadway and railway assessment, DNL calculation results, roadway and railway input variables) with the mouse.
- **Note #2:** DNL Calculator assumes roadway data is always entered.

DNL Calculator

Site ID	Landmark 601 - NAL 1: NW Corner of Main Building
Record Date	11/20/2025
User's Name	Phase Engineering RS

Road # 1 Name:	**W. Lewis Street**

Road #1

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	120		120
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	2262		82
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	50	0	58
Calculate Road #1 DNL	58	Reset	

Road # 2 Name:	**S. Frazier Street**

Road #2

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	325		325
Distance to Stop Sign			
Average Speed	55		55

Average Daily Trips (ADT)	15031		1045
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	57	0	63
Calculate Road #2 DNL	64	Reset	

Road # 3 Name: **W. Phillips St & W. Davis St**

Road #3

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	1060		1060
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	32745		1615
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	48	0	56
Calculate Road #3 DNL	57	Reset	

Railroad #1 Track Identifier: **Union Pacific**

Rail # 1

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		1895
Average Train Speed		30
Engines per Train		2

Railway cars per Train		50
Average Train Operations (ATO)		7
Night Fraction of ATO		43
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	56
Calculate Rail #1 DNL	56	Reset

Railroad #2 Track Identifier:	**BNSF**

Rail # 2

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		2785
Average Train Speed		49
Engines per Train		2
Railway cars per Train		50
Average Train Operations (ATO)		5
Night Fraction of ATO		40
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	50
Calculate Rail #2 DNL	50	Reset

Add Road Source | Add Rail Source

Airport Noise Level	

Loud Impulse Sounds?	○ **Yes** ◉ **No**
Combined DNL for all Road and Rail sources	**66**
Combined DNL including Airport	**N/A**
Site DNL with Loud Impulse Sound	

Calculate Reset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:

- **No Action Alternative**: Cancel the project at this location
- **Other Reasonable Alternatives**: Choose an alternate site
- **Mitigation**
  - **Contact your Field or Regional Environmental Officer (/programs/environmental-review/hud-environmental-staff-contacts/)**
  - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
  - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
  - Incorporate natural or man-made barriers.
  - Construct noise barrier. See the **Barrier Performance Module (/programs/environmental-review/bpm-calculator/)**

Tools and Guidance

Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)

Federal Railroad Administration Railroad Operations Data Sources (https://www.hudexchange.info/resource/6027/federal-railroad-administration-railroad-operations-data-sources/)

Site ID	Landmark 601 - NAL 2: SW Corner of Main Building
Record Date	11/20/2025
User's Name	Phase Engineering RS

Road # 1 Name:	**W. Lewis Street**

Road #1

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	225		225
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	2262		82
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	46	0	54
Calculate Road #1 DNL	54	Reset	

Road # 2 Name:	**S. Frazier Street**

Road #2

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	290		290
Distance to Stop Sign			
Average Speed	55		55

Average Daily Trips (ADT)	15031		1045
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	58	0	64
Calculate Road #2 DNL	65	Reset	

Road # 3 Name: **W. Phillips St & W. Davis St**

Road #3

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	955		955
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	32745		1615
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	48	0	57
Calculate Road #3 DNL	58	Reset	

Railroad #1 Track Identifier: **Union Pacific**

Rail # 1

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		1900
Average Train Speed		30
Engines per Train		2

Railway cars per Train		50
Average Train Operations (ATO)		7
Night Fraction of ATO		43
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	56
Calculate Rail #1 DNL	56	Reset

Railroad #2 Track Identifier:	**BNSF**

Rail # 2

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		2590
Average Train Speed		49
Engines per Train		2
Railway cars per Train		50
Average Train Operations (ATO)		5
Night Fraction of ATO		40
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	51
Calculate Rail #2 DNL	51	Reset

Add Road Source | Add Rail Source

Airport Noise Level	

Site ID	Landmark 601 - NAL 3: NE Corner of Main Building
Record Date	11/20/2025
User's Name	Phase Engineering RS

Road # 1 Name:	**W. Lewis Street**

Road #1

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	125		125
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	2262		82
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	50	0	57
Calculate Road #1 DNL	58	Reset	

Road # 2 Name:	**S. Frazier Street**

Road #2

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	705		705
Distance to Stop Sign			
Average Speed	55		55

Average Daily Trips (ADT)	15031		1045
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	52	0	58
Calculate Road #2 DNL	59	Reset	

Road # 3 Name: **W. Phillips St & W. Davis St**

Road #3

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	1030		1030
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	32745		1615
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	48	0	57
Calculate Road #3 DNL	57	Reset	

Railroad #1 Track Identifier: **Union Pacific**

Rail # 1

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		1490
Average Train Speed		30
Engines per Train		2

Railway cars per Train		50
Average Train Operations (ATO)		7
Night Fraction of ATO		43
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	58
Calculate Rail #1 DNL	58	Reset

Railroad #2 Track Identifier:	**BNSF**

Rail # 2

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		2590
Average Train Speed		49
Engines per Train		2
Railway cars per Train		50
Average Train Operations (ATO)		5
Night Fraction of ATO		40
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	51
Calculate Rail #2 DNL	51	Reset

Add Road Source | Add Rail Source

Airport Noise Level	

Loud Impulse Sounds?	○ **Yes** ◉ **No**
Combined DNL for all Road and Rail sources	**64**
Combined DNL including Airport	**N/A**
Site DNL with Loud Impulse Sound	

Calculate Reset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:

- **No Action Alternative**: Cancel the project at this location
- **Other Reasonable Alternatives**: Choose an alternate site
- **Mitigation**
  - **Contact your Field or Regional Environmental Officer (/programs/environmental-review/hud-environmental-staff-contacts/)**
  - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
  - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
  - Incorporate natural or man-made barriers.
  - Construct noise barrier. See the **Barrier Performance Module (/programs/environmental-review/bpm-calculator/)**

Tools and Guidance

Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)

Federal Railroad Administration Railroad Operations Data Sources (https://www.hudexchange.info/resource/6027/federal-railroad-administration-railroad-operations-data-sources/)

Site ID	Landmark 601 - NAL 4: SE Corner of Proposed Building
Record Date	11/20/2025
User's Name	Phase Engineering RS

Road # 1 Name:	**W. Lewis Street**

Road #1

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	450		450
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	2262		82
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	42	0	49
Calculate Road #1 DNL	50	Reset	

Road # 2 Name:	**S. Frazier Street**

Road #2

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	650		650
Distance to Stop Sign			
Average Speed	55		55

Average Daily Trips (ADT)	15031		1045
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	53	0	59
Calculate Road #2 DNL	60	Reset	

Road # 3 Name: **W. Phillips St & W. Davis St**

Road #3

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	710		710
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	32745		1615
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	50	0	59
Calculate Road #3 DNL	60	Reset	

Railroad #1 Track Identifier: **Union Pacific**

Rail # 1

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		1450
Average Train Speed		30
Engines per Train		2

Railway cars per Train		50
Average Train Operations (ATO)		7
Night Fraction of ATO		43
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	58
Calculate Rail #1 DNL	58	Reset

Railroad #2 Track Identifier:	**BNSF**

Rail # 2

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		2280
Average Train Speed		49
Engines per Train		2
Railway cars per Train		50
Average Train Operations (ATO)		5
Night Fraction of ATO		40
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	52
Calculate Rail #2 DNL	52	Reset

Add Road Source | Add Rail Source

Airport Noise Level	

Loud Impulse Sounds?	○ **Yes** ◉ **No**
Combined DNL for all Road and Rail sources	**64**
Combined DNL including Airport	**N/A**
Site DNL with Loud Impulse Sound	

Calculate Reset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:

- **No Action Alternative**: Cancel the project at this location
- **Other Reasonable Alternatives**: Choose an alternate site
- **Mitigation**
  - **Contact your Field or Regional Environmental Officer (/programs/environmental-review/hud-environmental-staff-contacts/)**
  - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
  - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
  - Incorporate natural or man-made barriers.
  - Construct noise barrier. See the **Barrier Performance Module (/programs/environmental-review/bpm-calculator/)**

Tools and Guidance

Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)

Federal Railroad Administration Railroad Operations Data Sources (https://www.hudexchange.info/resource/6027/federal-railroad-administration-railroad-operations-data-sources/)

Site ID	Landmark 601 - NAL 5: Dog Park
Record Date	11/20/2025
User's Name	Phase Engineering RS

Road # 1 Name:	**W. Lewis Street**

Road #1

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	310		310
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	2262		82
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	44	0	51
Calculate Road #1 DNL	52	Reset	

Road # 2 Name:	**S. Frazier Street**

Road #2

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	465		465
Distance to Stop Sign			
Average Speed	55		55

Average Daily Trips (ADT)	15031		1045
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	55	0	61
Calculate Road #2 DNL	62	Reset	

Road # 3 Name: **W. Phillips St & W. Davis St**

Road #3

Vehicle Type	**Cars** ☑	**Medium Trucks** ☐	**Heavy Trucks** ☑
Effective Distance	855		855
Distance to Stop Sign			
Average Speed	30		30
Average Daily Trips (ADT)	32745		1615
Night Fraction of ADT	15		15
Road Gradient (%)			2
Vehicle DNL	49	0	58
Calculate Road #3 DNL	58	Reset	

Railroad #1 Track Identifier: **Union Pacific**

Rail # 1

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		1685
Average Train Speed		30
Engines per Train		2

Railway cars per Train		50
Average Train Operations (ATO)		7
Night Fraction of ATO		43
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	57
Calculate Rail #1 DNL	57	Reset

Railroad #2 Track Identifier:	**BNSF**

Rail # 2

Train Type	**Electric** ☐	**Diesel** ☑
Effective Distance		2515
Average Train Speed		49
Engines per Train		2
Railway cars per Train		50
Average Train Operations (ATO)		5
Night Fraction of ATO		40
Railway whistles or horns?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Bolted Tracks?	Yes: ☐ No: ☐	Yes: ☑ No: ☐
Train DNL	0	51
Calculate Rail #2 DNL	51	Reset

Add Road Source | Add Rail Source

Airport Noise Level	

Loud Impulse Sounds?	○ **Yes** ◉ **No**
Combined DNL for all Road and Rail sources	**65**
Combined DNL including Airport	**N/A**
Site DNL with Loud Impulse Sound	

Calculate Reset

Mitigation Options

If your site DNL is in Excess of 65 decibels, your options are:


- **No Action Alternative**: Cancel the project at this location
- **Other Reasonable Alternatives**: Choose an alternate site
- **Mitigation**
  - **Contact your Field or Regional Environmental Officer (/programs/environmental-review/hud-environmental-staff-contacts/)**
  - Increase mitigation in the building walls (only effective if no outdoor, noise sensitive areas)
  - Reconfigure the site plan to increase the distance between the noise source and noise-sensitive uses
  - Incorporate natural or man-made barriers.
  - Construct noise barrier. See the **Barrier Performance Module (/programs/environmental-review/bpm-calculator/)**

Tools and Guidance


Day/Night Noise Level Assessment Tool User Guide (/resource/3822/day-night-noise-level-assessment-tool-user-guide/)

Day/Night Noise Level Assessment Tool Flowcharts (/resource/3823/day-night-noise-level-assessment-tool-flowcharts/)


Federal Railroad Administration Railroad Operations Data Sources (https://www.hudexchange.info/resource/6027/federal-railroad-administration-railroad-operations-data-sources/)




1) S. Frazier Street AADT & Truck Percent (TXDOT)




2) S. Frazier Street Speed Limit (TXDOT)



3) W. Phillips Street & W. Davis Street AADT & Truck Percent (TXDOT) – Data provided as one roadway



4) W. Phillips Street & W. Davis Street Speed Limit (TXDOT)



5) W. Lewis Street AADT & Truck Percent (TXDOT)

U. S. DOT CROSSING INVENTORY FORM

DEPARTMENT OF TRANSPORTATION
FEDERAL RAILROAD ADMINISTRATION

OMB No. 2130-0017

Instructions for the initial reporting of the following types of new or previously unreported crossings: For public highway-rail grade crossings, complete the entire inventory Form. For private highway-rail grade crossings, complete the Header, Parts I and II, and the Submission Information section. For public pathway grade crossings (including pedestrian station grade crossings), complete the Header, Parts I and II, and the Submission Information section. For Private pathway grade crossings, complete the Header, Parts I and II, and the Submission Information section. For grade-separated highway-rail or pathway crossings (including pedestrian station crossings), complete the Header, Part I, and the Submission Information section. For changes to existing data, complete the Header, Part I Items 1-3, and the Submission Information section, in addition to the updated data fields. Note: For private crossings only, Part I Item 20 and Part III Item 2.K. are required unless otherwise noted. An asterisk * denotes an optional field.

A. Revision Date *(MM/DD/YYYY)*	B. Reporting Agency	C. Reason for Update *(Select only one)*	D. DOT Crossing Inventory Number
08 / 28 / 2025	☒ Railroad ☐ Transit ☐ State ☐ Other	☒ Change in Data ☐ New Crossing ☐ Closed ☐ No Train Traffic ☐ Quiet Zone Update ☐ Re-Open ☐ Date Change Only ☐ Change in Primary Operating RR ☐ Admin. Correction	435487P

Part I: Location and Classification Information

1. Primary Operating Railroad	2. State	3. County
Union Pacific Railroad Company [UP]	TEXAS	MONTGOMERY

4. City / Municipality	5. Street/Road Name & Block Number	6. Highway Type & No.
☒ In ☐ Near CONROE	LEWIS STREET *(Street/Road Name)* | * *(Block Number)*	ST 0000

7. Do Other Railroads Operate a Separate Track at Crossing?	8. Do Other Railroads Operate Over Your Track at Crossing?
☐ Yes ☒ No If Yes, Specify RR	☒ Yes ☐ No If Yes, Specify RR BNSF

9. Railroad Division or Region	10. Railroad Subdivision or District	11. Branch or Line Name	12. RR Milepost
☐ None HOUSTON	☐ None Palestine Sub	☒ None	| 0194.230 | *(prefix) | (nnnn.nnn) | (suffix)*

13. Line Segment *	14. Nearest RR Timetable Station *	15. Parent RR *(if applicable)*	16. Crossing Owner *(if applicable)*
		☒ N/A	☐ N/A UP

17. Crossing Type	18. Crossing Purpose	19. Crossing Position	20. Public Access *(if Private Crossing)*	21. Type of Train	22. Average Passenger Train Count Per Day
☒ Public ☐ Private	☒ Highway ☐ Pathway, Ped. ☐ Station, Ped.	☒ At Grade ☐ RR Under ☐ RR Over	☐ Yes ☐ No	☒ Freight ☐ Intercity Passenger ☐ Commuter ☐ Transit ☐ Shared Use Transit ☐ Tourist/Other	☐ Less Than One Per Day ☐ Number Per Day 0

23. Type of Land Use
☐ Open Space ☐ Farm ☒ Residential ☐ Commercial ☐ Industrial ☐ Institutional ☐ Recreational ☐ RR Yard

24. Is there an Adjacent Crossing with a Separate Number?	25. Quiet Zone *(FRA provided)*
☐ Yes ☒ No If Yes, Provide Crossing Number	☒ No ☐ 24 Hr ☐ Partial ☐ Chicago Excused Date Established

26. HSR Corridor ID	27. Latitude in decimal degrees	28. Longitude in decimal degrees	29. Lat/Long Source
☒ N/A	*(WGS84 std: nn.nnnnnnn)* 30.3157174	*(WGS84 std: -nnn.nnnnnnn)* -95.4558340	☒ Actual ☐ Estimated

30.A. Railroad Use *	**31.A. State Use** *
30.B. Railroad Use *	**31.B. State Use** *
30.C. Railroad Use *	**31.C. State Use** * State Phone# updated - date updated 2024-12-06
30.D. Railroad Use *	**31.D. State Use** *
32.A. Narrative *(Railroad Use)* *	**32.B. Narrative** *(State Use)* *

33. Emergency Notification Telephone No. *(posted)*	34. Railroad Contact *(Telephone No.)*	35. State Contact *(Telephone No.)*
800-848-8715	402-544-3721	512-416-2684

Part II: Railroad Information

1. Estimated Number of Daily Train Movements

1.A. Total Day Thru Trains *(6 AM to 6 PM)*	1.B. Total Night Thru Trains *(6 PM to 6 AM)*	1.C. Total Switching Trains	1.D. Total Transit Trains	1.E. Check if Less Than One Movement Per Day ☐ How many trains per week?
4	3	0	0	

2. Year of Train Count Data *(YYYY)*	3. Speed of Train at Crossing
2025	3.A. Maximum Timetable Speed *(mph)* 30 3.B. Typical Speed Range Over Crossing *(mph)* From 15 to 30

4. Type and Count of Tracks
Main 1 Siding 1 Yard 0 Transit 0 Industry 0

5. Train Detection *(Main Track only)*
☒ Constant Warning Time ☐ Motion Detection ☐ AFO ☐ PTC ☐ DC ☐ Other ☐ None

6. Is Track Signaled?	7.A. Event Recorder	7.B. Remote Health Monitoring
☒ Yes ☐ No	☐ Yes ☒ No	☐ Yes ☒ No

U. S. DOT CROSSING INVENTORY FORM

DEPARTMENT OF TRANSPORTATION
FEDERAL RAILROAD ADMINISTRATION

OMB No. 2130-0017

Instructions for the initial reporting of the following types of new or previously unreported crossings: For public highway-rail grade crossings, complete the entire inventory Form. For private highway-rail grade crossings, complete the Header, Parts I and II, and the Submission Information section. For public pathway grade crossings (including pedestrian station grade crossings), complete the Header, Parts I and II, and the Submission Information section. For Private pathway grade crossings, complete the Header, Parts I and II, and the Submission Information section. For grade-separated highway-rail or pathway crossings (including pedestrian station crossings), complete the Header, Part I, and the Submission Information section. For changes to existing data, complete the Header, Part I Items 1-3, and the Submission Information section, in addition to the updated data fields. Note: For private crossings only, Part I Item 20 and Part III Item 2.K. are required unless otherwise noted. An asterisk * denotes an optional field.

A. Revision Date (MM/DD/YYYY)	B. Reporting Agency	C. Reason for Update (Select only one)	D. DOT Crossing Inventory Number
12 / 17 / 2024	☒ Railroad ☐ Transit ☐ State ☐ Other	☒ Change in Data ☐ New Crossing ☐ Closed ☐ No Train Traffic ☐ Quiet Zone Update ☐ Re-Open ☐ Date Change Only ☐ Change in Primary Operating RR ☐ Admin. Correction	024354M

Part I: Location and Classification Information

1. Primary Operating Railroad	2. State	3. County
BNSF Railway Company [BNSF]	TEXAS	MONTGOMERY

4. City / Municipality	5. Street/Road Name & Block Number	6. Highway Type & No.
☒ In ☐ Near CONROE	SAN JACINTO ST (Street/Road Name) | * (Block Number)	ST 0000

7. Do Other Railroads Operate a Separate Track at Crossing?	8. Do Other Railroads Operate Over Your Track at Crossing?
☐ Yes ☒ No If Yes, Specify RR	☐ Yes ☒ No If Yes, Specify RR

9. Railroad Division or Region	10. Railroad Subdivision or District	11. Branch or Line Name	12. RR Milepost
☐ None RED RIVER	☐ None CONROE	☐ None SOMERVL-SILSBEE	(prefix) | 0071.930 (nnnn.nnn) | (suffix)

13. Line Segment *	14. Nearest RR Timetable Station *	15. Parent RR (if applicable)	16. Crossing Owner (if applicable)
7502	CONROE	☒ N/A	☐ N/A BNSF

17. Crossing Type	18. Crossing Purpose	19. Crossing Position	20. Public Access (if Private Crossing)	21. Type of Train	22. Average Passenger Train Count Per Day
☒ Public ☐ Private	☒ Highway ☐ Pathway, Ped. ☐ Station, Ped.	☒ At Grade ☐ RR Under ☐ RR Over	☐ Yes ☐ No	☒ Freight ☐ Intercity Passenger ☐ Commuter ☐ Transit ☐ Shared Use Transit ☐ Tourist/Other	☐ Less Than One Per Day ☐ Number Per Day 0

23. Type of Land Use
☐ Open Space ☐ Farm ☒ Residential ☐ Commercial ☐ Industrial ☐ Institutional ☐ Recreational ☐ RR Yard

24. Is there an Adjacent Crossing with a Separate Number?	25. Quiet Zone (FRA provided)
☐ Yes ☒ No If Yes, Provide Crossing Number	☒ No ☐ 24 Hr ☐ Partial ☐ Chicago Excused Date Established

26. HSR Corridor ID	27. Latitude in decimal degrees	28. Longitude in decimal degrees	29. Lat/Long Source
☒ N/A	(WGS84 std: nn.nnnnnnn) 30.3081270	(WGS84 std: -nnn.nnnnnnn) -95.459209	☒ Actual ☐ Estimated

30.A. Railroad Use *	31.A. State Use *
30.B. Railroad Use *	31.B. State Use *
30.C. Railroad Use *	31.C. State Use * State Phone# updated - date updated 2024-12-06
30.D. Railroad Use *	31.D. State Use *
32.A. Narrative (Railroad Use) * (I.27 I.28 I.29)Value Provided by Railroad, Not Ye	32.B. Narrative (State Use) *

33. Emergency Notification Telephone No. (posted)	34. Railroad Contact (Telephone No.)	35. State Contact (Telephone No.)
800-832-5452	817-352-1549	512-416-2684

Part II: Railroad Information

1. Estimated Number of Daily Train Movements

1.A. Total Day Thru Trains (6 AM to 6 PM)	1.B. Total Night Thru Trains (6 PM to 6 AM)	1.C. Total Switching Trains	1.D. Total Transit Trains	1.E. Check if Less Than One Movement Per Day ☐ How many trains per week?
3	2	0	0	

2. Year of Train Count Data (YYYY)	3. Speed of Train at Crossing
2023	3.A. Maximum Timetable Speed (mph) 49 3.B. Typical Speed Range Over Crossing (mph) From 1 to 49

4. Type and Count of Tracks
Main 1 Siding 0 Yard 0 Transit 0 Industry 0

5. Train Detection (Main Track only)
☒ Constant Warning Time ☐ Motion Detection ☐ AFO ☐ PTC ☐ DC ☐ Other ☐ None

6. Is Track Signaled?	7.A. Event Recorder	7.B. Remote Health Monitoring
☐ Yes ☒ No	☐ Yes ☐ No	☐ Yes ☐ No

EXHIBIT H – Contractor Submittal Reviews

1. If "VE" of a product or required submittal package has occurred during bidding/procurement and this has been approved in writing by owner, it is the General Contractors responsibility to confirm compliance with all codes/ordinances/laws as the project is subject to. If requested, reviews by Architect and their consultants may be subject to additional services.
2. If a product substitution is being proposed after owner has entered into an agreement with the GC, a form identifying the below items must accompany the submittals.
    a. A transmittal that acknowledges a review has been performed by the GC and a description of all deviations from the design/permit drawings in that review.
    b. A post-bid request for substitution. To prevent utilizing lesser/cheaper products on the project that have not been identified in price negotiations with the owner. These substitutions would come with an identified cost savings to the owner and be sent to the design team only after approval from the owner as an informational submittal.
3. The Architects submittal review is based on all like products being submitted under one cover (IE, no separated piece submittals: bathtubs separate from other plumbing, etc.).
4. Submittals are reviewed by our office one time, resubmittals are limited to checking if deficiencies have been corrected. If work beyond this level (2 reviews) is required, the work will be subject to additional services and hourly billing.

Additionally, attached is an example list for MEP systems submittals with corresponding spec section #s, with information for sub-contractors regarding full and complete submittals.

Confirmation of acknowledgement and receipt _____

GC to sign and date prior to commencement of shop drawing reviews.

Section #	Section Title	Segment Text
01-9113	General Commissioning Requirements	Product Data: If submittals to Architect do not include the following, submit copies as soon as possible:
		Manufacturer's product data, cut sheets, and shop drawings.
		Manufacturer's installation instructions.
		Startup, operating, and troubleshooting procedures.
		Fan and pump curves.
		Factory test reports.
		Warranty information, including details of Owner's responsibilities in regard to keeping warranties in force.
01-9113	General Commissioning Requirements	Manufacturers' Instructions: Submit copies of all manufacturer-provided instructions that are shipped with the equipment as soon as the equipment is delivered.
01-9113	General Commissioning Requirements	Startup Plans and Reports.
01-9113	General Commissioning Requirements	Completed Prefunctional Checklists.
01-9113	General Commissioning Requirements	HERS Rating Report: Include the following mandatory completed reports for ENERGY STAR Certified Homes:
		HVAC Commissioning Checklist.
01-9113	General Commissioning Requirements	HERS (Home Energy Rating System) Rater: Residential Energy Services Network (RESNET) certified professional.
21-0500	Common Work Results for Fire Suppression	Product Data: Provide manufacturers catalogue information. Indicate valve data and ratings.
21-0500	Common Work Results for Fire Suppression	Shop Drawings: Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation, layout, weights, mounting and support details, and piping connections.
21-0500	Common Work Results for Fire Suppression	Project Record Documents: Record actual locations of components and tag numbering.
21-0500	Common Work Results for Fire Suppression	Operation and Maintenance Data: Include installation instructions and spare parts lists.
21-0500	Common Work Results for Fire Suppression	Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
21-0523	General-Duty Valves for Water-Based Fire-Suppression Piping	Product Data: Provide data on valves including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
21-0523	General-Duty Valves for Water-Based Fire-Suppression Piping	Warranty: Submit manufacturer warranty and ensure that forms have been completed in 's name and registered with manufacturer.
21-0523	General-Duty Valves for Water-Based Fire-Suppression Piping	Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, maintenance and repair data, and parts listings.
21-0523	General-Duty Valves for Water-Based Fire-Suppression Piping	Manufacturer:
		Obtain valves for each valve type from single manufacturer.
		Company must specialize in manufacturing products specified in this section, with not less than three years of documented experience.
21-0523	General-Duty Valves for Water-Based Fire-Suppression Piping	Installer and Maintenance Contractor Qualifications:
		Company specializing in performing the work of this section with minimum five years documented experience.
		Trained and approved by manufacturer to design, install, test and maintain the equipment specified herein.
		Complies with manufacturer's certification requirements.

		Complies with manufacturer's insurance requirements.
21-0553	Identification for Fire Suppression Piping and Equipment	Product Data: Provide manufacturers catalog literature for each product required.
21-1200	Fire-Suppression Standpipes	Product Data: Provide manufacturer's catalog sheet for equipment indicating rough-in size, finish, and accessories.
21-1200	Fire-Suppression Standpipes	Shop Drawings: Indicate supports, components, accessories, and sizes.
		Submit shop drawings, product data, and hydraulic calculations to authority having jurisdiction for approval. Drawings and calculations shall be stamped by a licenced professional engineer.
		Installation shall be fully coordinated with structure and all other trades. Coordination shall be performed with installed conditions, not just the construction drawings. Rework of piping due to conflicts with field conditions shall be performed without cost to the Owner or Engineer.
21-1200	Fire-Suppression Standpipes	Project Record Documents: Record actual locations of components.
21-1200	Fire-Suppression Standpipes	Operation Data: Include manufacturer's data.
21-1200	Fire-Suppression Standpipes	Certificates: Provide certificate of compliance from authority having jurisdiction indicating approval of field acceptance tests.
21-1200	Fire-Suppression Standpipes	Installer Qualifications: Company specializing in performing the work of this section with minimum three years experience .
21-1300	Fire Suppression Sprinklers	Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.
21-1300	Fire Suppression Sprinklers	Shop Drawings:
		Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation. Additionally, indicate general routing of piping for review by Architect.
		Indicate hydraulic calculations, detailed pipe layout, hangers and supports, sprinklers, components and accessories. Indicate system controls.
		Submit shop drawings, product data, and hydraulic calculations to authority having jurisdiction for approval. Drawings and calculations shall be stamped by a licenced professional engineer.
		Installation shall be fully coordinated with structure and all other trades. Coordination shall be performed with installed conditions, not just the construction drawings. Rework of sprinkler piping due to conflicts with field conditions shall be performed without cost to the Owner or Engineer.
21-1300	Fire Suppression Sprinklers	Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.
21-1300	Fire Suppression Sprinklers	Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.
21-1300	Fire Suppression Sprinklers	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		See Section 016000 - Product Requirements, for additional provisions.
		Extra Sprinklers: Type and size matching those installed, in quantity required by referenced NFPA design and installation standard.
		Sprinkler Wrenches: For each sprinkler type.
21-1300	Fire Suppression Sprinklers	Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in Texas.
21-1300	Fire Suppression Sprinklers	EXTRA MATERIALS
		Provide extra sprinklers of type and size matching those installed, in quantity required by referenced NFPA design and installation standard.

		Provide suitable wrenches for each sprinkler type.
		Provide metal storage cabinet located adjacent to alarm valve.
22-0553	Identification for Plumbing Piping and Equipment	List: Submit list of wording, symbols, letter size, and color coding for mechanical identification.
22-0553	Identification for Plumbing Piping and Equipment	Chart and Schedule: Submit valve chart and schedule, including valve tag number, location, function, and valve manufacturer's name and model
22-0553	Identification for Plumbing Piping and Equipment	Product Data: Provide manufacturers catalog literature for each product required.
22-0553	Identification for Plumbing Piping and Equipment	Project Record Documents: Record actual locations of tagged valves.
22-0719	Plumbing Piping Insulation	Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service
22-1005	Plumbing Piping	Product Data: Provide data on pipe materials, pipe fittings, valves, and accessories. Provide manufacturers catalog information. Indicate valve data and ratings.
22-1005	Plumbing Piping	Project Record Documents: Record actual routing of piping. Record actual locations of valves.
22-1005	Plumbing Piping	Welder Qualifications: Certified in accordance with ASME BPVC-IX.
22-1006	Plumbing Piping Specialties	Product Data: Provide component sizes, rough-in requirements, service sizes, and finishes.
22-1006	Plumbing Piping Specialties	Certificates: Certify that grease interceptors meet or exceed specified requirements.
22-3000	Plumbing Equipment	Product Data:
		Provide dimension drawings of water heaters indicating components and connections to other equipment and piping.
		Indicate pump type, capacity, power requirements.
		Provide certified pump curves showing pump performance characteristics with pump and system operating point plotted. Include NPSH curve when applicable.
		Provide electrical characteristics and connection requirements.
22-3000	Plumbing Equipment	Shop Drawings:
		Indicate dimensions of tanks, tank lining methods, anchors, attachments, lifting points, tappings, and drains.
22-3000	Plumbing Equipment	Project Record Documents: Record actual locations of components.
22-3000	Plumbing Equipment	Operation and Maintenance Data: Include operation, maintenance, and inspection data, replacement part numbers and availability, and service depot location and telephone number.
22-3000	Plumbing Equipment	Warranty: Submit manufacturer warranty and ensure forms have been completed in 's name and registered with manufacturer.
22-3000	Plumbing Equipment	Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.
22-3000	Plumbing Equipment	WARRANTY
		Provide five year manufacturer warranty for domestic water heaters.
22-4000	Plumbing Fixtures	Product Data: Provide catalog illustrations of fixtures, sizes, rough-in dimensions, utility sizes, trim, and finishes.
22-4000	Plumbing Fixtures	Maintenance Data: Include fixture trim exploded view and replacement parts lists.
22-4000	Plumbing Fixtures	Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.
22-4000	Plumbing Fixtures	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.

		Extra Faucet Washers: Two sets of each type and size.
		Flush Valve Service Kits: Two for each type and size.
22-4000	Plumbing Fixtures	WARRANTY
		Provide five year manufacturer warranty for electric water cooler.
23-0593	Testing, Adjusting, and Balancing for HVAC	Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days after award of Contract.
23-0593	Testing, Adjusting, and Balancing for HVAC	Final Report: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.
		Submit to the Construction Manager within two weeks after completion of testing, adjusting, and balancing.
		Revise TAB plan to reflect actual procedures and submit as part of final
		Provide reports in soft cover, letter size, 3-ring binder manuals, complete with index page and indexing tabs, with cover identification at front and side. Include set of reduced drawings with air outlets and equipment identified to correspond with data sheets, and indicating thermostat locations.
		Include actual instrument list, with manufacturer name, serial number, and date of calibration.
		Form of Test Reports: Where the TAB standard being followed recommends a report format use that; otherwise, follow ASHRAE Std 111.
		Units of Measure: Report data in I-P (inch-pound) units only.
		Include the following on the title page of each report:
		Name of Testing, Adjusting, and Balancing Agency.
		Address of Testing, Adjusting, and Balancing Agency.
		Telephone number of Testing, Adjusting, and Balancing Agency.
		Project name.
		Project location.
		Report date.
23-0593	Testing, Adjusting, and Balancing for HVAC	Project Record Documents: Record actual locations of flow measuring stations and balancing valves and rough setting.
23-0593	Testing, Adjusting, and Balancing for HVAC	TAB Agency Qualifications:
		Company specializing in the testing, adjusting, and balancing of systems specified in this section.
		Having minimum of three years documented experience.
		Certified by one of the following:
		AABC, Associated Air Balance Council: www.aabchq.com; upon completion submit AABC National Performance Guaranty.
		NEBB, National Environmental Balancing Bureau: www.nebb.org/#sle.
23-0593	Testing, Adjusting, and Balancing for HVAC	TAB Supervisor Qualifications: Professional Engineer licensed in Oklahoma.
23-0713	Duct Insulation	Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.
23-0713	Duct Insulation	Manufacturer's Instructions: Indicate installation procedures necessary to ensure acceptable workmanship and that installation standards will be achieved.
23-0713	Duct Insulation	Manufacturer Qualifications: Company specializing in manufacturing products of the type specified in this section with not less than three years of documented experience.
23-0713	Duct Insulation	Applicator Qualifications: Company specializing in performing the type of work specified in this section, with minimum three years of experience and approved by manufacturer.
23-0719	HVAC Piping Insulation	Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.

23-3100	HVAC Ducts and Casings	Project Record Documents: Record actual locations of ducts and duct fittings. Record changes in fitting location and type. Show additional
23-3300	Air Duct Accessories	Product Data: Provide for shop fabricated assemblies including volume control dampers. Include electrical characteristics and connection
23-3300	Air Duct Accessories	Shop Drawings: Indicate for shop fabricated assemblies including volume control dampers.
23-3300	Air Duct Accessories	Manufacturer's Installation Instructions: Provide instructions for fire
23-3300	Air Duct Accessories	Project Record Drawings: Record actual locations of access doors and test holes.
23-3700	Air Outlets and Inlets	Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlets showing type, size, location, application, and noise level.
23-4000	HVAC Air Cleaning Devices	Product Data: Provide data on filter media, filter performance data, filter assembly and filter frames, dimensions, motor locations and electrical characteristics and connection requirements.
23-4000	HVAC Air Cleaning Devices	Shop Drawings: Indicate filter assembly and filter frames, dimensions, motor locations, and electrical characteristics and connection requirements.
23-4000	HVAC Air Cleaning Devices	EXTRA MATERIALS
		Provide one set of disposable panel filters. Filters shall be delivered to
23-8127	Small Split-System Heating and Cooling	Product Data: Provide rated capacities, weights, accessories, electrical nameplate data, and wiring diagrams.
23-8127	Small Split-System Heating and Cooling	Shop Drawings: Indicate assembly, required clearances, and location and size of field connections.
23-8127	Small Split-System Heating and Cooling	Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, installation instructions, maintenance and repair data, and parts listing.
23-8127	Small Split-System Heating and Cooling	Warranty: Submit manufacturers warranty and ensure forms have been filled out in Owner s name and registered with manufacturer.
23-8127	Small Split-System Heating and Cooling	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		See Section 016000 - Product Requirements, for additional provisions.
		Extra Filters: One for each unit.
23-8127	Small Split-System Heating and Cooling	WARRANTY
		Provide five year manufacturers warranty for heat exchangers.
		Provide five year manufacturers warranty for compressors.
26-0519	Low-Voltage Electrical Power Conductors and Cables	Product Data: Provide manufacturer's standard catalog pages and data sheets for conductors and cables, including detailed information on materials, construction, ratings, listings, and available sizes, configurations, and stranding.
26-0519	Low-Voltage Electrical Power Conductors and Cables	Design Data: Indicate voltage drop and ampacity calculations for aluminum conductors substituted for copper conductors. Include proposed modifications to raceways, boxes, wiring gutters, enclosures, etc. to accommodate substituted conductors.
26-0519	Low-Voltage Electrical Power Conductors and Cables	Project Record Documents: Record actual installed circuiting arrangements. Record actual routing for underground circuits.
26-0526	Grounding and Bonding for Electrical Systems	Product Data: Provide manufacturer's standard catalog pages and data sheets for grounding and bonding system components.
26-0526	Grounding and Bonding for Electrical Systems	Test Reports: Indicate overall resistance to ground .
26-0526	Grounding and Bonding for Electrical Systems	Project Record Documents: Record actual locations of grounding electrode system components and connections.

26-0526	Grounding and Bonding for Electrical Systems	Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
26-0526	Grounding and Bonding for Electrical Systems	Installer Qualifications for Signal Reference Grids: Company with minimum five years documented experience with high frequency grounding systems.
26-0529	Hangers and Supports for Electrical	Product Data: Provide manufacturer’s catalog data for fastening systems.
26-0534	Conduit	Product Data: Provide manufacturer's standard catalog pages and data sheets for conduits and fittings.
26-0534	Conduit	Project Record Documents: Record actual routing for conduits installed underground, conduits embedded within concrete slabs, and conduits 2 inch (53 mm) trade size and larger.
26-0537	Boxes	Project Record Documents: Record actual locations and mounting heights of outlet, pull, and junction boxes on project record documents.
26-0919	Enclosed Contactors	Product Data: Provide dimensions, size, voltage ratings and current ratings.
26-0919	Enclosed Contactors	Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of
26-0923	Lighting Control Devices	Product Data: Include ratings, configurations, standard wiring diagrams, dimensions, colors, service condition requirements, and installed features.
		Occupancy Sensors: Include detailed motion detection coverage range diagrams.
26-0923	Lighting Control Devices	Manufacturer's Installation Instructions: Include application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
26-0923	Lighting Control Devices	Operation and Maintenance Data: Include detailed information on device programming and setup.
26-0923	Lighting Control Devices	Project Record Documents: Record actual installed locations and settings for lighting control devices.
26-0923	Lighting Control Devices	WARRANTY
		Provide five year manufacturer warranty for all occupancy sensors.
26-2100	Low-Voltage Electrical Service Entrance	Product Data: Provide manufacturer's standard catalog pages and data sheets for each product. Include ratings, configurations, standard wiring diagrams, outline and support point dimensions, finishes, weights, service condition requirements, and installed features.
26-2100	Low-Voltage Electrical Service Entrance	Shop Drawings: Include dimensioned plan views and sections indicating locations and arrangement of Utility Company and service entrance equipment, metering provisions, required clearances, and proposed service routing.
		Obtain Utility company approval of shop drawings prior to submittal.
26-2413	Switchboards	Product Data: Provide manufacturer's standard catalog pages and data sheets for switchboards, enclosures, overcurrent protective devices, and other installed components and accessories.
26-2413	Switchboards	Shop Drawings: Indicate dimensions, voltage, bus ampacities, overcurrent protective device arrangement and sizes, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.
26-2413	Switchboards	Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.
26-2416	Panelboards	Product Data: Provide manufacturer's standard catalog pages and data sheets for panelboards, enclosures, overcurrent protective devices, and other installed components and accessories.

		Include characteristic trip curves for each type and rating of overcurrent protective device upon request.
26-2416	Panelboards	Shop Drawings: Indicate outline and support point dimensions, voltage, main bus ampacity, overcurrent protective device arrangement and sizes, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.
		Clearly indicate whether proposed short circuit current ratings are fully rated or, where acceptable, series rated systems.
		Include documentation of listed series ratings upon request.
26-2416	Panelboards	Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
26-2416	Panelboards	Project Record Documents: Record actual installed locations of panelboards and actual installed circuiting arrangements.
26-2416	Panelboards	Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.
26-2416	Panelboards	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		Panelboard Keys: Two of each different key.
26-2717	Equipment Wiring	Product Data: Provide wiring device manufacturer’s catalog information showing dimensions, configurations, and construction.
26-2726	Wiring Devices	Product Data: Provide manufacturer's catalog information showing dimensions, colors, and configurations.
26-2726	Wiring Devices	Operation and Maintenance Data:
		GFI Receptacles: Include information on status indicators and testing procedures and intervals.
26-2726	Wiring Devices	Project Record Documents: Record actual installed locations of wiring devices.
26-2813	Fuses	Product Data: Provide manufacturer's standard data sheets including voltage and current ratings, interrupting ratings, time-current curves, and current limitation curves.
26-2813	Fuses	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		See Section 016000 - Product Requirements, for additional provisions.
		Extra Fuses: One set(s) of three for each type and size installed.
		Fuse Pullers: One set(s) compatible with each type and size installed.
26-2818	Enclosed Switches	Product Data: Provide manufacturer's standard catalog pages and data sheets for enclosed switches and other installed components and
26-2818	Enclosed Switches	Shop Drawings: Indicate outline and support point dimensions, voltage and current ratings, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.
26-2818	Enclosed Switches	Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.
26-2818	Enclosed Switches	Project Record Documents: Record actual locations of enclosed switches.
26-2818	Enclosed Switches	Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.

26-4300	Surge Protective Devices	Product Data: Include detailed component information, voltage, surge current ratings, repetitive surge current capacity, voltage protection rating (VPR) for all protection modes, maximum continuous operating voltage (MCOV), nominal discharge current (I-n), short circuit current rating (SCCR), connection means including any required external overcurrent protection, enclosure ratings, outline and support point dimensions, weight, service condition requirements, and installed features.
26-4300	Surge Protective Devices	Shop Drawings: Include wiring diagrams showing all factory and field connections with wire and circuit breaker/fuse sizes.
26-4300	Surge Protective Devices	Certificates: Manufacturer's documentation of listing for compliance with the following standards:
		UL 1449.
		UL 1283 (for Type 2 SPDs).
26-4300	Surge Protective Devices	Manufacturer's Installation Instructions: Include application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
26-4300	Surge Protective Devices	Operation and Maintenance Data: Include information on status indicators and recommended maintenance procedures and intervals.
26-4300	Surge Protective Devices	Warranty: Submit sample of manufacturer's warranty and documentation of final executed warranty completed in Owner's name and registered with manufacturer.
26-4300	Surge Protective Devices	Project Record Documents: Record actual connections and locations of surge protective devices.
26-4300	Surge Protective Devices	WARRANTY
		Manufacturer's Warranty: Provide minimum ten year warranty covering repair or replacement of surge protective devices showing evidence of failure due to defective materials or workmanship.
26-5100	Interior Lighting	Shop Drawings:
		Indicate dimensions and components for each luminaire that is not a standard product of the manufacturer.
26-5100	Interior Lighting	Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed
		LED Luminaires:
		Include estimated useful life, calculated based on IES LM-80 test data.
		Lamps: Include rated life, color temperature, color rendering index (CRI), and initial and mean lumen output.
		Fluorescent Emergency Power Supply Unit: Include list of compatible lamp configurations and associated lumen output.
26-5100	Interior Lighting	Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.
26-5100	Interior Lighting	Operation and Maintenance Data: Instructions for each product including information on replacement parts.
26-5100	Interior Lighting	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		See Section 016000 - Product Requirements, for additional provisions.

		Extra Lamps: Ten percent of total quantity installed for each type, but not less than two of each type.
		Extra Ballasts: Two percent of total quantity installed for each type, but not less than one of each type.
26-5100	Interior Lighting	Project Record Documents: Record actual connections and locations of luminaires and any associated remote components.
26-5100	Interior Lighting	WARRANTY
		See Section 017800 - Closeout Submittals, for additional warranty requirements.
		Provide two year manufacturer warranty for all linear fluorescent ballasts.
		Provide five year pro-rata warranty for batteries for emergency lighting
		Provide ten year pro-rata warranty for batteries for self-powered exit signs.
		Provide five year full warranty for fluorescent emergency power supply
26-5600	Exterior Lighting	Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, weight, effective projected area (EPA), and installed accessories; include model number nomenclature clearly marked with all proposed features.
		LED Luminaires:
		Include estimated useful life, calculated based on IES LM-80 test data.
		Poles: Include information on maximum supported effective projected area (EPA) and weight for the design wind speed.
26-5600	Exterior Lighting	Certificates for Poles and Accessories: Manufacturer's documentation that products are suitable for the luminaires to be installed.
26-5600	Exterior Lighting	Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.
26-5600	Exterior Lighting	Operation and Maintenance Data: Instructions for each product including information on replacement parts.
26-5600	Exterior Lighting	Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
		Touch-Up Paint: 2 gallons, to match color of pole finish.
26-5600	Exterior Lighting	Project Record Documents: Record actual connections and locations of pole foundations, luminaires, and any pull or junction boxes.
26-5600	Exterior Lighting	WARRANTY
		See Section 017800 - Closeout Submittals, for additional warranty requirements.
		Provide five year manufacturer warranty for all LED luminaires, including drivers.
28-3100	Fire Detection and Alarm	Certification by Contractor that the system design will comply with the contract documents.
28-3100	Fire Detection and Alarm	Evidence of designer qualifications.
28-3100	Fire Detection and Alarm	Design Documents: Submit all information required for plan review and permitting by authorities having jurisdiction, including but not limited to floor plans, riser diagrams, and description of operation:
		Copy (if any) of list of data required by authority having jurisdiction.
		NFPA 72 "Record of Completion", filled out to the extent known at the time.
		Clear and concise description of operation, with input/output matrix similar to that shown in NFPA 72 Appendix A-7-5-2.2(9), and complete listing of software required.

		System zone boundaries and interfaces to fire safety systems.
		Location of all components, circuits, and raceways; mark components with identifiers used in control unit programming.
		Circuit layouts; number, size, and type of raceways and conductors; conduit fill calculations; spare capacity calculations; notification appliance circuit voltage drop calculations.
		List of all devices on each signaling line circuit, with spare capacity
		Manufacturer's detailed data sheet for each component, including wiring diagrams, installation instructions, and circuit length limitations.
		Description of power supplies; if secondary power is by battery include calculations demonstrating adequate battery power.
		Certification by either the manufacturer of the control unit or by the manufacturer of each other component that the components are compatible with the control unit.
		Certification by the manufacturer of the control unit that the system design complies with the contract documents.
		Certification by Contractor that the system design complies with the contract documents.
28-3100	Fire Detection and Alarm	Evidence of maintenance contractor qualifications, if different from
28-3100	Fire Detection and Alarm	Inspection and Test Reports:
		Submit inspection and test plan prior to closeout demonstration.
		Submit documentation of satisfactory inspections and tests.
		Submit NFPA 72 "Inspection and Test Form," filled out.
28-3100	Fire Detection and Alarm	Operating and Maintenance Data: Revise and resubmit until acceptable; have one set available during closeout demonstration:
		Complete set of specified design documents, as approved by authority having jurisdiction.
		Additional printed set of project record documents and closeout documents, bound or filed in same manuals.
		Contact information for firm that will be providing contract maintenance and trouble call-back service.
		List of recommended spare parts, tools, and instruments for testing.
		Replacement parts list with current prices, and source of supply.
		Detailed troubleshooting guide and large scale input/output matrix.
		Preventive maintenance, inspection, and testing schedule complying with NFPA 72; provide printed copy and computer format acceptable to Owner.
		Detailed but easy to read explanation of procedures to be taken by non-technical administrative personnel in the event of system trouble, when routine testing is being conducted, for fire drills, and when entering into contracts for remodeling.
28-3100	Fire Detection and Alarm	Project Record Documents: Have one set available during closeout demonstration:
		Complete set of floor plans showing actual installed locations of components, conduit, and zones.
		"As installed" wiring and schematic diagrams, with final terminal
		"As programmed" operating sequences, including control events by device, updated input/output chart, and voice messages by event.
28-3100	Fire Detection and Alarm	Certification by manufacturer that the system has been installed in compliance with his installation requirements, is complete, and is in satisfactory operating condition.
28-3100	Fire Detection and Alarm	Certificate of Occupancy.

28-3100	Fire Detection and Alarm	Designer Qualifications: Registered engineer, employed by fire alarm control panel manufacturer, Contractor, or installer, with experience designing fire alarm systems in the jurisdictional area of the authorities
28-3100	Fire Detection and Alarm	Installer Qualifications: Firm with minimum 3 years documented experience installing fire alarm systems of the specified type and providing contract maintenance service as a regular part of their business.
		Authorized representative of control unit manufacturer; submit manufacturer's certification that installer is authorized; include name and title of manufacturer's representative making certification.
		Installer Personnel: At least 2 years of experience installing fire alarm systems.
		Supervisor: NICET level III or IV (3 or 4) certified fire alarm technician; furnish name and address.
28-3100	Fire Detection and Alarm	WARRANTY
		Provide control panel manufacturer's warranty that system components other than wire and conduit are free from defects and will remain so for 1 year after date of Substantial Completion.
		Provide installer's warranty that the installation is free from defects and will remain so for 1 year after date of Substantial Completion.

Multi-Family Apartment Complex


Geotechnical Engineering Report

Conroe, Texas

December 9, 2025 | Terracon Project No. 97255117

Prepared for:

Jones Gillam Renz Architects
1881 Main Street, Suite 301
Kansas City, Missouri 64108



Terracon
Explore with us

Nationwide
Terracon.com

- Facilities
- Environmental
- Geotechnical
- Materials

11133 I-45 South, Building T
Conroe, Texas 77302
P (936) 539-1384
Terracon.com

December 9, 2025

Jones Gillam Renz Architects
1881 Main Street, Suite 301
Kansas City, Missouri 64108

Attn: Chris Gilliam
P: (785) 827-0386
E: cgillam@jgrarchitects.com

Re: Geotechnical Engineering Report
Multi-Family Apartment Complex
601 West Lewis Street
Conroe, Texas
Terracon Project No. 97255117

Dear Mr. Gilliam:

We have completed the scope of Geotechnical Engineering services for the above referenced project in general accordance with Terracon Proposal No. P97255117 dated November 5, 2025. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations, floor slabs, and pavements for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,

Terracon Consultants, Inc.
(Texas Firm Registration No.: F-3272)

Marion Hall
Field Engineer

STATE OF TEXAS
REBECCA C. RICE
132914
LICENSED
PROFESSIONAL ENGINEER

Rebecca C. Rice, P.E.
Geotechnical Services Manager

Table of Contents

Introduction **1**
Project Description **1**
Site Conditions **2**
Geotechnical Characterization **3**
Geology 3
Subsurface Profile 3
Groundwater Conditions 4
Seismic Site Class **4**
Geotechnical Overview **5**
Earthwork **6**
Site Preparation 6
Fill Material Types 6
Utility Trench Backfill 8
Grading and Drainage 8
Wet Weather/Soft Subgrade Considerations 9
Demolition Considerations 10
Shallow Foundations **10**
Design Recommendations – Slab-on-Grade Foundation System 10
Design Recommendations – Shallow Spread/Strip Footings 13
Construction Considerations – Shallow Foundations 14
Foundation Construction Monitoring 14
Floor Slab **14**
Pavements **15**
General Comments **19**

Figures

GeoModel

Attachments

Exploration and Testing Procedures
Site Location and Exploration Plan
Exploration and Laboratory Results
Supporting Information

Note: This report was originally delivered in a web-based format. **Blue Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the Terracon logo will bring you

back to this page. For more interactive features, please view your project online at **client.terracon.com**.

Refer to each individual Attachment for a listing of contents.

Introduction

Terracon Consultants, Inc. (Terracon) is pleased to submit our geotechnical engineering report for the proposed new multi-family apartment building to be located at 601 West Lewis Street in Conroe, Texas. This project was authorized by Mr. Chris Gilliam, Principal with Jones Gillam Renz Architects, through signature of our "Agreement for Services" on November 6, 2025. The project scope was performed in general accordance with Terracon Proposal No. P97255117 dated November 5, 2025. The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Seismic site classification per IBC
- Demolition considerations
- Site preparation and earthwork
- Foundation design and construction
- Floor slab design and construction
- Pavement design and construction

The geotechnical engineering Scope of Services for this project included the advancement of five borings to depths that ranged from about 5 to 20 feet below existing grade, laboratory testing, engineering analysis, and preparation of this report.

Maps showing the site and boring locations are shown on the **Site Location** and **Exploration Plan**, respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs in the **Exploration Results** section.

Project Description

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

Item	Description
Information Provided	A written request for geotechnical work and site plan was provided by the client via email on October 27, 2025. Additional information about the foundations and structural loads was provided by Ryan Hagedorn P.E. with Bob D. Campbell & Company on November 24, 2025.

Item	Description
Project Description	The project consists of a new two-story multi-family apartment building with a footprint area of approximately 9,900 square feet and associated parking and driveway areas.
Building Construction	Wood-frame structure
Finished Floor Elevation	Within approximately one or two feet above existing grade.
Maximum Loads	▪ Columns: 25 kips ▪ Walls: 3 kips per linear foot (klf) ▪ Slabs: 125 pounds per square foot (psf) (assumed)
Anticipated Foundation Systems	Either a conventionally-reinforced, monolithically-poured slab-on-grade or shallow spread/strip footings.
Pavements	We assume rigid (concrete) pavement sections are being considered.
Building Code	2018 IBC

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration.

Item	Description
Parcel Information	The project is located at 601 West Lewis Street in Conroe, Texas. See **Site Location**
Existing Improvements	Existing parking lot with light poles. We understand the light poles will be demolished as part of the proposed development.
Current Ground Cover	The site was occupied by concrete pavement, light poles, and grassy perimeter during our field exploration.
Existing Topography	Relativity level

Geotechnical Characterization

Geology

Based on the geologic maps published by the Bureau of Economic Geology, the site is located in the Willis Formation, the oldest formation of the Houston Group. The Willis Formation was deposited early in the Pleistocene epoch, during the Aftonian Interglacial Stage. It is fluviatile, consisting of sands, silts, and clays in approximately equal amounts.

The coastal plain in this region has a complex tectonic geology, several major features of which are: Gulf Coastal geosyncline, salt domes, and major sea level fluctuations during the glacial stages, subsidence and geologic faulting activities. Most of these geologic faulting activities have ceased for millions of years, but some are still active. A detailed geologic fault investigation and study of the site geology are beyond the scope of this report.

Subsurface Profile

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in the **Exploration Results** and the GeoModel can be found in the **Figures** attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Model Layer	Layer Name	General Description
1	Silty Sand	Tan, gray, dark gray, and reddish brown, medium dense, with scattered roots
2	Sandy Lean Clay	Tan, gray, light gray, and reddish brown, medium stiff to very stiff, with sand seams, ferrous stains, and calcareous nodules
3	Fat Clay	Tan, gray, light gray, and reddish brown, stiff to very stiff, with ferrous stains and slickensides

Groundwater Conditions

Borings B-1 through B-5 were advanced using dry drilling techniques to the boring termination depths that ranged from approximately 5 to 20 feet in an effort to evaluate groundwater conditions at the time of our field program. Groundwater was not observed during or upon completion of drilling.

These water level observations provide an approximate indication of the groundwater conditions existing on the site at the time the observations were made. Longer-term observations using cased holes or piezometers, sealed from the influence of surface water, would be required for a better evaluation of the groundwater conditions on this site.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff, and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than the levels indicated on the boring logs. Also, trapped or "perched" water could be present within the sand or silt seams within native clay soils and/or in cohesionless soils above lower permeability clay soil layers. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project.

Seismic Site Class

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC). Based on the soil properties observed at the site and as described on the exploration logs and results, our professional opinion is that a **Seismic Site Classification of D** be considered for the project. Subsurface explorations at this site extended to a maximum depth of 20 feet. The site properties below the boring depth to 100 feet were estimated based on our experience and knowledge of geologic conditions of the general area. Additional deeper borings or geophysical testing may be performed to confirm the conditions below the current boring depth.

Geotechnical Overview

Based on the information obtained from our subsurface exploration, the site can be developed for the proposed project. A summary of our findings and recommendations is provided below.

Expansive soils were observed at this site. This report provides recommendations to help reduce the effects of soil shrinkage and expansion. However, even if these procedures are followed, some movement and distress in the building addition should be anticipated. The severity of distress will increase if any modification of the site results in excessive wetting or drying of the expansive soils. Eliminating the risk of movement associated with expansive soils may not be feasible. However, this risk can be significantly reduced if the building addition is designed as a structural slab over a void space with the structural loads supported by a foundation system terminated below the active zone. Terracon can provide recommendations for this option, if requested.

The surficial soils observed in portions of the site exhibited low plasticities and a high silt and sand content. If wet and/or soft conditions are present at the time of construction, remedial efforts may be necessary for preparation of the surficial soils in the building and pavement areas to create a working surface. Remedial effort options are discussed in the **Wet Weather/Soft Subgrade Considerations** section of this report.

Demolition of the existing light poles, utilities, pavements, etc. will be performed to facilitate the construction of the proposed building planned at this site. Special care should be exercised to demolish and remove the existing structures, foundations elements, pavements, utilities, and any buried structure to minimize disturbance of the subgrade and potential detrimental effects on construction of the proposed development at this site.

We understand the proposed building at this site is planned to be supported on either a conventionally-reinforced, monolithically-poured slab-on-grade or a shallow spread/strip footing foundation system. These types of foundations may be utilized to support the proposed building planned at this site provided the subgrade is prepared as discussed in this report.

A minimum 66-inch thick select fill pad should be placed under the proposed building to provide uniform support to the floor slab and reduce the estimated Potential Vertical Rise (PVR) of the subgrade to approximately one inch or less.

Rigid pavement sections vary from 5.0 to 7.0 inches of reinforced concrete with chemically treated subgrade.

The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the **Exploration Results**), engineering analyses, and our current understanding of the proposed project. The **General Comments** section provides an understanding of the report limitations.

Earthwork

Earthwork is anticipated to include demolition, stripping, excavations, and fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs, and pavements.

Site Preparation

Construction areas should be stripped of vegetation, topsoil, trees, existing pavements (including crushed stone material) and other debris/unsuitable surface material. Roots of trees to be removed within the construction areas should be grubbed to full depths. Care should be taken to replace or recompact all soil removed or loosened by the removal of tree roots and stumps as recommended in subsequent paragraphs. Proper site drainage should be maintained during construction so that ponding of surface runoff does not occur and cause construction delays and/or inhibit site access.

Demolition of existing light poles, pavements/flatwork, utilities, etc. should be addressed as recommended in **Demolition Considerations**. Once final subgrade elevations have been achieved, the exposed subgrade should be proofrolled with a 20 ton pneumatic roller or equivalent equipment, such as a fully loaded dump truck, to detect weak zones in the subgrade. Weak areas detected during proofrolling, as well as zones containing organic matter and/or debris, should be removed and replaced with soils exhibiting similar classification, moisture content, and density as the adjacent in-situ soils. Proofrolling should be performed under the direct observation of the Geotechnical Engineer or his/her representative and may be waived at the discretion of the Geotechnical Engineer.

Subsequent to proofrolling, and just prior to placement of fill, the exposed subgrade within the construction area should be evaluated for moisture and density. If the moisture and/or density do not meet the criteria described in **Fill Compaction Requirements** for on-site soils, the subgrade should be scarified to a minimum depth of 6 inches, moisture adjusted, and compacted to at least 95 percent of the Standard Effort (ASTM D 698) maximum dry density.

Fill Material Types

Select fill soils to be used at this site for grade adjustments should meet the following criteria:

Fill Type	USCS Classification	Acceptable Location for Placement
Select fill soils	CL and/or SC (10≤PI≤20)	Must be used to construct the select fill pad under the floor slab and for all grade adjustments within the building area.
On-site soils[1]	Varies	The on-site soils appear suitable for use as fill within the pavement areas, provided they are free of organics and debris.

1. The utilization of on-site silty/sandy soils may present difficulties during construction due to the increased sand and silt content of these soils, especially during and soon after periods of wet weather. If the utilization of the silty/sandy soils as fill is planned in the pavement areas, treatment of these soils with lime-flyash should produce a material that would be more suitable for use as fill.

If blended or mixed soils are intended for use as select fill, Terracon should be contacted to provide additional recommendations. Blended or mixed soils do not occur naturally. These soils are a blend of sand and clay and will require mechanical mixing at the site with a pulvimixer. If these soils are not mixed thoroughly to break down the clay clods and blend-in the sand to produce a uniform soil matrix, the fill material may be detrimental to the performance of the foundations. If blended soils are used, we recommend that additional samples of the blended soils as well as the clay clods, be obtained prior to and during earthwork operations to evaluate if the blended soils can be used in lieu of select fill. The actual type and amount of mechanical mixing at the site will depend on the amount of clay and sand, and properties of the clay.

Fill Compaction Requirements

Select fill and on-site soils should meet the following compaction requirements.

Item	Description
Fill lift thickness	The fill soils should be placed on prepared surfaces in lifts not to exceed 8 inches loose measure.

Item	Description
Compaction Requirements	■ Select fill and on-site soils placed below 3 feet of final grade should be compacted to at least 100 percent of the Standard Effort (ASTM D 698) maximum dry density. ■ Select fill and on-site soils placed within 3 feet of the final grade should be compacted to at least 95 percent of the Standard Effort (ASTM D 698) maximum dry density. ■ The select fill soils and on-site silty sand soils should be moisture adjusted to within 2 percent of the optimum moisture content. ■ The on-site clay soils should be moisture adjusted to between optimum +4 percent of the optimum moisture content.

Prior to any filling operations, samples of the proposed borrow and on-site materials should be obtained for laboratory moisture-density testing. The tests will provide a basis for evaluation of fill compaction by in-place density testing. A qualified soil technician should perform sufficient in-place density tests during the filling operations to evaluate that proper levels of compaction, including dry unit weight and moisture content, are being attained.

Utility Trench Backfill

Utility trenches are a common source of water infiltration and migration. All utility trenches that penetrate beneath the structures should be effectively sealed to restrict water intrusion and flow through the trenches, which could migrate below the structure. The trench should provide an effective trench plug that extends at least 5 feet out from the face of the structure exterior. The plug material should consist of clay compacted at a water content at or above the soils optimum water content. The clay fill should be placed to completely surround the utility line and be compacted in accordance with recommendations in this report.

Grading and Drainage

All grades must provide effective drainage away from the proposed building during and after construction. Water permitted to pond next to the building can result in distress in the building. These greater movements can result in unacceptable differential slab movements, cracked slabs and walls, and roof leaks. Slabs and foundation performances described in this report are based on effective drainage for the life of the building and cannot be relied upon if effective drainage is not maintained.

Exposed ground should be sloped away from the building for at least 10 feet beyond the perimeter of the building. After construction and landscaping, we recommend verifying final grades to document that effective drainage has been achieved. Grades around the building should also be periodically inspected and adjusted as necessary, as part of the building's maintenance program.

Planters located within 10 feet of the proposed building should be self-contained to prevent water accessing the building and pavement subgrade soils. Locate sprinkler mains and spray heads a minimum of 5 feet away from the building lines. Low-volume, drip-style landscaped irrigation should not be used near the building. Collect roof runoff in drains or gutters. Discharge roof drains and downspouts onto pavements and/or flatworks which slope away from the building or extend down spouts a minimum of 10 feet away from the building.

Flatworks will be subject to post construction movement. Maximum grades practical should be used for flatwork to prevent water from ponding. Allowances in final grades should also consider post-construction movement of flatwork, particularly if such movement would be critical. Where flatwork abuts the building, effectively seal and maintain joints to prevent surface water infiltration.

Wet Weather/Soft Subgrade Considerations

Due to the high silt and sand content and low plasticities of the surficial soils in portions of the site, proper compaction may be difficult to achieve. In addition, construction during and soon after wet weather periods may encounter difficulties due to wet and soft surficial soils becoming a general hindrance to equipment as a result of rutting and/or pumping of the soil surface. Clearing activities can worsen site conditions. This condition is primarily due to their lack of cohesion (low clay content) and little to no confining pressure near the ground surface. If the subgrade cannot be adequately compacted to the minimum densities as described above, one of the following methods should be used to improve the soils: 1) removal and replacement with select fill, 2) chemical treatment of the soil to dry the subgrade, or 3) drying by natural means if the schedule allows.

Based on our experience with similar soils, chemical treatment is an efficient and effective method to increase the supporting value of wet and soft subgrade such as that observed at this site. Chemical treatment may be necessary to depths of approximately one to two feet or greater of the near-surface silty/sandy soils, depending on the condition of the subgrade at the time of construction. We suggest that a cost be included in the construction budget for chemical treatment of the soils using a lime-flyash mixture to aid drying and improve the condition of the soil if the soil is wet and/or soft at the time of construction. We recommend that this cost be in the form of a contingency or allowance to be used if needed. Terracon should be contacted for additional recommendations if chemical treatment of the soils is planned due to soft and/or wet subgrade.

Demolition Considerations

Special care should be exercised to demolish and remove any existing structures, light poles, pavements, and utilities to minimize disturbance of the subgrade and potential detrimental effects on construction of the proposed development at this site.

We anticipate that the existing light poles are supported on either shallow footings or drilled footings. Shallow footings should be removed and the excavation backfilled with properly placed and compacted select fill. If drilled footings are observed, we recommend the shafts be broken off at an elevation about 24 inches below the bottom of the proposed grade beam depth. If portions of drilled footings are left in place, they should be surveyed and superimposed on the proposed development plans to evaluate the potential for obstructions to the new development. Terracon should be contacted if drilled footings are planned to be excavated and completely removed. Complete removal of drilled footings will require significant earthwork activities to backfill the resulting excavations in such a manner as to make the site suitable for new construction.

All utilities and associated bedding material that are planned to be abandoned should be completely removed from within the new building and pavement areas. As an alternate to complete removal, the existing utilities may be abandoned in-place if they do not interfere with the planned construction. If the utilities are abandoned in-place, they should be properly pressure-grouted to completely fill the utility.

The excavations resulting from foundation and utility removal should be backfilled in accordance with the recommendations provided in **Earthwork**. If situations are encountered where compaction of fill would not be efficient because of the size or location of an excavation, the use of cement stabilized sand or flowable fill may be considered as a suitable alternative to select fill. The compressive strength of the cement stabilized sand or flowable fill utilized should be maintained between 50 to 100 pounds per square inch (psi).

Although not observed during our field activities, the potential exists that other types of buried structures (wells, cisterns, etc.) could exist on this site. These buried structures will need to be addressed on an individual basis if encountered during construction.

Shallow Foundations

If the site has been prepared in accordance with the requirements noted in **Earthwork**, the following design parameters are applicable for shallow foundations.

Design Recommendations – Slab-on-Grade Foundation System

Planned finished grades at the site were not available at the time of this report. We anticipate that the finished floor elevation for the proposed building is planned to be within approximately one to two feet above existing grade. If cuts and/or significant fills are

planned, Terracon should be notified to review and/or modify our recommendations given in this subsection.

The near-surface soils at this site generally exhibited a high expansion potential. These soils can subject the lightly loaded interior floor slab to significant movements (due to shrinking and swelling) with fluctuations in their moisture content. This movement potential is influenced primarily by the properties of the subgrade soils, as well as the moisture content of the subgrade at the time of construction, overburden pressures, and the stability of the moisture contents throughout the life of the building. Based on the information developed from our field and laboratory programs and on method TEX-124-E in the Texas Department of Transportation (TxDOT) Manual of Testing Procedures, we estimate that the subgrade soils at this site exhibit a Potential Vertical Rise (PVR) of up to approximately 3¾ inches. Therefore, we highly recommend that the near-surface soils be prepared as stated below to reduce the potential for slab movement associated with volumetric changes of the near-surface clay soils due to moisture variations to a more acceptable level. The actual movements could be greater if poor drainage, ponded water, and/or other sources of moisture are allowed to infiltrate beneath the structure after construction.

The most common method of subgrade preparation to reduce the potential expansion of the subgrade would be to provide a pad of properly placed and compacted select fill beneath the building area. The corresponding decrease in the potential soil moments is primarily a function of the fill pad thickness and the moisture levels of the underlying clay subgrade. While the indicated preparations do not eliminate the potential for soil moment, the magnitude of such movements should be reduced to more acceptable levels. To provide uniform support to the floor slab and to reduce the estimated PVR to approximately one inch or less, we recommend that a minimum 66 inches of properly placed and compacted select fill material be constructed immediately beneath the floor slab. The select fill pad should extend a minimum of 5 feet beyond the edge of the proposed building. The final exterior grade adjacent to the structure should be sloped to promote effective drainage away from the building.

Select fill soils should be utilized for all grade adjustments within the proposed building area. The subgrade soils and select fill pad soils should be prepared as outlined in **Earthwork**, which contains material and placement requirements for select fill, as well as other subgrade preparation recommendations.

The subgrade soils for flatwork outside the building which will be sensitive to movement should be prepared as discussed previously. This preparation will be important on surrounding sidewalks and paving immediately adjacent to the building. If these adjacent flatwork areas are not prepared as stated above for the building area, the estimated PVR for these areas could approach those indicated previously for in-situ conditions. If the soils swell in those areas, this movement could result in significant distress to the adjacent sidewalks and paving and possibly result in reversed drainage (flow of runoff toward the building) around the perimeter of the building.

Based upon the above recommendations, the grade beams of the slab-on-grade foundation should bear within properly placed and compacted select fill soils, provided that the select fill pad and subgrade soils are prepared as outlined in **Earthwork**.

The slab-on-grade foundation may be designed using the following parameters provided that the building subgrade is prepared as discussed above:

Description	Design Parameters
Select fill pad	Minimum thickness of 66 inches
Estimated PVR [1]	Approximately one inch or less
Climatic rating	25
Design Plasticity Index [1]	26
Soil support Index [1]	0.92
Minimum grade beam embedment depth	18 inches below exterior grade
Allowable bearing capacity	Dead Load Plus Sustained Live Load: 1,000 psf Total Net Load: 1,500 psf

1. Design parameters based on a minimum 66-inch thick select fill pad.

The parameters indicated for the above design conditions are based on criteria published by the Building Research Advisory Board (B.R.A.B.) and Wire Reinforcing Institute (W.R.I.). The B.R.A.B. and W.R.I. methods are essentially empirical design techniques and the parameters provided are based on our interpretation of the project soil borings and criteria published in the B.R.A.B. and W.R.I. design manuals.

The slab-on-grade foundation system should be designed using B.R.A.B., W.R.I., or other appropriate method to tolerate the anticipated soil movement and provide satisfactory support to the proposed building. The foundation should have adequate interior and exterior grade beams, if necessary, to provide sufficient rigidity to the foundation system such that the slab deflections that result are considered tolerable to the supported building. Grade beams may be thickened and widened at column locations to serve as spread footings at areas of concentrated loadings. The minimum grade beam depth recommendation provided above is to reduce surface water migration below the foundation elements and develop end bearing and is not based on structural considerations.

Post construction settlements for the described slab-on-grade foundation system should be about one inch, provided that the subgrade soils are prepared as outlined herein and that the select fill is properly placed and compacted in accordance with the recommendations contained in this report. Settlement response of the foundation

system is expected to be influenced more by the quality of construction and fill placement than by soil-structure interaction.

Design Recommendations – Shallow Spread/Strip Footings

Item	Description
Minimum embedment depth[1]	3 feet below final grade (grade at the time of our field program)
Allowable bearing pressures[2] **(individual footings)**	Net dead plus sustained live load – 2,000 psf Net total load – 3,000 psf
Allowable bearing pressures[3] **(strip footing)**	Net dead plus sustained live load – 1,600 psf Net total load – 2,400 psf
Approximate post-construction settlement[4]	Approximately one inch
Estimated post-construction differential settlement[5]	Approximately ½ of post-construction settlement
Allowable passive pressure[6]	750 psf
Allowable frictional resistance[7]	250 psf
Uplift resistance[8]	Foundation Weight (150 pcf) & Soil Weight (120 pcf)

1. The footings should bear within properly placed and compacted select fill soils.
2. Whichever condition yields a larger bearing area.
3. Defined as a footing at least twice as long as it is wide.
4. This estimated post-construction settlement of the shallow footings is based on proper construction practices being followed. A clear distance between footings of one footing size of the larger of the two footings should not produce overlapping stress distributions and would essentially behave as independent foundations.
5. The post-construction differential settlements may result from variances in subsurface conditions, loading conditions, and construction procedures. The settlement response of the footings will be more dependent upon the quality of construction than upon the response of the subgrade to the foundation loads.
6. The passive pressure along the exterior face of the footings should be neglected within the upper 4 feet due to surface effects and the presence of fill and expansive soils unless pavement is provided up to the edge of the structures. For interior footings, the allowable passive pressure may be used for the entire depth of the footing.
7. To be utilized on the base of the footings.
8. Structural uplift loads on the shallow footings may be resisted by the weight of the foundation plus the weight of any soil directly above the foundation. The ultimate uplift capacity of shallow footings should be reduced by an appropriate factor of safety to compute allowable uplift capacity.

Construction Considerations – Shallow Foundations

Excavations for shallow footings and grade beams should be performed with equipment capable of providing a relatively clean bearing area. The bottom 6 inches of the foundation and grade beam excavations should be completed with a smooth-mouthed bucket or by hand labor. The excavations should be neatly excavated and properly formed. Debris in the bottom of the excavation should be removed prior to steel placement. Based on the groundwater observations obtained during our field program (refer to **Groundwater Conditions**), significant groundwater seepage is not anticipated for shallow footings or grade beams at the recommended bearing depth. However, water should not be allowed to accumulate at the bottom of the foundation excavations. To reduce the potential for groundwater seepage into the excavations and to minimize disturbance to the bearing area, we recommend that concrete and steel be placed as soon as possible after the excavations are completed. Excavations should not be left open overnight. The bearing surface of the footings should be evaluated immediately prior to placing concrete or a seal slab.

A thin seal slab of lean concrete (approximately 2 to 4 inches thick) should be placed at the bottom of the footing excavation to protect the bearing surface of the footings from disturbance and/or infiltration of ground/surface water if the footing cannot be poured within the same day of excavation.

Foundation Construction Monitoring

The performance of the foundation systems will be highly dependent upon the quality of construction. Thus, we recommend that subgrade preparation, fill compaction, and foundation installation be observed full time by an experienced Terracon soil technician under the direction of our geotechnical engineer. During foundation construction, the base of the footing excavations should be observed to evaluate the condition of the subgrade. We would be pleased to develop a plan for compaction and foundation installation observation to be incorporated in the overall quality control program.

Floor Slab

Planned finished grade for the proposed building was not available at the time of this report. We anticipate that the finished floor elevation of the proposed building is planned to be within about one to two feet above existing grade. If the grading is planned to be altered from what has been previously described, Terracon should be notified to review and/or modify our recommendations given in the subsection.

As stated in **Design Recommendations - Slab-on-Grade Foundation System**, the subgrade soils at the site are estimated to exhibit a PVR of up approximately 3¾ inches.

To provided uniform support to the floor slab and to reduce the estimated PVR to approximately one inch or less, we recommend that a minimum 66 inches of properly placed and compacted select fill be placed beneath the floor slab. The select fill pad area associated with the shallow spread/strip footings should be constructed as discussed in **Design Recommendations - Slab-on-Grade Foundation System**.

The subgrade and select fill beneath the floor slab should be prepared as outlined in the **Earthwork** section of this report, which contains material and placement requirements for select fill, as well as other subgrade preparation recommendations.

Pavements

Once the subgrade is properly prepared, a rigid pavement system may be considered for this project as planned. Detailed traffic loads and frequencies were not available. However, we understand that traffic will primarily consist of passenger vehicles in the parking areas and passenger vehicles combined with garbage trucks and large multi-axle moving trucks in driveway areas.

Tabulated in the following table are the assumed traffic frequencies and loads used to design pavement sections for this project. When actual traffic conditions have been determined Terracon should be contacted to review the information to consider a need for revision of the pavement design and related recommendations.

Pavement Area	Traffic Design Index[1]	Description
Automobile Parking Areas	DI-1	Light traffic (Few vehicles heavier than passenger cars, no regular use by heavily loaded two axle trucks.) (EAL[2] < 6)
Driveways (Light Duty)	DI-2	Medium to light traffic (Similar to DI-1 including not over 50 loaded two axle trucks or lightly loaded larger vehicles per day. No regular use by heavily loaded trucks with three or more axles.) (EAL = 6-20)
Driveways and Truck/Bus Traffic Areas (Medium Duty)	DI-3	Medium traffic (Including not over 300 heavily loaded two axle trucks plus lightly loaded trucks with three or more axles and no more than 30 heavily loaded trucks with more than three axles per day.) (EAL = 21-75)

1. Based on NSSGA traffic design indices.
2. Equivalent daily 18-kip single-axle load applications.

The top 6 inches of the finished subgrade soils directly beneath the pavements should be chemically treated with lime or a mixture of lime and flyash. The decision about the type and proper amount of additive should be made after the subgrade is open for inspection.

Chemical treatment will increase the supporting value of the subgrade and decrease the effect of moisture on subgrade soils. These 6 inches of treatment is a required part of the pavement design and is not a part of the site and subgrade preparation for wet/soft subgrade conditions.

Listed below are pavement component thicknesses, which may be used as a guide for pavement systems at the site for the traffic classifications stated herein. These systems were derived based on general characterization of the subgrade. Specific testing (such as CBR's, resilient modulus tests, etc.) was not performed for this project to evaluate the support characteristics of the subgrade.

Rigid Pavement Section			
Component	**Material Thickness, Inches**		
	DI-1	**DI-2**	**DI-3**
Reinforced concrete	5.0	6.0	7.0
Treated subgrade	6.0	6.0	6.0

Waste dumpster areas should be constructed of at least 7 inches of reinforced concrete pavement. The concrete pad areas should be designed so that the vehicle wheels of the collection truck are supported on the concrete while the dumpster is being lifted to support the large wheel loading imposed during waste collection.

Presented below are our recommended material requirements for the various pavement sections.

Reinforced Concrete Pavement – The materials and properties of reinforced concrete pavement should meet applicable requirements in the ACI Manual of Concrete Practice. The portland cement concrete mix should have a minimum 28-day compressive strength of 3,500 psi.

If river gravel is planned to be utilized in the portland cement concrete mix, Terracon should be contacted for additional services. The presence of river gravel in the portland cement concrete mix can result in excessive cracking and distress to the concrete pavement

Reinforcing Steel – ACI recommendations indicate that distributed steel reinforcement is not necessary when the pavement is properly jointed to form short panel lengths that will help reduce intermediate cracking. Provided the concrete pavement is designed and constructed as stated herein, the installation of reinforcing steel is optional and should be evaluated by the design team. Proper layout and installation of the joints within the pavement is critical to help control intermediate cracking.

If reinforcing steel is planned to be utilized in the concrete pavement by the design team, the following amount of reinforcing steel should be used as a guideline:

DI-1: #3 bars spaced at 18 inches or #4 bars spaced at 24 inches on centers in both directions.
DI-2: #3 bars spaced at 12 inches or #4 bars spaced at 18 inches on centers in both directions.
DI-3: #4 bars spaced at 18 inches on centers in both directions.

Control Joint Spacing – ACI recommendations indicate that control joints should be spaced at a maximum spacing of 30 times the thickness of the pavement for unreinforced parking lot pavements. Furthermore, ACI recommends a maximum control joint spacing of 12.5 feet for 5-inch pavements and a maximum control joint spacing of 15 feet for 6-inch or thicker pavements. Sawcut control joints should be cut within 4 to 12 hours of concrete placement to help control the formation of plastic shrinkage cracks as the concrete cures. The depth of the joint should be at least one-quarter of the slab depth when using a conventional saw or one inch when using early entry saws. The width of the cut should be in accordance with the joint sealant manufacturer recommendations.

Expansion Joint Spacing – ACI recommendations indicate that regularly spaced expansion joints may be deleted from concrete pavements. Therefore, the installation of expansion joints is optional and should be evaluated by the design team.

Construction Joints – When concrete is planned to be placed at different times, we recommend the use of a construction joint between paving areas. The construction joint should consist of a butt joint (not a keyway joint).

Concrete Curing Compound – A concrete curing compound, such as a Type 2 membrane curing compound conforming to TxDOT DMS-4650, "Hydraulic Cement Concrete Curing Materials and Evaporation Retardants" or equivalent, should be applied to the concrete surface immediately after placement of the concrete in accordance with TxDOT 2014 Standard Specifications Item 360.

Dowels at Expansion/Construction Joints – The dowels at expansion/construction joints should be spaced at 12-inch centers and consist of the following:

DI-1: 5/8-inch diameter, 12-inches long with 5-inch embedment.
DI-2: 3/4-inch diameter, 14-inches long with 6-inch embedment.
DI-3: 7/8-inch diameter, 14-inches long with 6-inch embedment.

Base Material – Base material should be composed of crushed limestone or crushed concrete meeting the requirements of TxDOT 2014 Standard Specifications Item 247, Type A or D, Grade 1-2. The crushed concrete or crushed limestone should be compacted to at least 95 percent of the Modified Effort (ASTM D1557) maximum dry density and be moisture adjusted to within 2 percent of the optimum moisture content.

Lime Treated Subgrade –The on-site medium to high plasticity soils (PI>20) should be treated with lime in accordance with the TXDOT 2014 Standard Specifications Item 260. The amount of lime should be determined for subgrade soils by conducting laboratory tests just prior to construction. Based on the classification test results, we anticipate that about 6 to 8 percent lime by dry weight may be used for estimating and planning. The percentages are given as application by dry weight and are typically equivalent to about 30 to 40 pounds of lime per square yard per 6-inch depth. The pulverization, mixing and curing of the lime treated subgrade is of particular importance in clay soils. The subgrade should be compacted to a minimum of 95 percent of the Standard Effort (ASTM D 698) maximum dry density at a moisture content between optimum and 4 percent wet of the optimum moisture content.

Lime Flyash Treated Subgrade – The on-site silt/sand soils and low to medium plasticity clay soils (PI≤20) should be treated with lime-flyash in accordance with TXDOT 2014 Standard Specifications Item 265. Based on the classification test results, we recommend that about 2 to 3 percent lime and 7 to 8 percent flyash by dry weight be used for estimating and planning. The percentages are given as application by dry weight of soil and are typically equivalent to about 10 to 15 pounds of lime and 35 to 40 pounds of flyash per square yard per 6-inch depth. Lime-flyash is also available pre-mixed, typically in percentages of 20 to 30 percent lime and 70 to 80 percent flyash. These pre-mixed products may be used if preferred at a rate of 50 pounds per square yard per 6-inch depth. The actual quantity of the lime and flyash should be determined at the time of construction based on laboratory testing conducted using bulk samples of the subgrade soils. The subgrade should be compacted to a minimum of 95 percent of the material's Standard Effort (ASTM D698) maximum dry density at a moisture content within 2 percent wet of the optimum moisture content.

Preferably, traffic should be kept off the treated subgrade for 7 days to facilitate curing of the soil-chemical mixture. In addition, the subgrade is not suitable for heavy construction traffic prior to paving.

The pavement design methods described above are intended to provide structural sections with adequate thickness over a particular subgrade such that wheel loads are reduced to a level the subgrade can support. The support characteristics of the subgrade for pavement design do not account for shrink/swell movements of an expansive clay subgrade such as the soils encountered at this site. Thus, the pavement may be adequate from a structural standpoint, yet still experience cracking and deformation due to shrink/swell related movement of the subgrade. Post-construction subgrade movements and some cracking of pavements are not uncommon for subgrade conditions such as those observed at this site. Reducing moisture changes in the subgrade is important to reduce shrink/swell movements. Although chemical treatment will help to reduce such movement/cracking, this movement/cracking cannot be economically eliminated.

Related civil design factors such as subgrade drainage, shoulder support, cross-sectional configurations, surface elevations and environmental factors which will significantly affect the service life must be included in the preparation of the construction drawings and specifications. Normal periodic maintenance will be required.

Long-term pavement performance will be dependent upon several factors, including maintaining subgrade moisture levels and providing for preventative maintenance. The following recommendations should be implemented to help promote long-term pavement performance:

- The subgrade and the pavement surface should be designed to promote proper surface drainage, preferably at a minimum grade of 2 percent;
- Install joint sealant and seal cracks immediately;
- Extend curbs into the treated subgrade for a depth of at least 4 inches to help reduce moisture migration into the subgrade soils beneath the pavement section; and
- Place compacted, low permeability clayey backfill against the exterior side of the curb and gutter.

Preventative maintenance should be planned and provided for the pavements at this site. Preventative maintenance activities are intended to slow the rate of pavement deterioration, and consist of both localized maintenance (e.g. crack and joint sealing and patching) and global maintenance (e.g. surface sealing). Prior to implementing any maintenance, additional engineering observations are recommended to determine the type and extent of preventative maintenance.

General Comments

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner

is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly affect excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety and cost estimating including excavation support and dewatering requirements/design are the responsibility of others. Construction and site development have the potential to affect adjacent properties. Such impacts can include damages due to vibration, modification of groundwater/surface water flow during construction, foundation movement due to undermining or subsidence from excavation, as well as noise or air quality concerns. Evaluation of these items on nearby properties are commonly associated with contractor means and methods and are not addressed in this report. The owner and contractor should consider a preconstruction/precondition survey of surrounding development. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

Figures


Contents:

GeoModel

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

GeoModel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
1	Silty Sand	Tan, gray, dark gray, and reddish brown, medium dense, with scattered roots
2	Clayey Sand and Sandy Lean Clay	Tan, gray, light gray, and reddish brown, loose to medium dense or medium stiff to very stiff, with sand seams, ferrous stains, and calcareous nodules
3	Fat Clay	Tan, gray, light gray, and reddish brown, stiff to very stiff, with ferrous stains and slickensides

Legend	
Silty Sand	Sandy Lean Clay
Fat Clay	Concrete
Clayey Sand	

NOTES:
Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Attachments

Exploration and Testing Procedures

Field Exploration

Number of Borings	Approximate Boring Depth (feet)	Location
3 (B-1 through B-3)	20	Building area
2 (B-4 and B-5)	5	Parking/driveway area

Boring Layout and Elevations: Terracon personnel provided the boring layout using handheld GPS equipment (estimated horizontal accuracy of about ±20 feet) and referencing existing site features. The boring depths were measured from the existing ground surface at the time of our field activities.

Subsurface Exploration Procedures: We advanced the borings with an ATV-mounted rotary drill rig using continuous flight augers (solid stem). Six samples were obtained in the upper 12 feet of each boring and at intervals of 5 feet thereafter, or to the boring termination depths of 5 feet. In the thin-walled tube sampling procedure, a thin-walled, seamless steel tube with a sharp cutting edge was pushed hydraulically into the soil to obtain a relatively undisturbed sample. In the split-barrel sampling procedure, a standard 2-inch outer diameter split-barrel sampling spoon was driven into the ground by a 140-pound hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. The SPT resistance values, also referred to as N-values, are indicated on the boring logs at the test depths. For safety purposes, all borings were backfilled with auger cuttings after their completion. Pavements were patched with pre-mixed concrete.

We also observed the boreholes while drilling and at the completion of drilling for the presence of groundwater. Groundwater was not observed at these times in the boreholes.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials observed during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Dry Unit Weight
- Unconfined Compression
- Atterberg Limits
- Percent Passing the No. 200 Sieve

The laboratory testing program included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.

Samples not tested in the laboratory will be stored for a period of 30 days subsequent to the submittal of this report and will be discarded after this period unless we are notified otherwise.

Site Location and Exploration Plan

Contents:

Site Location
Exploration Plan

Note: All attachments are one page unless noted above.

Site Location




DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

Exploration Plan




DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES MAP PROVIDED BY MICROSOFT BING MAPS

Exploration and Laboratory Results

Contents:

Boring Logs (B-1 through B-5)

Note: All attachments are one page unless noted above.

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

Boring Log No. B-1

Location: See Exploration Plan

Latitude: 30.3146° Longitude: -95.4604°

Model Layer	Graphic Log	Depth (Ft.)	Description	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Strength Test: Test Type	Strength Test: Compressive Strength (tsf)	Strength Test: Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits: LL-PL-PI	Percent Fines
1		2.0	SILTY SAND (SM), tan, gray, and reddish brown, medium dense, with scattered roots				4.5 (HP)				7.3			35.0
2		10.0	SANDY LEAN CLAY (CL), tan, gray, and reddish brown, stiff to very stiff				6-11-12 N=23							
				5			11-13-17 N=30				12.2		45-13-32	
			- with sand seams and calcareous nodules 6 to 8 feet				2.5 (HP)							
							1.5 (HP)				17.9		37-12-25	
3		20.0	FAT CLAY (CH), tan and gray, very stiff, with ferrous stains	10			2.5 (HP)							
							3.5 (HP)							
				15										
			- with slickensides below 18 feet				4.5 (HP)							
			Boring Terminated at 20 Feet	20										

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Water Level Observations
Groundwater not observed during or upon completion of drilling

Drill Rig
ATV

Hammer Type
Rope and Cathead

Driller
DAS

Notes

Advancement Method
Dry augered to about 20 feet.

Abandonment Method
Boring backfilled with auger cuttings upon completion.

Logged by
J. Richardson

Boring Started
11-17-2025

Boring Completed
11-17-2025

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

Boring Log No. B-2

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 30.3147° Longitude: -95.4608° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Strength Test: Test Type	Strength Test: Compressive Strength (tsf)	Strength Test: Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits: LL-PL-PI	Percent Fines
		PAVEMENT, about 7 inches of concrete underlain by about 12 inches of sand and crushed stone material 1.6											
1		SILTY SAND (SM), tan, gray, and dark gray, medium dense, with scattered roots 3.6				2.5 (HP)							
2		SANDY LEAN CLAY (CL), gray and reddish brown, medium stiff to very stiff - with calcareous nodules 3.6 feet to 7.6 feet	5			1.5 (HP)	UC	0.95	6.3	17.0	113	44-12-32	
						1.5 (HP)							
		- tan ang gray 7.6 feet to 11.6 feet				1.5 (HP)							
		11.6	10			3.0 (HP)				24.5		48-15-33	
3		FAT CLAY (CH), tan and gray, very stiff, with ferrous stains and slickensides				3.0 (HP)							
		- reddish brown and light gray below 14.6 feet	15			3.5 (HP)							
		21.6	20			3.5 (HP)							
		Boring Terminated at 21.6 Feet											

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Water Level Observations
Groundwater not observed during or upon completion of drilling

Drill Rig
ATV

Driller
DAS

Notes

Advancement Method
Dry augered to about 21.6 feet.

Logged by
J. Richardson

Boring Started
11-17-2025

Abandonment Method
Boring backfilled with auger cuttings upon completion and patched at the surface with a concrete patch.

Boring Completed
11-17-2025

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

Boring Log No. B-3

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 30.3146° Longitude: -95.4609° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Strength Test: Test Type	Strength Test: Compressive Strength (tsf)	Strength Test: Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits: LL-PL-PI	Percent Fines
		PAVEMENT, about 8 inches of concrete underlain by about 21 inches of sand and crushed stone material											
		2.5											
3		FAT CLAY (CH), reddish brown and gray, stiff to very stiff				1.5 (HP)				24.8		59-15-44	
			5			1.5 (HP)	UC	1.39	15	24.2	99		
						1.5 (HP)							
						1.5 (HP)				25.5		65-18-47	
			10			2.0 (HP)							
		- reddish brown and light gray, with slickensides below 10.5 feet				2.0 (HP)							
			15										
		- with ferrous stains below 15.5 feet				3.5 (HP)							
			20			4.5 (HP)							
		22.5											
		Boring Terminated at 22.5 Feet											

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Water Level Observations
Groundwater not observed during or upon completion of drilling

Drill Rig
ATV

Driller
DAS

Notes

Advancement Method
Dry augered to about 22.5 feet.

Abandonment Method
Boring backfilled with auger cuttings upon completion and patched at the surface with a concrete patch.

Logged by
J. Richardson

Boring Started
11-17-2025

Boring Completed
11-17-2025

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

Boring Log No. B-4

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 30.3149° Longitude: -95.4610° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Strength Test: Test Type	Strength Test: Compressive Strength (tsf)	Strength Test: Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits: LL-PL-PI	Percent Fines
		PAVEMENT, about 7 inches of concrete underlain by about 10 inches of sand and crushed stone material 1.4											
3		FAT CLAY (CH), reddish brown and gray, stiff	5			1.5 (HP)				24.2		67-17-50	
						1.5 (HP)							
		7.4				1.5 (HP)							
		Boring Terminated at 7.4 Feet											

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Water Level Observations
Groundwater not observed during or upon completion of drilling

Drill Rig
ATV

Driller
DAS

Notes

Advancement Method
Dry augered to about 7.4 feet.

Logged by
J. Richardson

Boring Started
11-17-2025

Abandonment Method
Boring backfilled with auger cuttings upon completion and patched at the surface with a concrete patch.

Boring Completed
11-17-2025

Multi-Family Apartment Complex
601 West Lewis Street | Conroe, Texas
Terracon Project No. 97255117

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

Boring Log No. B-5

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 30.3149° Longitude: -95.4604° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Strength Test: Test Type	Strength Test: Compressive Strength (tsf)	Strength Test: Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits: LL-PL-PI	Percent Fines
		PAVEMENT, about 34 inches of concrete underlain by about 12 inches of sand and crushed stone material											
		3.8											
2		CLAYEY SAND (SC), tan and gray, loose to medium dense	5			1.0 (HP)				21.0		49-14-35	47.4
		- reddish brown and light gray below 5.8 feet				2.0 (HP)							
						1.5 (HP)							
		9.8											
		Boring Terminated at 9.8 Feet											

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Water Level Observations
Groundwater not observed during or upon completion of drilling

Drill Rig
ATV

Driller
DAS

Notes

Advancement Method
Dry augered to about 9.8 feet.

Logged by
J. Richardson

Boring Started
11-17-2025

Abandonment Method
Boring backfilled with auger cuttings upon completion and patched at the surface with a concrete patch.

Boring Completed
11-17-2025

Supporting Information

Contents:


General Notes
Unified Soil Classification System

Note: All attachments are one page unless noted above.

Terracon
11133 Interstate 45 S Ste T
Conroe, TX

General Notes

Sampling



Water Level



Water Initially Encountered

Water Level After a Specified Period of Time

Water Level After a Specified Period of Time

Cave In Encountered

Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations.

Field Tests

N	Standard Penetration Test Resistance (Blows/Ft.)
(HP)	Hand Penetrometer
(T)	Torvane
(DCP)	Dynamic Cone Penetrometer
UC	Unconfined Compressive Strength
(PID)	Photo-Ionization Detector
(OVA)	Organic Vapor Analyzer

Descriptive Soil Classification

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

Location And Elevation Notes

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

Strength Terms

Relative Density of Coarse-Grained Soils (More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance		Consistency of Fine-Grained Soils (50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance		
Relative Density	Standard Penetration or N-Value (Blows/Ft.)	Consistency	Unconfined Compressive Strength Qu (tsf)	Standard Penetration or N-Value (Blows/Ft.)
Very Loose	0 - 3	Very Soft	less than 0.25	0 - 1
Loose	4 - 9	Soft	0.25 to 0.50	2 - 4
Medium Dense	10 - 29	Medium Stiff	0.50 to 1.00	4 - 8
Dense	30 - 50	Stiff	1.00 to 2.00	8 - 15
Very Dense	> 50	Very Stiff	2.00 to 4.00	15 - 30
		Hard	> 4.00	> 30


Relevance of Exploration and Laboratory Test Results

Exploration/field results and/or laboratory test data contained within this document are intended for application to the project as described in this document. Use of such exploration/field results and/or laboratory test data should not be used independently of this document.

Unified Soil Classification System

Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests [A]				Soil Classification	
				Group Symbol	Group Name [B]
Coarse-Grained Soils: More than 50% retained on No. 200 sieve	**Gravels:** More than 50% of coarse fraction retained on No. 4 sieve	**Clean Gravels:** Less than 5% fines [C]	Cu≥4 and 1≤Cc≤3 [E]	GW	Well-graded gravel [F]
			Cu<4 and/or [Cc<1 or Cc>3.0] [E]	GP	Poorly graded gravel [F]
		Gravels with Fines: More than 12% fines [C]	Fines classify as ML or MH	GM	Silty gravel [F, G, H]
			Fines classify as CL or CH	GC	Clayey gravel [F, G, H]
	Sands: 50% or more of coarse fraction passes No. 4 sieve	**Clean Sands:** Less than 5% fines [D]	Cu≥6 and 1≤Cc≤3 [E]	SW	Well-graded sand [I]
			Cu<6 and/or [Cc<1 or Cc>3.0] [E]	SP	Poorly graded sand [I]
		Sands with Fines: More than 12% fines [D]	Fines classify as ML or MH	SM	Silty sand [G, H, I]
			Fines classify as CL or CH	SC	Clayey sand [G, H, I]
Fine-Grained Soils: 50% or more passes the No. 200 sieve	**Silts and Clays:** Liquid limit less than 50	**Inorganic:**	PI > 7 and plots above "A" line [J]	CL	Lean clay [K, L, M]
			PI < 4 or plots below "A" line [J]	ML	Silt [K, L, M]
		Organic:	$\frac{LL\ oven\ dried}{LL\ not\ dried} < 0.75$	OL	Organic clay [K, L, M, N]
					Organic silt [K, L, M, O]
	Silts and Clays: Liquid limit 50 or more	**Inorganic:**	PI plots on or above "A" line	CH	Fat clay [K, L, M]
			PI plots below "A" line	MH	Elastic silt [K, L, M]
		Organic:	$\frac{LL\ oven\ dried}{LL\ not\ dried} < 0.75$	OH	Organic clay [K, L, M, P]
					Organic silt [K, L, M, Q]
Highly organic soils:	Primarily organic matter, dark in color, and organic odor			PT	Peat

[A] Based on the material passing the 3-inch (75-mm) sieve.
[B] If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.
[C] Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.
[D] Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.
[E] $Cu = D_{60}/D_{10}$ $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$
[F] If soil contains ≥ 15% sand, add "with sand" to group name.
[G] If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.
[H] If fines are organic, add "with organic fines" to group name.
[I] If soil contains ≥ 15% gravel, add "with gravel" to group name.
[J] If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.
[K] If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.
[L] If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.
[M] If soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.
[N] PI ≥ 4 and plots on or above "A" line.
[O] PI < 4 or plots below "A" line.
[P] PI plots on or above "A" line.
[Q] PI plots below "A" line.



SECTION 01010

GENERAL WORK REQUIREMENTS

1. GENERAL
Should conflict occur between these General Work Requirements and the General Conditions, the requirements of this Section take precedence.

2. INTENT OF DOCUMENTS
The Contract Drawings are complementary and what is called for by anyone shall be as binding as if called by all. The intention of the documents is to include all labor and materials, equipment and transportation necessary for the proper execution of the work.

3. MANUFACTURERS' DIRECTIONS
All manufactured articles, materials and equipment shall be applied, installed, connected, erected, used, cleaned and conditioned as directed by the manufacturers, unless herein specified to the contrary.

4. COOPERATION - CONTRACTOR WITH OWNER
It shall be clearly understood that the Owner reserves the right to install various equipment in the building prior to completion and acceptance, and it shall be the duty of the Contractor to cooperate with the Owner's employees rendering such assistance and so arranging their work that the entire project will be delivered complete in the best possible condition when required.

5. BUILDING PERMIT
As stated in Subparagraph 4.7.1, AIA DOCUMENT A201, General Conditions, the General Contractor shall secure and pay for the building permit.

6. CONSTRUCTION COORDINATION
Before starting construction, a meeting shall be held with Contractor(s), Architect, Consulting Engineers in attendance to plan and coordinate the schedule of construction and to review intent of Contract Documents. Contractor(s) shall follow instructions received at meeting in prosecuting the Work.

7. MATERIALS - EQUIPMENT - SUBSTITUTION
   a. In general, these Specifications identify the required materials and equipment by naming one or more manufacturers, brand, model, catalog number and/or other identification; the first-named manufacturer's product used as a basis for design; the other named brands considered equivalent. Equivalent brand manufacturers named must furnish products consistent with the Specifications for the first-named product, as determined by the Architect. Base Bid shall include only those brands named and must be used on the project, except as hereinafter provided.

   b. Hazardous Materials are prohibited from this project and any equipment specified. All materials, systems, and/or equipment must not contain hazardous materials in excess of the US EPA criteria.

   c. Materials or equipment specified exclusively, Base Bid shall be based on same and used on project, except as hereinafter provided.

   d. Prior to receipt of bids, should Contractor wish to incorporate in Base Bid, brands or products other than those named in the Specifications, he shall submit written request for substitution to Architect not later than seven (7) days prior to date bids are due. Architect will consider request and items approved will be listed in an addendum issued to all bidders.

   e. After execution of Contract, substitution of product brands for those named in the Specifications will be considered, only if request is received within thirty (30) days after Contract Date and request includes showing credit due Owner.

   f. Materials specified equivalent and those proposed for substitution must be equal or better than first-named material in construction, efficiency, utility, aesthetic design, physical size shall not be larger than space provided for it. Request for substitution by full description and technical

data in two (2) copies, including manufacturer's name, model, catalog number, photographs or cuts, physical dimensions, operating characteristics, and any other information for comparison.

g. Owner reserves the right:
   1) To require any or all bidders, before execution of Contract, to state what materials they will use.
   2) To require "if bound with the Bid Form," the Contractor to fill out a BID SUPPLEMENT listing the BASE BID and "ADD" or "DEDUCT" for other materials he proposes to use.

8. APPROVAL OF SUBCONTRACTORS - MATERIALS
   a. The Contractor, if requested, must submit for approval before signing Agreement, list of Subcontractors and material suppliers enumerating items of work to be performed, name of materials, equipment, etc., to be furnished and/or installed. Refer to Paragraph - MATERIALS - EQUIPMENT - SUBSTITUTION.

   b. If the list is not requested prior to signing of Agreement, list, as described in previous paragraph, shall be furnished within ten (10) days of signing Agreement.

9. PROTECTION - Supplement, ARTICLE 10, AIA GENERAL CONDITIONS
   a. Refer to Paragraph - WEATHER CONDITIONS.

   b. Each Contractor shall assume responsibility for their materials stored on the premises.

   c. General Contractor shall take charge and assume general responsibility for proper protection of project during construction.

   d. The General Contractor shall protect trees, shrubs, lawns and all landscape from damage, providing guards and covering. Damaged work shall be repaired or replaced at their expense. Protect streets and sidewalks and make repairs at their expense.
      1) Water Protection. The General Contractor shall, at all times, protect the excavation, trenches, and/or the building from damage by rain water, spring water, ground water, backing up of drains or sewers and all other water. He shall provide all pumps and equipment and enclosures to provide this protection.
      2) Temporary Drainage. The General Contractor shall construct and maintain all necessary temporary drainage and do all pumping necessary to keep the excavation free of water.
      3) Snow and Ice. The General Contractor shall remove all snow and ice from public sidewalks and from the building, as may be required for the proper protection and/or prosecution of the Work.
      4) Bracing, Shoring and Sheeting. The General Contractor shall provide all shoring, bracing and sheeting as required for safety and for the proper execution of the work and have same removed when the work is completed.
      5) Guard Lights. The General Contractor shall provide and maintain guard lights at all barricades, railings, obstructions in the streets, roads or sidewalks and at all trenches or pits adjacent to public walks or roads.
      6) Weather Conditions. The General Contractor shall, at all times, provide protection against weather; rain, winds, storms, frost, or heat, so as to maintain all work, materials, apparatus, and fixtures, free from injury or damage. At the end of the day's work, all new work likely to be damaged shall be covered.

10. WEATHER CONDITIONS
The Contractor shall protect all portions of their work and all materials, at all times from damage by water, freezing, frost and is to repair, replace and make good to the satisfaction of the Architect, any portion of same which may in the Architect's opinion, have been damaged by the elements.

11. GRADES, LINES, LEVELS, AND SURVEYS
The Owner will establish the lot lines, restrictions and a bench mark. All other grades, lines, levels, and bench marks shall be established and maintained by the General Contractor, who shall be responsible for same. The General Contractor shall verify all grades, lines, levels and dimensions as shown on the Drawings and they shall report all errors or inconsistencies in the above to the Architect before commencing work.

a. The General Contractor shall provide and maintain well-built batter boards at all corners. They shall establish bench marks in not less than two (2) widely separated places. As the work progresses, he shall establish bench marks at each floor, giving exact levels of the various floors.
b. As the work progresses, the General Contractor shall lay out in the forms and the rough flooring the exact location of all partitions as a guide to all trades.

c. The General Contractor shall verify all grades, lines, levels and dimensions as shown on the Drawings and they shall report any errors or inconsistencies in the above to the Architect before commencing work.

12. USE OF COMPLETED PORTIONS

The Owner reserves the right to take possession of and use any completed or partially completed portions of the building, and further reserves the right to install equipment and facilities which are not a part of the Contract, notwithstanding the fact that the time of completion of entire work or portions thereof may not have expired; but such taking possession or installation of facilities shall not be deemed an acceptance of any work not completed in accordance with the Contract Documents. The Owner, in taking possession of completed portions or installing such equipment, and facilities, shall do so at his own expense any damage which may occur either directly or indirectly by reason of such action.

a. Building Completion-Occupancy. Owner reserves the right to occupy building when the time for completion of work as stipulated in Contract has been reached, even though all parts of the work have not been completed and accepted by Owner. All work, including heating, electrical, and water service, will be discontinued only to Owner schedule.

b. Limit of Contract is not confined to any particular area of the site, but includes any area required to perform work shown on the Drawings and/or specified in these Specifications.

13. REQUIREMENTS IMMEDIATELY AFTER EXECUTION OF CONTRACT

Immediately after execution of the Contract, the Contractor shall deliver to the Architect the following items which are described more fully in following Articles:

Schedule of Values
Schedule of Operations
Progress Charts
Samples
Superintendent's name and resume of experience
List of Subcontractors and Material Suppliers

a. Schedule of Values on AIA Form G702, or other form approved by the Architect, a detailed breakdown of the Contract Sum indicating the amounts allotted to the various divisions of the work for labor and material. The schedule will serve as a guide to the Architect in determining the amounts due each month as the work progresses. The schedule shall be broken down as directed by the Architect.

b. Schedule of Operations based on the above Schedule of Values and indicating the progress of the work up to the first day of each month shall be prepared by the Contractor in a form approved by the Architect and shall be delivered to the Architect in duplicate with each application for payment.

c. Progress Charts based on the above specified schedule of operations and indicating the progress of the work up to the first day of each month shall be prepared by the Contractor in a form approved by the Architect and shall be delivered to the Architect in duplicate with each application for payment. Progress charts shall be in the form of a bar graph. Along with progress charts the Contractor shall provide an estimated monthly cash flow chart.

14. CONSTRUCTION PROCEDURE

a. Each Contractor shall schedule their work so as to cause a minimum of interference with business operations during all of the construction work.

b. In-Use Areas. Construction work within areas immediately adjacent to existing in-use areas shall be coordinated with the Owner, so that work is accomplished during periods of light occupancy of the areas and cause the least disturbance. Work shall be executed by methods that will create the last amount of noise. Work shall be prefabricated when practical to do so. New facilities shall be ready for use prior to disturbing existing areas.

c. Precautions and Cooperation

1) Notify the Owner 7 days in advance before any utility (natural gas, water, electricity, or sewer) is to be interrupted.

2) With proper notification, interruption in utilities up to 4 hours will be permitted without special provisions by the Contractor. *If any interruption of a utility exceeds 4 hours the Contractor must make arrangements for temporary alternate utility service.

3) Interruption of utilities must be coordinated with the Owner with changeovers and out of service at night. Weekend and evening changeovers of utilities shall occur with no additional cost to the Owner.

15. TIME EXTENSIONS ADVERSE WEATHER

a. The Contractor shall comply with all provisions of the General Conditions in submitting any request for extension of Contract Time due to unusually severe weather.

b. Definitions:

1. Adverse Weather - Atmospheric conditions at a definite time and place which are unfavorable to construction activities.

2. Unusually Severe Weather - Weather which is more severe than the adverse weather anticipated for the season, location, or activity involved.

c. In order for any request of time extension due to unusually severe weather to be valid, the Contractor must document both of the following conditions.

1. The weather experienced at the project site during the Contract period is more severe that the adverse weather anticipated for the project location during any given month.

2. The unusually severe weather actually caused a delay to the completion of the project. The delay must be beyond the control and without fault or negligence by the Contractor.

d. The following schedule of monthly anticipated adverse weather delays will constitute the baseline for monthly weather time evaluations. The Contractor's Progress Schedule must reflect these anticipated adverse weather delays in all weather affected activities:
MONTHLY ANTICIPATED ADVERSE WEATHER DELAY WORK DAYS BASED ON FIVE (5) DAY WORK WEEK

JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
10	8	7	6	7	7	5	5	5	4	5	9

END OF SECTION 01010

SECTION 01019

SPECIAL PROVISIONS

1. GENERAL

Should conflict occur between these Special Provisions and the General Conditions, the requirements of the Special Provisions shall take precedence.

2. TIME OF CONSTRUCTION - LIQUIDATED DAMAGES

a. Time of Construction - The Contractor will commence the work within ten (10) days after the Architect shall have given the Contractor written notice to commence construction to the satisfaction of the Owner within the calendar days as Contractor so stated in his Bid Form. The time for completion herein set forth shall be extended for the period of any reasonable delay which is due exclusively to causes beyond the control and without the fault of the Contractor, including acts of God, fires, floods, and direction by the Architect. It is impractical to perform any operation of construction and acts of omissions of the Owner with respect to matters for which Owner is solely responsible; provided, however, that no such extension of time for completion shall be granted the Contractor, unless within ten (10) days after the happening of any event relied upon by the Contractor for such extension of time, the Contractor shall have made a request, therefore, in writing to the Architect. Extended time will be submitted with pay request for Owner's approval.

b. Liquidated Damages - The time of completion of the construction of the project is of the essence of this Contract. Should the Contractor neglect, refuse, or fail to complete the project within the time herein agreed upon, after giving effect to extensions of time, if any, herein provided; then in that event and in view of the difficulty of estimating with exactness damages caused by such delay, the Owner shall have the right to deduct from and retain out of such money, which may then be due or which may become due and payable to the Contractor, the sum of THREE HUNDRED DOLLARS ($300.00) per day for each and every day that such construction is delayed in its completion beyond the specified time, as liquidated damages and not as a penalty. If the amount due and to become due from the Contractor to the Owner is insufficient to pay in full any such liquidated damages, the Contractor shall pay to the Owner the amount necessary to effect such payment in full; provided, however, that the Owner shall promptly notify the Contractor in writing of the manner in which the amount retained, deducted or claimed as liquidated damages was computed.

c. Joint Responsibility - The General Contractor and/or Subcontractors causing the delay in completion of the project shall be responsible for payment of liquidated damages. In no case shall the total liquidated damages for all contracts exceed the sum of daily liquidated damages multiplied by the number of days of delay in completion.

3. ALTERNATES - Refer to Alternate Schedule, Section 01030

a. Alternates specified are not a part of Base Bid, but are Alternates to same, their acceptance being at option of Owner.

4. CASH ALLOWANCES

a. Costs included in Allowances: Cost of Product to Contractor or Subcontractor, less applicable trade discounts, delivery to site, except those taxes saved by use of Owner's tax exemption.

b. Costs Not Included in the Allowance: Fees for overhead and profit, product handling at the site, including unloading, uncrating, and storage; protection of Products from elements and from damage and labor for installation and finishing.

c. Architect Responsibilities:
   1. Consult with Contractor in consideration and selection of Products, suppliers and installers.
   2. Select Products in consultation with Owner and transmit decision to Contractor.
   3. Prepare Proposal Requests and Change Orders.

d. Contractor Responsibilities:
   1. Assist Architect/Engineer in selection of Products, suppliers and installers.
   2. Obtain proposals from suppliers and installers and offer recommendations.
   3. On notification of selection by Architect, execute purchase agreement with designated supplier and installer.
   4. Arrange for and process shop drawings, product data, and samples. Arrange for delivery.
   5. Promptly inspect Products upon delivery for completeness, damage, and defects. Submit claims for transportation damage.
   6. Product handling at the site, including unloading, uncrating and storage, protection of Products from elements and from damage and labor for installation and finishing.
   7. The Contractor shall include in his Bid all fees for all cash allowances.

e. Funds will be drawn from Cash Allowances only by written authorization from Owner.

f. Cash Allowances:
   1. Contractor to provide a cash allowance in the amount of $15,000 for the fabrication and installation of one new "fin-style" building mounted sign, including design coordination, shop drawings, mounting hardware, electrical connections, and all associated work necessary for a complete and operational installation. The Contractor shall coordinate with the Architect and Owner to finalize design, materials, dimensions, and placement.

5. ENUMERATION OF DRAWINGS AND SPECIFICATIONS
   a. Correlation. Accompanying these Specifications are the Drawings, which jointly with these Specifications, are intended to explain each other and describe and coordinate the work to be performed under the Contract.
   b. Verification of Documents. Before submitting his bid, each Bidder shall check his set(s) of Drawings and Specifications and advise the Architect if any sheets are missing.
   c. Specifications Explanations. For convenience of reference, the Specifications are separated into Titled Divisions and Sections. Such separation shall not, however, operate to make the Architect an arbiter to establish limits between the Contractor and Subcontractor or Sub-Subcontractor.
   d. Drawings. Refer to LIST OF DRAWINGS.
   e. Specifications. Refer to TABLE OF CONTENTS.

6. WARRANTIES
   Before being eligible for final payment, Contractor shall deliver to Owner, through Architect, all special warranties specified for materials, equipment and installation.

7. OPERATING INSTRUCTIONS
   Before being eligible for final payment, Contractor shall deliver to Owner, through Architect, three (3) copies of manufacturer's operating instructions, one (1) complete set of shop drawings on each piece of equipment, and such framed instructions as instructed.

8. AS-BUILT DRAWINGS
   Before being eligible for final payment, the Electrical and Mechanical Contractors shall prepare and deliver to Owner, through Architect, one (1) set of AS-BUILT DRAWINGS. These drawings may consist of marked-up prints, if the Contractor so chooses, but shall show the correct location of every item of equipment, piping, conduit, panel boards, ductwork, switches, valves, etc. If marked-up prints are used, they shall be new white prints.

9. CERTIFICATE OF COMPLIANCE
   Upon completion of project, Contractor is to furnish written Certification to the Architect that he has complied with every paragraph of the Specifications and Drawings.

10. CONTRACTOR'S MONTHLY APPLICATION FOR PAYMENT FORM
    Contractor's monthly Application for Payment shall be submitted as per General Conditions. AIA Document G702, Application and Certificate for Payment is approved and acceptable.

11. FILING AND RECORDING OF BONDS
    In addition to furnishing the number of combination Performance Bond and Labor and Materials Payment Bond, and Statutory Bond, if required, the Contractor shall file copies of such bonds with Clerk of the District Court and furnish Architect with receipt furnished by Clerk of the District Court, covering charges for filing and recording of said bonds.

12. STATUTORY BONDS
    In addition to furnishing the combination Performance and Labor and Materials Payment Bond specified in General Conditions, the Contractor shall furnish Statutory Bond in an amount not less than 100% of the Agreement in such numbers and form stated in Sample Copy bound in the Specifications. Statutory Bond shall be filed and recorded with Clerk of the District Court, as specified in Paragraph - FILING AND RECORDING OF BONDS.

13. DOCUMENTS FURNISHED CONTRACTORS
    The General Contractor will be furnished, free of charge, the following working drawings and specifications, including modifications for construction of the project - 20 sets. The General Contractor will be responsible for distribution of these sets to the Subcontractors and suppliers. The Contractor shall pay the actual cost of reproduction and postage for all additional sets requested by him.

14. SALES TAX EXEMPTIONS

a. Materials, labor and equipment incorporated into this project are not exempt from the payment of sales tax under the laws of the **State of Texas** and such sales tax **shall be included in the Bid of the Bidder.**

END OF SECTION 01019

SECTION 01500

TEMPORARY FACILITIES

1. GENERAL

Should conflict occur between the Temporary Facilities and the General Conditions, the requirements of this Section take precedence.

2. TEMPORARY HEAT

a. The General Contractor shall provide heat, fuel and services as necessary to protect all work and materials against injury from dampness and cold until final acceptance of all work and material in the Contract, unless the building or buildings are fully occupied by the Owner prior to such acceptance, in which case, the Owner shall assume all expenses of heating from date of occupancy. The General Contractor shall provide heat as follows:
   1) At all times during the placing, setting and curing of concrete, provide sufficient heat to insure the heating of the spaces involved to not less than 50° F.
   2) From the beginning of the application of gypsum board taping and during the setting and curing period, provide sufficient heat to produce a temperature in the spaces involved of not less than 50° F.
   3) For a period of ten (10) days previous to the placing of interior wood finish and throughout the placing of this and other interior finishing, varnishing, painting, etc., and until final acceptance of the work or until full occupancy by the Owner, provide sufficient heat to produce a temperature of not less than 70° F. Heating Subcontractor shall set such necessary temporary radiation as may be required.
   4) Mechanical Subcontractor shall, as soon as possible, provide temporary heating facilities through the installed heating equipment.

3. SIGN AND ADVERTISING

a. The General Contractor shall furnish and erect one (1) painted sign, 4'-0" x 8'-0" in size, as shown on the last page of this Section and placed where directed. Sign shall have the following:
   1) Name of Project
   2) Name and Address of Architect
   3) Name and Address of General Contractor
   4) Name of Mechanical Subcontractor
   5) Name of Electrical Subcontractor
   6) Picture of Project (coordinate with Architect)

b. Post entire construction with DANGER and NO TRESPASSING signs to comply with safety and insurance regulations.

c. Keep premises clear and free from other signs or posters.

4. TEMPORARY FIELD OFFICES

a. General Contractor shall provide and maintain in good condition, a painted weatherproof field office (adequate size trailer acceptable) for use of General Contractor and Architect's representative. Provide such building with heat, electric lights, telephone, locked doors, windows, table, and rack for Drawings. Building to remain property of General Contractor.

b. Electrical and Mechanical Subcontractors shall maintain similar field office, meeting requirements of previous paragraph, except provisions for Architect's representative not needed.

5. TEMPORARY ENCLOSURES

General Contractor to provide:

a. Temporary weathertight enclosures for all exterior openings as soon as possible as walls and roofs are built to protect work from weather. Temporary exterior doors equipped with padlocks.

b. In cold weather, provide additional precautions necessary, including heat at such openings to protect building and contents.

6. TEMPORARY SHEDS

The Contractor shall provide and maintain on the premises watertight storage sheds for storage of all materials which may be damaged by weather. These sheds shall have wood floors raised above the ground.

7. TEMPORARY CONSTRUCTION ITEMS

General Contractor shall furnish necessary temporary stairs, chutes, runways, scaffolds, ladders and hoist.

8. TEMPORARY TOILET ACCOMMODATIONS

a. The General Contractor shall provide for the use of all workmen, in accordance with local ordinances, ample temporary sanitary toilet accommodations and keep such clean and free from flies. Prior to completion of the Contract, all connections and appliances connected with same will be removed and the premises left perfectly clean.

b. The Mechanical Subcontractor shall, as soon as conditions of the work will allow, install inside building a temporary toilet with connections to the sewer.

9. TEMPORARY TELEPHONE

The General Contractor shall install at his own expense, a job telephone, and shall pay for all local calls. All long distance calls shall be paid by party making the call.

10. TEMPORARY LIGHT AND POWER

a. For new construction, the General Contractor shall arrange for temporary service, pay for all expenses therewith and bring services to building and run extensions to locations necessary for operations.

b. Permit other Subcontractors to use same. Other Subcontractors requiring additional extensions, make and remove same at their expense. General Contractor shall pay for all electricity consumed.

11. WATER FOR CONSTRUCTION

The Owner will furnish all water for construction. The General Contractor will be responsible for necessary water connections to existing source.

END OF SECTION 01500

SECTION 02110

SITE CLEARING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Remove surface debris.
- C. Clear site of plant life and grass.
- D. Remove trees and shrubs.
- E. Remove root system of trees and shrubs.
- F. Topsoil excavation.

1.02 REGULATORY REQUIREMENTS
- A. Conform to applicable local codes and ordinances for disposal of debris, burning debris on site, use of herbicides, etc.
- B. Coordinate clearing Work with utility companies as required.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.01 PREPARATION
- A. Verify that existing plant life designated to remain, is tagged or identified.

3.02 PROTECTION
- A. Locate, identify, and protect utilities that remain, from damage.
- B. Protect trees, plant growth, and features designated to remain, as final landscaping.
- C. Protect bench marks and existing structures from damage or displacement.

3.03 CLEARING
- A. Clear areas required for access to site and execution of Work.
- B. Remove paving, curbs, and improvements designated.
- C. Remove trees and shrubs indicated. Remove stumps, root system surface rock and other areas indicated or implied for completion of the project.
- D. Clear undergrowth and deadwood, without disturbing subsoil. Strip and clear vegetation from areas designated to be filled, excavated, regraded, or landscaped.

3.04 REMOVAL
- A. Remove debris, rock, and extracted plant life from site.

3.05 TOPSOIL EXCAVATION
- A. Excavate clean topsoil from areas to be further excavated, filled, re-landscaped, or regraded.
- B. Stockpile in area designated on site to depth not exceeding 8 feet. Protect from erosion. Remove excess topsoil not being reused, from site.

END OF SECTION 02110

SECTION 02205

SOIL MATERIALS

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Subsoil and topsoil materials.

1.02 RELATED SECTIONS
A. Document:
The Geotechnical Engineering Report, Exhibit K. The engineering study, subsurface exploration, boring location diagram, boring logs, laboratory test results, and geotechnical recommendations.

1.03 REFERENCES
A. ANSI/ASTM D698 - Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures, Using 5.5 lb (2.49 Kg) Rammer and 12 inch (304.8 mm) Drop.
B. ASTM D2487 - Classification of Soils for Engineering Purposes.

PART 2 PRODUCTS

2.01 SOIL MATERIALS
A. Fill Material: Under slabs and within the zone of influence of foundation elements must be a material approved by the geotechnical engineer and as indicated in the geotechnical report, in coordination with.

B. Fill and Backfill Material: Other areas, foundation backfill, site grading, and pavement, should be clean site material or similar borrow material, in coordination with.

2.02 SOURCE QUALITY CONTROL
A. Inspection and testing will be performed by an independent laboratory, Contractor shall bear all related costs under provisions of General Requirements.
B. Tests and analysis of soil material will be performed in accordance with ANSI/ASTM D698.
C. If tests indicate materials do not meet specified requirements, change material and retest at no cost to Owner.

PART 3 EXECUTION

3.01 STOCKPILING
A. Stockpile materials on site at locations indicated or in areas that will not impact project completion.
B. Stockpile in sufficient quantities to meet project schedule and requirements.
C. Separate differing materials with dividers or stockpile apart to prevent mixing.
D. Direct surface water away from stockpile site to prevent erosion or deterioration of materials.

3.02 STOCKPILE CLEANUP
A. Remove stockpile, leave area in a clean and neat condition. Grade site surface to prevent free-standing surface water.

END OF SECTION 02205

SECTION 02211

ROUGH GRADING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Removal of topsoil and subsoil.
- B. Cutting, grading, filling and rough contouring the site for site structures, building pads and paving.

1.02 RELATED SECTIONS
- A. Document:
  The Geotechnical Engineering Report, Exhibit K. The engineering study, subsurface exploration, boring location diagram, boring logs, laboratory test results, and geotechnical recommendations.

PART 2 PRODUCTS

2.01 MATERIALS
- A. Topsoil, Fill and Structural Fill: As specified in Section 02205.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify that survey bench mark and intended elevations for the Work are as indicated.

3.02 PREPARATION
- A. Identify required lines, levels, contours, and datum.
- B. Stake and flag locations of known utilities. Locate, identify, and protect utilities that remain, from damage. Notify utility company to remove and relocate utilities.
- C. Protect above and below grade utilities that remain.
- D. Protect plant life, lawns, rock outcropping and other features remaining as a portion of final landscaping.
- E. Protect bench marks, existing structures, fences, sidewalks, paving, and curbs from excavating equipment and vehicular traffic.

3.03 SUBSOIL EXCAVATION
- A. Excavate subsoil from areas to be further excavated, relandscaped, or regraded.
- B. Stockpile in area designated on site to depth not exceeding 8 feet. Protect from erosion. Remove subsoil not being reused, from site.
- C. When excavating through roots, perform work by hand and cut roots with sharp axe.

3.04 FILLING
- A. Fill areas to contours and elevations with unfrozen materials.
- B. Place fill materials on continuous layers and compact in accordance with Schedule at end of Section.
- C. Maintain optimum moisture content of fill materials to attain required compaction density.
- D. Slope grade away from building minimum 2 inches in 10 ft. unless noted otherwise.
- E. Make grade changes gradual. Blend slope into level areas.
- F. Remove surplus fill materials from site.

3.05 TOLERANCES
- A. Top Surface of Subgrade: Plus or minus 1/10 foot.

3.06 FIELD QUALITY CONTROL
- A. Field inspection and testing will be performed under provisions of the General Requirements.
- B. Compaction testing will be performed in accordance with ANSI/ASTM D698.
- C. If tests indicate Work does not meet specified requirements, remove Work, replace and retest at no additional cost to the Owner.

3.07 SCHEDULES

A. Structural Fill: (Building and Paving)
   1. Fill Maximum 8 inches compacted depth.
   2. Compact to minimum 95 percent of maximum density.

B. Subsoil Fill:
   1. Fill Maximum 8 inches compacted depth.
   2. Compact to minimum 90 percent of maximum density.

C. Topsoil Fill:
   1. Fill Maximum 8 inches depth.

END OF SECTION 02211

SECTION 02222

EXCAVATING

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Excavating for building foundations and footings.
B. Excavating for slabs-on-grade, paving, landscaping.
C. Excavating for site structures.

1.02 RELATED SECTIONS
A. Document:
The Geotechnical Engineering Report, Exhibit K. The engineering study, subsurface exploration, boring location diagram, boring logs, laboratory test results, and geotechnical recommendations.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.01 PREPARATION
A. Identify required lines, levels, contours, and datum.
B. Locate, identify, and protect utilities that remain, from damage.
C. Notify utility company to remove and relocate utilities.
D. Protect plant life, lawns, rock outcropping and other features remaining as a portion of final landscaping.
E. Protect bench marks, existing structures, fences, sidewalks, paving and curbs from excavation equipment and vehicular traffic.

3.02 EXCAVATION
A. Underpin adjacent structures which may be damaged by excavation work.
B. Excavate subsoil required to accommodate building foundations, slabs-on-grade, paving and site structures, construction operations.
C. Machine slope banks to angle of repose or less, until shored.
D. Do not interfere with 45 degree bearing splay of foundation.
E. Grade top perimeter of excavation to prevent surface water from draining into excavation.
F. Hand trim excavation. Remove loose matter.
G. Remove lumped subsoil, boulders, and rock up to 1/3 cu yd measured by volume.
H. Notify Architect/Engineer of unexpected subsurface conditions and discontinue affected Work in area until notified to resume work.
I. Correct areas over-excavated in accordance with Section 02223.
J. Stockpile excavated material in area designated on site and remove excess material not being reused, from site.
K. Execute work in coordination with the Soils Report

3.03 FIELD QUALITY CONTROL
A. Field inspection will be performed under provisions of the General Requirements.
B. Provide for visual inspection of bearing surfaces.

3.04 PROTECTION
A. Protect excavations by methods required to prevent cave-in or loose soil from falling into excavation.
B. Protect bottom of excavations and soil adjacent to and beneath foundation, from freezing.

END OF SECTION 02222

SECTION 02223

BACKFILLING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Building perimeter and site structure backfilling to subgrade elevations.
- B. Site filling and backfilling.
- C. Fill under slabs-on-grade, paving.
- D. Consolidation and compaction as scheduled.
- E. Fill for over-excavation.

1.02 RELATED SECTIONS
- A. Document:
  The Geotechnical Engineering Report, Exhibit K. The engineering study, subsurface exploration, boring location diagram, boring logs, laboratory test results, and geotechnical recommendations.

1.03 REFERENCES
- A. ANSI/ASTM D698 - Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures, Using 5.5 lb (2.49 Kg) Rammer and 12 inch (304.8 mm) Drop.

PART 2 PRODUCTS

2.01 FILL MATERIALS
- A. Fill: As specified in Section 02205.
- B. Execute all fill in coordination with **Geotechnical Report, Exhibit K.**

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify subdrainage, dampproofing or waterproofing installation has been inspected and completed.

3.02 PREPARATION
- A. Compact subgrade to density requirements for subsequent backfill materials.
- B. Cut out soft areas of subgrade not capable of in situ compaction. Backfill with fill and compact to density equal to or greater than requirements for subsequent fill material.
- C. Scarify and proof roll subgrade surface to a depth of 4 inches to identify soft spots; fill and compact to density equal to or greater than requirements for subsequent fill material.

3.03 BACKFILLING
- A. Backfill areas to contours and elevations with unfrozen materials.
- B. Systematically backfill to allow maximum time for natural settlement. Do not backfill over porous, wet, frozen or spongy subgrade surfaces.
- C. Fill, place and compact materials in continuous layers not exceeding 8 inches compacted depth.
- D. Employ a placement method that does not disturb or damage other work.
- E. Maintain optimum moisture content of backfill materials to attain required compaction density. Backfill against supported foundation walls. Do not backfill against unsupported foundation walls.
- F. Backfill simultaneously on each side of unsupported foundation walls until supports are in place.
- G. Slope grade away from building minimum 2 inches in 10 ft. unless noted otherwise.
- H. Make gradual grade changes. Blend slope into level areas.
- I. Remove surplus backfill materials from site.
- J. Leave fill material stockpile areas free of excess fill materials.

3.04 TOLERANCES
- A. Top Surface of Backfilling Under Paved Areas: Plus or minus 1 inch from required elevations.
- B. Top Surface of General Backfilling: Plus or minus 1 inch from required elevations.

3.05 FIELD QUALITY CONTROL

A. Field inspection and testing will be performed under provisions of the General Requirements.
B. Compaction testing will be performed in accordance with ANSI/ASTM D698.
C. If tests indicate Work does not meet specified requirements, remove Work, replace and retest at no additional cost to the Owner.
D. Proof roll compacted fill surfaces under slabs-on-grade, and paving.

3.06 PROTECTION OF FINISHED WORK

A. Protect finished Work under provisions of the General Requirements.
B. Reshape and re-compact fills subjected to vehicular traffic.

3.07 SCHEDULE

A. Interior Slab-On-Grade:
   1. Fill compacted to 95 percent
   2. Cover with Sand Fill 2 inches thick, compacted to 95 percent.
B. Exterior Side of Foundation Walls Retaining Walls and Over Granular Filter Material and Foundation Perimeter Drainage:
   1. Fill to subgrade elevation, each lift, compacted to 90 percent.
C. Fill Under Grass Areas:
   1. Fill to 4 inches below finish grade.
D. Fill Under Asphalt or Concrete Paving:
   1. Compact subsoil to 95 percent of its maximum dry density.
E. Fill to Correct Overexcavation:
   1. Lean concrete to minimum compressive strength of 1000 psi.
   2. Compact approved fill to 95 percent of its maximum dry density.

END OF SECTION 02223

SECTION 02225

TRENCHING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Excavating trenches for utilities from 5 feet outside building to municipal utilities.
- B. Compacted fill from top of utility bedding to subgrade elevations.
- C. Backfilling and compaction.

1.02 RELATED SECTIONS
- A. Document:
  The Geotechnical Engineering Report, Exhibit K. The engineering study, subsurface exploration, boring location diagram, boring logs, laboratory test results, and geotechnical recommendations.

1.03 REFERENCES
- A. ANSI/ASTM D698 - Test Methods for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures, Using 5.5 lb (2.49 Kg) Rammer and 12 inch (304.8 mm) Drop.

1.04 FIELD MEASUREMENTS
- A. Verify that survey bench mark and intended elevations for the Work are as shown on drawings.

1.05 COORDINATION
- A. Coordinate all work as required.
- B. Verify work associated with lower elevation utilities are complete before placing higher elevation utilities.

PART 2 PRODUCTS

2.01 FILL MATERIALS
- A. Fill: As specified in Section 02205.

PART 3 EXECUTION

3.01 PREPARATION
- A. Identify required lines, levels, contours, and datum.
- B. Protect plant life, lawns, rock outcropping and other features remaining as a portion of final landscaping.
- C. Protect bench marks, existing structures, fences, sidewalks, paving, and curbs from excavation equipment and vehicular traffic.
- D. Maintain and protect above and below grade utilities which are to remain.
- E. Cut out soft areas of subgrade not capable of in situ compaction. Backfill with fill and compact to density equal to or greater than requirements for subsequent backfill material.

3.02 EXCAVATION
- A. Excavate subsoil required for utilities to municipal utilities.
- B. Cut trenches sufficiently wide to enable installation and allow inspection.
- C. Do not interfere with 45 degree bearing splay of foundations.
- D. Hand trim excavation. Remove loose matter.
- E. Remove lumped subsoil, boulders, and rock up to 1/3 cu yd measured by volume.
- F. Correct areas over excavated in accordance with Section 02222.
- G. Stockpile excavated material in area designated on site and remove excess material not being used, from site.

3.03 BACKFILLING
- A. Backfill trenches to contours and elevations with unfrozen materials.
- B. Systematically backfill to allow maximum time for natural settlement. Do not backfill over porous, wet, frozen or spongy subgrade surfaces.

C. Granular Fill: Place and compact materials in continuous layers not exceeding 8 inches compacted depth.
D. Soil Fill: Place and compact material in continuous layers not exceeding 8 inches compacted depth.
E. Employ a placement method that does not disturb or damage foundation perimeter drainage, conduit or pipes in trench.
F. Maintain optimum moisture content of fill materials to attain required compaction density.
G. Remove surplus fill materials from site.
H. Leave fill material stockpile areas completely free of excess fill materials.

3.04 TOLERANCES
A. Top Surface of Backfilling: Plus or minus 1 inch from required elevations.

3.05 FIELD QUALITY CONTROL
A. Field inspection and testing will be performed under provisions of the General Requirements.
B. Compaction testing will be performed in accordance with ANSI/ASTM D698.
C. If tests indicate Work does not meet specified requirements, remove Work, replace, compact, and retest at no additional cost to the owner.

3.06 PROTECTION OF FINISHED WORK
A. Protect or reshape and recompact fills subjected to vehicular traffic during construction.

END OF SECTION 02225

SECTION 02281

TERMITE CONTROL

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Soil treatment for termite control below grade, to interior and exterior foundation perimeter.

1.02 QUALIFICATIONS
A. Applicator: Company specializing in performing the work of this Section with minimum 5 years documented experience approved by manufacturer, licensed and approved regulations.

1.03 REGULATORY REQUIREMENTS
A. Conform to requirements for application, application licensing, and authority to use toxicant chemicals and in accordance with EPA.
B. Provide certificate of compliance from authority having jurisdiction indicating approval of toxicants.

1.04 SEQUENCING
A. Apply toxicant 12 hours prior to installation of vapor barrier under slabs-on-grade and finish grading work outside foundations.
B. Notify Architect 24 hours prior to application.

1.05 WARRANTY
A. Provide five year warranty under provisions of the General Requirements.
B. Warranty: Include coverage for damage and repairs to building and building contents caused by termites. Repair damage. Re-treat where required.
C. Inspect and report annually to Owner in writing. Owner reserves the right to renew warranty for an additional five years.

PART 2 PRODUCTS

2.01 MATERIALS
A. Toxicant Chemical: EPA and Local authority approved; (DRAGNET, DURSBAN TC, or as approved equal) synthetically color dyed to permit visual identification of treated soil.
B. Diluent: Recommended by toxicant manufacturer.
C. Mix toxicant to manufacturer’s instructions.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify all the site conditions and become familiar with project scope.
B. Verify that soil surfaces are unfrozen, sufficiently dry to absorb toxicant, and ready to receive treatment.
C. Verify final grading is complete.

3.02 APPLICATION
A. Spray apply or Inject toxicant in accordance with manufacturer’s instructions.
B. Apply toxicant at locations indicated in Schedule at end of Section.
C. Apply extra treatment to structure penetration surfaces such as pipe or ducts, and soil penetrations such as grounding rods or posts.
D. Re-treat disturbed treated soil with same toxicant as original treatment. Retreat around building perimeter after top soil has been placed, directly adjacent to foundation wall.
E. If inspection or testing identifies the presence of termites, re-treat soil and re-test.

3.03 PROTECTION OF FINISHED WORK
A. Protect finished Work, post signage to warn workers that soil poisoning has been applied.
B. Do not permit soil grading over treated work.

3.04 SCHEDULES

A. Locations:

1. Under Slabs-on-Grade including porches and stoops.
2. Both Sides of Foundation Surfaces.
3. Soil Within 10 feet of Building Perimeter.

END OF SECTION 02281

SECTION 024119

SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Demolition and removal of selected portions of building or structure.
   2. Demolition and removal of selected site elements.
   3. Salvage of existing items to be reused or recycled.

1.2 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.
B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.
   1. Carefully salvage in a manner to prevent damage and promptly protect, store and prepare for re-installation, in not scheduled for re-installation or use coordinate with Owner

1.3 PREINSTALLATION MEETINGS

A. Pre-demolition Conference: Conduct conference at Project site, any & all clarifications to be discussed with Owner or Architect.
B. Ensure all contractors, subs & suppliers are familiar with any building hazardous materials to remain, protected or be removed.

1.4 INFORMATIONAL SUBMITTALS

A. Proposed Protection Measures: Provide proper and safe measures for protecting individuals and property, environmental protection, for dust debris control.. Indicate proposed locations and construction of barriers.
B. Schedule of selective demolition activities with starting and ending dates for each activity.
C. Pre-demolition photographs or video.

1.5 CLOSEOUT SUBMITTALS

A. Inventory of items that have been removed and salvage and any discrepancy of number and/or condition.

1.6 QUALITY ASSURANCE

A. Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification program.

1.7 FIELD CONDITIONS

A. Owner will NOT occupy any portions of building adjacent to selective demolition area.
B. Conditions existing at time of inspection are identified in Reports for bidding purpose.
C. Notify Architect and Owner of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
D. Hazardous Materials: Reference reports and Coordinate with removal contractors. After removal, understand item sand materials to remain and or hazardous materials to be encountered in the Work.
   1. Selected Hazardous materials will be removed by separate contract before start of the Work.

2. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials shall be removed by authorized contractor under a separate contract.

E. Storage or sale of removed items or materials on-site is not permitted.

F. Utility Service: Verify and provide new taps and connections to utilities indicated for service and protect them against damage during all work and operations.

1.8 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials and using approved contractors so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ANSI/ASSP A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

B. Perform survey of condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective building demolition operations.

C. Inventory and record the condition of items to be removed and salvaged.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Existing Services/Systems to Be Removed,: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Arrange and coordinate any work or connection to utilities with utility companies.
2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
3. Disconnect, demolish, and remove ALL fire-suppression systems, plumbing, Electrical and HVAC systems, equipment, and components through-out building and site, and as indicated on Drawings to be removed.
    a. Piping, Plumbing equipment & fixtures, Electrical wire, conduit, & devices, to Be Removed: Remove All indicated to be removed, only cap or terminate at public connections or public service, If new tap or connection is required or desired.
    b. Equipment to Be Removed: Disconnect and only cap or terminate at public or service providers equipment, lines or services.
    c. Ducts to Be Removed: Remove all ducts and equipment indicated to be removed.

3.3 PROTECTION

A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.

B. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

C. Remove temporary barricades and protections where hazards no longer exist.

3.4 SELECTIVE DEMOLITION

A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
   1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
   2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
   3. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
   4. Maintain fire watch during and for at least 2 hours after flame-cutting operations.
   5. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
   6. Dispose of demolished items and materials promptly. Comply with requirements for Construction Waste Management and Disposal.

B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

C. Removed and Salvaged Items:
   1. Clean salvaged items.
   2. Pack or crate items after cleaning. Identify contents of containers.
   3. Store items in a secure area until re-installation or delivery to Owner.
   4. Protect items from damage during transport and storage.

D. Removed and Reinstalled Items:
   1. Clean and repair items to functional condition adequate for intended reuse.
   2. Pack or crate items after cleaning and repairing. Identify contents of containers.
   3. Protect items from damage during transport and storage.
   4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

E. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition, cleaned, restored, and reinstalled in their original or indicated locations after selective demolition operations are complete.

3.5 CLEANING

A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction and recycle or dispose of them according to Construction Waste Management and Disposal.
   1. Do not allow demolished materials to accumulate on-site.
   2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
4. Comply with standard requirements and Construction Waste Management and Disposal.

B. Burning: Do not burn demolished materials.

C. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

SECTION 02520

PORTLAND CEMENT CONCRETE PAVING

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Concrete sidewalks and stair steps, integral curbs, gutters, driveways and parking areas.

1.02 PERFORMANCE REQUIREMENTS
A. Paving: Designed for parking and light duty commercial vehicles.

1.03 QUALITY ASSURANCE
A. Perform work in accordance with ACI 301, requirements of Sections 03100, 03200 and 03300.
B. Obtain cementitious materials from same source throughout.

1.04 ENVIRONMENTAL REQUIREMENTS
A. Do not place concrete when base surface temperature is less than 40 degrees F, or surface is wet or frozen.

PART 2 PRODUCTS

2.01 FORM MATERIALS
A. Wood or Steel form material, profiled to suit conditions.
B. Joint Filler: ANSI/ASTM D1751 type; 3/4 inch thick.

2.02 REINFORCEMENT
A. Welded Steel Wire Fabric: Plain type, ANSI/ASTM A185; 6x6 - 6x6 in flat sheets or coiled rolls.
B. Reinforcing Steel: ASTM A615; 40 ksi yield grade; deformed billet steel bars; unfinished.

2.03 CONCRETE MATERIALS
A. Cement: ASTM C150 Air Entraining - Type IA Portland type, natural color.
B. Fine and Coarse Mix Aggregates: ASTM C33.
C. Water: Potable, not detrimental to concrete.
D. Air Entrainment: ASTM C260.
E. Chemical Admixture: ASTM C494, as approved by Architect.

2.04 CONCRETE MIX - BY PERFORMANCE CRITERIA
A. Mix concrete in accordance with, ACI 304. Deliver concrete in accordance with ASTM C94.
B. Provide concrete to the following criteria:
1. Compressive Strength: Reference schedule below.
2. Slump: 1 to 2 inches.
3. Minimum Water/Cement Ratio: 6.5 gallon/5.5 sack.
4. Air Entrained: 5 percent.
C. Use accelerating admixtures in cold weather only when approved by Architect/Engineer. Use of admixtures will not relax cold weather placement requirements.
D. Use calcium chloride only when approved by Architect/Engineer.
E. Use set retarding admixtures during hot weather only when approved by Architect/Engineer.

2.05 SOURCE QUALITY CONTROL
A. Submit proposed mix design of each class of concrete to the architect and appointed testing laboratory firm for review prior to commencement of work.
B. Tests on cement and aggregates shall be performed to ensure conformance with specified requirements.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify compacted subgrade, granular base and stabilized soil is acceptable and ready to support paving and imposed loads.
B. Verify gradients and elevations of base are correct.

3.02 PREPARATION

A. Moisten base to minimize absorption of water from fresh concrete.
B. Coat surfaces of manholes, catch basins and frames with oil to prevent bond with concrete pavement.
C. Notify Architect/Engineer minimum 24 hours prior to commencement of concreting operations.

3.03 FORMING

A. Place and secure forms to correct location, dimension, and profile.
B. Assemble formwork to permit easy stripping and dismantling without damaging concrete.
C. Place joint filler vertical in position, in straight lines. Secure to formwork during concrete placement.

3.04 REINFORCEMENT

A. Place reinforcement at mid-height of slabs-on-grade.
B. Interrupt reinforcement at expansion joints.
C. Place dowels and reinforcement to achieve pavement and curb alignment as detailed.
D. Provide doweled joints 12 inch o.c. at interruptions of concrete.

3.05 PLACING CONCRETE

A. Place concrete in accordance with ACI 301.
B. Ensure reinforcement, inserts, embedded parts, are not disturbed during concrete placement.
C. Place concrete continuously between predetermined construction joints. Do not break or interrupt successive pours such that cold joints occur.
D. Place concrete to indicated pattern.

3.06 JOINTS

A. Place 1/2 inch expansion joints at 60 foot intervals. Align curb, gutter, and sidewalk joints.
B. Place joint filler between paving components and building or other appurtenances. Recess top of filler 1/4 inch for sealant placement by Section 07900.
C. Provide scored or sawn joints at 4 feet intervals U.N.O. at sidewalks and curbs and 15 feet at pavement.
D. Saw cut contraction joints 3/16 inch wide at an optimum time after finishing. Cut 1/3 into depth of slab.

3.07 FINISHING

A. Parking: Light broom.
B. Sidewalk Paving: Light broom, radius to 1/4 inch and trowel joint edges.
C. Handicapped Ramps: Reference ADA.
D. Curbs and Gutters: Trowel finish.
E. Inclined Vehicular Ramps: Broom perpendicular to slope.
F. Place curing compound on exposed concrete surfaces immediately after finishing. Apply in accordance with manufacturer's instructions.

3.08 FIELD QUALITY CONTROL

A. Three concrete test cylinders shall be taken for every 100 or less cu yds of each class of concrete placed each day.
B. One additional test cylinder shall be taken during cold weather and cured on site under same conditions as concrete it represents.
C. One slump test shall be taken for each set of test cylinders taken.

3.09 PROTECTION

A. Immediately after placement, protect pavement from premature drying, excessive hot or cold temperatures, and mechanical injury.

3.10 SCHEDULES

A. Concrete Sidewalks, Ramps, Stairs and Retaining Walls: 3,000 psi 28 day concrete, 4 inches thick, 6x6 - 10x10 inch mesh reinforcement, natural color Portland cement, broom finish, detectable warnings per ADA at ramps and curb cuts.
B. Concrete Aprons and Driveways: 4,000 psi 28 day concrete, 6 inches thick, 6x6 - 6x6 W.W.F. reinforced, natural color Portland cement, broom finish.

END OF SECTION 02520

SECTION 02810

IRRIGATION SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes a complete irrigation system including but not limited to; wells, pumps, piping, valves, sprinklers, heads, specialties, controls, and wiring for pumps and automatic control of the well pumps and irrigation system.

B. Include all submittals, permits, and requirements associated with federal, state and local requirements and regulations.

1.3 DEFINITIONS

A. Retain abbreviations and definitions that remain after this Section has been edited.

B. Circuit Piping: Downstream from control valves to sprinklers, specialties, and drain valves. Piping is under pressure during flow.

C. Drain Piping: Downstream from circuit-piping drain valves. Piping is not under pressure.

D. Irrigation Main Piping: Downstream from point of connection to water distribution piping to, and including, control valves. Piping is under water-distribution-system pressure.

E. The following are industry abbreviations for plastic materials:

1. ABS: Acrylonitrile-butadiene-styrene plastic.
2. FRP: Fiberglass-reinforced plastic.
3. PA: Polyamide (nylon) plastic.
4. PE: Polyethylene plastic.
5. PP: Polypropylene plastic.
6. PTFE: Polytetrafluoroethylene plastic.
7. PVC: Polyvinyl chloride plastic.
8. TFE: Tetrafluoroethylene plastic.

1.4 PERFORMANCE REQUIREMENTS

A. Test, Locate and drill all wells, consistent with federal, state and local authorities and regulations. Design and size piping, controls and pumps consistent with federal, state and local authorities and regulations. Provide shop drawings for approval.

B. Design 100 percent water-coverage irrigation system for lawns and exterior plants indicated.

C. Retain paragraph below if complete system design and calculations are in the Contract Documents.

D. Location of Sprinklers and Specialties: Provide shop drawings for approval. Make minor adjustments necessary to avoid plantings and obstructions such as signs and light standards. Maintain 100 percent water coverage of turf and planting areas indicated.

E. Retain paragraph and subparagraphs below with either paragraph above.

F. Minimum Working Pressures: The following are minimum pressure requirements for piping, valves, and specialties, unless otherwise indicated:

1. Irrigation Main Piping: 200 psig.
2. Circuit Piping: 150 psig.
3. Drain Piping: 100 psig.

1.5 SUBMITTALS

A. Product Data: Include pressure ratings, rated capacities, and settings of selected models for the following:

1. Water wells, pumps, regulators.
2. Water hammer arresters.
3. General-duty valves.
4. Specialty valves.
5. Control-valve boxes.
6. Sprinklers.
7. Irrigation specialties.
8. Controllers. Include wiring diagrams.
9. Control cables. Include splice kits and conduit.

B. Shop Drawings: Show well locations, pumps, irrigation system piping, including plan layout, and locations, types, sizes, capacities, and flow characteristics of irrigation system piping components. Include water meters, backflow preventers, valves, piping, sprinklers and devices, accessories, controls, and wiring. Show areas of sprinkler spray and overspray. Show wire size and number of conductors for each control cable.
C. Coordination Drawings: Show piping and major system components. Indicate interface and spatial relationship between piping, system components, adjacent utilities, and proximate structures.
D. Field quality-control test reports.
E. Operation and Maintenance Data: For irrigation systems, to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 1 Section "Closeout Procedures Operation and Maintenance Data," include data for the following:
1. Automatic-control valves.
2. Sprinklers.
3. Controllers.
4. Pumps and wells

1.6 QUALITY ASSURANCE
A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.7 DELIVERY, STORAGE, AND HANDLING
A. Deliver piping with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe-end damage and to prevent entrance of dirt, debris, and moisture.
B. Store plastic piping protected from direct sunlight. Support to prevent sagging and bending.

1.8 COORDINATION
A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 3.

1.9 EXTRA MATERIALS
A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Sprinkler Units: 2 Each
2. Emitter Units: 2 Each
3. Drip Tube Units: 2 Each
4. Valve Keys: 2 Each

PART 2 - PRODUCTS

2.1 MANUFACTURERS
A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
2. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 PIPES, TUBES, AND FITTINGS
A. PVC Pipe: ASTM D 1785, PVC 1120 compound, Schedule 40.
1. PVC Socket Fittings, Schedule 40: ASTM D 2466.
B. Transition Fittings: Refer to Division 2 Section "Piped Utilities -- Basic Materials and Methods" for transition fittings.
C. Dielectric Fittings: Refer to Division 2 Section "Piped Utilities -- Basic Materials and Methods" for dielectric fittings.

2.3 JOINING MATERIALS
A. Refer to Division 2 Section "Piped Utilities -- Basic Materials and Methods" for commonly used joining materials.

2.4 GENERAL-DUTY VALVES

A. AWWA, Cast-Iron Gate Valves, nonrising-stem, gray- or ductile-iron body and bonnet gate valve; with bronze stem and stem nut.
   1. Minimum Working Pressure: 200 psig.
   2. End Connections: Mechanical joint.
   3. Interior Coating: Complying with AWWA C550.

B. Valve Boxes: Comply with AWWA M44 for cast-iron valve boxes. Include top section, adjustable extension of length required for depth of burial of valve, plug with lettering "WATER," bottom section with base of size to fit over valve, and approximately 5-inch- diameter barrel.
   1. Operating Wrenches: Furnish total of two steel, tee-handle operating wrench(es) with one pointed end, stem of length to operate deepest buried valve, and socket matching valve operating nut.

C. MSS, Cast-Iron, Nonrising-Stem Gate Valves: MSS SP-70, Type I, Class 125, with solid wedge and flanged ends. Include all bronze trim, cast-iron body, and handwheel.

D. MSS, Cast-Iron, Rising-Stem Gate Valves: MSS SP-70, Type I, Class 125, with solid wedge and flanged ends. Include all bronze trim, cast-iron body, and handwheel.

E. Curb Valves: AWWA C800. Include bronze body, ball or ground-key plug, and wide tee head, with inlet and outlet matching piping material.

2.5 SERVICE BOXES FOR CURB VALVES: Similar to AWWA M44 requirements for cast-iron valve boxes. Include cast-iron telescoping top section of length required for depth of burial of valve, plug with lettering "WATER," bottom section with base of size to fit over curb valve, and approximately 3-inch- diameter barrel.
   1. Shutoff Rods: Furnish total of two steel, tee-handle shutoff rod(s) with one pointed end, stem of length to operate deepest buried valve, and slotted end matching curb valve.

B. COPPER-ALLOY BALL VALVES: MSS SP-110, one-piece brass or bronze body with chrome-plated bronze ball, PTFE or TFE seats, and 400-psig minimum CWP rating.

C. PVC BALL VALVES: MSS SP-122, union type, with full-port ball detachable end connectors, and pressure rating not less than **150 psig**.
   1. Material Option: MSS SP-122, of plastic other than PVC and suitable for potable water. Include threaded ends and pressure rating not less than 150 psig, unless otherwise indicated.

2.6 CONTROL-VALVE BOXES

A. Plastic Control-Valve Boxes: Box and cover, with open bottom and openings for piping; designed for installing flush with grade. Include size as required for valves and service.

B. Drainage Backfill: Cleaned gravel or crushed stone, graded from 3/4 inch minimum to 3 inches maximum.

2.7 PIPING SPECIALTIES

A. Water Regulators: ASSE 1003, single-seated, direct-operated, water-pressure regulators, rated for 150-psig minimum initial-inlet working pressure, with size, flow rate, and inlet and outlet pressures indicated. Include integral factory-installed or separate field-installed Y-pattern strainer that is compatible with unit for size and capacity.

B. Water Hammer Arresters: ASSE 1010 or PDI WH 201, with bellows or piston-type pressurized cushioning chamber and in sizes complying with PDI WH 201, Sizes A to F.

C. Pressure Gages: ASME B40.1. Include 4-1/2-inch- diameter dial, dial range of 2 times system operating pressure, and bottom outlet.

2.8 SPRINKLERS

A. Description: Brass or plastic housing and corrosion-resistant interior parts designed for uniform coverage over entire spray area indicated, at available water pressure.
   1. Flush, Surface Sprinklers: Fixed pattern, with screw-type flow adjustment.
   2. Bubblers: Fixed pattern, with screw-type flow adjustment.
   3. Shrubbery Sprinklers: Fixed pattern, with screw-type flow adjustment.
   4. Pop-up, Spray Sprinklers: Fixed pattern, with screw-type flow adjustment and stainless-steel retraction spring.
   5. Pop-up, Rotary, Spray Sprinklers: Gear drive, full-circle and adjustable part-circle types.
   6. Pop-up, Rotary, Impact Sprinklers: Impact drive, full-circle and part-circle types.
   7. Aboveground, Rotary, Impact Sprinklers: Impact drive, full-circle and part-circle types.

2.9 AUTOMATIC-CONTROL SYSTEM

A. Exterior Control Enclosures: NEMA 250, Type 4, weatherproof, with locking cover and two matching keys; include provision for grounding.

B. Control Transformer: 24-V secondary, with primary fuse.

C. Controller Stations for Automatic Control Valves: Each station is variable from approximately 5 to 60 minutes. Include switch for manual or automatic operation of each station.

D. Timing Device: Adjustable, 24-hour, 14-day clock, with automatic operations to skip operation any day in timer period, to operate every other day, or to operate 2 or more times daily.
   1. Manual or Semiautomatic Operation: Allows this mode without disturbing preset automatic operation.
   2. Nickel-Cadmium Battery and Trickle Charger: Automatically powers timing device during power outages.
   3. Surge Protection: Metal-oxide-varistor type on each station and primary power.

E. Wiring: UL 493, Type UF-B multiconductor, with solid-copper conductors and insulated cable; suitable for direct burial.
   1. Feeder-Circuit Cables: No. 12 AWG minimum, between building and controllers.
   2. Low-Voltage, Branch-Circuit Cables: No. 14 AWG minimum, between controllers and automatic control valves; color-coded different from feeder-circuit-cable jacket color; with jackets of different colors for multiple-cable installation in same trench.
   3. Splicing Materials: Manufacturer's packaged kit consisting of insulating, spring-type connector or crimped joint and epoxy resin moisture seal; suitable for direct burial.

F. Concrete Base: Reinforced precast concrete with opening for wiring.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Refer to Division 2 Section "Earthwork" for excavating, trenching, and backfilling.

B. Install warning tape directly above pressure piping, 12 inches below finished grades, except 6 inches below subgrade under pavement and slabs.

C. Install piping and wiring in sleeves under sidewalks, roadways, parking lots, and railroads.
   1. Install piping sleeves by boring or jacking under existing paving if possible.

D. Drain Pockets: Excavate to sizes indicated. Backfill with cleaned gravel or crushed stone, graded from 3/4 to 3 inches, to 12 inches below grade. Cover gravel or crushed stone with sheet of asphalt-saturated felt and backfill remainder with excavated material.

E. Provide minimum cover over top of underground piping according to the following:
   1. Irrigation Main Piping: Minimum depth of 36 inches below finished grade, or not less than 18 inches below average local frost depth, whichever is deeper.
   2. Circuit Piping: 12 inches.
   3. Drain Piping: 12 inches.
   4. Sleeves: 24 inches.

3.2 PREPARATION

A. Set stakes to identify locations of proposed irrigation system. Obtain Architect's approval before excavation.

3.3 PIPING INSTALLATION

A. Location and Arrangement: Drawings indicate location and arrangement of piping systems. Install piping as indicated unless deviations are approved on Coordination Drawings.

B. Install piping at minimum uniform slope of 0.5 percent down toward drain valves.

C. Install piping free of sags and bends.

D. Install groups of pipes parallel to each other, spaced to permit valve servicing.

E. Install fittings for changes in direction and branch connections.

F. Install unions adjacent to valves and to final connections to other components with NPS 2 or smaller pipe connection.

G. Install flanges adjacent to valves and to final connections to other components with NPS 2-1/2 or larger pipe connection.

H. Install dielectric fittings to connect piping of dissimilar metals.

I. Install underground thermoplastic piping according to ASTM D 2774.

J. Lay piping on solid subbase, uniformly sloped without humps or depressions.

K. Install ductile-iron piping according to AWWA C600.

L. Install PVC piping in dry weather when temperature is above 40 deg F 5 deg C. Allow joints to cure at least 24 hours at temperatures above 40 deg F 5 deg C before testing unless otherwise recommended by manufacturer.
M. Install water regulators with shutoff valve and strainer on inlet and pressure gage on outlet. Install shutoff valve on outlet.
N. Water Hammer Arresters: Install between connection to building main and circuit valves in valve box.

3.4 JOINT CONSTRUCTION
A. Refer to Division 2 Section "Piped Utilities -- Basic Materials and Methods" for basic pipe joint construction.

3.5 VALVE INSTALLATION
A. Underground Gate Valves: Install in valve box with top flush with grade.
1. Install valves and PVC pipe with restrained, gasketed joints.
B. Underground Curb Stops: Install in service box with top flush with grade.
C. Underground, Manual Control Valves: Install in manual control-valve box.
D. Control Valves: Install in control-valve box.
E. Drain Valves: Install in control-valve box.

3.6 SPRINKLER INSTALLATION
A. Flush circuit piping with full head of water and install sprinklers after hydrostatic test is completed.
B. Install sprinklers at manufacturer's recommended heights.
C. Locate part-circle sprinklers to maintain a minimum distance of 4 inches from walls and 2 inches from other boundaries, unless otherwise indicated.

3.7 AUTOMATIC-CONTROL SYSTEM INSTALLATION
A. Install freestanding controllers on precast concrete bases not less than 36 by 24 by 4 inches thick, and not less than 6 inches greater in each direction than overall dimensions of controller.
B. Install control cable in same trench as irrigation piping and at least 2 inches below piping. Provide conductors of size not smaller than recommended by controller manufacturer. Install cable in separate sleeve under paved areas if irrigation piping is installed in sleeve.

3.8 CONNECTIONS
A. Drawings indicate general arrangement of piping, fittings, and specialties.
B. Ground equipment according to Division 16 Section "Grounding and Bonding."
C. Connect wiring according to Division 16 Section "Conductors and Cables."
D. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.9 LABELING AND IDENTIFYING
A. Equipment Nameplates and Signs: Install engraved plastic-laminate equipment nameplates and signs on each automatic controller.
1. Text: In addition to identifying unit, distinguish between multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations.
B. Refer to Division 2 Section "Piped Utilities -- Basic Materials and Methods" for equipment nameplates and signs.

C. Warning Tapes: Arrange for installation of continuous, underground, detectable warning tape over underground piping, during backfilling of trenches.
D. Refer to Division 2 Section "Earthwork" for warning tapes.

3.10 FIELD QUALITY CONTROL
A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connection, and to assist in field testing. Report results in writing.
B. Perform the following field tests and inspections and prepare test reports:
1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
2. Operational Test: After electrical circuitry has been energized, operate controllers and automatic control valves to confirm proper system operation.

3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

C. Remove and replace units and[retest / reinspect as specified above.

3.11 STARTUP SERVICE

A. Engage a factory-authorized service representative to perform startup service.
B. Verify that controllers are installed and connected according to the Contract Documents.
C. Verify that electrical wiring installation complies with manufacturer's submittal and installation requirements in Division 16 Sections.
D. Complete startup checks according to manufacturer's written instructions.

3.12 MAINTENANCE & ADJUSTING

A. Adjust settings of controllers.
B. Adjust automatic control valves to provide flow rate of rated operating pressure required for each sprinkler circuit.
C. Adjust sprinklers so they will be flush with, or not more than 1/2 inch above, finish grade.
D. Provide Maintenance, and Adjusting for 1 full year, a Min. of 1 full season of watering, after substantial completion.

3.13 CLEANING

A. Flush dirt and debris from piping before installing sprinklers and other devices.

3.14 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain controller and automatic control valves.

END OF SECTION 02810

SECTION 02920

LAWNS AND GRASSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Seeding.
   2. Sodding.

B. Related Sections include the following:
   1. Division 2 Section "Site Clearing" for topsoil stripping and stockpiling.
   2. Division 2 Section "Earthwork" for excavation, filling and backfilling, and rough grading.
   3. Division 2 Section "Subdrainage" for subsurface drainage.

1.3 DEFINITIONS

A. Finish Grade: Elevation of finished surface of planting soil.

B. Manufactured Soil: Soil produced off-site by homogeneously blending mineral soils or sand with stabilized organic soil amendments to produce topsoil or planting soil.

C. Planting Soil: Native or imported topsoil, manufactured topsoil, or surface soil modified to become topsoil; mixed with soil amendments.

D. Subgrade: Surface or elevation of subsoil remaining after completing excavation, or top surface of a fill or backfill immediately beneath planting soil.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Certification of Grass Seed: From seed vendor for each grass-seed monostand or mixture stating the botanical and common name and percentage by weight of each species and variety, and percentage of purity, germination, and weed seed. Include the year of production and date of packaging.

C. Qualification Data: For landscape Installer.

D. Planting Schedule: Indicating anticipated planting dates for each type of planting.

E. Maintenance Instructions: Recommended procedures to be established by Owner for maintenance of lawns during a calendar year. Submit before expiration of required maintenance periods.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A qualified landscape installer whose work has resulted in successful lawn establishment.
   1. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when planting is in progress.

B. Soil-Testing Laboratory Qualifications: An independent laboratory, recognized by the State Department of Agriculture, with the experience and capability to conduct the testing indicated and that specializes in types of tests to be performed.

C. Topsoil Analysis: Furnish soil analysis by a qualified soil-testing laboratory stating percentages of organic matter; gradation of sand, silt, and clay content; cation exchange capacity; deleterious material; pH; and mineral and plant-nutrient content of topsoil.
   1. Report suitability of topsoil for lawn growth. State recommended quantities of nitrogen, phosphorus, and potash nutrients and soil amendments to be added to produce a satisfactory topsoil.

D. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

1.6 DELIVERY, STORAGE, AND HANDLING

A. Seed: Deliver seed in original sealed, labeled, and undamaged containers.

B. Sod: Harvest, deliver, store, and handle sod according to requirements in TPI's "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" in its "Guideline Specifications to Turfgrass Sodding."

1.7 SCHEDULING

A. Planting Restrictions: Plant according to manufacturer's recommendations. Coordinate planting periods with maintenance periods to provide required maintenance from date of Substantial Completion.

B. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit.

1.8 LAWN MAINTENANCE

A. Begin maintenance immediately after each area is planted and continue until acceptable lawn is established, but for not less than the following periods:
   1. Seeded Lawns: **1 Year from date of Substantial Completion**.
      a. When full maintenance period has not elapsed before end of planting season, or if lawn is not fully established, continue maintenance during next planting season.

B. Maintain and establish lawn by watering, fertilizing, weeding, mowing, trimming, replanting, and other operations. Roll, regrade, and replant bare or eroded areas and re-mulch to produce a uniformly smooth lawn.
   1. In areas where mulch has been disturbed by wind or maintenance operations, add new mulch. Anchor as required to prevent displacement.

C. Watering: Provide and maintain temporary piping, hoses, and lawn-watering equipment to convey water from sources and to keep lawn uniformly moist to a depth of 4 inches.
   1. Schedule watering to prevent wilting, puddling, erosion, and displacement of seed or mulch. Lay out temporary watering system to avoid walking over muddy or newly planted areas.
   2. Water lawn at a minimum rate of 1 inch per week.

D. Mow lawn as soon as top growth is tall enough to cut. Repeat mowing to maintain specified height without cutting more than 40 percent of grass height. Remove no more than 40 percent of grass-leaf growth in initial or subsequent mowing. Do not delay mowing until grass blades bend over and become matted. Do not mow when grass is wet.

E. Lawn Post fertilization: Apply fertilizer after initial mowing and when grass is dry.
   1. Use fertilizer that will provide actual nitrogen of at least 1 lb/1000 sq. ft. to lawn area.

PART 2 - PRODUCTS

2.1 SEED

A. Grass Seed: Fresh, clean, dry, new-crop seed complying with AOSA's "Journal of Seed Technology; Rules for Testing Seeds" for purity and germination tolerances.

B. Seed Species: Seed of grass species as follows, with not less than 95 percent germination, not less than 85 percent pure seed, and not more than 0.5 percent weed seed:
   1. Full Sun: Recommended species for area, soil, and climate.
   2. Sun and Partial Shade: Recommended species for area, soil, and climate
   3. Shade: Recommended species for area, soil, and climate.

2.2 TOPSOIL

A. Topsoil: ASTM D 5268, pH range of 5.5 to 7, a minimum of 2 percent organic material content; free of stones 1/2 inch or larger in any dimension and other extraneous materials harmful to plant growth.
   1. Topsoil Source: Reuse surface soil stockpiled on-site. Verify suitability of stockpiled surface soil to produce topsoil. Clean surface soil of roots, plants, sod, stones, clay lumps, and other extraneous materials harmful to plant growth.
      a. Supplement with imported or manufactured topsoil from off-site sources when quantities are insufficient. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.
   2. Topsoil Source: Import topsoil or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.
   3. Topsoil Source: Amend existing in-place surface soil to produce topsoil. Verify suitability of surface soil to produce topsoil. Clean surface soil of roots, plants, sod, stones, clay lumps, and other extraneous materials harmful to plant growth.
      a. Surface soil may be supplemented with imported or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.

2.3 PLANTING ACCESSORIES

A. Selective Herbicides: EPA registered and approved, of type recommended by manufacturer for application.

2.4 FERTILIZER

A. Bonemeal: Commercial, raw or steamed, finely ground; a minimum of 4 percent nitrogen and 10 percent phosphoric acid.

B. Superphosphate: Commercial, phosphate mixture, soluble; a minimum of 20 percent available phosphoric acid.

C. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:

1. Composition: 1 lb/1000 sq. ft. of actual nitrogen, 4 percent phosphorous, and 2 percent potassium, by weight.
2. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing agency.

D. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:

1. Composition: 20 percent nitrogen, 10 percent phosphorous, and 10 percent potassium, by weight.
2. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing agency.

2.5 MULCHES

A. Straw Mulch: Provide air-dry, clean, mildew- and seed-free, salt hay or threshed straw of wheat, rye, oats, or barley.

B. Peat Mulch: Sphagnum peat moss, partially decomposed, finely divided or granular texture, with a pH range of 3.4 to 4.8.

C. Peat Mulch: Finely divided or granular texture, with a pH range of 6 to 7.5, containing partially decomposed moss peat, native peat, or reed-sedge peat and having a water-absorbing capacity of 1100 to 2000 percent.

D. Compost Mulch: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1-inch sieve; soluble salt content of 5 to 10 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings; and as follows:

1. Organic Matter Content: 50 to 60 percent of dry weight.
2. Feedstock: Agricultural, food, or industrial residuals; biosolids; yard trimmings; or source-separated or compostable mixed solid waste.

E. Fiber Mulch: Biodegradable, dyed-wood, cellulose-fiber mulch; nontoxic; free of plant-growth or germination inhibitors; with maximum moisture content of 15 percent and a pH range of 4.5 to 6.5.

F. Nonasphaltic Tackifier: Colloidal tackifier recommended by fiber-mulch manufacturer for slurry application; nontoxic and free of plant-growth or germination inhibitors.

G. Asphalt Emulsion: ASTM D 977, Grade SS-1; nontoxic and free of plant-growth or germination inhibitors.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive lawns and grass for compliance with requirements and other conditions affecting performance. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Protect structures, utilities, sidewalks, pavements, and other facilities, trees, shrubs, and plantings from damage caused by planting operations.

1. Protect adjacent and adjoining areas from hydroseeding overspray.

B. Provide erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.

3.3 LAWN PREPARATION

A. Limit lawn subgrade preparation to areas to be planted.

B. Newly Graded Subgrades: Loosen subgrade to a minimum depth of 4 inches Remove stones larger than 1/2 inch in any dimension and sticks, roots, rubbish, and other extraneous matter and legally dispose of them off Owner's property.
   1. Apply fertilizer directly to subgrade before loosening.
   2. Thoroughly blend planting soil mix off-site before spreading or spread topsoil, apply soil amendments and fertilizer on surface, and thoroughly blend planting soil mix.
      a. Delay mixing fertilizer with planting soil if planting will not proceed within a few days.
      b. Mix lime with dry soil before mixing fertilizer.
   3. Spread planting soil mix to a depth of 4 inches but not less than required to meet finish grades after light rolling and natural settlement. Do not spread if planting soil or subgrade is frozen, muddy, or excessively wet.
      a. Spread approximately one-half the thickness of planting soil mix over loosened subgrade. Mix thoroughly into top 2 inches of subgrade. Spread remainder of planting soil mix.
      b. Reduce elevation of planting soil to allow for soil thickness of sod.

C. Unchanged Subgrades: If lawns are to be planted in areas unaltered or undisturbed by excavating, grading, or surface soil stripping operations, prepare surface soil as follows:
   1. Remove existing grass, vegetation, and turf. Do not mix into surface soil.
   2. Loosen surface soil to a depth of at least of 6 inches. Apply soil amendments and fertilizers according to planting soil mix proportions and mix thoroughly into top 4 inches of soil. Till soil to a homogeneous mixture of fine texture.
   3. Remove stones larger than 1/2 inch in any dimension and sticks, roots, trash, and other extraneous matter.
   4. Legally dispose of waste material, including grass, vegetation, and turf, off Owner's property.

D. Finish Grading: Grade planting areas to a smooth, uniform surface plane with loose, uniformly fine texture. Grade to within plus or minus 1/2 inch of finish elevation. Roll and rake, remove ridges, and fill depressions to meet finish grades. Limit fine grading to areas that can be planted in the immediate future.

E. Moisten prepared lawn areas before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.

F. Restore areas if eroded or otherwise disturbed after finish grading and before planting.

3.4 SEEDING

A. Sow seed with spreader or seeding machine. Do not broadcast or drop seed when wind velocity exceeds 5 mph. Evenly distribute seed by sowing equal quantities in two directions at right angles to each other.
   1. Do not use wet seed or seed that is moldy or otherwise damaged.

B. Sow seed at the rate of 3 to 4 lb/1000 sq. ft..

C. Rake seed lightly into top 1/8 inch of topsoil, roll lightly, and water with fine spray.

D. Protect seeded areas with slopes exceeding 1:6 with erosion-control fiber mesh and 1:4 with erosion-control blankets installed and stapled according to manufacturer's written instructions.

E. Protect seeded areas with slopes not exceeding 1:6 by spreading straw mulch. Spread uniformly at a minimum rate of 2 tons/acre to form a continuous blanket 1-1/2 inches in loose depth over seeded areas. Spread by hand, blower, or other suitable equipment.
   1. Anchor straw mulch by crimping into topsoil with suitable mechanical equipment.
   2. Bond straw mulch by spraying with asphalt emulsion at the rate of 10 to 13 gal./1000 sq. ft.. Take precautions to prevent damage or staining of structures or other plantings adjacent to mulched areas. Immediately clean damaged or stained areas.

F. Protect seeded areas from hot, dry weather or drying winds by applying any compost mulch, peat mulch, planting soil, or topsoil within 24 hours after completing seeding operations. Soak and scatter uniformly to a depth of 3/16 inch and roll to a smooth surface.

3.5 SATISFACTORY LAWNS

A. Satisfactory Seeded Lawn: At end of maintenance period, a healthy, uniform, close stand of grass has been established, free of weeds and surface irregularities, with coverage exceeding 90 percent over any 10 sq. ft. and bare spots not exceeding 5 by 5 inches.

B. Satisfactory Sodded Lawn: At end of maintenance period, a healthy, well-rooted, even-colored, viable lawn has been established, free of weeds, open joints, bare areas, and surface irregularities.

C. Satisfactory Plugged Lawn: At end of maintenance period, the required number of plugs has been established as well-rooted, viable patches of grass; and areas between plugs are free of weeds and other undesirable vegetation.

D. Satisfactory Sprigged Lawn: At end of maintenance period, the required number of sprigs has been established as well-rooted, viable plants; and areas between sprigs are free of weeds and other undesirable vegetation.
E. Reestablish lawns that do not comply with requirements and continue maintenance until lawns are satisfactory.

3.6 CLEANUP AND PROTECTION

A. Promptly remove soil and debris created by lawn work from paved areas. Clean wheels of vehicles before leaving site to avoid tracking soil onto roads, walks, or other paved areas.
B. Erect barricades and warning signs as required to protect newly planted areas from traffic. Maintain barricades throughout maintenance period and remove after lawn is established.
C. Remove erosion-control measures after grass establishment period.

END OF SECTION 02920

SECTION 02930

EXTERIOR PLANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Trees.
   2. Shrubs.
   3. Ground cover.
   4. Plants.
   5. Edgings.
   6. Planters.

B. Related Sections include the following:
   1. Division 2 Section "Site Clearing" for protection of existing trees and planting, topsoil stripping and stockpiling, and site clearing.
   2. Division 2 Section "Earthwork" for excavation, filling, and rough grading and for subsurface aggregate drainage and drainage backfill materials.
   3. Division 2 Section "Subdrainage" for below-grade drainage of landscaped areas, paved areas, and wall perimeters.
   4. Division 12 Section "Interior Plants" for interior plants, trees, and vines.
   5. Division 12 Section "Interior Planters" for pots and urns for interior plantings.

1.3 DEFINITIONS

A. Balled and Burlapped Stock: Exterior plants dug with firm, natural balls of earth in which they are grown, wrapped, tied, rigidly supported, and drum-laced as recommended by ANSI Z60.1.

B. Balled and Potted Stock: Exterior plants dug with firm, natural balls of earth in which they are grown and placed, unbroken, in a container.

C. Bare-Root Stock: Exterior plants with a well-branched, fibrous-root system developed by transplanting or root pruning, with soil or growing medium removed, and with not less than minimum root spread according to ANSI Z60.1 for kind and size of exterior plant required.

D. Container-Grown Stock: Healthy, vigorous, well-rooted exterior plants grown in a container with well-established root system reaching sides of container and maintaining a firm ball when removed from container. Container shall be rigid enough to hold ball shape and protect root mass during shipping and be sized according to ANSI Z60.1 for kind, type, and size of exterior plant required.

E. Fabric Bag-Grown Stock: Healthy, vigorous, well-rooted exterior plants established and grown in-ground in a porous fabric bag with well-established root system reaching sides of fabric bag. Fabric bag size is not less than diameter, depth, and volume required by ANSI Z60.1 for type and size of exterior plant.

F. Finish Grade: Elevation of finished surface of planting soil.

G. Manufactured Topsoil: Soil produced off-site by homogeneously blending mineral soils or sand with stabilized organic soil amendments to produce topsoil or planting soil.

H. Planting Soil: Native or imported topsoil, manufactured topsoil, or surface soil modified to become topsoil; mixed with soil amendments.

I. Subgrade: Surface or elevation of subsoil remaining after completing excavation, or top surface of a fill or backfill, before placing planting soil.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Samples for Verification: For each of the following:
   1. 5 lb of mineral mulch for each color and texture of stone required, in labeled plastic bags.
   2. Edging materials and accessories, of manufacturer's standard size, to verify color selected.

C. Product Certificates: For each type of manufactured product, signed by product manufacturer, and complying with the following:
   1. Manufacturer's certified analysis for standard products.

2. Analysis of other materials by a recognized laboratory made according to methods established by the Association of Official Analytical Chemists, where applicable.

D. Qualification Data: For landscape Installer.

E. Material Test Reports: For existing surface soil and imported topsoil.

F. Planting Schedule: Indicating anticipated planting dates for exterior plants.

G. Maintenance Instructions: Recommended procedures to be established by Owner for maintenance of exterior plants during a calendar year. Submit before expiration of required maintenance periods.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A qualified landscape installer whose work has resulted in successful establishment of exterior plants.
1. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when exterior planting is in progress.

B. Soil-Testing Laboratory Qualifications: An independent laboratory, recognized by the State Department of Agriculture, with the experience and capability to conduct the testing indicated and that specializes in types of tests to be performed.

C. Topsoil Analysis: Furnish soil analysis by a qualified soil-testing laboratory stating percentages of organic matter; gradation of sand, silt, and clay content; cation exchange capacity; deleterious material; pH; and mineral and plant-nutrient content of topsoil.
1. Report suitability of topsoil for plant growth. State recommended quantities of nitrogen, phosphorus, and potash nutrients and soil amendments to be added to produce a satisfactory topsoil.

D. Provide quality, size, genus, species, and variety of exterior plants indicated, complying with applicable requirements in ANSI Z60.1, "American Standard for Nursery Stock."
1. Selection of exterior plants purchased under allowances will be made by Architect, who will tag plants at their place of growth before they are prepared for transplanting.

E. Tree and Shrub Measurements: Measure according to ANSI Z60.1 with branches and trunks or canes in their normal position. Do not prune to obtain required sizes. Take caliper measurements 6 inches above ground for trees up to 4-inch caliper size, and 12 inches above ground for larger sizes. Measure main body of tree or shrub for height and spread; do not measure branches or roots tip-to-tip.

F. Observation: Architect may observe trees and shrubs either at place of growth or at site before planting for compliance with requirements for genus, species, variety, size, and quality. Architect retains right to observe trees and shrubs further for size and condition of balls and root systems, insects, injuries, and latent defects and to reject unsatisfactory or defective material at any time during progress of work. Remove rejected trees or shrubs immediately from Project site.
1. Notify Architect of sources of planting materials seven days in advance of delivery to site.

G. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver exterior plants freshly dug.
1. Immediately after digging up bare-root stock, pack root system in wet straw, hay, or other suitable material to keep root system moist until planting.

B. Do not prune trees and shrubs before delivery, except as approved by Architect. Protect bark, branches, and root systems from sun scald, drying, sweating, whipping, and other handling and tying damage. Do not bend or bind-tie trees or shrubs in such a manner as to destroy their natural shape. Provide protective covering of exterior plants during delivery. Do not drop exterior plants during delivery.

C. Handle planting stock by root ball.

D. Deliver exterior plants after preparations for planting have been completed and install immediately. If planting is delayed more than six hours after delivery, set exterior plants trees in shade, protect from weather and mechanical damage, and keep roots moist.
1. Heel-in bare-root stock. Soak roots in water for two hours if dried out.
2. Set balled stock on ground and cover ball with soil, peat moss, sawdust, or other acceptable material.
3. Do not remove container-grown stock from containers before time of planting.
4. Water root systems of exterior plants stored on-site with a fine-mist spray. Water as often as necessary to maintain root systems in a moist condition.

1.7 COORDINATION

A. Planting Restrictions: Plant during one of the following periods. Coordinate planting periods with maintenance periods to provide required maintenance from date of Substantial Completion.

1. Spring Planting: As recommended for area, soil, and climate.
2. Fall Planting: As recommended for area, soil, and climate.

B. Weather Limitations: Proceed with planting only when existing and forecasted weather conditions permit.

C. Coordination with Lawns: Plant trees and shrubs after finish grades are established and before planting lawns, unless otherwise acceptable to Architect.
1. When planting trees and shrubs after lawns, protect lawn areas and promptly repair damage caused by planting operations.

1.8 WARRANTY

A. Special Warranty: Warrant the following exterior plants, for the warranty period indicated, against defects including death and unsatisfactory growth, except for defects resulting from lack of adequate maintenance, neglect, or abuse by Owner, or incidents that are beyond Contractor's control.
1. Warranty Period for Trees and Shrubs: **One year from date of Substantial Completion.**
2. Warranty Period for Ground Cover and Plants: **Six months from date of Substantial Completion.**
3. Remove dead exterior plants immediately. Replace immediately unless required to plant in the succeeding planting season.
4. Replace exterior plants that are more than 25 percent dead or in an unhealthy condition at end of warranty period.
5. A limit of one replacement of each exterior plant will be required, except for losses or replacements due to failure to comply with requirements.

1.9 MAINTENANCE

A. Trees and Shrubs: Maintain for the following maintenance period by pruning, cultivating, watering, weeding, fertilizing, restoring planting saucers, tightening and repairing stakes and guy supports, and resetting to proper grades or vertical position, as required to establish healthy, viable plantings. Spray as required to keep trees and shrubs free of insects and disease. Restore or replace damaged tree wrappings.
1. Maintenance Period: Six months from date of Substantial Completion.

B. Ground Cover and Plants: Maintain for the following maintenance period by watering, weeding, fertilizing, and other operations as required to establish healthy, viable plantings:
1. Maintenance Period: Six months from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 TREE AND SHRUB MATERIAL

A. General: Furnish nursery-grown trees and shrubs complying with ANSI Z60.1, with healthy root systems developed by transplanting or root pruning. Provide well-shaped, fully branched, healthy, vigorous stock free of disease, insects, eggs, larvae, and defects such as knots, sun scald, injuries, abrasions, and disfigurement.

B. Grade: Provide trees and shrubs of sizes and grades complying with ANSI Z60.1 for type of trees and shrubs required. Trees and shrubs of a larger size may be used if acceptable to Architect, with a proportionate increase in size of roots or balls.

C. Label each tree and shrub with securely attached waterproof tag bearing legible designation of botanical and common name.

D. Label at least one tree and one shrub of each variety and caliper with a securely attached, waterproof tag bearing legible designation of botanical and common name.

E. If formal arrangements or consecutive order of trees or shrubs is shown, select stock for uniform height and spread, and number label to assure symmetry in planting.

2.2 SHADE AND FLOWERING TREES

A. Small Trees: Branched or pruned naturally according to species and type, with relationship of caliper, height, and branching according to ANSI Z60.1.

B. Multistem Trees: Branched or pruned naturally according to species and type, with relationship of caliper, height, and branching according to ANSI Z60.1.

2.3 DECIDUOUS SHRUBS

A. Form and Size: Deciduous shrubs with not less than the minimum number of canes required by and measured according to ANSI Z60.1 for type, shape, and height of shrub.

2.4 CONIFEROUS EVERGREENS

A. Form and Size: Normal-quality, well-balanced, coniferous evergreens, of type, height, spread, and shape required, complying with ANSI Z60.1.

2.5 BROADLEAF EVERGREENS

A. Form and Size: Normal-quality, well-balanced, broadleaf evergreens, of type, height, spread, and shape required, complying with ANSI Z60.1.

2.6 GROUND COVER PLANTS

A. Ground Cover: Provide ground cover of species indicated, established and well rooted in pots or similar containers, and complying with ANSI Z60.1.

B. Dichondra: Provide dichondra seed with 99 percent minimum pure seed, not less than 85 percent germination, and not more than 0.25 percent weed seed.

C. Dichondra: Provide dichondra plants grown in flats and suitable for cutting into plugs.

2.7 PLANTS

A. Annuals: Provide healthy, disease-free plants of species and variety shown or listed. Provide only plants that are acclimated to outdoor conditions before delivery and that are in bud but not yet in bloom.

B. Perennials: Provide healthy, field-grown plants from a commercial nursery, of species and variety shown or listed.

C. Fast-Growing Vines: Provide vines of species indicated complying with requirements in ANSI Z60.1 as follows:

1. Two-year plants with heavy, well-branched tops, with not less than 3 runners 18 inches or more in length, and with a vigorous well-developed root system.
2. Provide field-grown vines. Vines grown in pots or other containers of adequate size and acclimated to outside conditions will also be acceptable.

2.8 TOPSOIL

A. Topsoil: ASTM D 5268, pH range of 5.5 to 7, a minimum of 4 percent organic material content; free of stones 1/2 inch or larger in any dimension and other extraneous materials harmful to plant growth.

1. Topsoil Source: Reuse surface soil stockpiled on-site. Verify suitability of stockpiled surface soil to produce topsoil. Clean surface soil of roots, plants, sod, stones, clay lumps, and other extraneous materials harmful to plant growth.
    a. Supplement with imported or manufactured topsoil from off-site sources when quantities are insufficient. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.
2. Topsoil Source: Import topsoil or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.
3. Topsoil Source: Amend existing in-place surface soil to produce topsoil. Verify suitability of surface soil to produce topsoil. Clean surface soil of roots, plants, sod, stones, clay lumps, and other extraneous materials harmful to plant growth.
    a. Surface soil may be supplemented with imported or manufactured topsoil from off-site sources. Obtain topsoil displaced from naturally well-drained construction or mining sites where topsoil occurs at least 4 inches deep; do not obtain from agricultural land, bogs or marshes.

2.9 ORGANIC SOIL AMENDMENTS

A. Compost: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1-inch sieve; soluble salt content of 5 to 10 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings.

B. Peat: Sphagnum peat moss, partially decomposed, finely divided or granular texture, with a pH range of 3.4 to 4.8.

C. Peat: Finely divided or granular texture, with a pH range of 6 to 7.5, containing partially decomposed moss peat, native peat, or reed-sedge peat and having a water-absorbing capacity of 1100 to 2000 percent.

D. Wood Derivatives: Decomposed, nitrogen-treated sawdust, ground bark, or wood waste; of uniform texture, free of chips, stones, sticks, soil, or toxic materials.

E. Manure: Well-rotted, unleached, stable or cattle manure containing not more than 25 percent by volume of straw, sawdust, or other bedding materials; free of toxic substances, stones, sticks, soil, weed seed, and material harmful to plant growth.

2.10 FERTILIZER

A. Bonemeal: Commercial, raw or steamed, finely ground; a minimum of 4 percent nitrogen and 10 percent phosphoric acid.

B. Superphosphate: Commercial, phosphate mixture, soluble; a minimum of 20 percent available phosphoric acid.

C. Commercial Fertilizer: Commercial-grade complete fertilizer of neutral character, consisting of fast- and slow-release nitrogen, 50 percent derived from natural organic sources of urea formaldehyde, phosphorous, and potassium in the following composition:

1. Composition: 1 lb/1000 sq. ft of actual nitrogen, 4 percent phosphorous, and 2 percent potassium, by weight.
2. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing agency.

D. Slow-Release Fertilizer: Granular or pelleted fertilizer consisting of 50 percent water-insoluble nitrogen, phosphorus, and potassium in the following composition:

1. Composition: 20 percent nitrogen, 10 percent phosphorous, and 10 percent potassium, by weight.
2. Composition: Nitrogen, phosphorous, and potassium in amounts recommended in soil reports from a qualified soil-testing agency.

2.11 MULCHES

A. Organic Mulch: Free from deleterious materials and suitable as a top dressing of trees and shrubs.

B. Compost Mulch: Well-composted, stable, and weed-free organic matter, pH range of 5.5 to 8; moisture content 35 to 55 percent by weight; 100 percent passing through 1-inch sieve; soluble salt content of 5 to 10 decisiemens/m; not exceeding 0.5 percent inert contaminants and free of substances toxic to plantings.

2.12 WEED-CONTROL BARRIERS

A. Polyethylene Sheeting: ASTM D 4397, black, 0.006-inch- minimum thickness.

B. Nonwoven Fabric: Polypropylene or polyester fabric, 3 oz./sq. yd. minimum.

C. Composite Fabric: Woven, needle-punched polypropylene substrate bonded to a nonwoven polypropylene fabric, 4.8 oz./sq. yd.

2.13 STAKES AND GUYS

A. Upright and Guy Stakes: Rough-sawn, sound, new hardwood, redwood, or pressure-preservative-treated softwood, free of knots, holes, cross grain, and other defects, 2 by 2 inches by length indicated, pointed at one end.

B. Guy and Tie Wire: ASTM A 641/A 641M, Class 1, galvanized-steel wire, 2-strand, twisted, 0.106 inch in diameter.

C. Guy Cable: 5-strand, 3/16-inch- diameter, galvanized-steel cable, with zinc-coated turnbuckles, a minimum of 3 inches long, with two 3/8-inch galvanized eyebolts.

D. Hose Chafing Guard: Reinforced rubber or plastic hose at least 1/2 inch in diameter, black, cut to lengths required to protect tree trunks from damage.

E. Flags: Standard surveyor's plastic flagging tape, white, 6 inches long.

2.14 LANDSCAPE EDGINGS

A. Wood Edging: Of sizes shown, and wood stakes.

B. Steel Edging: Standard commercial-steel edging, rolled edge, fabricated in sections of standard lengths, with loops stamped from or welded to face of sections to receive stakes.

C. Aluminum Edging: Standard-profile extruded-aluminum edging, ASTM B 221, alloy 6063-T6, fabricated in standard lengths with interlocking sections with loops stamped from face of sections to receive stakes.

D. Polyethylene Edging: Standard black polyethylene edging, V-lipped bottom, extruded in standard lengths, with 9-inch steel angle stakes.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas to receive exterior plants for compliance with requirements and conditions affecting installation and performance. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Protect structures, utilities, sidewalks, pavements, and other facilities, and lawns and existing exterior plants from damage caused by planting operations.

B. Provide erosion-control measures to prevent erosion or displacement of soils and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways.

C. Lay out individual tree and shrub locations and areas for multiple exterior plantings. Stake locations, outline areas, adjust locations when requested, and obtain Architect's acceptance of layout before planting. Make minor adjustments as required.

D. Lay out exterior plants at locations directed by Architect. Stake locations of individual trees and shrubs and outline areas for multiple plantings.

E. Apply antidesiccant to trees and shrubs using power spray to provide an adequate film over trunks, branches, stems, twigs, and foliage to protect during digging, handling, and transportation.

1. If deciduous trees or shrubs are moved in full leaf, spray with antidesiccant at nursery before moving and again two weeks after planting.

3.3 PLANTING BED ESTABLISHMENT

A. Loosen subgrade of planting beds to a minimum depth of 4 inches. Remove stones larger than 1/2 inch in any dimension and sticks, roots, rubbish, and other extraneous matter and legally dispose of them off Owner's property.

B. Finish Grading: Grade planting beds to a smooth, uniform surface plane with loose, uniformly fine texture. Roll and rake, remove ridges, and fill depressions to meet finish grades.

C. Restore planting beds if eroded or otherwise disturbed after finish grading and before planting.

3.4 TREE AND SHRUB EXCAVATION

A. Pits and Trenches: Excavate circular pits with sides sloped inward. Trim base leaving center area raised slightly to support root ball and assist in drainage. Do not further disturb base. Scarify sides of plant pit smeared or smoothed during excavation.

1. Excavate approximately three times as wide as ball diameter for balled and burlapped stock.
2. Excavate at least 12 inches wider than root spread and deep enough to accommodate vertical roots for bare-root stock.
3. If drain tile is shown or required under planted areas, excavate to top of porous backfill over tile.

B. Subsoil removed from excavations may be used as backfill.

C. Obstructions: Notify Architect if unexpected rock or obstructions detrimental to trees or shrubs are encountered in excavations.

1. Hardpan Layer: Drill 6-inch diameter holes into free-draining strata or to a depth of 10 feet, whichever is less, and backfill with free-draining material.

D. Drainage: Notify Architect if subsoil conditions evidence unexpected water seepage or retention in tree or shrub pits.

E. Fill excavations with water and allow to percolate away before positioning trees and shrubs.

3.5 TREE AND SHRUB PLANTING

A. Set balled and burlapped stock plumb and in center of pit or trench with top of root ball flush with adjacent finish grades.

1. Remove burlap and wire baskets from tops of root balls and partially from sides, but do not remove from under root balls. Remove pallets, if any, before setting. Do not use planting stock if root ball is cracked or broken before or during planting operation.
2. Place planting soil mix around root ball in layers, tamping to settle mix and eliminate voids and air pockets. When pit is approximately one-half backfilled, water thoroughly before placing remainder of backfill. Repeat watering until no more water is absorbed. Water again after placing and tamping final layer of planting soil mix.

B. Set balled and potted stock plumb and in center of pit or trench with top of root ball flush with adjacent finish grades.

1. Carefully remove root ball from container without damaging root ball or plant.

2. Place planting soil mix around root ball in layers, tamping to settle mix and eliminate voids and air pockets. When pit is approximately one-half backfilled, water thoroughly before placing remainder of backfill. Repeat watering until no more water is absorbed. Water again after placing and tamping final layer of planting soil mix.

C. Set fabric bag-grown stock plumb and in center of pit or trench with top of root ball flush with adjacent finish grades.
1. Carefully remove root ball from fabric bag without damaging root ball or plant. Do not use planting stock if root ball is cracked or broken before or during planting operation.
2. Place planting soil mix around root ball in layers, tamping to settle mix and eliminate voids and air pockets. When pit is approximately one-half backfilled, water thoroughly before placing remainder of backfill. Repeat watering until no more water is absorbed. Water again after placing and tamping final layer of planting soil mix.

D. Set and support bare-root stock in center of pit or trench with root collar or trunk flare, flush with adjacent finish grade. Spread roots without tangling or turning toward surface, and carefully work backfill around roots by hand. Puddle with water until backfill layers are completely saturated. Plumb before backfilling, and maintain plumb while working backfill around roots and placing layers above roots. Tamp final layer of backfill. Remove injured roots by cutting cleanly; do not break.

E. Organic Mulching: Apply 2-inch average thickness of organic mulch extending 12 inches beyond edge of planting pit or trench. Do not place mulch within 3 inches of trunks or stems.

F. Wrap trees of 2-inch caliper and larger with trunk-wrap tape. Start at base of trunk and spiral cover trunk to height of first branches. Overlap wrap, exposing half the width, and securely attach without causing girdling. Inspect tree trunks for injury, improper pruning, and insect infestation; take corrective measures required before wrapping.

3.6 TREE AND SHRUB PRUNING

A. Prune, thin, and shape trees and shrubs as required to keep consistent and healthy.

B. Prune, thin, and shape trees and shrubs according to standard horticultural practice. Prune trees to retain required height and spread. Unless otherwise indicated by Architect, do not cut tree leaders; remove only injured or dead branches from flowering trees. Prune shrubs to retain natural character. Shrub sizes indicated are sizes after pruning.

3.7 GUYING AND STAKING

A. Upright Staking and Tying: Stake trees of 2- through 5-inch caliper. Stake trees of less than 2-inch caliper only as required to prevent wind tip-out. Use a minimum of 2 stakes of length required to penetrate at least 18 inches below bottom of backfilled excavation and to extend at least 72 inches above grade. Set vertical stakes and space to avoid penetrating root balls or root masses. Support trees with two strands of tie wire encased in hose sections at contact points with tree trunk. Allow enough slack to avoid rigid restraint of tree. Use the number of stakes as follows:
1. Use 2 stakes for trees up to 12 feet high and 2-1/2 inches or less in caliper; 3 stakes for trees less than 14 feet high and up to 4 inches in caliper. Space stakes equally around trees.

B. Guying and Staking: Guy and stake trees exceeding 14 feet in height and more than 3 inches in caliper, unless otherwise indicated. Securely attach no fewer than 3 guys to stakes 30 inches long, driven to grade.
1. For trees more than 6 inches in caliper, anchor guys to pressure-preservative-treated deadmen 8 inches in diameter and 48 incheslong buried at least 36 inches below grade. Provide turnbuckles for each guy wire and tighten securely.
2. Attach flags to each guy wire, 30 inches above finish grade.
3. Paint turnbuckles with luminescent white paint.

3.8 PLANTERS

A. Planters: Place a layer of gravel at least 4 inches thick in bottom of planters, cover with nonwoven fabric, and fill with planter soil mix. Place soil in lightly compacted layers to an elevation of 1-1/2 inches below top of planter, allowing natural settlement.
1. Planter Soil Mix: One part topsoil, one part coarse sand, one part peat, and 3 lb of dolomitic limestone per cubic yard of mix.

3.9 GROUND COVER AND PLANT PLANTING

A. Set out and space ground cover and plants as indicated or recommended.

B. Dig holes large enough to allow spreading of roots, and backfill with planting soil.

C. Work soil around roots to eliminate air pockets and leave a slight saucer indentation around plants to hold water.

D. Water thoroughly after planting, taking care not to cover plant crowns with wet soil.
E. Protect plants from hot sun and wind; remove protection if plants show evidence of recovery from transplanting shock.

3.10 PLANTING BED MULCHING

A. Install weed-control barriers before mulching according to manufacturer's written instructions. Completely cover area to be mulched, overlapping edges a minimum of 6 inches.
B. Mulch backfilled surfaces of planting beds and other areas indicated.
   1. Organic Mulch: Apply 2-inch average thickness of organic mulch, and finish level with adjacent finish grades. Do not place mulch against plant stems.
   2. Mineral Mulch: Apply 2-inch average thickness of mineral mulch, and finish level with adjacent finish grades. Do not place mulch against plant stems.

3.11 EDGING INSTALLATION

A. Wood Edgings: Install wood headers or edgings where indicated. Anchor with wood stakes spaced up to 36 inches apart, driven at least 1 inch below top elevation of header or edging. Use 2 galvanized nails per stake to fasten headers and edging; length as needed to penetrate both members and provide 1/2-inch clinch at point. Predrill stakes if needed to avoid splitting.
B. Steel Edging: Install steel edging where indicated according to manufacturer's written instructions. Anchor with steel stakes spaced approximately 30 inches apart, driven below top elevation of edging.
C. Aluminum Edging: Install aluminum edging where indicated according to manufacturer's written instructions. Anchor with aluminum stakes spaced approximately 36 inches apart, driven below top elevation of edging.
D. Plastic Edging: Install plastic edging where indicated according to manufacturer's written instructions. Anchor with steel stakes spaced approximately 36 inches apart, driven through upper base grooves or V-lip of edging.

3.12 TREE GRATE INSTALLATION

A. Tree Grates: Set grate segments flush with adjoining surfaces as shown on Drawings. Shim from supporting substrate with soil-resistant plastic. Maintain a 3-inch- (75-mm-) minimum growth radius around base of tree; break away units of casting, if necessary, according to manufacturer's written instructions.

3.13 CLEANUP AND PROTECTION

A. During exterior planting, keep adjacent pavings and construction clean and work area in an orderly condition.
B. Protect exterior plants from damage due to landscape operations, operations by other contractors and trades, and others. Maintain protection during installation and maintenance periods. Treat, repair, or replace damaged exterior planting.

3.14 DISPOSAL

A. Disposal: Remove surplus soil and waste material, including excess subsoil, unsuitable soil, trash, and debris, and legally dispose of them off Owner's property.

END OF SECTION 02930

SECTION 03100

CONCRETE FORMWORK

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Formwork for cast-in place concrete, with shoring, bracing and anchorage.
- B. Openings for other work.
- C. Form accessories.
- D. Form stripping.

1.02 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site per the suppliers and/or manufacturer's recommendations.
- B. Store off ground in ventilated and protected manner to prevent deterioration from moisture.

1.03 COORDINATION
- A. Coordinate this Section with other Sections of work which require attachment of components to formwork.
- B. If formwork is placed after reinforcement resulting in insufficient concrete cover over reinforcement before proceeding, request instructions from Architect/Engineer.

PART 2 PRODUCTS

2.01 WOOD FORM MATERIALS
- A. Form Materials: At the discretion of the Contractor.

2.02 PREFABRICATED FORMS
- A. Preformed Steel Forms: Minimum gage matched, tight fitting, stiffened to support weight of concrete without deflection detrimental to tolerances and appearance of finished surfaces.
- B. Glass Fiber Fabric Reinforced Plastic Forms: Matched, tight fitting, stiffened to support weight of concrete without deflection detrimental to tolerances and appearance of finished concrete surfaces.

2.03 FORMWORK ACCESSORIES
- A. Form Ties: Removable or Snap-off type, metal, size and shape to minimize filling, waterproofing and refinishing concrete surfaces.
- B. Form Release Agent: Colorless mineral oil which will not stain concrete, or absorb moisture, or impair natural bonding or color characteristics of coating intended for use on concrete.
- C. Corners: Chamfer, exposed edges 1/2 inch unless otherwise noted or detailed on the drawings.
- D. Dovetail Anchor Slot: Galvanized steel, 22 gage thick, release tape sealed slots, anchors for securing to concrete formwork.
- E. Flashing Reglets: Galvanized steel 22 gage thick, longest possible lengths, with alignment splines for joints, release tape sealed slots, anchors for securing to concrete formwork.
- F. Nails, Spikes, Lag Bolts, Through Bolts, Anchorages: Sized as required, of sufficient strength and character to maintain formwork in place while placing concrete.
- G. Waterstops: Rubber Polyvinyl chloride, minimum 1,750 psi tensile strength, minimum 50 degrees F to plus 175 degrees F working temperature range, maximum possible lengths, ribbed profile, preformed corner sections, heat welded jointing.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify lines, levels and centers before proceeding with formwork. Ensure that dimensions agree with drawings.

3.02 EARTH FORMS
- A. Earth forms if permitted, hand trim sides and bottom of earth forms. Remove loose soil prior to placing concrete.

3.03 ERECTION - FORMWORK
- A. Erect formwork, shoring and bracing to achieve design requirements, in accordance with requirements of ACI 301.

B. Provide bracing to ensure stability of formwork. Shore or strengthen formwork subject to over stressing by construction loads.
C. Arrange and assemble formwork to permit dismantling and stripping. Do not damage concrete during stripping. Permit removal of remaining principal shores.
D. Align joints and make watertight. Keep form joints to a minimum.
E. Obtain approval before framing openings in structural members which are not indicated on Drawings.
F. Provide chamfer strips on external corners of beams joists columns and exposed decorative concrete edges.
G. Install void forms in accordance with manufacturer's recommendations. Protect forms from moisture or crushing.

3.04 APPLICATION - FORM RELEASE AGENT
A. Apply form release agent on formwork in accordance with manufacturer's recommendations.
B. Apply prior to placement of reinforcing steel, anchoring devices, and embedded items.
C. Do not apply form release agent where concrete surfaces will receive special finishes or applied coverings which are effected by agent. Soak inside surfaces of untreated forms with clean water. Keep surfaces coated prior to placement of concrete.

3.05 INSERTS, EMBEDDED PARTS, AND OPENINGS
A. Provide formed openings where required for items to be embedded in passing through concrete work.
B. Locate and set in place items which will be cast directly into concrete.
C. Coordinate with work of other sections in forming and placing openings, slots, reglets, recesses, sleeves, bolts, anchors, other inserts, and components of other Work.
D. Position recessed reglets for brick veneer masonry anchors to spacing and intervals specified in Section 04300.
E. Install accessories in accordance with manufacturer's instructions, straight, level, and plumb. Ensure items are not disturbed during concrete placement.
F. Install waterstops continuous without displacing reinforcement. Heat seal joints watertight.
G. Provide temporary ports or openings in formwork where required to facilitate cleaning and inspection. Locate openings at bottom of forms to allow flushing water to drain.
H. Close temporary openings with tight fitting panels, flush with inside face of forms, and neatly fitted so joints will not be apparent in exposed concrete surfaces.

3.06 FORM CLEANING
A. Clean forms as erection proceeds, to remove foreign matter within forms.
B. Clean formed cavities of debris prior to placing concrete.
C. Flush with water or use compressed air to remove remaining foreign matter. Ensure that water and debris drain to exterior through clean-out ports.
D. During cold weather, remove ice and snow from within forms. Do not use de-icing salts. Do not use water to clean out forms, unless formwork and concrete construction proceed within heated enclosure. Use compressed air or other means to remove foreign matter.

3.07 FORMWORK TOLERANCES
A. Construct formwork to maintain tolerances required by ACI 301. Construct and align formwork for elevator hoistway in accordance with ANSI/ASME A17.1.

3.08 FIELD QUALITY CONTROL
A. Inspect erected formwork, shoring, and bracing to ensure that work is in accordance with formwork design, and that supports, fastenings, wedges, ties, and items are secure.
B. Do not reuse wood formwork more than 2 times for concrete surfaces to be exposed to view. Do not patch formwork.

3.09 FORM REMOVAL
A. Do not remove forms or bracing until concrete has gained sufficient strength to carry its own weight and
B. Loosen forms carefully. Do not wedge pry bars, hammers, or tools against finish concrete surfaces scheduled for exposure to view.
C. Store removed forms in manner that surfaces to be in contact with fresh concrete will not be damaged. Discard damaged forms.

END OF SECTION 03100

SECTION 03200

CONCRETE REINFORCEMENT

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Reinforcing steel bars, wire fabric and accessories for cast-in-place concrete.

1.02 SUBMITTALS
- A. Submit under provisions of the General Requirements.
- B. Shop Drawings: Indicate bar sizes, spacings, locations, and quantities of reinforcing steel and wire fabric, bending and cutting schedules, and supporting and spacing devices.

1.03 QUALITY ASSURANCE
- A. Perform Work in accordance with CRSI - Manual of Standard Practice and ACI 301.

1.04 QUALIFICATIONS
- A. Design reinforcement under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State of Texas.

1.05 COORDINATION
- A. Coordinate with placement of formwork, formed openings and other Work.

PART 2 PRODUCTS

2.01 REINFORCEMENT
- A. Reinforcing Steel: ASTM A615, 40, 60, or 75 ksi yield grade as indicated on the drawings; deformed billet steel bars, unfinished.
- B. Reinforcing Steel Plain Bar and Rod Mats: ASTM A704, ASTM A615, Grade 40 or 60 as indicated on the drawings; steel bars or rods, unfinished.
- C. Stirrup Steel: ANSI/ASTM A82, unfinished.
- D. Welded Steel Wire Fabric: ASTM A815; in flat sheets or coiled rolls; unfinished.

2.02 ACCESSORY MATERIALS
- A. Tie Wire: Minimum 16 gage annealed type.
- B. Chairs, Bolsters, Bar Supports, Spacers: Sized and shaped for strength and support of reinforcement during concrete placement conditions including load bearing pad on bottom to prevent vapor barrier puncture.
- C. Special Chairs, Bolsters, Bar Supports, Spacers Adjacent to Weather Exposed Concrete Surfaces: Plastic coated steel type; size and shape as required.

2.03 FABRICATION
- A. Fabricate concrete reinforcing in accordance with CRSI Manual of Practice.
- B. Weld reinforcement in accordance with ANSI/AWS D1.4.
- C. Locate reinforcing splices not indicated on drawings, at point of minimum stress.

PART 3 EXECUTION

3.01 PLACEMENT
- A. Place, support and secure reinforcement against displacement. Do not deviate from required position.
- B. Do not displace or damage vapor barrier.
- C. Accommodate placement of formed openings.

D. Maintain concrete cover around reinforcing as indicated on the drawings or if not indicated as follows:

Item	Coverage
Beams	1 1/2 inch
Column Ties	1 1/2 inch
Walls (exposed to weather or backfill)	2 inch
Footings and Concrete Formed Against Earth	3 inch
Slabs on Fill	3/4 inch

END OF SECTION 03200

SECTION 03300

CAST-IN-PLACE CONCRETE

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Cast-in-place concrete floors, foundation walls, retaining walls, steps and ramps.
- B. Floors and slabs on grade.
- C. Control, expansion and contraction joint devices associated with concrete work, including joint sealants.
- D. Equipment pads, light pole base and flagpole base.

1.02 SUBMITTALS
- A. Submit under provisions of the General Requirements.
- B. Product Data: Provide data on joint devices, attachment accessories.
- C. Samples: Submit 2-inch long samples of expansion/contraction joint.
- D. Manufacturer's Installation Instructions: Indicate installation procedures and interface required with adjacent Work.

1.03 PROJECT RECORD DOCUMENTS
- A. Accurately record actual locations of embedded utilities and components which are concealed from view.

1.04 QUALITY ASSURANCE
- A. Perform Work in accordance with ACI 301.
- B. Acquire cement and aggregate from same source for all work.
- C. Conform to ACI 305R when concreting during hot weather.
- D. Conform to ACI 306R when concreting during cold weather.

1.05 COORDINATION
- A. Coordinate the placement of joint devices with erection of concrete formwork and placement of form accessories.

PART 2 PRODUCTS

2.01 CONCRETE MATERIALS
- A. Cement: ASTM C150, Type I - Normal or Type III - High Early Strength Type V - Sulfate Resistant as required Portland type.
- B. Fine and Coarse Aggregates: ASTM C33.
- C. Water: Clean and not detrimental to concrete.

2.02 ADMIXTURES
- A. Air Entrainment: ASTM C260.
- B. Chemical: ASTM C494 Type A - Water Reducing, Type B - Retarding, Type C - Accelerating, Type D - Water Reducing and Retarding, Type E - Water Reducing and Accelerating.

2.03 ACCESSORIES
- A. Bonding Agent: Polymer resin emulsion, polyvinyl acetate, Latex emulsion, two component modified epoxy resin, non-solvent two component polysulfide epoxy, mineral filled polysulfide polymer epoxy, mineral filled polysulfide polymer epoxy resin, or Polyamid cured epoxy as approved.
- B. Vapor Barrier: 6 mil thick clear polyethylene film, type recommended for below grade application.
- C. Non-Shrink Grout: Premixed compound consisting of nonmetallic aggregate, cement, water reducing and plasticizing agents; capable of developing minimum compressive strength of 2,400 psi in 48 hours and 7,000 psi in 28 days.

2.04 JOINT DEVICES AND FILLER MATERIALS
- A. Joint Filler:
  1. Joint Filler Type A: ASTM D1751; Asphalt impregnated fiberboard or felt, 1/4 inch thick.
  2. Joint Filler Type B: ASTM D1752; Closed cell polyvinyl chloride foam, resiliency recovery of 95 percent if not compressed more than 50 percent of original thickness.

B. Expansion and Contraction Joint Devices: ASTM B221 alloy, extruded aluminum; resilient elastomeric, vinyl, or neoprene, filler strip with a Shore A hardness of 35 to permit plus or minus 25 percent joint movement with full recovery; extruded aluminum or vinyl cover plate, of longest manufactured length at each location, recess mounted; color as selected.
C. Sealant: Rubber or synthetic rubber compound.

2.05 CONCRETE MIX
A. Mix concrete in accordance with ACI 304. Deliver concrete in accordance with ASTM C94.
B. Select proportions for normal weight concrete in accordance with ACI 301.
C. Provide concrete with compressive strength of 3,500 psi at 28 days.
D. Use accelerating admixtures in cold weather only when approved by Architect/Engineer. Use of admixtures will not relax cold weather placement requirements.
E. Use calcium chloride only when approved by Architect/Engineer.
F. Use set retarding admixtures during hot weather only when approved by Architect/Engineer.
G. Add air entraining agent to normal weight concrete mix for work exposed to exterior.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify requirements for concrete cover over reinforcement.
B. Verify that anchors, seats, plates, reinforcement and other items to be cast into concrete are accurately placed, positioned securely, and will not cause hardship in placing concrete.

3.02 PREPARATION
A. Prepare previously placed concrete by cleaning with steel brush and applying bonding agent in accordance with manufacturer's instructions.
B. In locations where new concrete is dowelled to existing work, drill holes in existing concrete, insert steel dowels and pack solid with non-shrink grout.

3.03 PLACING CONCRETE
A. Place concrete in accordance with ACI 301.
B. Notify Architect/Engineer minimum 24 hours prior to commencement of operations.
C. Ensure reinforcement, inserts, embedded parts, formed expansion and contraction joints are not disturbed during concrete placement.
D. Install vapor barrier under interior slabs on grade. Lap joints minimum 6 inches and seal watertight by sealant applied between overlapping edges and ends or taping edges and ends.
E. Repair vapor barrier damaged during placement of concrete reinforcing. Repair with vapor barrier material; lap over damaged areas minimum 6 inches and seal watertight.
F. Separate slabs on grade from vertical surfaces with 1/2 inch thick joint filler.
G. Place joint filler in floor slab pattern placement sequence. Set top to required elevations. Secure to resist movement by wet concrete.
H. Extend joint filler from bottom of slab to within 1/2 inch of finished slab surface. Conform to Section 07900 for finish joint sealer requirements.
I. Install joint devices in accordance with manufacturer's instructions.
J. Install construction joint devices in coordination with floor slab pattern placement sequence. Set top to required elevations. Secure to resist movement by wet concrete.
K. Install joint device anchors. Maintain correct position to allow joint cover to be flush with floor and wall finish.
L. Install joint covers in longest practical length, when adjacent construction activity is complete.
M. Apply sealants in joint devices in accordance with Section 07900.
N. Maintain records of concrete placement. Record date, location, quantity, air temperature, and test samples taken.
O. Place concrete continuously between predetermined expansion, control, and construction joints.
P. Do not interrupt successive placement; do not permit cold joints to occur where possible.
Q. Place floor slabs in checkerboard or saw cut pattern indicated.
R. Saw cut joints within 24 hours after placing. Use 3/16 inch thick blade, cut into 1/4 depth of slab thickness.
S. Screed floors and slabs on grade level, maintaining surface flatness of maximum 1/4 inch in 10 ft.

3.04 CONCRETE FINISHING
A. Provide formed concrete surfaces to be left exposed concrete walls columns beams joists with smooth rubbed finish.
B. Finish concrete floor surfaces in accordance with ACI 301.

C. Wood float surfaces which will receive quarry tile, ceramic tile, or terrazzo with full bed setting system.
D. Steel trowel surfaces which will receive carpeting, resilient flooring, seamless flooring, thin set quarry tile, or thin set ceramic tile.
E. Steel trowel surfaces which are scheduled to be exposed.
F. In areas with floor drains, maintain floor elevation at walls; pitch surfaces uniformly to drains at 1/4 inch per foot or as indicated on drawings.

3.05 CURING AND PROTECTION
A. Immediately after placement, protect concrete from premature drying, excessively hot or cold temperatures, and mechanical injury.
B. Maintain concrete with minimal moisture loss at relatively constant temperature for period necessary for hydration of cement and hardening of concrete.
C. Cure floor surfaces in accordance with ACI 308.
D. Ponding: Maintain 100 percent coverage of water over floor slab areas continuously for 4 days.
E. Spraying: Spray water over floor slab areas and maintain wet for 7 days.

3.06 FIELD QUALITY CONTROL
A. Field inspection and testing will be performed in accordance with ACI 301 and under provisions of the General Requirements.
B. Provide free access to Work and cooperate with appointed firm.
C. Submit proposed mix design of each class of concrete to inspection and testing firm for review prior to commencement of Work.
D. Tests of cement and aggregates may be performed to ensure conformance with specified requirements.
E. Three concrete test cylinders will be taken for every 75 or less cu yds of each class of concrete placed.
F. One additional test cylinder will be taken during cold weather concreting, cured on job site under same conditions as concrete it represents.
G. One slump test will be taken for each set of test cylinders taken.

3.07 PATCHING
A. Allow Architect/Engineer to inspect concrete surfaces immediately upon removal of forms.
B. Excessive honeycomb or embedded debris in concrete is not acceptable. Notify Architect/Engineer upon discovery.
C. Patch imperfections as directed or in accordance with ACI 301.

3.08 DEFECTIVE CONCRETE
A. Defective Concrete: Concrete not conforming to required lines, details, dimensions, tolerances or specified requirements.
B. Repair or replacement of defective concrete will be determined by the Architect/Engineer.
C. Do not patch, fill, touch-up, repair, or replace exposed concrete except upon express direction of Architect/Engineer for each individual area.

END OF SECTION 03300

PRESERVATION BRIEF 1

Assessing Cleaning and Water-Repellent Treatments for Historic Masonry Buildings

- Preparing for a Cleaning Project
- Understanding the Building Materials
- Cleaning Methods and Materials
- Planning a Cleaning Project
- Water-Repellent Coatings and Waterproof Coatings

Inappropriate cleaning and coating treatments are a major cause of damage to historic masonry buildings. While either or both treatments may be appropriate in some cases, they can be very destructive to historic masonry if they are not selected carefully. Historic masonry, as considered here, includes stone, brick, architectural terra cotta, cast stone, concrete and concrete block. It is frequently cleaned because cleaning is equated with improvement. Cleaning may sometimes be followed by the application of a water-repellent coating. However, unless these procedures are carried out under the guidance and supervision of an architectural conservator, they may result in irrevocable damage to the historic resource.

The purpose of this Brief is to provide information on the variety of cleaning methods and materials that are available for use on the exterior of historic masonry buildings, and to provide guidance in selecting the most appropriate method or combination of methods. The difference between water-repellent coatings and waterproof coatings is explained, and the purpose of each, the suitability of their application to historic masonry buildings, and the possible consequences of their inappropriate use are discussed.

The Brief is intended to help develop sensitivity to the qualities of historic masonry that makes it so special, and to assist historic building owners and property managers in working cooperatively with architects, architectural conservators, and contractors. Although specifically intended for historic buildings, the information is applicable to all masonry buildings. The Brief is not meant to be a cleaning manual or a guide for preparing specifications. Rather, it provides general information to raise awareness of the many factors involved in selecting cleaning and water-repellent treatments for historic masonry buildings.

Preparing for a Cleaning Project, Reasons for Cleaning

First, it is important to determine whether it is appropriate to clean the masonry. The objective of cleaning a historic masonry building must be considered carefully before arriving at a decision to clean. There are several major reasons for cleaning a historic masonry building: improve the appearance of the building by removing unattractive dirt or soiling materials, or non-historic paint from the masonry; retard deterioration by removing soiling materials that may be damaging the masonry; or provide a clean surface to accurately match repointing mortars or patching compounds, or to conduct a condition survey of the masonry.

Identify What is to be Removed

The general nature and source of dirt or soiling material on a building must be identified to remove it in the gentlest means possible--that is, in the most effective, yet least harmful, manner. Soot and smoke, for example, require a different cleaning agent to remove than oil stains or metallic stains. Other common cleaning problems include biological growth such as mold or mildew, and organic matter such as the tendrils left on masonry after removal of ivy.

Consider the Historic Appearance of the Building

If the proposed cleaning is to remove paint, it is important in each case to learn whether or not unpainted masonry is historically appropriate. And, it is necessary to consider why the building was painted. Was it to cover bad repointing or unmatched repairs? Was the building painted to protect soft brick or to conceal deteriorating stone? Or, was painted masonry simply a fashionable treatment in a particular historic period? Many buildings were painted at the time of construction or shortly thereafter; retention of the paint, therefore, may be more appropriate historically than removing it. And, if the

building appears to have been painted for a long time, it is also important to think about whether the paint is part of the character of the historic building and if it has acquired significance over time.

Consider the Practicalities of Cleaning or Paint Removal

Some gypsum or sulfate crusts may have become integral with the stone and, if cleaning could result in removing some of the stone surface, it may be preferable not to clean. Even where unpainted masonry is appropriate, the retention of the paint may be more practical than removal in terms of long range preservation of the masonry. In some cases, however, removal of the paint may be desirable. For example, the old paint layers may have built up to such an extent that removal is necessary to ensure a sound surface to which the new paint will adhere.

Study the Masonry

Although not always necessary, in some instances it can be beneficial to have the coating or paint type, color, and layering on the masonry researched before attempting its removal. Analysis of the nature of the soiling or of the paint to be removed from the masonry, as well as guidance on the appropriate cleaning method, may be provided by professional consultants, including architectural conservators, conservation scientists, and preservation architects. The State Historic Preservation Office (SHPO), local historic district commissions, architectural review boards, and preservation-oriented websites may also be able to supply useful information on masonry cleaning techniques.

Understanding the Building Materials

The construction of the building must be considered when developing a cleaning program because inappropriate cleaning can have a deleterious effect on the masonry as well as on other building materials. The masonry material or materials must be correctly identified. It is sometimes difficult to distinguish one type of stone from another; for example, certain sandstones can be easily confused with limestones. Or, what appears to be natural stone may not be stone at all, but cast stone or concrete. Historically, cast stone and architectural terra cotta were frequently used in combination with natural stone, especially for trim elements or on upper stories of a building where, from a distance, these substitute materials looked like real stone. Other features on historic buildings that appear to be stone, such as decorative cornices, entablatures and window hoods, may not even be masonry, but metal.

Identify Prior Treatments

Previous treatments of the building and its surroundings should be researched and building maintenance records should be obtained, if available. Sometimes if streaked or spotty areas do not seem to get cleaner following an initial cleaning, closer inspection and analysis may be warranted. The discoloration may turn out not to be dirt but the remnant of a water-repellent coating applied long ago which has darkened the surface of the masonry over time. Successful removal may require testing several cleaning agents to find something that will dissolve and remove the coating. Complete removal may not always be possible. Repairs may have been stained to match a dirty building, and cleaning may make these differences apparent. De-icing salts used near the building that have dissolved can migrate into the masonry. Cleaning may draw the salts to the surface, where they will appear as efflorescence (a powdery, white substance), which may require a second treatment to be removed. Allowances for dealing with such unknown factors, any of which can be a potential problem, should be included when investigating cleaning methods and materials. Just as more than one kind of masonry on a historic building may necessitate multiple cleaning approaches, unknown conditions that are encountered may also require additional cleaning treatments.

Choose the Appropriate Cleaner

The importance of testing cleaning methods and materials cannot be over emphasized. Applying the wrong cleaning agents to historic masonry can have disastrous results. Acidic cleaners can be extremely damaging to acid-sensitive stones, such as marble and limestone, resulting in etching and dissolution of these stones. Other kinds of masonry can also be damaged by incompatible cleaning agents, or even by cleaning agents that are usually compatible. There are also numerous kinds of sandstone, each with a considerably different geological composition. While an acid-based cleaner may be safely used on some sandstones, others are acid-sensitive and can be severely etched or dissolved by an acid cleaner. Some sandstones contain water-soluble minerals and can be eroded by water cleaning. And, even if the stone type is correctly identified, stones, as well as some bricks, may contain unexpected impurities, such as iron particles, that may react negatively with a particular cleaning agent and result in staining. Thorough

understanding of the physical and chemical properties of the masonry will help avoid the inadvertent selection of damaging cleaning agents.
Other building materials also may be affected by the cleaning process. Some chemicals, for example, may have a corrosive effect on paint or glass. The portions of building elements most vulnerable to deterioration may not be visible, such as embedded ends of iron window bars. Other totally unseen items, such as iron cramps or ties which hold the masonry to the structural frame, also may be subject to corrosion from the use of chemicals or even from plain water. The only way to prevent problems in these cases is to study the building construction in detail and evaluate proposed cleaning methods with this information in mind. However, due to the very likely possibility of encountering unknown factors, any cleaning project involving historic masonry should be viewed as unique to that particular building.

Cleaning Methods and Materials

Masonry cleaning methods generally are divided into three major groups: water, chemical, and abrasive. Water methods soften the dirt or soiling material and rinse the deposits from the masonry surface. Chemical cleaners react with dirt, soiling material or paint to effect their removal, after which the cleaning effluent is rinsed off the masonry surface with water. Abrasive methods include blasting with grit, and the use of grinders and sanding discs, all of which mechanically remove the dirt, soiling material or paint (and, usually, some of the masonry surface). Abrasive cleaning is also often followed with a water rinse. Laser cleaning, although not discussed here in detail, is another technique that is used sometimes by conservators to clean small areas of historic masonry. It can be quite effective for cleaning limited areas, but it is expensive and generally not practical for most historic masonry cleaning projects.
Although it may seem contrary to common sense, masonry cleaning projects should be carried out starting at the bottom and proceeding to the top of the building always keeping all surfaces wet below the area being cleaned. The rationale for this approach is based on the principle that dirty water or cleaning effluent dripping from cleaning in progress above will leave streaks on a dirty surface but will not streak a clean surface as long as it is kept wet and rinsed frequently.
Water Cleaning
Water cleaning methods are generally the gentlest means possible, and they can be used safely to remove dirt from all types of historic masonry. There are essentially four kinds of water-based methods: soaking; pressure water washing; water washing supplemented with non-ionic detergent; and steam, or hot-pressurized water cleaning. Once water cleaning has been completed, it is often necessary to follow up with a water rinse to wash off the loosened soiling material from the masonry.
Water cleaning methods may not be appropriate to use on some badly deteriorated masonry because water may exacerbate the deterioration, or on gypsum or alabaster, which are very soluble in water.

Soaking

Prolonged spraying or misting with water is particularly effective for cleaning limestone and marble. It is also a good method for removing heavy accumulations of soot, sulfate crusts or gypsum crusts that tend to form in protected areas of a building not regularly washed by rain. Water is distributed to lengths of punctured hose or pipe with non-ferrous fittings hung from moveable scaffolding or a swing stage that continuously mists the surface of the masonry with a very fine spray. A timed on-off spray is another approach to using this cleaning technique. After one area has been cleaned, the apparatus is moved on to another. Soaking is often used in combination with water washing and is also followed by a final water rinse. Soaking is a very slow method—it may take several days or a week—but it is a very gentle method to use on historic masonry.

Water Washing

Washing with low-pressure or medium-pressure water is probably one of the most commonly used methods for removing dirt or other pollutant soiling from historic masonry buildings. Starting with a very low pressure (100 psi or below), even using a garden hose, and progressing as needed to slightly higher pressure—generally no higher than 300-400 psi—is always the recommended way to begin. Scrubbing with natural bristle or synthetic bristle brushes—never metal which can abrade the surface and leave metal particles that can stain the masonry—can help in cleaning areas of the masonry that are especially dirty.

Water Washing with Detergents

Non-ionic detergents—which are not the same as soaps—are synthetic organic compounds that are especially effective in removing oily soil. (Examples of some of the numerous proprietary non-ionic detergents include Igepal by GAF, Tergitol by Union Carbide and Triton by Rohm & Haas.) Thus, the addition of a non-ionic detergent, or surfactant, to a low- or medium-pressure water wash can be a useful aid in the cleaning process. (A non-ionic detergent, unlike most household detergents, does not leave a solid, visible residue on the masonry.) Adding a non-ionic detergent and scrubbing with a natural bristle or synthetic bristle brush can facilitate cleaning textured or intricately carved masonry. This should be followed with a final water rinse.

Steam/Hot-Pressurized Water Cleaning

Steam cleaning is actually low-pressure hot water washing because the steam condenses almost immediately upon leaving the hose. This is a gentle and effective method for cleaning stone and particularly for acid-sensitive stones. Steam can be especially useful in removing built-up soiling deposits and dried-up plant materials, such as ivy disks and tendrils. It can also be an efficient means of cleaning carved stone details and, because it does not generate a lot of liquid water, it can sometimes be appropriate to use for cleaning interior masonry.

Potential Hazards of Water Cleaning

Despite the fact that water-based methods are generally the most gentle, even they can be damaging to historic masonry. Before beginning a water cleaning project, it is important to make sure that all mortar joints are sound and that the building is watertight. Otherwise water can seep through the walls to the interior, resulting in rusting metal anchors and stained and ruined plaster.

Some water supplies may contain traces of iron and copper which may cause masonry to discolor. Adding a chelating or complexing agent to the water, such as EDTA (ethylene diamine tetra-acetic acid), which inactivates other metallic ions, as well as softens minerals and water hardness, will help prevent staining on light-colored masonry.

Any cleaning method involving water should never be done in cold weather or if there is any likelihood of frost or freezing because water within the masonry can freeze, causing spalling and cracking. Since a masonry wall may take over a week to dry after cleaning, no water cleaning should be permitted for several days prior to the first average frost date, or even earlier if local forecasts predict cold weather.

Most important of all, it is imperative to be aware that using water at too high a pressure, a practice common to "power washing" and "water blasting", is very abrasive and can easily etch marble and other soft stones, as well as some types of brick. In addition, the distance of the nozzle from the masonry surface and the type of nozzle, as well as gallons per minute (gpm), are also important variables in a water cleaning process that can have a significant impact on the outcome of the project. This is why it is imperative that the cleaning be closely monitored to ensure that the cleaning operators do not raise the pressure or bring the nozzle too close to the masonry in an effort to "speed up" the process. The appearance of grains of stone or sand in the cleaning effluent on the ground is an indication that the water pressure may be too high.

Chemical Cleaning

Chemical cleaners, generally in the form of proprietary products, are another material frequently used to clean historic masonry. They can remove dirt, as well as paint and other coatings, metallic and plant stains, and graffiti. Chemical cleaners used to remove dirt and soiling include acids, alkalies and organic compounds. Acidic cleaners, of course, should not be used on masonry that is acid sensitive. Paint removers are alkaline, based on organic solvents or other chemicals.

Chemical Cleaners to Remove Dirt

Both alkaline and acidic cleaning treatments include the use of water. Both cleaners are also likely to contain surfactants (wetting agents), that facilitate the chemical reaction that removes the dirt. Generally, the masonry is wet first for both types of cleaners, then the chemical cleaner is sprayed on at very low pressure or brushed onto the surface. The cleaner is left to dwell on the masonry for an amount of time recommended by the product manufacturer or, preferably, determined by testing, and rinsed off with a low- or moderate-pressure cold, or sometimes hot, water wash.

More than one application of the cleaner may be necessary, and it is always a good practice to test the product manufacturers recommendations concerning dilution rates and dwell times. Because each cleaning situation is unique, dilution rates and dwell times can vary considerably. The masonry surface

may be scrubbed lightly with natural or synthetic bristle brushes prior to rinsing. After rinsing, pH strips should be applied to the surface to ensure that the masonry has been neutralized completely.

Acidic Cleaners

Acid-based cleaning products may be used on non-acid sensitive masonry, which generally includes: granite, most sandstones, slate, unglazed brick and unglazed architectural terra cotta, cast stone and concrete. Most commercial acidic cleaners are composed primarily of hydrofluoric acid, and often include some phosphoric acid to prevent rust-like stains from developing on the masonry after the cleaning. Acid cleaners are applied to the pre-wet masonry which should be kept wet while the acid is allowed to "work", and then removed with a water wash.

Alkaline Cleaners

Alkaline cleaners should be used on acid-sensitive masonry, including: limestone, polished and unpolished marble, calcareous sandstone, glazed brick and glazed architectural terra cotta, and polished granite. (Alkaline cleaners may also be used sometimes on masonry materials that are not acid sensitive--after testing, of course--but they may not be as effective as they are on acid-sensitive masonry.) Alkaline cleaning products consist primarily of two ingredients: a non-ionic detergent or surfactant; and an alkali, such as potassium hydroxide or ammonium hydroxide. Like acidic cleaners, alkaline products are usually applied to pre-wet masonry, allowed to dwell, and then rinsed off with water. (Longer dwell times may be necessary with alkaline cleaners than with acidic cleaners.) Two additional steps are required to remove alkaline cleaners after the initial rinse. First the masonry is given a slightly acidic wash--often with acetic acid--to neutralize it, and then it is rinsed again with water.

Chemical Cleaners to Remove Paint and Other Coatings, Stains and Graffiti

Removing paint and some other coatings, stains and graffiti can best be accomplished with alkaline paint removers, organic solvent paint removers, or other cleaning compounds. The removal of layers of paint from a masonry surface usually involves applying the remover either by brush, roller or spraying, followed by a thorough water wash. As with any chemical cleaning, the manufacturer's recommendations regarding application procedures should always be tested before beginning work.

Alkaline Paint Removers

These are usually of much the same composition as other alkaline cleaners, containing potassium or ammonium hydroxide, or trisodium phosphate. They are used to remove oil, latex and acrylic paints, and are effective for removing multiple layers of paint. Alkaline cleaners may also remove some acrylic water-repellent coatings. As with other alkaline cleaners, both an acidic neutralizing wash and a final water rinse are generally required following the use of alkaline paint removers.

Organic Solvent Paint Removers

The formulation of organic solvent paint removers varies and may include a combination of solvents, including methylene chloride, methanol, acetone, xylene and toluene.

Other Paint Removers and Cleaners

Other cleaning compounds that can be used to remove paint and some painted graffiti from historic masonry include paint removers based on N-methyl-2-pyrrolidone (NMP), or on petroleum-based compounds. Removing stains, whether they are industrial (smoke, soot, grease or tar), metallic (iron or copper), or biological (plant and fungal) in origin, depends on carefully matching the type of remover to the type of stain. Successful removal of stains from historic masonry often requires the application of a number of different removers before the right one is found. The removal of layers of paint from a masonry surface is usually accomplished by applying the remover either by brush, roller or spraying, followed by a thorough water wash.

Potential Hazards of Chemical Cleaning

Since most chemical cleaning methods involve water, they have many of the potential problems of plain water cleaning. Like water methods, they should not be used in cold weather because of the possibility of freezing. Chemical cleaning should never be undertaken in temperatures below 40 degrees F (4 degrees C), and generally not below 50 degrees F. In addition, many chemical cleaners simply do not work in cold temperatures. Both acidic and alkaline cleaners can be dangerous to cleaning operators, and clearly, there are environmental concerns associated with the use of chemical cleaners.

If not carefully chosen, chemical cleaners can react adversely with many types of masonry. Obviously, acidic cleaners should not be used on acid-sensitive materials; however, it is not always clear exactly what the composition is of any stone or other masonry material. For, this reason, testing the cleaner on an inconspicuous spot on the building is always necessary. While certain acid-based cleaners may be appropriate if used as directed on a particular type of masonry, if left too long or if not adequately rinsed from the masonry they can have a negative effect. For example, hydrofluoric acid can etch masonry leaving a hazy residue (whitish deposits of silica or calcium fluoride salts) on the surface. While this efflorescence may usually be removed by a second cleaning—although it is likely to be expensive and time-consuming—hydrofluoric acid can also leave calcium fluoride salts or a colloidal silica deposit on masonry which may be impossible to remove. Other acids, particularly hydrochloric (muriatic) acid, which is very powerful, should not be used on historic masonry, because it can dissolve lime-based mortar, damage brick and some stones, and leave chloride deposits on the masonry.
Alkaline cleaners can stain sandstones that contain a ferrous compound. Before using an alkaline cleaner on sandstone it is always important to test it, since it may be difficult to know whether a particular sandstone may contain a ferrous compound. Some alkaline cleaners, such as sodium hydroxide (caustic soda or lye) and ammonium bifluoride, can also damage or leave disfiguring brownish-yellow stains and, in most cases, should not be used on historic masonry. Although alkaline cleaners will not etch a masonry surface as acids can, they are caustic and can burn the surface. In addition, alkaline cleaners can deposit potentially damaging salts in the masonry which can be difficult to rinse thoroughly.

Poulticing to Remove Stains and Graffiti

Graffiti and stains, which have penetrated into the masonry, often are best removed by using a poultice. A poultice consists of an absorbent material or clay powder (such as kaolin or fullerís earth, or even shredded paper or paper towels), mixed with a liquid (a solvent or other remover) to form a paste which is applied to the stain. The poultice is kept moist and left on the stain as long as necessary for it to draw the stain out of the masonry. As it dries, the paste absorbs the staining material so that it is not redeposited on the masonry surface.

Some commercial cleaning products and paint removers are specially formulated as a paste or gel that will cling to a vertical surface and remain moist for a longer period of time in order to prolong the action of the chemical on the stain. Pre-mixed poultices are also available as a paste or in powder form needing only the addition of the appropriate liquid. The masonry must be pre-wet before applying an alkaline cleaning agent, but not when using a solvent. Once the stain has been removed, the masonry must be rinsed thoroughly.

Abrasive and Mechanical Cleaning

Generally, abrasive cleaning methods are not appropriate for use on historic masonry buildings. Abrasive cleaning methods are just that—abrasive. Grit blasters, grinders, and sanding discs all operate by abrading the dirt or paint off the surface of the masonry, rather than reacting with the dirt and the masonry which is how water and chemical methods work. Since the abrasives do not differentiate between the dirt and the masonry, they can also remove the outer surface of the masonry at the same time, and result in permanently damaging the masonry. Brick, architectural terra cotta, soft stone, detailed carvings, and polished surfaces, are especially susceptible to physical and aesthetic damage by abrasive methods. Brick and architectural terra cotta are fired products which have a smooth, glazed surface which can be removed by abrasive blasting or grinding. Abrasively-cleaned masonry is damaged aesthetically as well as physically, and it has a rough surface which tends to hold dirt and the roughness will make future cleaning more difficult. Abrasive cleaning processes can also increase the likelihood of subsurface cracking of the masonry. Abrasion of carved details causes a rounding of sharp corners and other loss of delicate features, while abrasion of polished surfaces removes the polished finish of stone. Mortar joints, especially those with lime mortar, also can be eroded by abrasive or mechanical cleaning. In some cases, the damage may be visual, such as loss of joint detail or increased joint shadows. As mortar joints constitute a significant portion of the masonry surface (up to 20 per cent in a brick wall), this can result in the loss of a considerable amount of the historic fabric. Erosion of the mortar joints may also permit increased water penetration, which will likely necessitate repointing.

Abrasive Blasting

Blasting with abrasive grit or another abrasive material is the most frequently used abrasive method. Sandblasting is most commonly associated with abrasive cleaning. Finely ground silica or glass powder, glass beads, ground garnet, powdered walnut and other ground nut shells, grain hulls, aluminum oxide, plastic particles and even tiny pieces of sponge, are just a few of the other materials that have also been

used for abrasive cleaning. Although abrasive blasting is not an appropriate method of cleaning historic masonry, it can be safely used to clean some materials. Finely-powdered walnut shells are commonly used for cleaning monumental bronze sculpture, and skilled conservators clean delicate museum objects and finely detailed, carved stone features with very small, micro-abrasive units using aluminum oxide.
A number of current approaches to abrasive blasting rely on materials that are not usually thought of as abrasive, and not as commonly associated with traditional abrasive grit cleaning. Some patented abrasive cleaning processes—one dry, one wet—use finely-ground glass powder intended to "erase" or remove dirt and surface soiling only, but not paint or stains. Cleaning with baking soda (sodium bicarbonate) is another patented process. Baking soda blasting is being used in some communities as a means of quick graffiti removal. However, it should not be used on historic masonry which it can easily abrade and can permanently "etch" the graffiti into the stone; it can also leave potentially damaging salts in the stone which cannot be removed. Most of these abrasive grits may be used either dry or wet, although dry grit tends to be used more frequently.
Ice particles, or pelletized dry ice (carbon dioxide or CO2), are another medium used as an abrasive cleaner. This is also too abrasive to be used on most historic masonry, but it may have practical application for removing mastics or asphaltic coatings from some substrates.
Some of these processes are promoted as being more environmentally safe and not damaging to historic masonry buildings. However, it must be remembered that they are abrasive and that they "clean" by removing a small portion of the masonry surface, even though it may be only a minuscule portion. The fact that they are essentially abrasive treatments must always be taken into consideration when planning a masonry cleaning project. In general, abrasive methods should not be used to clean historic masonry buildings. In some, very limited instances, highly-controlled, gentle abrasive cleaning may be appropriate on selected, hard-to-clean areas of a historic masonry building if carried out under the watchful supervision of a professional conservator. But, abrasive cleaning should never be used on an entire building.

Grinders and Sanding Disks

Grinding the masonry surface with mechanical grinders and sanding disks is another means of abrasive cleaning that should not be used on historic masonry. Like abrasive blasting, grinders and disks do not really clean masonry but instead grind away and abrasively remove and, thus, damage the masonry surface itself rather than remove just the soiling material.

Planning a Cleaning Project

Once the masonry and soiling material or paint have been identified, and the condition of the masonry has been evaluated, planning for the cleaning project can begin.

Testing Cleaning Methods

In order to determine the gentlest means possible, several cleaning methods or materials may have to be tested prior to selecting the best one to use on the building. Testing should always begin with the gentlest and least invasive method proceeding gradually, if necessary, to more complicated methods, or a combination of methods. All too often simple methods, such as a low-pressure water wash, are not even considered, yet they frequently are effective, safe, and not expensive. Water of slightly higher pressure or with a non-ionic detergent additive also may be effective. It is worth repeating that these methods should always be tested prior to considering harsher methods; they are safer for the building and the environment, often safer for the applicator, and relatively inexpensive.
The level of cleanliness desired also should be determined prior to selection of a cleaning method. Obviously, the intent of cleaning is to remove most of the dirt, soiling material, stains, paint or other coating. A "brand new" appearance, however, may be inappropriate for an older building, and may require an overly harsh cleaning method to be achieved. When undertaking a cleaning project, it is important to be aware that some stains simply may not be removable. It may be wise, therefore, to agree upon a slightly lower level of cleanliness that will serve as the standard for the cleaning project. The precise amount of residual dirt considered acceptable may depend on the type of masonry, the type of soiling and difficulty of total removal, and local environmental conditions.
Cleaning tests should be carried out in an area of sufficient size to give a true indication of their effectiveness. It is preferable to conduct the test in an inconspicuous location on the building so that it will not be obvious if the test is not successful. A test area may be quite small to begin, sometimes as small as six square inches, and gradually may be increased in size as the most appropriate methods and cleaning agents are determined. Eventually the test area may be expanded to a square yard or more, and it should include several masonry units and mortar joints. It should be remembered that a single

building may have several types of masonry and that even similar materials may have different surface finishes. Each material and different finish should be tested separately. Cleaning tests should be evaluated only after the masonry has dried completely. The results of the tests may indicate that several methods of cleaning should be used on a single building.
When feasible, test areas should be allowed to weather for an extended period of time prior to final evaluation. A waiting period of a full year would be ideal in order to expose the test patch to a full range of seasons. If this is not possible, the test patch should weather for at least a month or two. For any building which is considered historically important, the delay is insignificant compared to the potential damage and disfigurement which may result from using an incompletely tested method. The successfully cleaned test patch should be protected as it will serve as a standard against which the entire cleaning project will be measured.

Environmental Considerations

The potential effect of any method proposed for cleaning historic masonry should be evaluated carefully. Chemical cleaners and paint removers may damage trees, shrubs, grass, and plants. A plan must be provided for environmentally safe removal and disposal of the cleaning materials and the rinsing effluent before beginning the cleaning project. Authorities from the local regulatory agency--usually under the jurisdiction of the federal or state Environmental Protection Agency (EPA)--should be consulted prior to beginning a cleaning project, especially if it involves anything more than plain water washing. This advance planning will ensure that the cleaning effluent or run-off, which is the combination of the cleaning agent and the substance removed from the masonry, is handled and disposed of in an environmentally sound and legal manner. Some alkaline and acidic cleaners can be neutralized so that they can be safely discharged into storm sewers. However, most solvent-based cleaners cannot be neutralized and are categorized as pollutants, and must be disposed of by a licensed transport, storage and disposal facility. Thus, it is always advisable to consult with the appropriate agencies before starting to clean to ensure that the project progresses smoothly and is not interrupted by a stop-work order because a required permit was not obtained in advance.
Vinyl guttering or polyethylene-lined troughs placed around the perimeter of the base of the building can serve to catch chemical cleaning waste as it is rinsed off the building. This will reduce the amount of chemicals entering and polluting the soil, and also will keep the cleaning waste contained until it can be removed safely. Some patented cleaning systems have developed special equipment to facilitate the containment and later disposal of cleaning waste.
Concern over the release of volatile organic compounds (VOCs) into the air has resulted in the manufacture of new, more environmentally responsible cleaners and paint removers, while some materials traditionally used in cleaning may no longer be available for these same reasons. Other health and safety concerns have created additional cleaning challenges, such as lead paint removal, which is likely to require special removal and disposal techniques.

Cleaning can also cause damage to non-masonry materials on a building, including glass, metal and wood. Thus, it is usually necessary to cover windows and doors, and other features that may be vulnerable to chemical cleaners. They should be covered with plastic or polyethylene, or a masking agent that is applied as a liquid which dries to form a thin protective film on glass, and is easily peeled off after the cleaning is finished. Wind drift, for example, can also damage other property by carrying cleaning chemicals onto nearby automobiles, resulting in etching of the glass or spotting of the paint finish. Similarly, airborne dust can enter surrounding buildings, and excess water can collect in nearby yards and basements.

Safety Considerations

Possible health dangers of each method selected for the cleaning project must be considered before selecting a cleaning method to avoid harm to the cleaning applicators, and the necessary precautions must be taken. The precautions listed in Material Safety Data Sheets (MSDS) that are provided with chemical products should always be followed. Protective clothing, respirators, hearing and face shields, and gloves must be provided to workers to be worn at all times. Acidic and alkaline chemical cleaners in both liquid and vapor forms can also cause serious injury to passers-by. It may be necessary to schedule cleaning at night or weekends if the building is located in a busy urban area to reduce the potential danger of chemical overspray to pedestrians. Cleaning during non-business hours will allow HVAC systems to be turned off and vents to be covered to prevent dangerous chemical fumes from entering the building which will also ensure the safety of the buildingís occupants. Abrasive and mechanical methods produce dust which can pose a serious health hazard, particularly if the abrasive or the masonry contains silica.

Water-Repellent Coatings and Waterproof Coatings

To begin with, it is important to understand that waterproof coatings and water-repellent coatings are not the same. Although these terms are frequently interchanged and commonly confused with one another, they are completely different materials. Water-repellent coatings—often referred to incorrectly as "sealers", but which do not or should not "seal"—are intended to keep liquid water from penetrating the surface but to allow water vapor to enter and leave, or pass through, the surface of the masonry. Water-repellent coatings are generally transparent, or clear, although once applied some may darken or discolor certain types of masonry while others may give it a glossy or shiny appearance. Waterproof coatings seal the surface from liquid water and from water vapor. They are usually opaque, or pigmented, and include bituminous coatings and some elastomeric paints and coatings.

Water-Repellent Coatings

Water-repellent coatings are formulated to be vapor permeable, or "breathable". They do not seal the surface completely to water vapor so it can enter the masonry wall as well as leave the wall. While the first water-repellent coatings to be developed were primarily acrylic or silicone resins in organic solvents, now most water-repellent coatings are water-based and formulated from modified siloxanes, silanes and other alkoxysilanes, or metallic stearates. While some of these products are shipped from the factory ready to use, other water-borne water repellents must be diluted at the job site. Unlike earlier water-repellent coatings which tended to form a "film" on the masonry surface, modern water-repellent coatings actually penetrate into the masonry substrate slightly and, generally, are almost invisible if properly applied to the masonry. They are also more vapor permeable than the old coatings, yet they still reduce the vapor permeability of the masonry. Once inside the wall, water vapor can condense at cold spots producing liquid water which, unlike water vapor, cannot escape through a water-repellent coating. The liquid water within the wall, whether from condensation, leaking gutters, or other sources, can cause considerable damage.

Water-repellent coatings are not consolidants. Although modern water-repellents may penetrate slightly beneath the masonry surface, instead of just "sitting" on top of it, they do not perform the same function as a consolidant which is to "consolidate" and replace lost binder to strengthen deteriorating masonry. Even after many years of laboratory study and testing, few consolidants have proven very effective. The composition of fired products such as brick and architectural terra cotta, as well as many types of building stone, does not lend itself to consolidation.

Some modern water-repellent coatings which contain a binder intended to replace the natural binders in stone that have been lost through weathering and natural erosion are described in product literature as both a water repellent and a consolidant The fact that the newer water-repellent coatings penetrate beneath the masonry surface instead of just forming a layer on top of the surface may indeed convey at least some consolidating properties to certain stones. However, a water-repellent coating cannot be considered a consolidant. In some instances, a water-repellent or "preservative" coating, if applied to already damaged or spalling stone, may form a surface crust which, if it fails, may exacerbate the deterioration by pulling off even more of the stone.

Is a Water-Repellent Treatment Necessary?

Water-repellent coatings are frequently applied to historic masonry buildings for the wrong reason. They also are often applied without an understanding of what they are and what they are intended to do. And these coatings can be very difficult, if not impossible, to remove from the masonry if they fail or become discolored. Most importantly, the application of water-repellent coatings to historic masonry is usually unnecessary.

Most historic masonry buildings, unless they are painted, have survived for decades without a water-repellent coating and, thus, probably do not need one now. Water penetration to the interior of a masonry building is seldom due to porous masonry, but results from poor or deferred maintenance. Leaking roofs, clogged or deteriorated gutters and downspouts, missing mortar, or cracks and open joints around door and window openings are almost always the cause of moisture-related problems in a historic masonry building. If historic masonry buildings are kept watertight and in good repair, water-repellent coatings should not be necessary.

Rising damp (capillary moisture pulled up from the ground), or condensation can also be a source of excess moisture in masonry buildings. A water-repellent coating will not solve this problem either and, in fact, may be likely to exacerbate it. Furthermore, a water-repellent coating should never be applied to a damp wall. Moisture in the wall would reduce the ability of a coating to adhere to the masonry and to penetrate below the surface. But, if it did adhere, it would hold the moisture inside the masonry

because, although a water-repellent coating is permeable to water vapor, liquid water cannot pass through it. In the case of rising damp, a coating may force the moisture to go even higher in the wall because it can slow down evaporation, and thereby retain the moisture in the wall.
Excessive moisture in masonry walls may carry waterborne soluble salts from the masonry units themselves or from the mortar through the walls. If the water is permitted to come to the surface, the salts may appear on the masonry surface as efflorescence (a whitish powder) upon evaporation. However, the salts can be potentially dangerous if they remain in the masonry and crystallize beneath the surface as subflorescence. Subflorescence eventually may cause the surface of the masonry to spall, particularly if a water-repellent coating has been applied which tends to reduce the flow of moisture out from the subsurface of the masonry. Although many of the newer water-repellent products are more breathable than their predecessors, they can be especially damaging if applied to masonry that contains salts, because they limit the flow of moisture through masonry.

When a Water-Repellent Coating May be Appropriate

There are some instances when a water-repellent coating may be considered appropriate to use on a historic masonry building. Soft, incompletely fired brick from the 18th-and early-19th centuries may have become so porous that paint or some type of coating is needed to protect it from further deterioration or dissolution. When a masonry building has been neglected for a long period of time, necessary repairs may be required in order to make it watertight. If, following a reasonable period of time after the building has been made watertight and has dried out completely, moisture appears actually to be penetrating through the repointed and repaired masonry walls, then the application of a water-repellent coating may be considered in selected areas only. This decision should be made in consultation with an architectural conservator. And, if such a treatment is undertaken, it should not be applied to the entire exterior of the building.
Anti-graffiti or barrier coatings are another type of clear coating—although barrier coatings can also be pigmented—that may be applied to exterior masonry, but they are not formulated primarily as water repellents. The purpose of these coatings is to make it harder for graffiti to stick to a masonry surface and, thus, easier to clean. But, like water-repellent coatings, in most cases the application of anti-graffiti coatings is generally not recommended for historic masonry buildings. These coatings are often quite shiny which can greatly alter the appearance of a historic masonry surface, and they are not always effective. Generally, other ways of discouraging graffiti, such as improved lighting, can be more effective than a coating. However, the application of anti-graffiti coatings may be appropriate in some instances on vulnerable areas of historic masonry buildings which are frequent targets of graffiti that are located in out-of-the-way places where constant surveillance is not possible.
Some water-repellent coatings are recommended by product manufacturers as a means of keeping dirt and pollutants or biological growth from collecting on the surface of masonry buildings and, thus, reducing the need for frequent cleaning. While this at times may be true, in some cases a coating may actually retain dirt more than uncoated masonry. Generally, the application of a water-repellent coating is not recommended on a historic masonry building as a means of preventing biological growth. Some water-repellent coatings may actually encourage biological growth on a masonry wall. Biological growth on masonry buildings has traditionally been kept at bay through regularly-scheduled cleaning as part of a maintenance plan. Simple cleaning of the masonry with low-pressure water using a natural- or synthetic-bristled scrub brush can be very effective if done on a regular basis. Commercial products are also available which can be sprayed on masonry to remove biological growth.
In most instances, a water-repellent coating is not necessary if a building is watertight. The application of a water-repellent coating is not a recommended treatment for historic masonry buildings unless there is a specific problem which it may help solve. If the problem occurs on only part of the building, it is best to treat only that area rather than an entire building. Extreme exposures such as parapets, for example, or portions of the building subject to driving rain can be treated more effectively and less expensively than the entire building. Water-repellent coatings are not permanent and must be reapplied periodically although, if they are truly invisible, it can be difficult to know when they are no longer providing the intended protection.
Testing a water-repellent coating by applying it in one small area may not be helpful in determining its suitability for the building because a limited test area does not allow an adequate evaluation of a treatment. Since water may enter and leave through the surrounding untreated areas, there is no way to tell if the coated test area is "breathable." But trying a coating in a small area may help to determine whether the coating is visible on the surface or if it will otherwise change the appearance of the masonry.

Waterproof Coatings

In theory, waterproof coatings usually do not cause problems as long as they exclude all water from the masonry. If water does enter the wall from the ground or from the inside of a building, the coating can intensify the damage because the water will not be able to escape. During cold weather this water in the wall can freeze causing serious mechanical disruption, such as spalling.

In addition, the water eventually will get out by the path of least resistance. If this path is toward the interior, damage to interior finishes can result; if it is toward the exterior, it can lead to damage to the masonry caused by built-up water pressure.

In most instances, waterproof coatings should not be applied to historic masonry. The possible exception to this might be the application of a waterproof coating to below-grade exterior foundation walls as a last resort to stop water infiltration on interior basement walls. Generally, however, waterproof coatings, which include elastomeric paints, should almost never be applied above grade to historic masonry buildings.

Summary

A well-planned cleaning project is an essential step in preserving, rehabilitating or restoring a historic masonry building. Proper cleaning methods and coating treatments, when determined necessary for the preservation of the masonry, can enhance the aesthetic character as well as the structural stability of a historic building. Removing years of accumulated dirt, pollutant crusts, stains, graffiti or paint, if done with appropriate caution, can extend the life and longevity of the historic resource. Cleaning that is carelessly or insensitively prescribed or carried out by inexperienced workers can have the opposite of the intended effect. It may scar the masonry permanently, and may actually result in hastening deterioration by introducing harmful residual chemicals and salts into the masonry or causing surface loss. Using the wrong cleaning method or using the right method incorrectly, applying the wrong kind of coating or applying a coating that is not needed can result in serious damage, both physically and aesthetically, to a historic masonry building. Cleaning a historic masonry building should always be done using the gentlest means possible that will clean, but not damage the building. It should always be taken into consideration before applying a water-repellent coating or a waterproof coating to a historic masonry building whether it is really necessary and whether it is in the best interest of preserving the building.

PRESERVATION BRIEFS 2

Repointing Mortar Joints in Historic Masonry Buildings

- Historical Background
- Identifying the Problem Before Repointing
- Finding an Appropriate Mortar Match
- Properties of Mortar
- Mortar Analysis
- Components of Mortar
- Mortar Type and Mix
- Execution of the Work
- Visually Examining the Mortar and the Masonry Units
- Summary

Masonry—brick, stone, terra-cotta, and concrete block—is found on nearly every historic building. Structures with all-masonry exteriors come to mind immediately, but most other buildings at least have masonry foundations or chimneys. Although generally considered "permanent," masonry is subject to deterioration, especially at the mortar joints. Repointing, also known simply as "pointing"or—somewhat inaccurately—"tuck pointing"*, is the process of removing deteriorated mortar from the joints of a masonry wall and replacing it with new mortar. Properly done, repointing restores the visual and physical integrity of the masonry. Improperly done, repointing not only detracts from the appearance of the building, but may also cause physical damage to the masonry units themselves.

The purpose of this Brief is to provide general guidance on appropriate materials and methods for repointing historic masonry buildings and it is intended to benefit building owners, architects, and contractors. The Brief should serve as a guide to prepare specifications for repointing historic masonry buildings. It should also help develop sensitivity to the particular needs of historic masonry, and to assist historic building owners in working cooperatively with architects, architectural conservators and historic preservation consultants, and contractors. Although specifically intended for historic buildings, the guidance is appropriate for other masonry buildings as well. This publication updates *Preservation Briefs 2: Repointing Mortar Joints in Historic Brick Buildings* to include all types of historic unit masonry. The scope of the earlier Brief has also been expanded to acknowledge that the many buildings constructed in the first half of the 20th century are now historic and eligible for listing in the National Register of Historic Places, and that they may have been originally constructed with portland cement mortar.

Historical Background

Mortar consisting primarily of lime and sand has been used as an integral part of masonry structures for thousands of years. Up until about the mid-19th century, lime or quicklime (sometimes called lump lime) was delivered to construction sites, where it had to be slaked, or combined with water. Mixing with water caused it to boil and resulted in a wet lime putty that was left to mature in a pit or wooden box for several weeks, up to a year. Traditional mortar was made from lime putty, or slaked lime, combined with local sand, generally in a ratio of 1 part lime putty to 3 parts sand by volume. Often other ingredients, such as crushed marine shells (another source of lime), brick dust, clay, natural cements, pigments, and even animal hair were also added to mortar, but the basic formulation for lime putty and sand mortar remained unchanged for centuries until the advent of portland cement or its forerunner, Roman cement, a natural, hydraulic cement.

Portland cement was patented in Great Britain in 1824. It was named after the stone from Portland in Dorset which it resembled when hard. This is a fast-curing, hydraulic cement which hardens under water. Portland cement was first manufactured in the United States in 1872, although it was imported before this date. But it was not in common use throughout the country until the early 20th century. Up until the turn of the century portland cement was considered primarily an additive, or "minor ingredient" to help accelerate mortar set time. By the 1930s, however, most masons used a mix of equal parts portland cement and lime putty. Thus, the mortar found in masonry structures built between 1873 and 1930 can range from pure lime and sand mixes to a wide variety of lime, portland cement, and sand combinations.

In the 1930s more new mortar products intended to hasten and simplify masons' work were introduced in the U.S. These included **masonry cement**, a premixed, bagged mortar which is a combination of portland cement and ground limestone, and **hydrated lime**, machine-slaked lime that eliminated the necessity of slaking quicklime into putty at the site.

Identifying the Problem Before Repointing return to top ▲

The decision to repoint is most often related to some obvious sign of deterioration, such as disintegrating mortar, cracks in mortar joints, loose bricks or stones, damp walls, or damaged plasterwork. It is, however, erroneous to assume that repointing alone will solve deficiencies that result from other problems. The root cause of the deterioration—leaking roofs or gutters, differential settlement of the building, capillary action causing rising damp, or extreme weather exposure—should always be dealt with prior to beginning work.

Without appropriate repairs to eliminate the source of the problem, mortar deterioration will continue and any repointing will have been a waste of time and money.

Use of Consultants

Because there are so many possible causes for deterioration in historic buildings, it may be desirable to retain a consultant, such as a historic architect or architectural conservator, to analyze the building. In addition to determining the most appropriate solutions to the problems, a consultant can prepare specifications which reflect the particular requirements of each job and can provide oversight of the work in progress. Referrals to preservation consultants frequently can be obtained from State Historic Preservation Offices, the American Institute for Conservation of Historic and Artistic Works (AIC), the Association for Preservation Technology (APT), and local chapters of the American Institute of Architects (AIA).

Finding an Appropriate Mortar Match

Preliminary research is necessary to ensure that the proposed repointing work is both physically and visually appropriate to the building. Analysis of unweathered portions of the historic mortar to which the new mortar will be matched can suggest appropriate mixes for the repointing mortar so that it will not damage the building because it is excessively strong or vapor impermeable.

Examination and analysis of the masonry units—brick, stone or terra cotta—and the techniques used in the original construction will assist in maintaining the building's historic appearance. A simple, non-technical, evaluation of the masonry units and mortar can provide information concerning the relative strength and permeability of each—critical factors in selecting the repointing mortar—while a visual analysis of the historic mortar can provide the information necessary for developing the new mortar mix and application techniques.

Although not crucial to a successful repointing project, for projects involving properties of special historic significance, a mortar analysis by a qualified laboratory can be useful by providing information on the original ingredients. However, there are limitations with such an analysis, and replacement mortar specifications should not be based solely on laboratory analysis. Analysis requires interpretation, and there are important factors which affect the condition and performance of the mortar that cannot be established through laboratory analysis. These may include: the original water content, rate of curing, weather conditions during original construction, the method of mixing and placing the mortar, and the cleanliness and condition of the sand. *The most useful information that can come out of laboratory analysis is the identification of sand by gradation and color.* This allows the color and the texture of the mortar to be matched with some accuracy because sand is the largest ingredient by volume.

In creating a repointing mortar that is compatible with the masonry units, the objective is to achieve one that matches the historic mortar as closely as possible, so that the new material can coexist with the old in a sympathetic, supportive and, if necessary, sacrificial capacity. The exact physical and chemical properties of the historic mortar are not of major significance as long as the new mortar conforms to the following criteria:

- The new mortar must match the historic mortar in **color, texture and tooling.** (If a laboratory analysis is undertaken, it may be possible to match the binder components and their proportions with the historic mortar, if those materials are available.)
- The **sand must match the sand** in the historic mortar. (The color and texture of the new mortar will usually fall into place if the sand is matched successfully.)
- The new mortar must have **greater vapor permeability** and be **softer** (measured in compressive strength) than the masonry units.
- The new mortar must be **as vapor permeable** and **as soft or softer** (measured in compressive strength) than the historic mortar. (Softness or hardness is not necessarily an indication of permeability; old, hard lime mortars can still retain high permeability.)

Mortar Analysis

Methods for analyzing mortars can be divided into two broad categories: **wet chemical** and **instrumental**. Many laboratories that analyze historic mortars use a simple **wet-chemical** method called acid digestion, whereby a sample of the mortar is crushed and then mixed with a dilute acid. The acid dissolves all the carbonate-containing minerals not only in the binder, but also in the aggregate (such as oyster shells, coral sands, or other carbonate-based materials), as well as any other acid-soluble materials. The sand and fine-grained acid-insoluble material is left behind. There are several variations on the simple acid digestion test. One involves collecting the carbon dioxide gas given off as the carbonate is digested by the acid; based on the gas volume the carbnate content of the mortar can be accurately determined (Jedrzejewska, 1960). Simple acid digestion methods are rapid, inexpensive, and easy to perform, but the information they provide about the original composition of a mortar is limited to the color and texture of the sand. The gas collection method provides more information about the binder than a simple acid digestion test.

Instrumental analysis methods that have been used to evaluate mortars include polarized light or thin-section microscopy, scanning electron microscopy, atomic absorption spectroscopy, X-ray diffraction, and differential thermal analysis. All instrumental methods require not only expensive, specialized equipment, but also highly-trained experienced analysts. However, instrumental methods can provide much more information about a mortar. Thin-section microscopy is probably the most commonly used instrumental method. Examination of thin slices of a mortar in transmitted light is often used to supplement acid digestion methods, particularly to look for carbonate-based aggregate. For example, the new ASTM test method, ASTM C 1324-96 "Test Method for Examination and Analysis of Hardened Mortars" which was designed specifically for the analysis of modern lime-cement and masonry cement mortars, combines a complex series of wet chemical analyses with thin-section microscopy.

The drawback of most mortar analysis methods is that mortar samples of known composition have not been analyzed in order to evaluate the method. Historic mortars were not prepared to narrowly defined specifications from materials of uniform quality; they contain a wide array of locally derived materials combined at the discretion of the mason. While a particular method might be able to accurately determine the original proportions of a lime-cement-sand mortar prepared from modern materials, the usefulness of that method for evaluating historic mortars is questionable unless it has been tested against mortars prepared from materials more commonly used in the past.

Properties of Mortar

Mortars for repointing should be softer or more permeable than the masonry units and no harder or more impermeable than the historic mortar to prevent damage to the masonry units. It is a common error to assume that hardness or high strength is a measure of appropriateness, particularly for lime-based historic mortars. Stresses within a wall caused by expansion, contraction, moisture migration, or settlement must be accommodated in some manner; in a masonry wall, these stresses should be relieved by the mortar rather than by the masonry units. A mortar that is stronger in compressive strength than the masonry units will not "give," thus causing stresses to be relieved through the masonry units—resulting in permanent damage to the masonry, such as cracking and spalling, that cannot be repaired easily.

While stresses can also break the bond between the mortar and the masonry units, permitting water to penetrate the resulting hairline cracks, this is easier to correct in the joint through repointing than if the break occurs in the masonry units.

Permeability, or rate of vapor transmission, is also critical. High lime mortars are more permeable than denser cement mortars. Historically, mortar acted as a bedding material—not unlike an expansion joint—rather than a "glue" for the masonry units, and moisture was able to migrate through the mortar joints rather than the masonry units. When moisture evaporates from the masonry it deposits any soluble salts either on the surface as *efflorescence* or below the surface as *subflorescence.* While salts deposited on the surface of masonry units are usually relatively harmless, salt crystallization within a masonry unit creates pressure that can cause parts ofthe outer surface to spall off or delaminate. If the mortar does not permitmoisture or moisture vapor to migrate out of the wall and evaporate, theresult will be damage to the masonry units.

Components of Mortar

Sand

Sand is the largest component of mortar and the material that gives mortar its distinctive color, texture and cohesiveness. Sand must be free of impurities, such as salts or clay. The three key characteristics of sand are: particle shape, gradation and void ratios.

When viewed under a magnifying glass or low-power microscope, particles of sand generally have either rounded edges, such as found in beach and river sand, or sharp, angular edges, found in crushed or manufactured sand. For repointing mortar, rounded or natural sand is preferred for two reasons. It is usually similar to the sand in the historic mortar and provides a better visual match. It also has better working qualities or plasticity and can thus be forced into the joint more easily, forming a good contact with the remaining historic mortar and the surface of the adjacent masonry units. Although manufactured sand is frequently more readily available, it is usually possible to locate a supply of rounded sand.

The gradation of the sand (particle size distribution) plays a very important role in the durability and cohesive properties of a mortar. Mortar must have a certain percentage of large to small particle sizes in order to deliver the optimum performance. Acceptable guidelines on particle size distribution may be found in ASTM C 144 (American Society for Testing and Materials). However, in actuality, since neither historic nor modern sands are always in compliance with ASTM C 144, matching the same particle appearance and gradation usually requires sieving the sand.

A scoop of sand contains many small voids between the individual grains. A mortar that performs well fills all these small voids with binder (cement/lime combination or mix) in a balanced manner. Well-graded sand generally has a 30 per cent void ratio by volume. Thus, 30 per cent binder by volume generally should be used, unless the historic mortar had a different binder: aggregate ratio. This represents the 1:3 binder to sand ratios often seen in mortar specifications.

For repointing, sand generally should conform to ASTM C 144 to assure proper gradation and freedom from impurities; some variation may be necessary to match the original size and gradation. Sand color and texture also should match the original as closely as possible to provide the proper color match without other additives.

Lime

Mortar formulations prior to the late-19th century used lime as the primary binding material. Lime is derived from heating limestone at high temperatures which burns off the carbon dioxide, and turns the limestone into quicklime. There are three types of limestone—calcium, magnesium, and dolomitic—differentiated by the different levels of magnesium carbonate they contain which impart specific qualities to mortar. Historically, calcium lime was used for mortar rather than the dolomitic lime (calcium magnesium carbonate) most often used today. But it is also important to keep in mind the fact that the historic limes, and other components of mortar, varied a great deal because they were natural, as opposed to modern lime which is manufactured and, therefore, standardized. Because some of the kinds of lime, as well as other components of mortar, that were used historically are no longer readily available, even when a conscious effort is made to replicate a "historic" mix, this may not be achievable due to the differences between modern and historic materials.

Lime, itself, when mixed with water into a paste is very plastic and creamy. It will remain workable and soft indefinitely, if stored in a sealed container. Lime (calcium hydroxide) hardens by carbonation absorbing carbon dioxide primarily from the air, converting itself to calcium carbonate. Once a lime and sand mortar is mixed and placed in a wall, it begins the process of carbonation. If lime mortar is left to dry too rapidly, carbonation of the mortar will be reduced, resulting in poor adhesion and poor durability. In addition, lime mortar is slightly water soluble and thus is able to re-seal any hairline cracks that may develop during the life of the mortar. Lime mortar is soft, porous, and changes little in volume during temperature fluctuations thus making it a good choice for historic buildings. *Because of these qualities, high calcium lime mortar may be considered for many repointing projects, not just those involving historic buildings.*

For repointing, lime should conform to ASTM C 207, Type S, or Type SA, Hydrated Lime for Masonry Purposes. This machine-slaked lime is designed to assure high plasticity and water retention. The use of quicklime which must be slaked and soaked by hand may have advantages over hydrated lime in some restoration projects if time and money allow.

Lime Putty

Lime putty is slaked lime that has a putty or paste-like consistency. It should conform to ASTM C 5. Mortar can be mixed using lime putty according to ASTM C 270 property or proportion specification.

Portland Cement

More recent, 20th-century mortar has used portland cement as a primary binding material. A straight portland cement and sand mortar is extremely hard, resists the movement of water, shrinks upon setting, and undergoes relatively large thermal movements. When mixed with water, portland cement forms a harsh, stiff paste that is quite unworkable, becoming hard very quickly. (Unlike lime, portland

cement will harden regardless of weather conditions and does not require wetting and drying cycles.) Some portland cement assists the workability and plasticity of the mortar without adversely affecting the finished project; it also provides early strength to the mortar and speeds setting. Thus, it may be appropriate to add some portland cement to an essentially lime-based mortar even when repointing relatively soft 18th or 19th century brick under some circumstances when a slightly harder mortar is required. The more portland cement that is added to a mortar formulation the harder it becomes—and the faster the initial set.

For repointing, portland cement should conform to ASTM C 150. White, non- staining portland cement may provide a better color match for some historic mortars than the more commonly available grey portland cement. But, it should not be assumed, however, that white portland cement is always appropriate for all historic buildings, since the original mortar may have been mixed with grey cement. The cement should not have more than 0.60 per cent alkali to help avoid efflorescence.

Masonry Cement

Masonry cement is a preblended mortar mix commonly found at hardware and home repair stores. It is designed to produce mortars with a compressive strength of 750 psi or higher when mixed with sand and water at the job site. It may contain hydrated lime, but it always contains a large amount of portland cement, as well as ground limestone and other workability agents, including air-entraining agents. Because masonry cements are not required to contain hydrated lime, and generally do not contain lime, they produce high strength mortars that can damage historic masonry. *For this reason, they generally are not recommended for use on historic masonry buildings.*

Lime Mortar (pre-blended)

Hydrated lime mortars, and pre-blended lime putty mortars with or without a matched sand are commercially available. Custom mortars are also available with color. In most instances, pre-blended lime mortars containing sand may not provide an exact match; however, if the project calls for total repointing, a pre-blended lime mortar may be worth considering as long as the mortar is compatible in strength with the masonry. If the project involves only selected, "spot" repointing, then it may be better to carry out a mortar analysis which can provide a custom pre-blended lime mortar with a matching sand. In either case, if a preblended lime mortar is to be used, it should contain Type S or SA hydrated lime conforming to ASTM C 207.

Water

Water should be potable—clean and free from acids, alkalis, or other dissolved organic materials.

Other Components

Historic components

In addition to the color of the sand, the texture of the mortar is of critical importance in duplicating historic mortar. Most mortars dating from the mid-19th century on—with some exceptions—have a fairly homogeneous texture and color. Some earlier mortars are not as uniformly textured and may contain lumps of partially burned lime or "dirty lime", shell (which often provided a source of lime, particularly in coastal areas), natural cements, pieces of clay, lampblack or other pigments, or even animal hair. The visual characteristics of these mortars can be duplicated through the use of similar materials in the repointing mortar.

Replicating such unique or individual mortars will require writing new specifications for each project. If possible, suggested sources for special materials should be included. For example, crushed oyster shells can be obtained in a variety of sizes from poultry supply dealers.

Pigments

Some historic mortars, particularly in the late 19th century, were tinted to match or contrast with the brick or stone. Red pigments, sometimes in the form of brick dust, as well as brown, and black pigments were commonly used. Modern pigments are available which can be added to the mortar at the job site, but they should not exceed 10 per cent by weight of the portland cement in the mix, and carbon black should be limited to 2 per cent. Only synthetic mineral oxides, which are alkali-proof and sun-fast, should be used to prevent bleaching and fading.

Modern Components

Admixtures are used to create specific characteristics in mortar, and whether they should be used will depend upon the individual project. *Air entraining agents*, for example, help the mortar to resist freeze-

thaw damage in northern climates. *Accelerators* are used to reduce mortar freezing prior to setting while *retarders* help to extend the mortar life in hot climates. Selection of admixtures should be made by the architect or architectural conservator as part of the specifications, not something routinely added by the masons.
Generally, modern chemical additives are unnecessary and may, in fact, have detrimental effects in historic masonry projects. The use of antifreeze compounds is not recommended. They are not very effective with high lime mortars and may introduce salts, which may cause efflorescence later. A better practice is to warm the sand and water, and to protect the completed work from freezing. No definitive study has determined whether air-entraining additives should be used to resist frost action and enhance plasticity, but in areas of extreme exposure requiring high-strength mortars with lower permeability, air-entrainment of 10-16 percent may be desirable (see formula for "severe weather exposure" in Mortar Type and Mix). Bonding agents are not a substitute for proper joint preparation, and they should generally be avoided. If the joint is properly prepared, there will be a good bond between the new mortar and the adjacent surfaces. In addition, a bonding agent is difficult to remove if smeared on a masonry surface.

Mortar Type and Mix

Mortars for repointing projects, especially those involving historic buildings, typically are custom mixed in order to ensure the proper physical and visual qualities. These materials can be combined in varying proportions to create a mortar with the desired performance and durability. The actual specification of a particular mortar type should take into consideration all of the factors affecting the life of the building including: current site conditions, present condition of the masonry, function of the new mortar, degree of weather exposure, and skill of the mason.
Thus, no two repointing projects are exactly the same. Modern materials specified for use in repointing mortar should conform to specifications of the American Society for Testing and Materials (ASTM) or comparable federal specifications, and the resulting mortar should conform to ASTM C 270, Mortar for Unit Masonry.
Specifying the proportions for the repointing mortar for a specific job is not as difficult as it might seem. Five mortar types, each with a corresponding recommended mix, have been established by ASTM to distinguish high strength mortar from soft flexible mortars. The ASTM designated them in decreasing order of approximate general strength as Type M (2,500 psi), Type S (1,800 psi), Type N (750 psi), Type O (350 psi) and Type K (75 psi). (The letters identifying the types are from the words MASON WORK using every other letter.) Type K has the highest lime content of the mixes that contain portland cement, although it is seldom used today, except for some historic preservation projects. The designation "L" in the accompanying chart identifies a straight lime and sand mix. Specifying the appropriate ASTM mortar by proportion of ingredients, will ensure the desired physical properties. Unless specified otherwise, measurements or proportions for mortar mixes are always given in the following order: cement-lime-sand. Thus, a Type K mix, for example, would be referred to as 1-3-10, or 1 part cement to 3 parts lime to 10 parts sand. Other requirements to create the desired visual qualities should be included in the specifications.
The strength of a mortar can vary. If mixed with higher amounts of portland cement, a harder mortar is obtained. The more lime that is added, the softer and more plastic the mortar becomes, increasing its workability. A mortar strong in compressive strength might be desirable for a hard stone (such as granite) pier holding up a bridge deck, whereas a softer, more permeable lime mortar would be preferable for a historic wall of soft brick. Masonry deterioration caused by salt deposition results when the mortar is less permeable than the masonry unit. A strong mortar is still more permeable than hard, dense stone. However, in a wall constructed of soft bricks where the masonry unit itself has a relatively high permeability or vapor transmission rate, a soft, high lime mortar is necessary to retain sufficient permeability.

Execution of the Work

Test Panels

These panels are prepared by the contractor using the same techniques that will be used on the remainder of the project. Several panel locations—preferably not on the front or other highly visible location of the building—may be necessary to include all types of masonry, joint styles, mortar colors, and other problems likely to be encountered on the job.
If cleaning tests, for example, are also to be undertaken, they should be carried out in the same location. Usually a 3 foot by 3 foot area is sufficient for brickwork, while a somewhat larger area may be

required for stonework. These panels establish an acceptable standard of work and serve as a benchmark for evaluating and accepting subsequent work on the building.

Joint Preparation

Old mortar should be removed to a minimum depth of 2 to 2-1/2 times the width of the joint to ensure an adequate bond and to prevent mortar "popouts." For most brick joints, this will require removal of the mortar to a depth of approximately Ω to 1 inch; for stone masonry with wide joints, mortar may need to be removed to a depth of several inches. Any loose or disintegrated mortar beyond this minimum depth also should be removed.

Although some damage may be inevitable, careful joint preparation can help limit damage to masonry units. The traditional manner of removing old mortar is through the use of hand chisels and mash hammers. Though labor-intensive, in most instances this method poses the least threat for damage to historic masonry units and produces the best final product.

The most common method of removing mortar, however, is through the use of power saws or grinders. The use of power tools by unskilled masons can be disastrous for historic masonry, particularly soft brick. Using power saws on walls with thin joints, such as most brick walls, almost always will result in damage to the masonry units by breaking the edges and by overcutting on the head, or vertical joints. However, small pneumatically-powered chisels generally can be used safely and effectively to remove mortar on historic buildings as long as the masons maintain appropriate control over the equipment. Under certain circumstances, thin diamond-bladed grinders may be used to cut out *horizontal* joints only on hard portland cement mortar common to most early-20th century masonry buildings. Usually, automatic tools most successfully remove old mortar without damaging the masonry units when they are used in combination with hand tools in preparation for repointing. Where horizontal joints are uniform and fairly wide, it may be possible to use a power masonry saw to assist the removal of mortar, such as by cutting along the middle of the joint; final mortar removal from the sides of the joints still should be done with a hand chisel and hammer. Caulking cutters with diamond blades can sometimes be used successfully to cut out joints without damaging the masonry. Caulking cutters are slow; they do not rotate, but vibrate at very high speeds, thus minimizing the possibility of damage to masonry units. Although mechanical tools may be safely used in limited circumstances to cut out horizontal joints in preparation for repointing, they should never be used on vertical joints because of the danger of slipping and cutting into the brick above or below the vertical joint. Using power tools to remove mortar without damaging the surrounding masonry units also necessitates highly skilled masons experienced in working on historic masonry buildings. Contractors should demonstrate proficiency with power tools before their use is approved.

Using any of these power tools may also be more acceptable on hard stone, such as quartzite or granite, than on terra cotta with its glass-like glaze, or on soft brick or stone. The test panel should determine the acceptability of power tools. If power tools are to be permitted, the contractor should establish a quality control program to account for worker fatigue and similar variables.

Mortar should be removed cleanly from the masonry units, leaving square corners at the back of the cut. Before filling, the joints should be rinsed with a jet of water to remove all loose particles and dust. At the time of filling, the joints should be damp, but with no standing water present. For masonry walls—limestone, sandstone and common brick—that are extremely absorbent, it is recommended that a continual mist of water be applied for a few hours before repointing begins.

Mortar Preparation

Mortar components should be measured and mixed carefully to assure the uniformity of visual and physical characteristics. Dry ingredients are measured by volume and thoroughly mixed before the addition of any water. Sand must be added in a damp, loose condition to avoid over sanding. Repointing mortar is typically pre-hydrated by adding water so it will just hold together, thus allowing it to stand for a period of time before the final water is added. Half the water should be added, followed by mixing for approximately 5 minutes. The remaining water should then be added in small portions until a mortar of the desired consistency is reached. The total volume of water necessary may vary from batch to batch, depending on weather conditions. It is important to keep the water to a minimum for two reasons: first, a drier mortar is cleaner to work with, and it can be compacted tightly into the joints; second, with no excess water to evaporate, the mortar cures without shrinkage cracks. Mortar should be used within approximately 30 minutes of final mixing, and "retempering," or adding more water, should not be permitted.

Using Lime Putty to Make Mortar

Mortar made with lime putty and sand, sometimes referred to as roughage or course stuff, should be measured by volume, and may require slightly different proportions from those used with hydrated lime. No additional water is usually needed to achieve a workable consistency because enough water is already contained in the putty. Sand is proportioned first, followed by the lime putty, then mixed for five minutes or until all the sand is thoroughly coated with the lime putty. But mixing, in the familiar sense of turning over with a hoe, sometimes may not be sufficient if the best possible performance is to be obtained from a lime putty mortar. Although the old practice of chopping, beating and ramming the mortar has largely been forgotten, recent field work has confirmed that lime putty and sand rammed and beaten with a wooden mallet or ax handle, interspersed by chopping with a hoe, can significantly improve workability and performance. The intensity of this action increases the overall lime/sand contact and removes any surplus water by compacting the other ingredients. It may also be advantageous for larger projects to use a mortar pan mill for mixing. Mortar pan mills which have a long tradition in Europe produce a superior lime putty mortar not attainable with today's modern paddle and drum type mixers.

For larger repointing projects the lime putty and sand can be mixed together ahead of time and stored indefinitely, on or off site, which eliminates the need for piles of sand on the job site. This mixture, which resembles damp brown sugar, must be protected from the air in sealed containers with a wet piece of burlap over the top or sealed in a large plastic bag to prevent evaporation and premature carbonation. The lime putty and sand mixture can be recombined into a workable plastic state months later with no additional water.

If portland cement is specified in a lime putty and sand mortar—Type O (1:2:9) or Type K (1:3:11)—the portland cement should first be mixed into a slurry paste before adding it to the lime putty and sand. Not only will this ensure that the portland cement is evenly distributed throughout the mixture, but if dry portland cement is added to wet ingredients it tends to "ball up," jeopardizing dispersion. (Usually water must be added to the lime putty and sand anyway once the portland cement is introduced.) Any color pigments should be added at this stage and mixed for a full five minutes. The mortar should be used within 30 minutes to 1Ω hours and it should not be retempered. Once portland cement has been added the mortar can no longer be stored.

Filling the Joint

Where existing mortar has been removed to a depth of greater than 1 inch, these deeper areas should be filled first, compacting the new mortar in several layers. The back of the entire joint should be filled successively by applying approximately 1/4 inch of mortar, packing it well into the back corners. This application may extend along the wall for several feet. As soon as the mortar has reached thumb-print hardness, another 1/4 inch layer of mortar—approximately the same thickness—may be applied. Several layers will be needed to fill the joint flush with the outer surface of the masonry. It is important to allow each layer time to harden before the next layer is applied; most of the mortar shrinkage occurs during the hardening process and layering thus minimizes overall shrinkage.

When the final layer of mortar is thumb-print hard, the joint should be tooled to match the historic joint. Proper timing of the tooling is important for uniform color and appearance. If tooled when too soft, the color will be lighter than expected, and hairline cracks may occur; if tooled when too hard, there may be dark streaks called "tool burning," and good closure of the mortar against the masonry units will not be achieved.

If the old bricks or stones have worn, rounded edges, it is best to recess the final mortar slightly from the face of the masonry. This treatment will help avoid a joint which is visually wider than the actual joint; it also will avoid creation of a large, thin featheredge which is easily damaged, thus admitting water. After tooling, excess mortar can be removed from the edge of the joint by brushing with a natural bristle or nylon brush. Metal bristle brushes should never be used on historic masonry.

Curing Conditions

The preliminary hardening of high-lime content mortars—those mortars that contain more lime by volume than portland cement, i.e., Type O (1:2:9), Type K (1:3:11), and straight lime/sand, Type "L" (0:1:3)—takes place fairly rapidly as water in the mix is lost to the porous surface of the masonry and through evaporation. A high lime mortar (especially Type "L") left to dry out too rapidly can result in chalking, poor adhesion, and poor durability. Periodic wetting of the repointed area after the mortar joints are thumb-print hard and have been finish tooled may significantly accelerate the carbonation process. When feasible, misting using a hand sprayer with a fine nozzle can be simple to do for a day or two after repointing. Local conditions will dictate the frequency of wetting, but initially it may be as often as every hour and gradually reduced to every three or four hours. Walls should be covered with burlap for the first three days after repointing. (Plastic may be used, but it should be tented out and not placed

directly against the wall.) This helps keep the walls damp and protects them from direct sunlight. Once carbonation of the lime has begun, it will continue for many years and the lime will gain strength as it reverts back to calcium carbonate within the wall.

Aging the Mortar

Even with the best efforts at matching the existing mortar color, texture, and materials, there will usually be a visible difference between the old and new work, partly because the new mortar has been matched to the unweathered portions of the historic mortar. Another reason for a slight mismatch may be that the sand is more exposed in old mortar due to the slight erosion of the lime or cement. Although spot repointing is generally preferable and some color difference should be acceptable, if the difference between old and new mortar is too extreme, it may be advisable in some instances to repoint an entire area of a wall, or an entire feature such as a bay, to minimize the difference between the old and the new mortar. If the mortars have been properly matched, usually the best way to deal with surface color differences is to let the mortars age naturally. Other treatments to overcome these differences, including cleaning the non-repointed areas or staining the new mortar, should be carefully tested prior to implementation.

Staining the new mortar to achieve a better color match is generally not recommended, but it may be appropriate in some instances. Although staining may provide an initial match, the old and new mortars may weather at different rates, leading to visual differences after a few seasons. In addition, the mixtures used to stain the mortar may be harmful to the masonry; for example, they may introduce salts into the masonry which can lead to efflorescence.

Cleaning the Repointed Masonry

If repointing work is carefully executed, there will be little need for cleaning other than to remove the small amount of mortar from the edge of the joint following tooling. This can be done with a stiff natural bristle or nylon brush after the mortar has dried, but before it is initially set (1-2 hours). Mortar that has hardened can usually be removed with a wooden paddle or, if necessary, a chisel.

Further cleaning is best accomplished with plain water and natural bristle or nylon brushes. If chemicals must be used, they should be selected with extreme caution. Improper cleaning can lead to deterioration of the masonry units, deterioration of the mortar, mortar smear, and efflorescence. New mortar joints are especially susceptible to damage because they do not become fully cured for several months. Chemical cleaners, particularly acids, should never be used on dry masonry. The masonry should always be completely soaked once with water before chemicals are applied. After cleaning, the walls should be flushed again with plain water to remove all traces of the chemicals.

Several precautions should be taken if a freshly repointed masonry wall is to be cleaned. First, the mortar should be fully hardened before cleaning. Thirty days is usually sufficient, depending on weather and exposure; as mentioned previously, the mortar will continue to cure even after it has hardened. Test panels should be prepared to evaluate the effects of different cleaning methods. Generally, on newly repointed masonry walls, only very low pressure (100 psi) water washing supplemented by stiff natural bristle or nylon brushes should be used, except on glazed or polished surfaces, where only soft cloths should be used.**

New construction "bloom" or efflorescence occasionally appears within the first few months of repointing and usually disappears through the normal process of weathering. If the efflorescence is not removed by natural processes, the safest way to remove it is by dry brushing with stiff natural or nylon bristle brushes followed by wet brushing. Hydrochloric (muriatic) acid, is generally ineffective, and it should not be used to remove efflorescence. It may liberate additional salts, which, in turn, can lead to more efflorescence.

Surface grouting is sometimes suggested as an alternative to repointing brick buildings, in particular. This process involves the application of a thin coat of cement-based grout to the mortar joints and the mortar/brick interface. To be effective, the grout must extend slightly onto the face of the masonry units, thus widening the joint visually. The change in the joint appearance can alter the historic character of the structure to an unacceptable degree. In addition, although masking of the bricks is intended to keep the grout off the remainder of the face of the bricks, some level of residue, called "veiling," will inevitably remain. Surface grouting cannot substitute for the more extensive work of repointing, and it is not a recommended treatment for historic masonry.

Visually Examining the Mortar and the Masonry Units

A simple *in situ* comparison will help determine the hardness and condition of the mortar and the masonry units. Begin by scraping the mortar with a screwdriver, and gradually tapping harder with a

cold chisel and mason's hammer. Masonry units can be tested in the same way beginning, even more gently, by scraping with a fingernail. This relative analysis which is derived from the 10-point hardness scale used to describe minerals, provides a good starting point for selection of an appropriate mortar. It is described more fully in "The Russack System for Brick & Mortar Description" referenced in Reading List at the end of this Brief.

Mortar samples should be chosen carefully, and picked from a variety of locations on the building to find unweathered mortar, if possible. Portions of the building may have been repointed in the past while other areas may be subject to conditions causing unusual deterioration. There may be several colors of mortar dating from different construction periods or sand used from different sources during the initial construction. Any of these situations can give false readings to the visual or physical characteristics required for the new mortar. Variations should be noted which may require developing more than one mix.

1. Remove with a chisel and hammer three or four unweathered samples of the mortar to be matched from several locations on the building. (Set the largest sample aside--this will be used later for comparison with the repointing mortar). Removing a full representation of samples will allow selection of a "mean" or average mortar sample.
2. Mash the remaining samples with a wooden mallet, or hammer if necessary, until they are separated into their constituent parts. There should be a good handful of the material.
3. Examine the powdered portion—the lime and/or cement matrix of the mortar. Most particularly, note the color. There is a tendency to think of historic mortars as having white binders, but grey portland cement was available by the last quarter of the 19th century, and traditional limes were also sometimes grey. Thus, in some instances, the natural color of the historic binder may be grey, rather than white. The mortar may also have been tinted to create a colored mortar, and this color should be identified at this point.
4. Carefully blow away the powdery material (the lime and/or cement matrix which bound the mortar together).
5. With a low power (10 power) magnifying glass, examine the remaining sand and other materials such as lumps of lime or shell.
6. Note and record the wide range of color as well as the varying sizes of the individual grains of sand, impurities, or other materials.

Other Factors to Consider

Color

Regardless of the color of the binder or colored additives, the sand is the primary material that gives mortar its color. A surprising variety of colors of sand may be found in a single sample of historic mortar, and the different sizes of the grains of sand or other materials, such as incompletely ground lime or cement, play an important role in the texture of the repointing mortar. Therefore, when specifying sand for repointing mortar, it may be necessary to obtain sand from several sources and to combine or screen them in order to approximate the range of sand colors and grain sizes in the historic mortar sample.

Pointing Style

Close examination of the historic masonry wall and the techniques used in the original construction will assist in maintaining the visual qualities of the building. Pointing styles and the methods of producing them should be examined. It is important to look at both the horizontal and the vertical joints to determine the order in which they were tooled and whether they were the same style. Some late-19th and early-20th century buildings, for example, have horizontal joints that were raked back while the vertical joints were finished flush and stained to match the bricks, thus creating the illusion of horizontal bands. Pointing styles may also differ from one facade to another; front walls often received greater attention to mortar detailing than side and rear walls. **Tuckpointing** is not true repointing but the application of a raised joint or lime putty joint on top of flush mortar joints. **Penciling** is a purely decorative, painted surface treatment over a mortar joint, often in a contrasting color.

Masonry Units

The masonry units should also be examined so that any replacement units will match the historic masonry. Within a wall there may be a wide range of colors, textures, and sizes, particularly with hand-made brick or rough-cut, locally-quarried stone. Replacement units should blend in with the full range of masonry units rather than a single brick or stone.

Matching Color and Texture of the Repointing Mortar

New mortar should match the unweathered interior portions of the historic mortar. The simplest way to check the match is to make a small sample of the proposed mix and allow it to cure at a temperature of approximately 70 degrees F for about a week, or it can be baked in an oven to speed up the curing; this sample is then broken open and the surface is compared with the surface of the largest "saved" sample of historic mortar.

If a proper color match cannot be achieved through the use of natural sand or colored aggregates like crushed marble or brick dust, it may be necessary to use a modern mortar pigment.

During the early stages of the project, it should be determined how closely the new mortar should match the historic mortar. Will "quite close" be sufficient, or is "exactly" expected? The specifications should state this clearly so that the contractor has a reasonable idea how much time and expense will be required to develop an acceptable match.

The same judgment will be necessary in matching replacement terra cotta, stone or brick. If there is a known source for replacements, this should be included in the specifications. If a source cannot be determined prior to the bidding process, the specifications should include an estimated price for the replacement materials with the final price based on the actual cost to the contractor.

Mortar Types (Measured by volume)

Designation	Cement	Hydrated Lime or Lime Putty	Sand
M	1	1/4	3 - 3 3/4
S	1	1/2	4–4 1/2
N	1	1	5–6
O	1	2	8–9
K	1	3	10–12
"L"	0	1	2 1/4–3

Suggested Mortar Types for Different Exposures

	Exposure		
Masonry Material	Sheltered	Moderate	Severe
Very durable: granite, hard-cored brick, etc.	O	N	S
Moderately durable:limestone, durable stone, molded brick	K	O	N
Minimally durable:soft hand-made brick	"L"	K	O

Summary and References

A good repointing job is meant to last, at least 30 years, and preferably 50- 100 years. Shortcuts and poor craftsmanship result not only in diminishing the historic character of a building, but also in a job that looks bad, and will require future repointing sooner than if the work had been done correctly. The mortar joint in a historic masonry building has often been called a wall's "first line of defense." Good repointing practices guarantee the long life of the mortar joint, the wall, and the historic structure. Although careful maintenance will help preserve the freshly repointed mortar joints, it is important to remember that mortar joints are intended to be sacrificial and will probably require repointing sometime in the future. Nevertheless, if the historic mortar joints proved durable for many years, then careful repointing should have an equally long life, ultimately contributing to the preservation of the entire building.

PRESERVATION BRIEF 6

Dangers of Abrasive Cleaning to Historic Buildings

- What is Abrasive Cleaning?
- Why are Abrasive Cleaning Methods Used?
- Problems of Abrasive Cleaning
- How Building Materials React to Abrasive Cleaning
- When is Abrasive Cleaning Permissible?
- Do Not Abrasively Clean these Historic Interiors
- Mitigating the Effects of Abrasive Cleaning
- Summary

Abrasive cleaning methods are responsible for causing a great deal of damage to historic building materials. To prevent indiscriminate use of these potentially harmful techniques, this brief has been prepared to explain abrasive cleaning methods, how they can be physically and aesthetically destructive to historic building materials, and why they generally are not acceptable preservation treatments for historic structures. There are alternative, less harsh means of cleaning and removing paint and stains from historic buildings. However, careful testing should precede general cleaning to assure that the method selected will not have an adverse effect on the building materials. A historic building is irreplaceable, and should be cleaned using only the "gentlest means possible" to best preserve it.

What is Abrasive Cleaning?

Abrasive cleaning methods include all techniques that physically abrade the building surface to remove soils, discolorations or coatings. Such techniques involve the use of certain *materials* which impact or abrade the surface under pressure, or abrasive *tools and equipment*. Sand, because it is readily available, is probably the most commonly used type of grit material. However, any of the following materials may be substituted for sand, and all can be classified as abrasive substances: ground slag or volcanic ash, crushed (pulverized) walnut or almond shells, rice husks, ground corncobs, ground coconut shells, crushed eggshells, silica flour, synthetic particles, glass beads and micro-balloons. Even *water* under pressure can be an abrasive substance. Tools and equipment that are abrasive to historic building materials include wire brushes, rotary wheels, power sanding disks and belt sanders. The use of water in combination with grit may also be classified as an abrasive cleaning method. Depending on the manner in which it is applied, water may soften the impact of the grit, but water that is too highly pressurized can be very abrasive. There are basically two different methods which can be referred to as "wet grit," and it is important to differentiate between the two. One technique involves the addition of a stream of water to a regular sandblasting nozzle. This is done primarily to cut down dust, and has very little, if any, effect on reducing the aggressiveness, or cutting action of the grit particles. With the second technique, a very small amount of grit is added to a pressurized water stream. This method may be controlled by regulating the amount of grit fed into the water stream, as well as the pressure of the water.

Why Are Abrasive Cleaning Methods Used?

Usually, an abrasive cleaning method is selected as an expeditious means of quickly removing years of dirt accumulation, unsightly stains, or deteriorating building fabric or finishes, such as stucco or paint. The fact that sandblasting is one of the best known and most readily available building cleaning treatments is probably the major reason for its frequent use. Many mid-19th century brick buildings were painted immediately or soon after completion to protect poor quality brick or to imitate another material, such as stone. Sometimes brick buildings were painted in an effort to produce what was considered a more harmonious relationship between a building and its natural surroundings. By the 1870s, brick buildings were often left unpainted as mechanization in the brick industry brought a cheaper pressed brick and fashion decreed a sudden preference for dark colors. However, it was still customary to paint brick of poorer quality for the additional protection the paint afforded.

It is a common 20th century misconception that all historic masonry buildings were initially unpainted. If the intent of a modern restoration is to return a building to its original appearance, removal of the paint not only may be historically inaccurate, but also harmful. Many older buildings were painted or stuccoed at some point to correct recurring maintenance problems caused by faulty construction techniques, to

hide alterations, or in an attempt to solve moisture problems. If this is the case, removal of paint or stucco may cause these problems to reoccur. Another reason for paint removal, particularly in rehabilitation projects, is to give the building a "new image" in response to contemporary design trends and to attract investors or tenants. Thus, it is necessary to consider the purpose of the intended cleaning. While it is clearly important to remove unsightly stains, heavy encrustations of dirt, peeling paint or other surface coatings, it may not be equally desirable to remove paint from a building which originally was painted. Many historic buildings which show only a slight amount of soil or discoloration are much better left as they are. A thin layer of soil is more often protective of the building fabric than it is harmful, and seldom detracts from the building's architectural and/or historic character. Too thorough cleaning of a historic building may not only sacrifice some of the building's character, but also, misguided cleaning efforts can cause a great deal of damage to historic building fabric. Unless there are stains, graffiti or dirt and pollution deposits which are destroying the building fabric, it is generally preferable to do as little cleaning as possible, or to repaint where necessary. It is important to remember that a historic building does not have to look as if it were newly constructed to be an attractive or successful restoration or rehabilitation project.

Problems of Abrasive Cleaning

The crux of the problem is that abrasive cleaning is just that--abrasive. An abrasively cleaned historic structure may be physically as well as aesthetically damaged. Abrasive methods "clean" by eroding dirt or paint, but at the same time they also tend to erode the surface of the building material. In this way, abrasive cleaning is destructive and causes irreversible harm to the historic building fabric. If the fabric is brick, abrasive methods remove the hard, outer protective surface, and therefore make the brick more susceptible to rapid weathering and deterioration. Grit blasting may also increase the water permeability of a brick wall. The impact of the grit particles tends to erode the bond between the mortar and the brick, leaving cracks or enlarging existing cracks where water can enter. Some types of stone develop a protective patina or "quarry crust" parallel to the worked surface (created by the movement of moisture towards the outer edge), which also may be damaged by abrasive cleaning. The rate at which the material subsequently weathers depends on the quality of the inner surface that is exposed. Abrasive cleaning can destroy, or substantially diminish, decorative detailing on buildings such as a molded brickwork or architectural terra-cotta, ornamental carving on wood or stone, and evidence of historic craft techniques, such as tool marks and other surface textures. In addition, perfectly sound and/or "tooled" mortar joints can be worn away by abrasive techniques. This not only results in the loss of historic craft detailing but also requires repointing, a step involving considerable time, skill and expense, and which might not have been necessary had a gentler method been chosen. Erosion and pitting of the building material by abrasive cleaning creates a greater surface area on which dirt and pollutants collect. In this sense, the building fabric "attracts" more dirt, and will require more frequent cleaning in the future. In addition to causing physical and aesthetic harm to the historic fabric, there are several adverse environmental effects of dry abrasive cleaning methods. Because of the friction caused by the abrasive medium hitting the building fabric, these techniques usually create a considerable amount of dust, which is unhealthy, particularly to the operators of the abrasive equipment. It further pollutes the environment around the job site, and deposits dust on neighboring buildings, parked vehicles and nearby trees and shrubbery. Some adjacent materials not intended for abrasive treatment such as wood or glass, may also be damaged because the equipment may be difficult to regulate. Wet grit methods, while eliminating dust, deposit a messy slurry on the ground or other objects surrounding the base of the building. In colder climates where there is the threat of frost, any wet cleaning process applied to historic masonry structures must be done in warm weather, allowing ample time for the wall to dry out thoroughly before cold weather sets in. Water which remains and freezes in cracks and openings of the masonry surface eventually may lead to spalling. High-pressure wet cleaning may force an inordinate amount of water into the walls, affecting interior materials such as plaster or joist ends, as well as metal building components within the walls.

Variable Factors

The greatest problem in developing practical guidelines for cleaning any historic building is the large number of variable and unpredictable factors involved. Because these variables make each cleaning project unique, it is difficult to establish specific standards at this time. This is particularly true of abrasive cleaning methods because their inherent potential for causing damage is multiplied by the following factors:

- the type and condition of the material being cleaned
- the size and sharpness of the grit particles or the mechanical equipment

- the pressure with which the abrasive grit or equipment is applied to the building surface
- the skill and care of the operator, and
- the constancy of the pressure on all surfaces during the cleaning process.
-

Pressure: The damaging effects of most of the variable factors involved in abrasive cleaning are self evident. However, the matter of pressure requires further explanation. In cleaning specifications, pressure is generally abbreviated as "psi" (pounds per square inch), which technically refers to the "tip" pressure, or the amount of pressure at the nozzle of the blasting apparatus. Sometimes "psig," or pressure at the gauge (which may be many feet away, at the other end of the hose), is used in place of "psi." These terms are often incorrectly used interchangeably. Despite the apparent care taken by most architects and building cleaning contractors to prepare specifications for pressure cleaning which will not cause harm to the delicate fabric of a historic building, it is very difficult to ensure that the same amount of pressure is applied to all parts of the building. For example, if the operator of the pressure equipment stands on the ground while cleaning a two-story structure, the amount of force reaching the first story will be greater than that hitting the second story, even if the operator stands on scaffolding or in a cherry picker, because of the "line drop" in the distance from the pressure source to the nozzle. Although technically it may be possible to prepare cleaning specifications with tight controls that would eliminate all but a small margin of error, it may not be easy to find professional cleaning firms willing to work under such restrictive conditions. The fact is that many professional building cleaning firms do not really understand the extreme delicacy of historic building fabric, and how it differs from modern construction materials. Consequently, they may accept building cleaning projects for which they have no experience. The amount of pressure used in any kind of cleaning treatment which involves pressure, whether it is dry or wet grit, chemicals or just plain water, is crucial to the outcome of the cleaning project. Unfortunately, no standards have been established for determining the correct pressure for cleaning each of the many historic building materials which would not cause harm. The considerable discrepancy between the way the building cleaning industry and architectural conservators define "high" and "low" pressure cleaning plays a significant role in the difficulty of creating standards.

Non-historic/Industrial: A representative of the building cleaning industry might consider "high" pressure water cleaning to be anything over 5,000 psi, or even as high as 10,000 to 15,000 psi! Water under this much pressure may be necessary to clean industrial structures or machinery, but would destroy most historic building materials. Industrial chemical cleaning commonly utilizes pressures between 1,000 and 2,500 psi.

Historic: By contrast, conscientious dry or wet abrasive cleaning of a historic structure would be conducted within the range of 20 to 100 psi at a range of 3 to 12 inches. Cleaning at this low pressure requires the use of a very fine 00 or 0 mesh grit forced through a nozzle with a 1/4-inch opening. A similar, even more delicate method being adopted by architectural conservators uses a micro-abrasive grit on small, hard-to-clean areas of carved, cut or molded ornament on a building facade. Originally developed by museum conservators for cleaning sculpture, this technique may employ glass beads, micro-balloons, or another type of micro-abrasive gently powered at approximately 40 psi by a very small, almost pencil-like pressure instrument. Although a slightly larger pressure instrument may be used on historic buildings, this technique still has limited practical applicability on a large scale building cleaning project because of the cost and the relatively few technicians competent to handle the task. In general, architectural conservators have determined that only through very controlled conditions can most historic building material be abrasively cleaned of soil or paint without measurable damage to the surface or profile of the substrate. Yet some professional cleaning companies which specialize in cleaning historic masonry buildings use chemicals and water at a pressure of approximately 1,500 psi, while other cleaning firms recommend lower pressures ranging from 200 to 800 psi for a similar project. An architectural conservator might decide, after testing, that some historic structures could be cleaned properly using a moderate pressure (200-600 psi), or even a high pressure (600-1800 psi) water rinse. However, cleaning historic buildings under such high pressure should be considered an exception rather than the rule, and would require *very careful* testing and supervision to assure that the historic surface materials could withstand the pressure without gouging, pitting or loosening. These differences in the amount of pressure used by commercial or industrial building cleaners and architectural conservators point to one of the main problems in using abrasive means to clean historic buildings: misunderstanding of the potentially fragile nature of historic building materials. There is no one cleaning formula or pressure suitable for all situations. Decisions regarding the proper cleaning process for historic structures can be made only after careful analysis of the building fabric, and testing.

How Building Materials React to Abrasive Cleaning

Brick and Architectural Terra-cotta: Abrasive blasting does not affect all building materials to the same degree. Such techniques quite logically cause greater damage to softer and more porous materials, such as brick or architectural terra-cotta. When these materials are cleaned abrasively, the hard, outer layer (closest to the heat of the kiln) is eroded, leaving the soft, inner core exposed and susceptible to accelerated weathering. Glazed architectural terra-cotta and ceramic veneer have a baked on glaze which is also easily damaged by abrasive cleaning. Glazed architectural terra-cotta was designed for easy maintenance, and generally can be cleaned using detergent and water; but chemicals or steam may be needed to remove more persistent stains. Large areas of brick or architectural terra-cotta which have been painted are best left painted, or repainted if necessary.

Plaster and Stucco: Plaster and stucco are types of masonry finish materials that are softer than brick or terra-cotta; if treated abrasively these materials will simply disintegrate. Indeed, when plaster or stucco is treated abrasively it is usually with the intention of removing the plaster or stucco from whatever base material or substrate it is covering. Obviously, such abrasive techniques should not be applied to clean sound plaster or stuccoed walls, or decorative plaster wall surfaces.

Building Stones: Building stones are cut from the three main categories of natural rock: dense, igneous rock such as granite; sandy, sedimentary rock such as limestone or sandstone; and crystalline, metamorphic rock such as marble. As opposed to kiln-dried masonry materials such as brick and architectural terra-cotta, building stones are generally homogeneous in character at the time of a building's construction. However, as the stone is exposed to weathering and environmental pollutants, the surface may become friable, or may develop a protective skin or patina. These outer surfaces are very susceptible to damage by abrasive or improper chemical cleaning. Building stones are frequently cut into ashlar blocks or "dressed" with tool marks that give the building surface a specific texture and contribute to its historic character as much as ornately carved decorative stonework. Such detailing is easily damaged by abrasive cleaning techniques; the pattern of tooling or cutting is erased, and the crisp lines of moldings or carving are worn or pitted. Occasionally, it may be possible to clean small areas of rough-cut granite, limestone or sandstone having a heavy dirt encrustation by using the "wet grit" method, whereby a small amount of abrasive material is injected into a controlled, pressurized water stream. However, this technique requires very careful supervision in order to prevent damage to the stone. Polished or honed marble or granite should never be treated abrasively, as the abrasion would remove the finish in much the way glass would be etched or "frosted" by such a process. It is generally preferable to underclean, as too strong a cleaning procedure will erode the stone, exposing a new and increased surface area to collect atmospheric moisture and dirt. Removing paint, stains or graffiti from most types of stone may be accomplished by a chemical treatment carefully selected to best handle the removal of the particular type of paint or stain without damaging the stone. (See section on the "Gentlest Means Possible.")

Wood: Most types of wood used for buildings are soft, fibrous and porous, and are particularly susceptible to damage by abrasive cleaning. Because the summer wood between the lines of the grain is softer than the grain itself, it will be worn away by abrasive blasting or power tools, leaving an uneven surface with the grain raised and often frayed or "fuzzy." Once this has occurred, it is almost impossible to achieve a smooth surface again except by extensive hand sanding, which is expensive and will quickly negate any costs saved earlier by sandblasting. Such harsh cleaning treatment also obliterates historic tool marks, fine carving and detailing, which precludes its use on any interior or exterior woodwork which has been hand planed, milled or carved.

Metals: Like stone, metals are another group of building materials which vary considerably in hardness and durability. Softer metals which are used architecturally, such as tin, zinc, lead, copper or aluminum, generally should not be cleaned abrasively as the process deforms and destroys the original surface texture and appearance, as well as the acquired patina. Much applied architectural metal work used on historic buildings--tin, zinc, lead and copper--is often quite thin and soft, and therefore susceptible to denting and pitting. Galvanized sheet metal is especially vulnerable, as abrasive treatment would wear away the protective galvanized layer. In the late 19th and early 20th centuries, these metals were often cut, pressed or otherwise shaped from sheets of metal into a wide variety of practical uses such as roofs, gutters and flashing, and facade ornamentation such as cornices, friezes, dormers, panels, cupolas, oriel windows, etc. The architecture of the 1920s and 1930s made use of metals such as chrome, nickel alloys, aluminum and stainless steel in decorative exterior panels, window frames, and

doorways. Harsh abrasive blasting would destroy the original surface finish of most of these metals, and would increase the possibility of corrosion. However, conservation specialists are now employing a sensitive technique of glass bead peening to clean some of the harder metals, in particular large bronze outdoor sculpture. Very fine (75125 micron) glass beads are used at a low pressure of 60 to 80 psi. Because these glass beads are completely spherical, there are no sharp edges to cut the surface of the metal. After cleaning, these statues undergo a lengthy process of polishing. Coatings are applied which protect the surface from corrosion, but they must be renewed every 3 to 5 years. A similarly delicate cleaning technique employing glass beads has been used in Europe to clean historic masonry structures without causing damage. But at this time the process has not been tested sufficiently in the United States to recommend it as a building conservation measure. Sometimes a very fine smooth sand is used at a low pressure to clean or remove paint and corrosion from copper flashing and other metal building components. Restoration architects recently found that a mixture of crushed walnut shells and copper slag at a pressure of approximately 200 psi was the only way to remove corrosion successfully from a mid-19th century terne-coated iron roof. Metal cleaned in this manner must be painted immediately to prevent rapid recurrence of corrosion. It is thought that these methods "work harden" the surface by compressing the outer layer, and actually may be good for the surface of the metal. But the extremely complex nature and the time required by such processes make it very expensive and impractical for large-scale use at this time. Cast and wrought iron architectural elements may be gently sandblasted or abrasively cleaned using a wire brush to remove layers of paint, rust and corrosion. Sandblasting was, in fact, developed originally as an efficient maintenance procedure for engineering and industrial structures and heavy machinery--iron and steel bridges, machine tool frames, engine frames, and railroad rolling stock--in order to clean and prepare them for repainting. Because iron is hard, its surface, which is naturally somewhat uneven, will not be noticeably damaged by controlled abrasion. Such treatment will, however, result in a small amount of pitting. But this slight abrasion creates a good surface for paint, since the iron must he repainted immediately to prevent corrosion. Any abrasive cleaning of metal building components will also remove the caulking from joints and around other openings. Such areas must be recaulked quickly to prevent moisture from entering and rusting the metal, or causing deterioration of other building fabric inside the structure.

When is Abrasive Cleaning Permissible?

For the most part, abrasive cleaning is destructive to historic building materials. A limited number of special cases have been explained when it may be appropriate, if supervised by a skilled conservator, to use a delicate abrasive technique on some historic building materials. The type of "wet grit" cleaning which involves a small amount of grit injected into a stream of low pressure water may be used on small areas of stone masonry (i.e., rough cut limestone, sandstone or unpolished granite), where milder cleaning methods have not been totally successful in removing harmful deposits of dirt and pollutants. Such areas may include stone window sills, the tops of cornices or column capitals, or other detailed areas of the facade. This is still an abrasive technique, and without proper caution in handling, it can be *just as harmful to the building surface as any other abrasive cleaning method*. Thus, the decision to use this type of "wet grit" process should be made only after consultation with an experienced building conservator. *Remember that it is very time consuming and expensive to use any abrasive technique on a historic building in such a manner that it does not cause harm to the often fragile and friable building materials*. At this time, and only under certain circumstances, abrasive cleaning methods may he used in the rehabilitation of interior spaces of warehouse or industrial buildings for contemporary uses. Interior spaces of factories or warehouse structures in which the masonry or plaster surfaces do not have significant design, detailing, tooling or finish, and in which wooden architectural features are not finished, molded, beaded or worked by hand, may be cleaned abrasively in order to remove layers of paint and industrial discolorations such as smoke, soot, etc. It is expected after such treatment that brick surfaces will be rough and pitted, and wood will be somewhat frayed or "fuzzy" with raised wood grain. These nonsignificant surfaces will be damaged and have a roughened texture, but because they are interior elements, they will not be subject to further deterioration caused by weathering.

Historic Interiors That Should Not Be Cleaned Abrasively

Those instances (generally industrial and some commercial properties), when it may be acceptable to use an abrasive treatment on the interior of historic structures have been described. But for the majority of historic buildings, the Secretary of the Interior's *Guidelines for Rehabilitation* do not recommend "changing the texture of exposed wooden architectural features (including structural members) and masonry surfaces through sandblasting or use of other abrasive techniques to remove paint, discolorations and plaster. Thus, it is not acceptable to clean abrasively interiors of historic residential

and commercial properties which have *finished* interior spaces featuring milled woodwork such as doors, window and door moldings, wainscoting, stair balustrades and mantelpieces. Even the most modest historic house interior, although it may not feature elaborate detailing, contains plaster and woodwork that is architecturally significant to the original design and function of the house. Abrasive cleaning of such an interior would be destructive to the historic integrity of the building. Abrasive cleaning is also impractical. Rough surfaces of abrasively cleaned wooden elements are hard to keep clean. It is also difficult to seal, paint or maintain these surfaces which can be splintery and a problem to the building's occupants. The force of abrasive blasting may cause grit particles to lodge in cracks of wooden elements, which will be a nuisance as the grit is loosened by vibrations and gradually sifts out. Removal of plaster will reduce the thermal and insulating value of the walls. Interior brick is usually softer than exterior brick, and generally of a poorer quality. Removing surface plaster from such brick by abrasive means often exposes gaping mortar joints and mismatched or repaired brickwork which was never intended to show. The resulting bare brick wall may require repointing, often difficult to match. It also may be necessary to apply a transparent surface coating (or sealer) in order to prevent the mortar and brick from "dusting." However. a sealer may not only change the color of the brick, but may also compound any existing moisture problems by restricting the normal evaporation of water vapor from the masonry surface.

"Gentlest Means Possible" There are alternative means of removing dirt, stains and paint from historic building surfaces that can be recommended as more efficient and less destructive than abrasive techniques. The "gentlest means possible" of removing dirt from a building surface can be achieved by using a low-pressure water wash, scrubbing areas of more persistent grime with a natural bristle (never metal) brush. Steam cleaning can also be used effectively to clean some historic building fabric. Low-pressure water or steam will soften the dirt and cause the deposits to rise to the surface, where they can be washed away. A third cleaning technique which may be recommended to remove dirt, as well as stains, graffiti or paint, involves the use of commercially available chemical cleaners or paint removers, which, when applied to masonry, loosen or dissolve the dirt or stains. These cleaning agents may be used in combination with water or steam, followed by a clear water wash to remove the residue of dirt and the chemical cleaners from the masonry. A natural bristle brush may also facilitate this type of chemically assisted cleaning, particularly in areas of heavy dirt deposits or stains, and a wooden scraper can be useful in removing thick encrustations of soot. A limewash or absorbent talc, whiting or clay poultice with a solvent can be used effectively to draw out salts or stains from the surface of the selected areas of a building facade. It is almost impossible to remove paint from masonry surfaces without causing some damage to the masonry, and it is best to leave the surfaces as they are or repaint them if necessary. Some physicists are experimenting with the use of pulsed laser beams and xenon flash lamps for cleaning historic masonry surfaces. At this time it is a slow, expensive cleaning method, but its initial success indicates that it may have an increasingly important role in the future. There are many chemical paint removers which, when applied to painted wood, soften and dissolve the paint so that it can be scraped off by hand. Peeling paint can be removed from wood by hand scraping and sanding. Particularly thick layers of paint may be softened with a heat gun or heat plate, providing appropriate precautions are taken, and the paint film scraped off by hand. Too much heat applied to the same spot can burn the wood, and the fumes caused by burning paint are dangerous to inhale, and can he explosive. Furthermore, the hot air from heat guns can start fires in the building cavity. Thus, adequate ventilation is important when using a heat gun or heat plate, as well as when using a chemical stripper. A torch or open flame should never he used.

Preparations for Cleaning: It cannot be overemphasized that all of these cleaning methods must be approached with caution. When using any of these procedures which involve water or other liquid cleaning agents on masonry, it is imperative that all openings be tightly covered, and all cracks or joints be well pointed in order to avoid the danger of water penetrating the building's facade, a circumstance which might result in serious moisture related problems such as efflorescence and/or subflorescence. Any time water is used on masonry as a cleaning agent, either in its pure state or in combination with chemical cleaners, it is very important that the work be done in warm weather when there is no danger of frost for several months. Otherwise water which has penetrated the masonry may freeze, eventually causing the surface of the building to crack and spall, which may create another conservation problem more serious to the health of the building than dirt.
Each kind of masonry has a unique composition and reacts differently with various chemical cleaning substances. Water and/or chemicals may interact with minerals in stone and cause new types of stains to leach out to the surface immediately, or more gradually in a delayed reaction. What may be a safe

and effective cleaner for certain stain on one type of stone, may leave unattractive discolorations on another stone, or totally dissolve a third type.

Testing: Cleaning historic building materials, particularly masonry, is a technically complex subject, and thus, should never be done without expert consultation and testing. No cleaning project should be undertaken without first applying the intended cleaning agent to a representative test patch area in an inconspicuous location on the building surface. The test patch or patches should be allowed to weather for a period of time, preferably through a complete seasonal cycle, in order to determine that the cleaned area will not he adversely affected by wet or freezing weather or any by-products of the cleaning process.

Mitigating the Effects of Abrasive Cleaning

There are certain restoration measures which can be adopted to help preserve a historic building exterior which has been damaged by abrasive methods. Wood that has been sandblasted will exhibit a frayed or "fuzzed" surface, or a harder wood will have an exaggerated raised grain. The only way to remove this rough surface or to smooth the grain is by laborious sanding. Sandblasted wood, unless it has been extensively sanded, serves as a dustcatcher, will weather faster, and will present a continuing and ever worsening maintenance problem. Such wood, after sanding, should be painted or given a clear surface coating to protect the wood, and allow for somewhat easier maintenance.

There are few successful preservative treatments that may be applied to grit-blasted exterior masonry. Harder, denser stone may have suffered only a loss of crisp edges or tool marks, or other indications of craft technique. If the stone has a compact and uniform composition, it should continue to weather with little additional deterioration. But some types of sandstone, marble and limestone will weather at an accelerated rate once their protective "quarry crust" or patina has been removed.

Softer types of masonry, particularly brick and architectural terra-cotta, are the most likely to require some remedial treatment if they have been abrasively cleaned. Old brick, being essentially a soft, baked clay product, is greatly susceptible to increased deterioration when its hard, outer skin is removed through abrasive techniques. This problem can be minimized by painting the brick. An alternative is to treat it with a clear sealer or surface coating but this will give the masonry a glossy, or shiny look. It is usually preferable to paint the brick rather than to apply a transparent sealer since sealers reduce the transpiration of moisture, allowing salts to crystallize as subflorescence that eventually spalls the brick. If a brick surface has been so extensively damaged by abrasive cleaning and weathering that spalling has already begun, it may be necessary to cover the walls with stucco, if it will adhere.

Of course, the application of paint, a clear surface coating (sealer), or stucco to deteriorating masonry means that the historical appearance will be sacrificed in an attempt to conserve the historic building materials. However, the original color and texture will have been changed already by the abrasive treatment. At this point it is more important to try to preserve the brick, and there is little choice but to protect it from "dusting" or spalling too rapidly. As a last resort, in the case of severely spalling brick, there may be no option but to replace the brick--a difficult, expensive (particularly if custom-made reproduction brick is used), and lengthy process. As described earlier, sandblasted interior brick work, while not subject to change of weather, may require the application of a transparent surface coating or painting as a maintenance procedure to contain loose mortar and brick dust. (See Preservation Briefs No. 1 for a more thorough discussion of coatings.) Metals, other than cast or wrought iron, that have been pitted and dented by harsh abrasive blasting usually cannot be smoothed out. Although fillers may be satisfactory for smoothing a painted surface, exposed metal that has been damaged usually will have to be replaced.

Summary

Sandblasting or other abrasive methods of cleaning or paint removal are by their nature destructive to historic building materials and should not be used on historic buildings except in a few well-monitored instances. There are exceptions when certain types of abrasive cleaning may be permissible, but only if conducted by a trained conservator, and if cleaning is necessary for the preservation of the historic structure. There is no one formula that will be suitable for cleaning all historic building surfaces. Although there are many commercial cleaning products and methods available, it is impossible to state definitively which of these will be the most effective without causing harm to the building fabric. It is often difficult to identify ingredients or their proportions contained in cleaning products; consequently it is hard to predict how a product will react to the building materials to be cleaned. Similar uncertainties affect the outcome of other cleaning methods as they are applied to historic building materials. Further advances in understanding the complex nature of the many variables of the cleaning techniques may

someday provide a better and simpler solution to the problems. But until that time, the process of cleaning historic buildings must be approached with caution through trial and error.
It is important to remember that historic building materials are neither indestructible, nor are they renewable. They must be treated in a responsible manner, which may mean little or no cleaning at all if they are to be preserved for future generations to enjoy. If it is in the best interest of the building to clean it, then it should be done "using the gentlest means possible."

PRESERVATION BRIEFS

7

The Preservation of Historic Glazed Architectural Terra-Cotta

de Teel Patterson Tiller

- What is Terra-Cotta?
- Types of Terra-Cotta
- Characteristics of Glazed Architectural Terra-Cotta
- Common Deterioration Problems
- Deterioration Inspection and Analysis
- Maintenance, Repair and Replacement
- Summary and References
- Reading List
- Download the PDF

Glazed architectural terra-cotta was significant in the development of important architectural idioms in this country—specifically, the "Chicago School," the High Rise and the Historic or Beaux Arts styles. In fact, glazed architectural terra-cotta is one of the most prevalent masonry building materials found in the urban environment today. Popular between the late 19th century and the 1930s, glazed architectural terra-cotta offered a modular, varied and relatively inexpensive approach to wall and floor construction. It was particularly adaptable to vigorous and rich ornamental detailing. However, with changing vogues in materials and architectural styles and rising production costs, glazed architectural terra-cotta fell into disfavor and disuse by the mid 20th century.

Today, information on the maintenance, rehabilitation and replacement of glazed architectural terra-cotta is limited, as are sources of new glazed architectural terra-cotta. This report, then, will discuss some of the major deterioration problems that commonly occur in historic glazed architectural terra-cotta, methods of determining the extent of that deterioration and recommendations for the maintenance, repair and replacement of the deteriorated historic material. What is Terra-Cotta?

What is Terra-Cotta? return to top ▲

Generically, the broadest definition of terra-cotta refers to a high grade of weathered or aged clay which, when mixed with sand or with pulverized fired clay, can be molded and fired at high temperatures to a hardness and compactness not obtainable with brick. Simply put, terra-cotta is an enriched molded clay brick or block. The word terra-cotta is derived from the Latin word terra-cotta—literally, "cooked earth." terra-cotta clays vary widely in color according to geography and types, ranging from red and brown to white.

Terra-cotta was usually hollow cast in blocks which were open to the back, like boxes, with internal compartment-like stiffeners called webbing. Webbing substantially strengthened the load-bearing capacity of the hollow terra-cotta block without greatly increasing its weight.

Terra-cotta blocks were often finished with a glaze; that is, a slip glaze (clay wash) or an aqueous solution of metal salts was brushed or sprayed on the air-dried block before firing. Glazing changed the color, imitated different finishes, and produced a relatively impervious surface on the weather face of the final product. The glaze on the terra-cotta unit possessed excellent weathering properties when properly maintained. It had rich color and provided a hard surface that was not easily chipped off. Glazing offered unlimited and fade-resistant colors to the designer. Even today, few building materials can match the glazes on terra-cotta for the range and, most importantly, the durability of colors.

Types of Terra-Cotta return to top ▲

Historically there are four types or categories of terra-cotta which have enjoyed wide use in the history of the American building arts: 1) brownstone, 2) fireproof construction, 3) ceramic veneer, and 4) glazed architectural.

Brownstone terra-cotta is the variety of this masonry material used earliest in American buildings (mid to late 19th century). The brownstone type is a dark red or brown block either glazed (usually a slip glaze) or unglazed. It was hollow cast and was generally used in conjunction with other masonry in imitation of sandstone, brick or real brownstone. It is often found in the architecture of Richard Upjohn, James Renwick, H. H. Richardson and is associated with the Gothic and Romanesque Revival movements through such ornamental detailing as moldings, finials and capitals.

Fireproof construction terra-cotta was extensively developed as a direct result of the growth of the High Rise building in America. Inexpensive, lightweight and fireproof, these rough-finished hollow building blocks were ideally suited to span the I-beam members in floor, wall and ceiling construction. Certain varieties are still in production today, although fireproof construction terra-cotta is no longer widely employed in the building industry.

Ceramic veneer was developed during the 1930s and is still used extensively in building construction today. Unlike traditional architectural terra-cotta, ceramic veneer is not hollow cast, but is as its name implies: a veneer of glazed ceramic tile which is ribbed on the back in much the same fashion as bathroom tile. Ceramic veneer is frequently attached to a grid of metal ties which has been anchored to the building.



Glazed architectural terra-cotta was a practical and highly decorative building material. Photo: NPS files.

Glazed architectural terra-cotta was the most complex development of terra-cotta as a masonry building material in this country. The hollow units were hand cast in molds or carved in clay and heavily glazed (often in imitation of stone) and fired. Sometimes called "architectural ceramics," glazed architectural terra-cotta was developed and refined throughout the first third of the 20th century and has been closely associated with the architecture of Cass Gilbert, Louis Sullivan, and Daniel H. Burnham, among others. Significant examples in this country include the Woolworth Building (1913) in New York City and the Wrigley Building (1921) in Chicago.

Late 19th and early 20th century advertising promoted the durable, impervious and adaptable nature of glazed architectural terra-cotta. It provided for crisp, vigorous modeling of architectural details as the molds were cast directly from clay prototypes without loss of refinement. Glazed architectural terra-cotta could accommodate subtle nuances of modeling, texture and color. Compared to stone, it was easier to handle, quickly set and more affordable to use. Thought to be fireproof and waterproof, it was readily adaptable to structures of almost any height. The cost of molding the clay, glazing and firing the blocks, when compared to carving stone, represented a considerable savings, especially when casts were used in a modular fashion—that is, repeated over and over again. Maintenance of the fired and glazed surface was easy; it never needed paint and periodic washings restored its original appearance.

With the passage of time, many of the phenomenal claims of the early proponents of glazed architectural terra-cotta have proven true. There are many examples throughout this country that attest to the durability and permanence of this material. Yet present-day deterioration of


other significant glazed architectural terra-cotta resources ultimately belie those claims. Why? Historically, the lack of foresight or understanding about the nature and limitations of the material has, in many instances, allowed serious deterioration problems to occur that are only now becoming apparent.

Characteristics of Glazed Architectural Terra-cotta as a Building Material return to top ▲

Glazed architectural terra-cotta has many material properties similar to brick or stone. It also has many material properties radically different from those traditional masonry materials. It is those differences which must be considered for a better understanding of some of the material characteristics of glazed architectural terra-cotta when it is used as a building material.

Difficult to Identify

Glazed architectural terra-cotta probably comprises one of the largest if not the largest constituent material in some of our urban environments today. However, the infinite varieties of glazing have hidden this fact from the casual observer. One of the attractive features of glazed architectural terra-cotta in its time was that it could be finished (glazed) in exact imitation of stone. In fact, many building owners and architects alike are often surprised to discover that what they presumed to be a granite or limestone building is glazed architectural terra-cotta instead.



Typical construction detail of glazed architectural terra-cotta ornament. Drawing: Detail, Architectural Terra Cotta, Charles E. White, Jr., 1920.

Two Separate Systems

Historically, glazed architectural terra-cotta has been used in association with two specific and very different types of building systems: as part of a traditional load-bearing masonry wall in buildings of modest height, and as a cladding material in High Rise construction. As cladding, glazed architectural terra-cotta often utilized an extensive metal anchoring system to attach it or to "hang it" onto a wall framing system or superstructure. In the first instance the anchoring was limited; in the second, the anchoring was often extensive and complex. Likewise, in the first instance, deterioration has generally been limited. However, where glazed architectural terra-cotta was used as cladding, particularly in high rise construction, present-day deterioration and failure are often severe.

Complexity of Deterioration

Deterioration is, by nature of the design, infinitely complex—particularly when glazed architectural terra-cotta has been used as a cladding material.

Deterioration creates a "domino"like breakdown of the whole system: glazed units, mortar, metal anchors, and masonry backfill. In no other masonry system is material failure potentially so complicated.

Poor Original Design

The root of deterioration in glazed architectural terra-cotta systems often lies in a misapplication of the material. Historically, glazed architectural terra-cotta was viewed as a highly waterproof system needing neither flashing, weep holes nor drips. This supposition, however, has proved to be untrue, as serious water-related failure was evident early in the life of many glazed architectural terra-cotta clad or detailed buildings.

Common Deterioration Problems

return to top ▲


No one case of deterioration in glazed architectural terra-cotta is ever identical to another owing to the infinite number of variations with the material: original manufacture, original installation inconsistencies, number of component parts, ongoing repairs or the various types and sources of deterioration. However, certain general statements may be made on the nature of glazed architectural terra-cotta deterioration.

Material failure can most commonly be attributed to water-related problems. However, less frequent though no less severe causes may include: faulty original craftsmanship, which is often

cited but hard to determine; stress-related deterioration; damage caused by later alterations and additions; or inappropriate repairs.

Water-related Deterioration

As with most building conservation and rehabilitation problems, water is a principal source of deterioration in glazed architectural terra-cotta. Terra-cotta systems are highly susceptible to such complex water-related deterioration problems as glaze crazing, glaze spalling and material loss, missing masonry units and deteriorated metal anchoring, among others.




Water and air-borne moisture entering the glazed architectural terra-cotta causes expansion of the porous clay body, increasing its volume. This upsets the "fit" of the glaze and makes its surface shatter, which is commonly called "crazing." Photo: NPS files.

Crazing, or the formation of small random cracks in the glaze, is a common form of water-related deterioration in glazed architectural terra-cotta. When the new terra-cotta unit first comes from the kiln after firing, it has shrunken (dried) to its smallest possible size. With the passage of time, however, it expands as it absorbs moisture from the air, a process which may continue for many years. The glaze then goes into tension because it has a lesser capacity for expansion than the porous tile body; it no longer "fits" the expanding unit onto which it was originally fired. If the strength of the glaze is exceeded, it will crack (craze). Crazing is a process not unlike the random hairline cracking on the surface of an old oil painting. Both may occur as a normal process in the aging of the material. Unless the cracks visibly extend into the porous tile body beneath the glaze, crazing should not be regarded as highly serious material failure. It does, however, tend to increase the water absorption capability of the glazed architectural terra-cotta unit.

Spalling, the partial loss of the masonry material itself, is, like crazing, caused by water and is usually a result not only of airborne water but more commonly of water trapped within the masonry system itself. Trapped water is often caused by poor water detailing in the original design, insufficient maintenance, rising damp or a leaking roof. In most cases, trapped water tends to migrate outward through masonry walls where it eventually evaporates. In glazed

architectural terra-cotta, the water is impeded in its journey by the relatively impervious glaze on the surface of the unit which acts as a water barrier. The water is stopped at the glaze until it builds up sufficient pressure (particularly in the presence of widely fluctuating temperatures) to pop off sections of the glaze (glaze spalling) or to cause the wholesale destruction of portions of the glazed architectural terra-cotta unit itself (material spalling).



Blistering of the glaze, like crazing, is the result of the increase in water in the porous clay body and the subsequent destruction of the glaze as a result of water migration and pressure. Glaze spalling may also be caused by deterioratoin of metal anchors behind the terra-cotta unit. Photo: NPS files.

Glaze spalling (left) may appear as small coin-size blisters where the glaze has ruptured and exposed the porous tile body beneath. This may occur as several spots on the surface or, in more advanced cases of deterioration, it may result in the wholesale disappearance of the glaze. Spalling of the glaze may also be symptomatic of deterioration (rusting) of the internal metal anchoring system which holds the terra-cotta units together and to the larger building structure. The increase in volume of the metal created by rusting creates increased internal pressures in the terra-cotta unit which, in turn, may spall the glaze, or in more extreme cases, cause material spalling.

Material spalling is a particularly severe situation. Not only is the visual integrity of the detailing impaired, but a large area of the porous underbody, webbing and metal anchoring is exposed to the destructive effects of further water entry and deterioration. Both glaze and material spalling must be dealt with as soon as possible. Missing units is a serious situation which particularly plagues architectural terra-cotta systems. Unlike brick or stone, damaged glazed architectural terra-cotta is exceedingly difficult to replace. New production is extremely limited. Missing units create gaps which increase the structural load on the remaining pieces and also permit water to

enter the system. Exposed or freestanding glazed architectural terra-cotta detailing (balusters, urns, parapet walls, etc.) are particularly susceptible to extensive loss of material.

These elements face the most severe vicissitudes of water and temperature-related deterioration in direct proportion to the extent of their exposure. The replacement of missing units should be a high priority work item in the rehabilitation of glazed architectural terra-cotta.

Deterioration of Metal Anchoring

Deteriorated anchoring systems are perhaps the most difficult form of glazed architectural terra-cotta deterioration to locate or diagnose. Often, the damage must be severe and irreparable before it is noticed on even the most intense "prima facie" examination. Water which enters the glazed architectural terra-cotta system can rust the anchoring system and substantially weaken or completely disintegrate those elements. Where water has been permitted to enter the system, some deterioration has more than likely taken place. Partial deterioration results in staining and material spalling. Total deterioration and the lack of any anchoring system may result in the loosening of the units themselves, threatening the architectural or structural integrity of the building. Recently, falling glazed architectural terra-cotta units have become a serious safety concern to many building owners and municipal governments. Early detection of failing anchoring systems is exceedingly difficult.

Deterioration of Mortar and Other Adjacent Materials

Deteriorated mortar has always been a key to the survival or failure of any masonry system. This is particularly true with glazed architectural terra-cotta. In recognition of the fragile nature of the system, the need for insuring a relatively dry internal system is important. Sound mortar is the "first line" of defense in terra-cotta systems. It is a maintenance "must." Deteriorated mortar joints are a singularly culpable source of water and, therefore, of deterioration. Mortar deterioration may result from improper original craftsmanship or air—and waterborne—pollution. More often, however, lack of ongoing maintenance is mainly responsible. Deteriorated mortar should not be overlooked as a major source of glazed architectural terra-cotta failure.

The deterioration of materials adjoining the glazed architectural terra-cotta (flashing, capping, roofing, caulking around windows and doors) bears significant responsibility in its deterioration. When these adjoining materials fail, largely as a result of lack of maintenance, water-related deterioration results. For instance, it is not uncommon to find wholesale terra-cotta spalling in close proximity to a window or doorway where the caulking has deteriorated.



The damage shown here is the result of direct live load on a mid-rise building. The steel frame has settled and shifted the weight onto the exterior terra-cotta cladding, resulting in rupturing of the material. Photo: NPS files.

Stress-related Deterioration

Stress-related deterioration of glazed architectural terra-cotta frequently occurs in high rise buildings. The evolution of stress relieving details (flexible joints, shelf angles, etc.) occurred late in the development of American building construction. Consequently, most early continuously clad High Rise buildings (c.1900-1920s) had little or no provisions for normal material and building movement in their original design.

The development of large stress-related cracks or wholesale material deterioration is often caused by unaccommodated building-frame shortening under load, thermal expansion and contraction of the facade and moisture expansion of the glazed architectural terra-cotta units themselves. Cracks running through many units or stories or large areas of material deterioration often indicate stress-related problems. This sort of deterioration, in turn, permits significant water entry into the terra-cotta system.

Inappropriate Repairs

Inappropriate repairs result because using new terra-cotta for replacement of deteriorated or missing glazed architectural terra-cotta has generally been impractical. Repairs, therefore, have traditionally been made in brick or cementitious build ups of numerous materials such as stucco or fiberglass. Some materials are appropriate temporary or permanent replacements, while others are not. (These issues are discussed at a later point in this report.) However, improper anchoring or bonding of the repair work or visual incompatibility of repairs have themselves, with the passage of time, become rehabilitation problems: replacement brick that is pulling free,

cement stucco that is cracking and spalling, or a cement or bituminous repairs that are not visually compatible with the original material.

Alteration Damage

Alteration damage has occurred as a result of the installation of such building additions as signs, screens, marquees or bird proofing. These installations often necessitated the boring of holes or cutting of the glazed architectural terra-cotta to anchor these additions to the building frame beneath. As the anchoring or caulking deteriorated, or as these elements were removed in subsequent renovation work, these holes have become significant sources of water-related damage to the glazed architectural terra-cotta system.

Deterioration Inspection and Analysis return to top ▲

Certain deterioration in glazed architectural terra-cotta may be on the building surface and patently obvious to the casual observer—crazing, spalling, deterioration of mortar joints. Other deterioration may be internal or within the masonry system and hard to determine—deterioration of anchoring, deterioration behind the glaze, crumbling of internal webbing. *Prima facie*, "first inspection," examination may indicate surface deterioration problems while not revealing others. This demonstrates one of the most frustrating aspects of dealing with deteriorated glazed architectural terra-cotta: that there are two systems or levels of deterioration, one which is visible and the other which is not.



Material spalling is the result of excessive expansion of the porous tile body caused by water and freezing temperatures. This is a serious condition, often difficult to repair. Photo: NPS files.

Material failure in glazed architectural terra-cotta is necessarily complex. For this reason, it is generally advised that the examination and repair of this material should be the responsibility of an experienced professional. Few restorationists have experience in the inspection, repair and

replacement of glazed architectural terra-cotta. This is certainly never the province of the amateur or the most well-intentioned but inexperienced architect or engineer.

There are some methods of internal and external inspection and analysis which are relatively simple to the trained professional. Other methods, however, are expensive, time consuming, and only in the experimental stage at this writing. These all generally preclude the use of anyone but an experienced professional.

Preliminary Cleaning

Before a terra-cotta building is analyzed for deterioration, it is often advisable, but not always necessary, to clean the surface of the material. This is particularly true when the material has been exposed to the vicissitudes of heavy urban pollution. While most building materials are cleaned for "cosmetic" purposes, the cleaning of glazed architectural terra-cotta for the purpose of inspection and analysis may be advised. Dirt on glazed architectural terra-cotta often hides a multitude of problems. It is only with cleaning that these problems become obvious. Recommended cleaning procedures are covered later in the report.

Methods of Inspection

Prima facie analysis is the unit by unit, firsthand, external inspection of the glazed architectural terra-cotta building surface. Special note of all visible surface deterioration (staining, crazing, spalling, cracking, etc.) should be made on elevation drawings. Binoculars are often used where cost, height, or inaccessibility prevent easy inspection. However, much deterioration may go unnoticed unless scaffolding or window-washing apparatus is used in a true "hands on" inspection of each unit of the facade.

Tapping, a somewhat inexact method of detection of internal deterioration is, nevertheless, the most reliable inspection procedure presently available. Quite simply, tapping is the striking of each unit with a wooden mallet. When struck, an undamaged glazed architectural terra-cotta unit gives a pronounced ring, indicating its sound internal condition. Conversely, deteriorated units (i.e., units which are failing internally) produce a flat, hollow sound. Metal hammers are never to be used, as they may damage the glazed surface of the unit. Extensive experience is the best teacher with this inspection method.

Infrared scanning is only in the experimental stage at this time, but its use seems to hold great promise in locating deteriorated internal material in terra-cotta. All materials emit heat—heat which can be measured in terms of infrared light. While infrared light cannot be seen by the human eye, it can be measured by infrared scanning. Infrared photography, a kind of infrared scanning, has been of particular use in detecting sources of heat loss in buildings in recent years. Broken or loose internal terra-cotta pieces have a less firm attachment to the surrounding firm or

attached pieces and, therefore, have different thermal properties, i.e., temperatures. These temperature differences become evident on the infrared scan and may serve as a fair indication of internal material deterioration in terra-cotta.

Sonic testing has been successfully used for some time to detect internal cracking of concrete members. In the hands of an experienced operator, there are conditions where it can detect internal failure in glazed architectural terra-cotta. Sonic testing registers the internal configuration of materials by penetrating the material with sound waves and reading the patterns that "bounce back" from the originating source of the sound. Readings at variance with those from undeteriorated material might indicate collapsed webbing or pools of water in the interior of the terra-cotta unit.

Metal detection is a non-destructive and generally useful way of locating the position of internal metal anchoring. Metal detectors indicate the presence of metals by electromagnetic impulses. These impulses are transmitted onto an oscilloscope where they may he seen or they are converted to sound patterns which may be heard by the operator. Original drawings are eminently useful in predicting where internal metal anchoring should be. Metal detectors can confirm that indeed they are still there. Without original drawings, the contractor or architect can still locate the metal anchoring, however. No reading where an anchor would be expected could indicate a missing anchor or one that has seriously deteriorated. The information produced by metal detection is, at best, only rough. However, it is the most viable way of locating the internal metal anchoring without physically removing, thus irreparably damaging, the glazed architectural terra-cotta units themselves.

Laboratory analysis may be carried out on samples of removed original material to find glaze absorption, permeability or glaze adhesion, or to evaluate material for porosity. These tests are useful in determining the present material characteristics of the historic glazed architectural terra-cotta and how they may be expected to perform in the future.

Maintenance, Repair and Replacement return to top ▲



Exposed or freestanding terra-cotta detailing (parapets, urns, balusters, etc.) have traditionally been subjected to the most severe vicissitudes of deterioration as a result of freezing temperatures and water. Photo: NPS files.

Deterioration in glazed architectural terra-cotta is, by definition, insidious in that the outward signs of decay do not always indicate the more serious problems within. It is, therefore, of paramount importance that the repair and replacement of deteriorated glazed architectural terra-cotta not be undertaken unless the causes of that deterioration have been determined and repaired. As mentioned before, one of the primary agents of deterioration in glazed architectural terra-cotta is water. Therefore, water-related damage can be repaired only when the sources of that water have been eliminated. Repointing, caulking and replacement of missing masonry pieces are also of primary concern. Where detailing to conduct water in the original design has been insufficient, the installation of new flashing or weep holes might be considered.

Where stress-related or structural problems have caused the deterioration of glazed architectural terra-cotta, the services of a structural engineer should be sought to mitigate these problems. This may include the installation of relieving joints, shelf angles or flexible joints. In any case, stress-related and structural deterioration, like water-related deterioration, must be stopped before effective consolidation or replacement efforts may begin.

Cleaning

The successful cleaning of glazed architectural terra-cotta removes excessive soil from the glazed surface without damaging the masonry unit itself. Of the many cleaning materials available, the most widely recommended are water, detergent, and a natural or nylon bristle brush. More stubborn pollution or fire-related dirt or bird droppings can be cleaned with steam or weak solutions of muriatic or oxalic acid.

A note of caution: Any acids, when used in strong enough solutions, may themselves deteriorate mortar and "liberate" salts within the masonry system, producing a situation called efflorescence.

Commercial cleaning solutions may be appropriate but probably are not necessary when water and detergent will suffice. There are, however, certain cleaning techniques for glazed terra-cotta which are definitely not recommended and which would damage the surface of the material. These include: all abrasive cleaning measures (especially sandblasting), the use of strong acids, (particularly fluoride-based acids), high-pressure water cleaning and the use of metal bristle brushes. All of these techniques will irreparably harm the glaze in one fashion or another and subsequently expose the porous tile body to the damaging effects of water.

It is important to remember that glazed architectural terra-cotta was designed to be cleaned cheaply and easily. This, in fact, was one of its major assets and was much advertised in the selling of the material early in this century.

Waterproofing

The covering of crazed glazing with waterproof coatings is the subject of an ongoing controversy today. The question involves whether or not the micro-cracks conduct substantial amounts of water into the porous tile body. Tests indicate that the glaze on new unexposed terra-cotta is itself not completely waterproof. Some testing also indicates that most crazing on historic glazed terra-cotta does not substantially increase the flow of moisture into the porous tile body when compared to new material. Excessive and serious crazing is, however, an exception and the coating of those areas on a limited scale may be wholly appropriate.

In an effort to stem water-related deterioration, architects and building owners often erroneously attribute water-related damage to glaze crazing when the source of the deterioration is, in fact, elsewhere: deteriorated caulking, flashing, etc. The waterproof coating of glazed architectural terra-cotta walls may cause problems on its own. Outward migration of water vapor normally occurs through the mortar joints in these systems. The inadvertent sealing of these joints in the wholesale coating of the wall may exacerbate an already serious situation. Spalling of the glaze, mortar, or porous body will, more than likely, result.



A worker cleans out mortar joints in preparation for repointing the architectural terra-cotta Photo: NPS files.

Repointing

Repointing of mortar which is severely deteriorated or improperly or infrequently maintained is one of the most useful preservation activities that can be performed on historic glazed architectural terra-cotta buildings. Ongoing and cyclical repointing guarantees the long life of this material. Repointing should always be carried out with a mortar which has a compressive strength (measured in p.s.i.) lower than the adjacent masonry unit. Hard (Portland cement) or coarsely screened mortars may cause point loading and/or prevent the outward migration of the water through the mortar joints, both of which ultimately damage the terra-cotta unit. Repointing with waterproof caulking compounds or similar waterproof materials should never be undertaken because, like waterproof coatings, they impede the normal outward migration of moisture through the masonry joints. Moisture then may build sufficient pressure behind the waterproof caulk and the glaze on the terra-cotta to cause damage to the unit itself.

Repair of Glaze Spalling

Glaze spalling is also a highly culpable source of water-related deterioration in glazed architectural terra-cotta. It is important to coat or seal these blistered areas and to prevent further entry of water into the system by this route. All loose or friable material should be removed. This may be done easily by hand; chisels or similar small tools are most effective. The exposed material is then painted over. At this time, no permanently effective reglazing materials are available. However, there are several acrylic-based proprietary products and masonry paints which can be used effectively to protect these exposed areas, thus preventing the entry of water. These materials are effective for 5 to 7 years and can be reapplied. They also can be tinted to approximate closely the original glaze color.

Repair of Minor Material Spalling

Minor material spalling, where visual or cosmetic considerations are negligible, should be treated in a manner similar to glaze spalling damage. That is, areas where small portions of the body and glaze have spalled and which are far removed from close scrutiny (i.e., detailing on entablatures, upper story windows, etc.) are best remedied by painting with a masonry paint or an acrylic-based proprietary product. Units on which material spalling is easily observed (on the street level, door surrounds, etc.), and on which visual integrity is a consideration, may be better replaced. Patching is not appropriate. Stucco-like or cementitious buildups are difficult to form satisfactorily, safely and compatibly in situ to replace missing pieces of glazed architectural terra-cotta. Cementitious repairs never satisfactorily bond to the original material. The

differential expansion coefficients of the two materials (the repair and the original) preclude a safe, effective and long-term attachment.

Repair of Major Spalling

Glazed architectural terra-cotta units, which have spalled severely thereby losing much of their material and structural integrity in the wall, should be replaced. Partial in situ repair will not be long lasting and may, in fact, cause complicated restoration problems at a later date. Appropriate methods of replacement are discussed at a later point in this report.

Temporary Stabilization

Stabilization measures are necessary when deterioration is so severe as to create a situation where pieces of glazed architectural terra-cotta may fall from the building. This is a particular concern with greatly exposed detailing: cornices, balconies, balustrades, urns, columns, buttresses, etc. Restoration work on these pieces is expensive and often must be carried on over a period of time. Unstable terra-cotta pieces are often removed or destroyed in lieu of such measures. This is particularly true in areas of heavy traffic-related vibrations or in earthquake zones. There are, however, less severe measures which may be employed on a temporary basis. Substantial success has been achieved in securing unstable glazed architectural terra-cotta pieces with metal strapping and nylon net. While these measures should not be seen as permanent preservation solutions, they do offer temporary alternatives to the wanton destruction of significant glazed architectural terra-cotta detailing in the name of public safety and local code compliance.



This crack is being measured. Structural cracking, whether static (nonmoving) or dynamic (moving) should be caulked to prevent water entry into the glazed architectural terra-cotta system. Photo: NPS files.

Repair of Addition and Structural Damage

Holes, sign anchors, slots for channel steel, or structural cracking in the surface of glazed architectural terra-cotta cladding should be permanently sealed with a material that will expand with the normal dynamics of the surrounding material, yet effectively keep water out of the system. Any one of a number of commercially available waterproof caulking compounds would be appropriate for this work. Holes and static (non-moving) cracks may be caulked with butyl sealants or acrylic latex caulks. For dynamic (moving or active) cracks, the polysulfide caulks are most often used, although others may be safely employed. It is, however, important to remember that these waterproof caulking compounds are not viable repointing materials and should not be used as such.

Temporary Replacement

Temporary replacement measures should be implemented when missing units are scheduled to be replaced but work cannot be undertaken immediately. Lengthy delivery time, prorating of work or seasonal considerations may postpone replacement work. Severe deterioration should at least be ameliorated until work can begin. Temporary repointing, removal and saving of undamaged units to be reset later, or the temporary installation of brick infill to retard further deterioration might be considered.

Removing Earlier Repairs

Removing earlier repairs may be necessary when the work has either deteriorated or has become visually incompatible. Cementitious stucco, caulkings with black bituminous compounds or brick repair work may become structurally or visually unstable or incompatible and should be removed and properly rehabilitated.

Replacement of Glazed Architectural Terra-cotta

Replacement of severely spalled, damaged, or missing glazed architectural terra-cotta elements is always difficult. Certainly, in-kind replacement is advisable, but it has a number of drawbacks. Stone, fiberglass, and precast concrete are also viable choices, but like in-kind replacement, also have their inherent problems.

Several notes on replacement: When replacing glazed architectural terra-cotta, all of the original deteriorated material should be completely removed. Half bricks or similar cosmetic replacement techniques are not advised.

- When possible and where applicable, replacement units should be anchored in a manner similar to the original. Both structural and visual

compatibility are major considerations when choosing replacement materials.

- Removing and re-anchoring damaged glazed architectural terra-cotta is an extremely difficult if not impossible task. The complexity of the interlocking system of masonry units, backfill, and metal anchoring system precludes the removal of the glazed architectural terra-cotta unit without destroying it.
- Re-anchoring deteriorated units is likewise impossible. Therefore, if the terra-cotta in question is loose, severely deteriorated, or its structural integrity in serious question, it is best removed and replaced.

In-kind replacement is possible today, but only on a limited basis. Most new glazed architectural terra-cotta is machine made, not hand made as the original. Thus, the porous tile body of the new material tends to be more uniform but less dense and often not as durable. The glaze on the new glazed architectural terra-cotta tends to be thinner than that on the older material and subsequently more brittle. Machine processing has also produced a glaze that is uniform in color as opposed to historic glazes which were slightly mottled and, therefore, richer. Visual compatibility is an important consideration when replacing in-kind.

Only a fairly limited inventory of in-kind pieces is presently available for replacement such as plain ashlar blocks and the simpler details such as cappings and sills. When deterioration severely damages the more ornate pieces (urns, cartouche work, balusters, etc.) either expensive hand casting or alternative materials must be sought. There is a tendency today to replace damaged ornamental work with simpler, cheaper and more readily available units. This decision cannot, however, be supported, as the removal of this work inevitably diminishes the character and integrity of the building. Another major consideration in choosing in-kind replacement is the question of delivery time, which is often quite lengthy. If new glazed architectural terra-cotta is chosen as a replacement material, the architect or building owner should plan far in advance.

Stone may be a suitable replacement material for damaged glazed architectural terra-cotta. Its durability makes it highly appropriate, although the increase in weight over the original hollow units may be of some concern. The fact that historic glazed architectural terra-cotta was glazed in imitation of stone, however, may make the choice of stone as a replacement material a fortuitous one. Metal anchoring may be accommodated easily in the carving. Cost, however, is the major drawback in stone replacement, particularly where rich detailing must be carved to match the original.

Fiberglass replacement is a viable alternative, particularly when rich and elaborate ornamentation has to be duplicated. Casting from original intact pieces can produce numerous

sharp copies of entablatures, moldings, balusters, voussoirs, etc. Anchoring is easily included in casting.

Significant drawbacks in using fiberglass replacement are color compatibility, fire code violations, and poor weathering and aging processes. The appropriate coloring of fiberglass is exceedingly difficult in many instances. Painting is often unsatisfactory, as it discolors at a rate different than that of the historic glazed original. While fiberglass casting is lighter than the original units and, therefore, of great interest in the rehabilitation of buildings in areas of high seismic activity, many fire code requirements cannot be met with the use of this material.

Precast concrete units show great promise in replacing glazed architectural terra-cotta at this writing. Precast concrete units can, like fiberglass, replicate nuances of detail in a modular fashion: they can also be cast hollow, use lightweight aggregate and be made to accommodate metal anchoring when necessary. Concrete can be colored or tinted to match the original material with excellent results. It is cost effective and once production is in process, precast concrete call be produced quickly and easily.

Experience shows that it is advisable to use a clear masonry coating on the weather face of the precast concrete units to guarantee the visual compatibility of the new unit, to prevent moisture absorption, to obtain the proper reflectivity in imitation of the original glaze and to prevent weathering of the unit itself. Precast concrete replacement units are presently enjoying great use in replicating historic glazed architectural terra-cotta and show promise for future rehabilitation programs.

Once the replacement material is selected (new glazed architectural terra-cotta. stone, precast concrete, or fiberglass), it must be reanchored into the masonry system. Original metal anchoring came in numerous designs, materials and coatings ranging from bituminous-coated iron to bronze. While most of these anchors are no longer available, they may be easily replicated in large quantities either in the original material when appropriate or out of more durable and available metals such as stainless steel.

Since the masonry backfill is already in place in the historic building, the new replacement unit with anchoring may simply be fitted into the existing backfill by boring a hole or slot for anchor and bedding the anchor and the unit itself in mortar. When replacing historic glazed architectural terra-cotta which originally employed metal anchoring, it is important to replace that anchoring when replacing the unit. Serious problems may result if anchoring is omitted in restoration, when it was used originally. It is erroneous to assume that mortar alone will be sufficient to hold these replacement pieces in place.

Summary and References return to top ▲

Today, many of this country's buildings are constructed of glazed architectural terra-cotta. However, many of these are in a state of serious deterioration and decay. Glazed architectural terra-cotta was, in many ways, the "wonder" material of the American building industry in the late 19th century and during the first decades of the 20th century. New technology and methods of rehabilitation now hold promise for the restoration and rehabilitation of these invaluable and significant resources. Restoration/rehabilitation work on glazed architectural terra-cotta is demanding and will not tolerate halfway measures. Today's preservation work should equal the spirit, attention to detail, pride in workmanship and care which characterized the craftsmanship associated with this widely used, historic masonry material.

Acknowledgements

This Preservation Brief was written by **de Teel Patterson Tiller**, Architectural Historian, Technical Preservation Services Division. Information for this publication was based in part upon interviews and consultation with Theodore H.M. Prudon, The Ehrenkrantz Group, P.C., New York, New York. Additional comments and information were provided by Si A. Bortz, Illinois Institute of Technology Research Institute, Chicago, Illinois, and Jerry G. Stockbridge, Wiss, Janney, Elstner, and Associates, Northbrook, Illinois.

This publication has been prepared pursuant to the National Historic Preservation Act of 1966, as amended, which directs the Secretary of the Interior to develop and make available information concerning historic properties. Technical Preservation Services (TPS), National Park Service prepares standards, guidelines, and other educational materials on responsible historic preservation treatments for a broad public.

June 1979

Reading List return to top ▲

"Recipes for Baked Earth." *Progressive Architecture* (November, 1977).

McIntyre, W.A. *Investigations into the Durability of Architectural Terra Cotta*. Special Report 12. London: Department of Scientific and Industrial Research, Building Research Station, 1929.

Prudon, Theodore H.M. "Architectural Terra-cotta: Analyzing the Deterioration Problems and Restoration Approaches." *Technology and Conservation*, Vol. 3 (Fall, 1978), pp. 30-38.

Prudon, Theodore H.M. *Terra Cotta as a Building Material*. A Bibliography. Ottawa, Ontario: Association for Preservation Technology, 1976.

SECTION 040120.63

BRICK MASONRY REPAIR

(Reference Preservation Briefs & Match Existing)

PART 1 - GENERAL

1.1 SUMMARY
A. Section includes repairing brick masonry, including replacing units.

1.2 UNIT PRICES
A. Work of this Section is affected by unit prices specified in Section 012200 "Unit Prices."

1.3 DEFINITIONS
A. Rebuilding (Setting) Mortar: Mortar used to set and anchor masonry in a structure, distinct from pointing mortar installed after masonry is set in place.

1.4 ACTION SUBMITTALS
A. Product Data: For each type of product.
B. Shop Drawings:
1. Include plans, elevations, sections, and locations of replacement masonry units on the structure.
2. Show provisions for expansion joints or other sealant joints.
C. Samples: For each exposed product and for each color and texture specified.

1.5 INFORMATIONAL SUBMITTALS
A. Quality-control program.

1.6 QUALITY ASSURANCE
A. Brick Masonry Repair Specialist Qualifications: Engage an experienced brick masonry repair firm to perform work of this Section. Firm shall have completed work similar in material, design, and extent to that indicated for this Project with a record of successful in-service performance. Experience in only installing masonry is insufficient experience for masonry repair work.
B. Quality-Control Program: Prepare a written quality-control program for this Project to systematically demonstrate the ability of personnel to properly follow methods and use materials and tools without damaging masonry. Include provisions for supervising performance and preventing damage.
C. Mockups: Prepare mockups of brick masonry repair to demonstrate aesthetic effects and to set quality standards for materials and execution and for fabrication and installation.
1. Masonry Repair: Prepare sample areas for each type of masonry repair work performed. If not otherwise indicated, size each mockup not smaller than two adjacent whole units or approximately 48 inches (1200 mm) in least dimension. Construct sample areas in locations in existing walls where directed by Architect unless otherwise indicated. Demonstrate quality of materials, workmanship, and blending with existing work.

PART 2 - PRODUCTS

2.1 MASONRY MATERIALS
A. Face Brick: **As required to complete brick masonry repair work.**

1. Brick Matching Existing: Units with colors, color variation within units, surface texture, size, and shape that match existing brickwork.
    a. Physical Properties: According to ASTM C 67.
    b. For existing brickwork that exhibits a range of colors or color variation within units, provide brick that proportionally matches that range and variation rather than brick that matches an individual color within that range.
2. Special Shapes:
    a. Provide molded, 100 percent solid shapes for applications where core holes or "frogs" could be exposed to view or weather when in final position and where shapes produced by sawing would result in sawed surfaces being exposed to view.
    b. Provide specially ground units, shaped to match patterns, for arches and where indicated.
    c. Mechanical chopping or breaking brick, or bonding pieces of brick together by adhesive, are unacceptable procedures for fabricating special shapes.

B. Building Brick: ASTM C 62, Grade SW where in contact with earth or Grade SW, MW, or NW for concealed backup; and of same vertical dimension as face brick, for masonry work concealed from view.

C.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C 150/C 150M, Type I or Type II, except Type III may be used for cold-weather construction; **white gray, or both required for color matching of mortar.**
1. Provide cement containing not more than 0.60 percent total alkali when tested according to ASTM C 114.

B. Hydrated Lime: ASTM C 207, Type S.

C. Masonry Cement: ASTM C 91/C 91M.

D. Mortar Cement: ASTM C 1329/C 1329M.

E. Mortar Sand: ASTM C 144.
1. Exposed Mortar: Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands if necessary to achieve suitable match.
2. Colored Mortar: Natural sand or ground marble, granite, or other sound stone of color necessary to produce required mortar color.

F. Mortar Pigments: ASTM C 979/C 979M, compounded for use in mortar mixes, and having a record of satisfactory performance in masonry mortars.

G. Water: Potable.

2.3 MANUFACTURED REPAIR MATERIALS

A. Brick Patching Compound: Factory-mixed cementitious product that is custom manufactured for patching brick masonry.
1. Use formulation that is vapor and water permeable (equal to or more than the masonry unit), exhibits low shrinkage, has lower modulus of elasticity than masonry units being repaired, and develops high bond strength to all types of masonry.
2. Formulate patching compound in colors and textures to match each masonry unit being patched.

2.4 ACCESSORY MATERIALS

A. Setting Buttons and Shims: Resilient plastic, nonstaining to masonry, sized to suit joint thicknesses and bed depths of masonry units, less the required depth of pointing materials unless removed before pointing.

B. Other Products: Select materials and methods of use based on the following, subject to approval of a mockup:
1. Previous effectiveness in performing the work involved.
2. Minimal possibility of damaging exposed surfaces.
3. Consistency of each application.
4. Uniformity of the resulting overall appearance.

5. Do not use products or tools that could leave residue on surfaces.

2.5 MORTAR MIXES

A. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

B. Colored Mortar: Produce mortar of color required by using specified ingredients. Do not alter specified proportions without Architect's approval.

1. Mortar Pigments: Where mortar pigments are indicated, do not add pigment exceeding 10 percent by weight of the cementitious or binder materials, except for carbon black which is limited to 2 percent.

C. Do not use admixtures in mortar unless otherwise indicated.

D. Mixes: Mix mortar materials in the following proportions:

1. Rebuilding (Setting) Mortar by Type: ASTM C 270, Proportion Specification, **Type N** unless otherwise indicated; with cementitious material limited to **portland cement and lime, masonry cement, or mortar cement**.

2. Pigmented, Colored Mortar: Add mortar pigments to produce exposed, setting (rebuilding) mortar of colors required.

PART 3 - EXECUTION

3.1 PROTECTION

A. Remove all items in the way, preventing proper review, required for scope of work and to be demolished; conduits, gutters, boxes, fans, door & windows, downspouts, brackets, clips, lights, etc. all affecting work adjacent to masonry. Store any items indicated to be used or re-installed, during masonry repair. Reinstall when repairs are complete.

1. Provide temporary rain drainage during work to direct water away from building.

3.2 BRICK REMOVAL AND REPLACEMENT

A. Remove Bricks at locations indicated, soft, damaged, deteriorated, and or spalled. Carefully remove entire units from joint to joint, without damaging surrounding masonry, in a manner that permits replacement with full-size units.

B. Support and protect remaining masonry that surrounds removal area.

C. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition.

D. Notify Architect of unforeseen detrimental conditions including voids, cracks, bulges, and loose units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items.

E. Remove in an undamaged condition as many whole bricks as possible.

1. Remove mortar, loose particles, and soil from brick by cleaning with hand chisels, brushes, and water.

2. Remove sealants by cutting close to brick with utility knife and cleaning with solvents.

F. Clean masonry surrounding removal areas by removing mortar, dust, and loose particles in preparation for brick replacement.

G. Install replacement brick into bonding and coursing pattern of existing brick. If cutting is required, use a motor-driven saw designed to cut masonry with clean, sharp, unchipped edges.

1. Maintain joint width for replacement units to match existing joints.

2. Use setting buttons or shims to set units accurately spaced with uniform joints.

H. Lay replacement brick with rebuilding (setting) mortar and with completely filled bed, head, and collar joints. Butter ends with enough mortar to fill head joints and shove into place. Wet both replacement and surrounding bricks that have ASTM C 67 initial rates of absorption (suction) of more than 30 g/30 sq. in. per min. (30 g/194 sq. cm per min.) Use wetting methods that ensure that units are nearly saturated but surface is dry when laid.

1. Tool exposed mortar joints in repaired areas to match joints of surrounding existing brickwork.
2. Rake out mortar used for laying brick before mortar sets according to Section 040120.64 "Brick Masonry Repointing." Point at same time as repointing of surrounding area.
3. When mortar is hard enough to support units, remove shims and other devices interfering with pointing of joints.

I. Curing: Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.
1. Hairline cracking within the mortar or mortar separation at edge of a joint is unacceptable. Completely remove such mortar and repoint.

3.3 MASONRY UNIT PATCHING

A. Patching Bricks:
1. Remove loose material from masonry surface. Carefully remove additional material so patch does not have feathered edges but has square or slightly undercut edges on area to be patched and is at least 1/4 inch (6 mm) thick, but not less than recommended in writing by patching compound manufacturer.
2. Mask adjacent mortar joint or rake out for repointing if patch extends to edge of masonry unit.
3. Mix patching compound in individual batches to match each unit being patched. Combine one or more colors of patching compound, as needed, to produce exact match.
4. Rinse surface to be patched and leave damp, but without standing water.
5. Brush-coat surfaces with slurry coat of patching compound according to manufacturer's written instructions.
6. Place patching compound in layers as recommended in writing by patching compound manufacturer, but not less than 1/4 inch (6 mm) or more than 2 inches (50 mm) thick. Roughen surface of each layer to provide a key for next layer.
7. Trowel, scrape, or carve surface of patch to match texture and surrounding surface plane or contour of masonry unit. Shape and finish surface before or after curing, as determined by testing, to best match existing masonry unit.
8. Keep each layer damp for 72 hours or until patching compound has set.

3.4 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water, applied by low pressure spray.
1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

END OF SECTION 040120.63

SECTION 040120.64

BRICK MASONRY REPOINTING

PART 1 - GENERAL

1.1 SUMMARY
A. Section includes repointing joints with mortar.

1.2 UNIT PRICES
A. N/A

1.3 PREINSTALLATION MEETINGS
A. Pre-installation Conference: Conduct conference at **Project site**.

1.4 ACTION SUBMITTALS
A. Product Data: For each type of product.
B. Samples: For each exposed product and for each color and texture specified.

1.5 INFORMATIONAL SUBMITTALS
A. Quality-control program.

1.6 QUALITY ASSURANCE
A. Brick Masonry Repointing Specialist Qualifications: Engage an experienced brick masonry repointing firm to perform work of this Section. Firm shall have completed work similar in material, design, and extent to that indicated for this Project with a record of successful in-service performance. Experience in only installing masonry is insufficient experience for masonry repointing work.
B. Quality-Control Program: Prepare a written quality-control program for this Project to systematically demonstrate the ability of personnel to properly follow methods and use materials and tools without damaging masonry. Include provisions for supervising performance and preventing damage.
C. Mockups: Prepare mockups of brick masonry repointing to demonstrate aesthetic effects and to set quality standards for materials and execution.
1. Repointing: Rake out joints in two separate areas, each approximately 36 inches (900 mm) high by 48 inches (1200 mm) wide, unless otherwise indicated, for each type of repointing required, and repoint one of the areas.

PART 2 - PRODUCTS

2.1 MORTAR MATERIALS
A. Portland Cement: ASTM C 150/C 150M, Type I or Type II, except Type III may be used for cold-weather construction; **white gray, or both where required for color matching of mortar**.
1. Provide cement containing not more than 0.60 percent total alkali when tested according to ASTM C 114.
B. Hydrated Lime: ASTM C 207, Type S.
C. Masonry Cement: ASTM C 91/C 91M.
D. Mortar Cement: ASTM C 1329/C 1329M.
E. Mortar Sand: ASTM C 144.

1. **Match size, texture, and gradation of existing mortar sand as closely as possible**. Blend several sands if necessary to achieve suitable match.
2. Color: Provide natural sand or ground marble, granite, or other sound stone of color necessary to produce required mortar color.

F. Mortar Pigments: ASTM C 979/C 979M, compounded for use in mortar mixes, and having a record of satisfactory performance in masonry mortars.

G. Water: Potable.

2.2 MORTAR MIXES

A. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.
1. Mixing Pointing Mortar: Thoroughly mix cementitious materials and sand together before adding any water. Then mix again, adding only enough water to produce a damp, unworkable mix that retains its form when pressed into a ball. Maintain mortar in this dampened condition for 15 to 30 minutes. Add remaining water in small portions until mortar reaches desired consistency. Use mortar within one hour of final mixing; do not retemper or use partially hardened material.

B. Colored Mortar: Produce mortar of color required by using specified ingredients. Do not alter specified proportions without Architect's approval.
1. Mortar Pigments: Where mortar pigments are indicated, do not add pigment exceeding 10 percent by weight of the cementitious or binder materials, except for carbon black which is limited to 2 percent.

C. Do not use admixtures in mortar unless otherwise indicated.

D. Mixes: Mix mortar materials in the following proportions:
1. Pointing Mortar by Type: ASTM C 270, Proportion Specification, **Type N** unless otherwise indicated; with cementitious material limited to **portland cement and lime masonry cement or mortar cement**. **Add mortar pigments to produce mortar colors required.**]

PART 3 - EXECUTION

3.1 PROTECTION

A. Remove all items in the way, preventing proper review, required for scope of work and to be demolished; conduits, gutters, boxes, fans, door & windows, downspouts, brackets, clips, lights, etc. all affecting work adjacent to masonry. Store any items indicated to be used or re-installed, during masonry repair. Reinstall when repairs are complete.
1. Provide temporary rain drainage during work to direct water away from building.

3.2 REPOINTING MASONRY

A. Rake out and repoint joints to the following extent:
1. All joints in areas indicated.
2. Joints indicated as sealant-filled joints. Seal joints according to Section 079200 "Joint Sealants."
3. Joints at locations of the following defects:
a. Holes and missing mortar.
b. Cracks that can be penetrated 1/4 inch (6 mm) or more by a knife blade 0.027 inch (0.7 mm) thick.
c. Cracks **1/16 inch (1.6 mm)** or more in width and of any depth.
d. Hollow-sounding joints when tapped by metal object.
e. Eroded surfaces 1/4 inch (6 mm) or more deep.

f. Deterioration to point that mortar can be easily removed by hand, without tools.
g. Joints filled with substances other than mortar.

B. Do not rake out and repoint joints where not required.

C. Rake out joints as follows, according to procedures demonstrated in approved mockup:
1. Remove mortar from joints to depth of **2 times joint width**, but not less than **3/4 inch (20 mm)** or not less than that required to expose sound, unweathered mortar. Do not remove unsound mortar more than **2 inches (50 mm)** deep; consult Architect for direction.
2. Remove mortar from masonry surfaces within raked-out joints to provide reveals with square backs and to expose masonry for contact with pointing mortar. Brush, vacuum, or flush joints to remove dirt and loose debris.
3. Do not spall edges of masonry units or widen joints. Replace or patch damaged masonry units as directed by Architect.

D. Notify Architect of unforeseen detrimental conditions including voids in mortar joints, cracks, loose masonry units, rotted wood, rusted metal, and other deteriorated items.

E. Pointing with Mortar:
1. Rinse joint surfaces with water to remove dust and mortar particles. Time rinsing application so, at time of pointing, joint surfaces are damp but free of standing water. If rinse water dries, dampen joint surfaces before pointing.
2. Apply pointing mortar first to areas where existing mortar was removed to depths greater than surrounding areas. Apply in layers not greater than **3/8 inch (9 mm)** until a uniform depth is formed. Fully compact each layer, and allow it to become thumbprint hard before applying next layer.
3. After deep areas have been filled to same depth as remaining joints, point joints by placing mortar in layers not greater than **3/8 inch (9 mm)**. Fully compact each layer and allow to become thumbprint hard before applying next layer. Where existing masonry units have worn or rounded edges, slightly recess finished mortar surface below face of masonry to avoid widened joint faces. Take care not to spread mortar beyond joint edges onto exposed masonry surfaces or to featheredge the mortar.
4. When mortar is thumbprint hard, tool joints to match original appearance of joints as demonstrated in approved mockup. Remove excess mortar from edge of joint by brushing.
5. Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.
6. Hairline cracking within mortar or mortar separation at edge of a joint is unacceptable. Completely remove such mortar and repoint.

F. Where repointing work precedes cleaning of existing masonry, allow mortar to harden at least 30 days before beginning cleaning work.

3.3 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water, applied by low pressure spray.
1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

END OF SECTION 040120.64

SECTION 04100

MORTAR AND MASONRY GROUT

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Mortar and grout for masonry, to match existing.

1.02 GENERAL
- A. All notes or specifications on structural drawings shall override any discrepancies listed.

1.03 SUBMITTALS
- A. Submit under provisions of the General Requirements.
- B. Include design mix, indicate whether the Proportion or Property specification of ASTM C270 is to be used, required environmental conditions, and admixture limitations.

1.04 QUALITY ASSURANCE
- A. Perform Work in accordance with ACI 530 and ACI 530.1 .

1.05 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect, and handle products to site under provisions of the General Requirements.
- B. Maintain packaged materials clean, dry, and protected against dampness, freezing, and foreign matter.

1.06 ENVIRONMENTAL REQUIREMENTS
- A. Maintain materials and surrounding air temperature to minimum 40 degrees F prior to, during, and 48 hours after completion of masonry work.
- B. Maintain materials and surrounding air temperature to maximum 90 degrees F prior to, during, and 48 hours after completion of masonry work.

PART 2 PRODUCTS

2.01 MATERIALS
- A. Portland Cement: ASTM C150, Type I.
- B. Masonry Cement: ASTM C91, Type S.
- C. Premix Mortar: ASTM C387, Type S.
- D. Mortar Aggregate: ASTM C144, standard masonry type.
- E. Hydrated Lime: ASTM C207, Type S.
- F. Water: Clean and potable.
- G. Bonding Agent: Latex or Epoxy type.

2.02 MORTAR COLOR
- A. Mortar Color: Mineral oxide pigment; color to match adjacent CMU color, as selected by Architect.

2.03 MORTAR MIXES
- A. Mortar For Load Bearing Walls and Partitions: ASTM C270, Type M or S using the Property specification.
- B. Mortar For Non-Load Bearing Walls and Partitions: ASTM C270, Type M or S using the Property specification.
- C. Mortar For Engineered Masonry: ASTM C270, Type M or S using the Property specification.
- D. Pointing Mortar: ASTM C270, Type N or O using the Property specification.

2.04 MORTAR MIXING
- A. Thoroughly mix mortar ingredients in accordance with ASTM C270 in quantities needed for immediate use.
- B. Maintain sand uniformly damp immediately before the mixing process.
- C. Add mortar color and admixtures in accordance with manufacturer’s instructions. Provide uniformity of mix and coloration.
- D. Do not use anti-freeze compounds to lower the freezing point of mortar.
- E. If water is lost by evaporation, re-temper only within two hours of mixing.

F. Use mortar within two hours after mixing at temperatures of 90 degrees F (32 degrees C), or two-and-one-half hours at temperatures under 40 degrees F.

2.05 GROUT MIXES

A. Bond Beams, and Lintels: 3,000 psi strength at 28 days; 8-10 inches slump; premixed type in accordance with ASTM C94.
B. Engineered Masonry: 3,000 psi strength at 28 days; 8-10 inches slump; premixed type in accordance with ASTM C94.

2.06 GROUT MIXING

A. Mix grout in accordance with ASTM C94.
B. Add admixtures in accordance with manufacturer's instructions; mix uniformly.
C. Do not use anti-freeze compounds to lower the freezing point of grout.

PART 3 EXECUTION

3.01 EXAMINATION

A. Request inspection of spaces to be grouted.

3.02 INSTALLATION

A. Install mortar and grout in accordance with premix mortar manufacturer's instructions.
B. Install mortar and grout in accordance with ASTM C270.
C. Work grout into masonry cores and cavities to eliminate voids.
D. Do not install grout in lifts greater than 16 inches or two CMU courses without consolidating grout by rodding.
E. Do not displace reinforcement while placing grout.
F. Remove excess mortar from grout spaces.

END OF SECTION 04100

SECTION 04300

UNIT MASONRY SYSTEM

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Concrete masonry or brick units.
B. Reinforcement, anchorage, and accessories.

1.02 SUBMITTALS
A. Submit under provisions of the General Requirements.
B. Product Data: Provide data for masonry and brick units and fabricated wire reinforcement.

1.03 QUALIFICATIONS
A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.

1.04 DELIVERY, STORAGE, AND HANDLING
A. Deliver, store, protect and handle products to site under provisions of the General Requirements.
B. Accept units on site. Inspect for damage.

1.05 ENVIRONMENTAL REQUIREMENTS
A. Maintain materials and surrounding air temperature to minimum 40 degrees F prior to, during, and 48 hours after completion of masonry work.
B. Maintain materials and surrounding air temperature to maximum 90 degrees F prior to, during, and 48 hours after completion of masonry work.
C. Hot Cold Weather Requirements: IMIAC - Recommended Practices and Guide Specifications for Hot or Cold Weather Masonry Construction.

PART 2 PRODUCTS

2.01 CONCRETE MASONRY UNITS
A. Non-Load Bearing Block Units (CMU): ASTM C90, Heavy weight, sand, light weight will not be accepted. Type I - Moisture Controlled.
B. Size and Shape: Nominal modular size of 8 and 4 x 16 x 8 inches. Provide special units for 90 degree corners.
C. Style and Color.
    1. Moisture controlled with coloring additive. Coloring to be determined by Architect.
    2. Provide as indicated on drawings:

2.02 REINFORCEMENT AND ANCHORAGE
A. Single Wythe Joint Reinforcement: Truss type; steel wire, hot dip galvanized to ASTM A641 after fabrication, No. 9 side rods with No. 9 cross ties.
    1. Manufacturers:
        a. DUR-O-WALL
        b. TRU-MESH
        c. BET-R-WALL
B. Reinforcing Steel: ASTM A615, 40 or 60 ksi yield grade, deformed billet bars, uncoated finish.
C. Wall Ties: Formed steel wire, 3/16 inch thick, adjustable, hot dip galvanized to ASTM A123 steel finish.
    1. Manufacturers:
        a. DUR-O-WALL
        b. TRU-MESH
        c. BET-R-WALL

2.03 MORTAR AND GROUT
A. Mortar and Grout: As specified in Section 04100.

2.04 FLASHINGS
A. Plastic Flashings: Sheet polyvinyl chloride or polyethylene; 20 mil thick.
B. Lap Sealant: Butyl type as specified in Section 07900.

2.05 ACCESSORIES

A. Preformed Control Joints: Rubber, Neoprene, Polyvinyl chloride material. Provide with corner and tee accessories, heat or cement fused joints.
B. Joint Filler: Closed cell polyvinyl chloride, polyethylene, polyurethane or rubber; oversized 50 percent to joint width; self expanding.
C. Building Paper: No. 30 asphalt saturated felt.
D. Nailing Strips: Softwood, preservative treated for moisture resistance, dovetail shape, sized to masonry joints.
E. Weeps: Preformed plastic cotton wick filled, or cotton rope.
F. Cavity Vents: Molded polyvinyl chloride grilles; insect resistant.
G. Cleaning Solution: Non-acidic, not harmful to masonry work or adjacent materials.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.
B. Verify items provided by other sections of work are properly sized and located.
C. Verify that built-in items are in proper location, and ready for roughing into masonry work.

3.02 PREPARATION

A. Direct and coordinate placement of metal anchors supplied to other sections.
B. Provide temporary bracing during installation of masonry work. Maintain in place until building structure provides permanent bracing.

3.03 COURSING

A. Establish lines, levels, and coursing indicated. Protect from displacement.
B. Maintain masonry courses to uniform dimension. Form vertical and horizontal joints of uniform thickness.
C. Concrete Masonry Units:
    1. Bond: Running unless otherwise indicated.
    2. Coursing: One unit and one mortar joint to equal 8 inches.
    3. Mortar Joints: Concave, unless noted otherwise.
D. Brick Units:
    1. Bond: Running, unless noted otherwise.
    2. Coursing: Three units and three mortar joints to equal 8 inches.
    3. Mortar Joints: Concave, unless noted otherwise.

3.04 PLACING AND BONDING

A. Lay solid masonry units in full bed of mortar, with full head joints, uniformly jointed with other work.
B. Lay hollow masonry units with face shell bedding on head and bed joints.
C. Buttering corners of joints or excessive furrowing of mortar joints are not permitted.
D. Remove excess mortar as work progresses.
E. Interlock intersections and external corners.
F. Do not shift or tap masonry units after mortar has achieved initial set. Where adjustment must be made, remove mortar and replace.
G. Perform job site cutting of masonry units with proper tools to provide straight, clean, unchipped edges. Prevent broken masonry unit corners or edges.
H. Cut mortar joints flush where wall tile is scheduled, resilient base is scheduled, cavity insulation vapor barrier adhesive is applied, or bitumen dampproofing is applied.
I. Isolate masonry partitions from vertical structural framing members with a control joint.
J. Isolate top joint of masonry partitions from horizontal structural framing members and slabs or decks with compressible joint filler.

3.05 WEEPS

A. Install weeps in veneer at 32 inches oc horizontally above through-wall flashing, above shelf angles and lintels, and at bottom of walls.

3.06 CAVITY WALL

A. Do not permit mortar to drop or accumulate into cavity air space or to plug weeps.
B. Build inner wythe ahead of outer wythe to receive cavity insulation and air/vapor barrier adhesive.

3.07 REINFORCEMENT AND ANCHORAGE

A. Install horizontal joint reinforcement 16 inches oc.

B. Place masonry joint reinforcement in first and second horizontal joints above and below openings. Extend minimum 16 inches each side of opening.
C. Place joint reinforcement continuous in first and second joint below top of walls.
D. Lap joint reinforcement ends minimum 6 inches.
E. Support and secure reinforcing bars from displacement. Maintain position within 1/2 inch of dimensioned position.
F. At masonry veneer, embed wall ties in masonry back-up to bond veneer at maximum 16 inches oc vertically and 36 inches oc horizontally. Place at maximum 3 inches oc each way around perimeter of openings, within 12 inches of openings.

3.08 MASONRY FLASHINGS
A. Extend flashings horizontally at foundation walls, above ledge or shelf angles and lintels, under parapet caps, and at bottom of walls.
B. Turn flashing up minimum 8 inches and bed into mortar joint of masonry, seal to concrete, seal or underlap at sheathing over framed back-up.
C. Lap end joints minimum 6 inches and seal watertight.
D. Turn flashing, fold, and seal at corners, bends, and interruptions.

3.09 GROUTED COMPONENTS
A. Reinforce bond beam as indicated or detailed.
B. Lap splices minimum 24 bar diameters.
C. Support and secure reinforcing bars from displacement. Maintain position within 1/2 inch of dimensioned position.
D. Place and consolidate grout fill without displacing reinforcing.
E. At bearing locations, fill masonry cores with grout for a minimum 12 inches either side of opening.

3.10 CONTROL AND EXPANSION JOINTS
A. Do not continue horizontal joint reinforcement through control and expansion joints.
B. Install preformed control joint device in continuous lengths. Seal butt and corner joints in accordance with manufacturer's instructions.
C. Size control joint in accordance with Section 07900 for sealant performance.
D. Form expansion joint as detailed.

3.11 BUILT-IN WORK
A. As work progresses, install built-in metal door and glazed frames, fabricated metal frames, window frames, wood nailing strips, fireplace accessories, anchor bolts, plates, and other items to be built-in the work and furnished by other sections.
B. Install built-in items plumb and level.
C. Bed anchors of metal door and glazed frames in adjacent mortar joints. Fill frame voids solid with grout. Fill adjacent masonry cores with grout minimum 12 inches from framed openings.
D. Do not build in organic materials subject to deterioration.

3.12 TOLERANCES
A. Maximum Variation From Alignment of Columns: 1/4 inch.
B. Maximum Variation From Unit to Adjacent Unit: 1/32 inch.
C. Maximum Variation from Plane of Wall: 1/4 inch in 10 ft and 1/2 inch in 20 ft or more.
D. Maximum Variation from Plumb: 1/4 inch per story non-cumulative; 1/2 inch in two stories or more.
E. Maximum Variation from Level Coursing: 1/8 inch in 3 ft and 1/4 inch in 10 ft; 1/2 inch in 30 ft.
F. Maximum Variation of Joint Thickness: 1/8 inch in 3 ft.
G. Maximum Variation from Cross Sectional Thickness of Walls: 1/4 inch.

3.13 CUTTING AND FITTING
A. Cut and fit for chases, pipes, conduit, sleeves, and grounds. Coordinate with other sections of work to provide correct size, shape, and location.
B. Obtain approval prior to cutting or fitting masonry work not indicated or where appearance or strength of masonry work may be impaired.

3.14 CLEANING
A. Remove excess mortar and mortar smears as work progresses.
B. Replace defective mortar. Match adjacent work.
C. Clean soiled surfaces with cleaning solution.
D. Use non-metallic tools in cleaning operations.

3.15 PROTECTION OF FINISHED WORK

A. Protect finished Work.

B. Without damaging completed work, provide protective boards at exposed external corners which may be damaged by construction activities.

END OF SECTION 04300

PRESERVATION BRIEFS 42

The Maintenance, Repair and Replacement of Historic Cast Stone

- An Imitative Building Material with Many Names
- History of Use and Manufacture
- Mechanisms and Modes of Deterioration
- Maintenance of Cast Stone Installations
- Methods of Repair
- Replacement of Historic Cast Stone Installations
- Appropriateness of GFRC as a Replacement Material

An Imitative Building Material with Many Names

The practice of using cheaper and more common materials on building exteriors in imitation of more expensive natural materials is by no means a new one. In the eighteenth century, sand impregnated paint was applied to wood to look like quarried stone. Stucco scored to simulate stone ashlar could fool the eye as well. In the 19th century, cast iron was also often detailed to appear like stone. Another such imitative building material was "cast stone" or, more precisely, precast concrete building units.

Cast stone was just one name given to various concrete mixtures that employed molded shapes, decorative aggregates, and masonry pigments to simulate natural stone. The basic mixtures included water, sand, coarse aggregate, and cementing agents. Natural cements, portland cements, oxychloride cements, and sodium silicate based cements were all used as binding agents. The differences in the resulting products reflected the different stone aggregates, binding agents, methods of manufacture and curing, and systems of surface finishing that were used to produce them. Versatile in representing both intricately carved ornament and plain blocks of wall ashlar, cast stone could be tooled with a variety of finishes.

During a century and a half of use in the United States, cast stone has been given various names. While the term "artificial stone" was commonly used in the 19th century, "concrete stone," "cast stone," and "cut cast stone" replaced it in the early 20th century. In addition, Coignet Stone, Frear Stone, and Ransome Stone were all names of proprietary systems for pre-cast concrete building units, which experienced periods of popularity in different areas of the United States in the 19th century. These systems may be contrasted with "Artistic Concrete," decorative molded concrete construction, both precast and cast-in-place, which made little effort to simulate natural stone.

Having gained popularity in the United States in the 1860s, cast stone had become widely accepted as an economical substitute for natural stone by the early decades of the 20th century. Now, it is considered an important historic material in its own right with unique deterioration problems that require traditional, as well as innovative solutions. This Preservation Brief discusses in detail the maintenance and repair of historic cast stone-precast concrete building units that simulate natural stone. It also covers the conditions that warrant replacement of historic cast stone with appropriate contemporary concrete products and provides guidance on their replication. Many of the issues and techniques discussed here are relevant to the repair and replacement of other precast concrete products, as well.

History of Use and Manufacture

Early Patented Systems

While some use of cast stone may be dated to the Middle Ages, more recent efforts to replicate stone with cementitious materials began in England and France at the end of the 18th century. Coade Stone, one of the best known of the early English manufactures, was used for architectural ornament and trim, and saw limited use for interior decoration in the United States as early as 1800. Significant advances in the artificial stone industry in the United States were tied to the production of natural cement or hydraulic lime, which began about 1820.

A large number of patented American, English, and French systems were marketed immediately after the Civil War. One of the earliest American patents for cast stone was awarded to George A. Frear of Chicago in 1868. Frear Stone was a mixture of natural cement and sand, to which a solution of shellac was added to provide initial curing strength. Frear's system was widely licensed around the country, and the resultant variation in materials and manufacturing methods apparently resulted in some significant failures.

Another product which utilized natural cement as its cementing agent was Beton Coignet (literally, "Coignet concrete," also known as "Coignet Stone"). Francois Coignet was a pioneer of concrete construction in France. He received United States patents in 1869 and 1870 for his system of pre-cast concrete construction, which consisted of portland cement, hydraulic lime, and sand. In the United States the formula was modified to a mix of sand with Rosendale Cement (a high quality natural cement manufactured in Rosendale, Ulster County, New York). In 1870 Coignet's U.S. patent rights were sold to an American, John C. Goodrich, Jr., who formed the New York and Long Island Coignet Stone Company. This company fabricated the cast stone for one of the earliest extant cast stone structures in the United States, the Cleft Ridge Span in Prospect Park, Brooklyn, New York.

Some proprietary systems substituted other cements for the portland cement or hydraulic lime. The British patent process of Frederick Ransome utilized a mixture of sand and sodium silicate, combined with calcium chloride, to form blocks of calcium silicate. The sodium chloride by-product was intended to be removed with water washes during the curing process. The Sorel cement process, developed in 1853 and later applied to the manufacture of grindstones, tiles, and cast stone for buildings, combined zinc oxide with zinc chloride, or magnesium oxide and magnesium chloride, to form a hydrated oxychloride cement mixture that bound together sand or crushed stone. The Union Stone Company in Boston manufactured cast stone using the Sorel process. Ultimately, however, alternate cementing systems were abandoned in favor of portland cement, which proved to be more dependable and less expensive.

Late 19th and 20th Century Development

The use of cast stone grew rapidly with the extraordinary development of the portland cement and concrete industries at the end of the 19th century. In the early decades of the 20th century, cast stone became widely accepted as an economical substitute for natural stone. It was sometimes used as the only exterior facing material for a building, but was more often used as trim on a rock-faced natural stone or brick wall.

In most early 20th century installations, cast stone was used for exterior window and door surrounds or lintels, copings, parapets and balustrades, banding courses, cornices and friezes, and sculptural ornament. On occasion, decorative interiors were also finished with cast stone, although elaborate interior cornices and ornaments were more frequently fabricated of plaster.

Manufacture

Manufacturers of cast stone used graded mixes of crushed marble, limestone, granite, and smelting slag to produce a variety of stone effects. A light cement matrix with an aggregate of crushed marble could replicate limestone, while a mix of marble and small amounts of smelting slag would give the effect of white granite. Some manufacturers added masonry pigments and varied colors on the faces of the stone to give a somewhat stylized effect of variegated sandstone. Each manufacturer prepared a variety of stock mixes as well. Not surprisingly, aggregates varied in different localities. In New York State, for example, crushed Gouverneur and Tuckahoe marbles were popular facing aggregates; in other areas crushed feldspar or granite and even silica sand were commonly used.

The two basic cast stone production systems were "dry tamp" and "wet cast." The dry tamp process employed a stiff, low slump concrete mix that was pressed and compacted into the molds. The decorative aggregate mix was frequently distributed only on the exterior facing of the cast units (typically 3/4" to 1 Ω" thick,) while the cores of the units were common concrete. Because of the stiff mix, dry tamp units required a relatively short period of time in the molds, which could then be used several times a day. After removal from the molds, the dry tamp units were often cured in steam rooms to assure proper hydration of the cement. The wet cast process, on the other hand, used a much more plastic concrete mix that could be poured and vibrated into the molds. This system used significantly more water in the mix, assuring proper hydration of the cement mix without elaborate curing, but requiring that the units be left in the molds for at least a day. Because of this method of fabrication, wet cast products necessarily distributed their decorative aggregate mix through the entire unit, rather than simply an outer facing.

Concrete was cast in molds of wood, plaster, sand and, early in the 20th century, even hide glue or gelatin, depending upon the production method, the intricacy of the piece to be cast, and the number of units to be manufactured. Metal molds were sometimes used for stock ornamental items, less frequently for custom architectural work. When the units were adequately hard, finish surfaces were worked to expose the decorative stone aggregate. When removed from the mold, wet cast units exhibit a surface film of cement paste, which must be removed to expose the aggregate. Partially cured units could be sprayed with water, rubbed with natural bristle brushes, etched with acid, or sandblasted to remove the cement layer. The surface of dry tamp products required less finishing.

High quality cast stone was frequently "cut" or tooled with pneumatic chisels and hammers similar to those used to cut natural stone. In some cases, rows of small masonry blades were used to create shallow parallel grooves similar to lineal chisel marks. The results were often strikingly similar in appearance to natural stone. Machine and hand tooling was expensive, however, and simple molded cut cast stone was sometimes only slightly less costly than similar work in limestone. Significant savings could be achieved over the cost of natural stone when repetitive units of ornate carved trim were required.

Finally, cast stone is sometimes today used to replace natural stone when the original historic stone is no longer available, or the greater strength of reinforced concrete is desired. Reinforced cast stone columns, for instance, are frequently used to replace natural stone columns in seismic retrofits of historic structures. Fine-grained stones, such as sandstones, may be very successfully replicated with cast stone. Coarse-grained granites and marbles with pronounced patterns or banding are, for obvious reasons, not so successfully matched with cast stone. The replacement of natural stone with cast stone requires careful attention to selection of fine aggregates and the pigmentation of the cementing matrix. Coarse aggregate, which is generally used in cast stone to control shrinkage and assure adequate compressive strength, can present an aesthetic problem if it is visible at the surface of cast stone elements which simulate sandstone. Careful control of aggregate sizes in the mix formulation can reduce this problem.

Mechanisms and Modes of Deterioration

The best historic cast stone can rival natural stone in longevity. Many quality cast stone installations from the first decades of the twentieth century are still in excellent condition, and require little repair. Like any other building material, however, cast stone is subject to deterioration, which may occur in several ways:

- Separation of the facing and core layers
- Deterioration of the aggregate
- Deterioration or erosion of the cementing matrix
- Deterioration of the iron or steel reinforcement
- Deterioration of cramps and anchors used in its installation.

Separation of the Facing and Core Layers

Separation of the facing and core layers of dry tamp units is not uncommon, and often reflects fabrication defects such as poor compaction, lengthy fabrication time, or improper curing. Where separation of facing and core layers is suspected, cast stone units may be "sounded" to establish the extent of delamination.

Deterioration of the Aggregate

Cast stone failure caused by deterioration of the aggregate is uncommon. Granites, marbles, and silica sand are generally durable, although limestone and marble aggregate are subject to the same dissolution problems that affect quarried units of these stones. In rare instances, a reaction between the alkalis in the cement matrix and the stone aggregate may also cause deterioration.

Deterioration or Erosion of the Cementing Matrix

While it is relatively uncommon in twentieth century cast stone, serious deterioration of the cementing matrix can cause extensive damage to cast stone units. A properly prepared cementing mix will be durable in most exterior applications, and any flaking of exterior surfaces signals problems in the cementing mix and in the method of manufacture. The use of poor quality or improperly stored cement, impure water, or set accelerators can cause cement problems to occur years after a structure is completed. Improper mixing and compaction can also result in a porous concrete that is susceptible to frost damage and scaling. Severe cement matrix problems may be impossible to repair properly and often necessitate replacement of the deteriorating cast stone units.

More common and less serious than flaking or scaling caused by deterioration of the cementing matrix is the erosion of the surface of the matrix. This usually occurs on surfaces of projecting features exposed to water runoff, such as sills, water tables, and window hoods. In these areas, the matrix may erode, leaving small grains of aggregate projecting from the surface. The resultant rough surface is not at all the intended original appearance. In some historic cast stone installations, the thin layer of cement and fine sand at the surface of the cast stone units was not originally tooled from the molded surface, but was finished with patterns of masonry pigments in a stylized imitation of highly figured sandstones or

limestones. Erosion of the pigmented surface layer on this type of cast stone results in an even more dramatic change in appearance.

Deterioration of the Iron or Steel Reinforcement

During their original manufacture, unusually long and thin cast stone units, such as window sills or balustrade railings, and units requiring structural capacity, such as lintels, were generally reinforced with mild steel reinforcing bars. Large pieces sometimes had cable loops or hooks cast into them to facilitate handling and attachment. On occasion, this reinforcement and wire may be too close (less than 2") to the surface of the piece and rusting will cause spalling of the surface. This frequently happens to sills, copings, and water tables where repeated heavy wetting leads to loss of alkalinity in the concrete, allowing the reinforcement to rust. If damage from the deteriorating reinforcement is extensive, as for instance, the splitting of a baluster from the rusting of a central reinforcing rod, the cast stone unit may require replacement.

Deterioration of Cramps and Anchors

Even when reinforcement has not been added to individual cast stone units, mild steel cramps may have been used to anchor a cast stone veneer to backup masonry. Where spalls have occurred primarily at the tops of ashlar or frieze units, this is generally the cause.

Maintenance of Cast Stone Installations

Cleaning

Cast stone installations with marble or limestone aggregates may sometimes be cleaned with the same alkaline pre-wash/acid afterwash chemical cleaning systems used to clean limestone and other calcareous natural stones. If no marble or limestone aggregates are present, acidic cleaners, such as those used for natural granites and sandstones, may be used.

In either case, dark particulate staining in protected areas may be persistent, however, and require experimentation with other cleaning methods. Some micro-abrasive cleaning techniques used under very controlled circumstances by skilled cleaning personnel can be appropriate for removing tenacious soiling. Ordinary sand blasting or wet grit blasting can seriously damage the surface of the cast stone and should not be used.

Repointing

Early cast stone installations may have been constructed with natural cement mortars, but in late nineteenth century and twentieth century installations, cast stone units were generally bedded and pointed with mortars composed of portland cement, lime, and sand. When repointing or replacement of the historic mortar is required, a Type N mortar (about one part cement, and one part lime to six parts of sand) is generally appropriate. When repointing any historic masonry, it is important to match both the character and color of the sand and color of the cement matrix in the historic mortar. Cement matrix color can often be adjusted by using combinations of white, "light," and gray portland cement in the mortar.

Joints in historic cast stone installations can be quite thin and the dense mortar thus difficult to remove. Unnecessary repointing can cause significant damage to historic cast stone. Cracked and open joints will most often be found on exposed features such as balustrades and copings and, of course, require repointing. When a hard and tenacious mortar was used in the original installation or a later repointing, the removal of the mortar can easily chip the edges of the cast stone units.

While the careless use of "grinders" to remove mortar has damaged countless historic masonry buildings, a skilled mason may sometimes use a hand held grinder fitted with a thin diamond blade to score the center of a joint, and then remove the rest of the mortar with a hand chisel. If this method is not done carefully, however, wandering of the blade can widen or alter joints and cause significant damage to the cast stone. Care must be taken to prevent damage from over cutting of vertical joints by stopping blades well short of adjacent units. The use of small pneumatic chisels, such as those used to tool stone, can also work well for mortar removal, but even this method can cause chipping to the edges of cast stone units if it is not done carefully.

Methods of Repair

Much historic cast stone is unnecessarily replaced when it could easily be repaired in situ, or left untreated. This is especially true of areas that exhibit isolated spalls from rusting reinforcement bars or anchorage, or installations where erosion of the matrix has left a rough surface of exposed aggregate. The weathering of cast stone, while different from that of natural stone, produces a patina of age, and does not warrant large-scale replacement, unless severe cement matrix problems or rusting reinforcement bars have caused extensive scaling or spalling. Severe rusting of reinforcement bars on small decorative features, such as balusters, may signal carbonation (loss of alkalinity) of the matrix. Where carbonation of the matrix has occurred, untreated reinforcement will continue to rust. Replacement may be an acceptable approach for exposed and severely deteriorated features, such as hand railings, roof balustrades, or wall copings, where disassembly is unlikely to damage adjacent construction. Conversely, small areas of damage should generally be repaired with mortar "composites," or left alone.

Re-securing Separated Surface Facing

Where the decorative facing of dry tamped cast stone has separated from core layers, injected grouts may be used to re-secure the facing. Re-attachment of a separated facing layer may be time consuming, and should be undertaken by a conservator, rather than a mason. This technique may be the best, most economical, approach for repair of figurative sculpture or unique elements that are not repeated elsewhere on a building. Theoretically, cementitious grouts are most appropriate for re-attaching separated facings, but hairline fissures may require the use of resin adhesives. Low-viscosity epoxies have been used for this purpose, and may be applied through small injection ports. Cracks that would allow adhesive to leak must be repaired prior to injection, of course. Holes made for adhesive injection will require patching after re-attachment is complete.

Repairing Reinforcement Spalls and Mechanical Damage

Drilled holes, mechanically damaged corners, and occasional spalls from rusting reinforcement bars and anchorage are repairable conditions that do not warrant the replacement of cast stone. Small "composite " repairs to damaged masonry units can be made with mortar formulated to visually match the original material, and may be successfully undertaken by a competent and sensitive mason. If deterioration appears widespread, however, or if large surface areas are spalling or cracking and replacement appears necessary, the owner may wish to consult a preservation architect or consultant to determine the cause of deterioration and to specify necessary repairs or replacement, as appropriate.

The methods of composite repair used for stone masonry are also generally applicable for the repair of historic cast stone. For repairs to damaged cast stone to be successful, however, both the cement matrix color and the aggregate size and coloration must match that of the historic unit. Crushed stone and slag (such as "Black Beauty" abrasive grit), which are similar to many common traditional aggregates, are widely available, although some additional crushing and/or sieving may be necessary to obtain aggregate of an appropriate size. Remember that half or more of a weathered surface is exposed aggregate, so careful aggregate selection and size grading is extremely important for patching. Even differences in aggregate angularity (rounded pebbles vs. crushed stone) will be noticeable in the final repair. If more than one aggregate was used in the cast stone, the ratio of the selected aggregates in the mix is, of course, equally important. Variation in coloring of the cement matrix may be achieved through the use of either white, "light, " or gray portland cement. If additional tinting is required, only inorganic alkali-resistant masonry pigments should be used. Because most historic cast stone was manufactured primarily from portland cement and aggregate (with a less than 15% lime/cement ratio), it is not necessary to add large amounts of hydrated lime to cast stone composite repair mixtures. Small amounts of lime may be added for plasticity of the working mix.

To repair a spall caused by deterioration of a ferrous reinforcement bar or anchorage, it is necessary to remove all cracked concrete adjacent to the spall; grind and brush the reinforcement to remove all rust and scale; and paint the metal with a rust-inhibiting primer prior to applying the cast stone composite. If the reinforcement bar is much too close to the surface of the stone, it may be advisable to cut out the deteriorating section of reinforcement after consultation with a structural engineer. If deteriorating cramps are removed, it may be necessary to install new stainless steel anchorage.

Where spalls have a feather edge, it will be necessary to cut back the repair area to a uniform depth (1/2" or more). As with natural stone composite repairs, a bonding agent may assist adhesion of the repair material to the original concrete. For unusually large or deep patches, mechanical anchoring of the repair with small nylon or stainless steel rods may be required. If the adjacent cast stone is tooled or

weathered, it will be necessary to scribe or brush the repaired area to give it a matching surface texture. Adding enough coarse aggregate to match adjacent original material will sometimes interfere with adhesion of the composite, and it may be necessary to press additional aggregate into the applied patch prior to finishing. If this is not skillfully done, however, the surface of the patch may take on a mosaic appearance. For this reason, it is advisable to undertake test composite repairs in an unobtrusive location first.

Surface Refinishing

While re-tooling of deteriorated natural stone may sometimes be appropriate, restoring the original appearance of cast stone where surface erosion has occurred is difficult or impossible.
Tooling or grinding of the surface of the cast stone may expose coarse aggregate beneath the surface and will not, in any case, restore original patterned pigmentation that has weathered away. Silicate paints or masonry stains may be applied in patterns to replicate the original appearance, but may not be durable or completely successful aesthetically. Where matrix has eroded, it is advisable to accept the weathered appearance of the cast stone, unless extensive replacement is mandated by other factors. Because cast stone depends on exposed aggregate to achieve its aesthetic effect, the use of an applied cementitious surface coating dramatically alters the visual effect of the material and is inappropriate as a cast stone repair technique. A cementitious surface coating can also trap moisture in the cast units and cause surface spalling.

Replacement of Historic Cast Stone Installations

Individual cast stone units, which are subject to repeated wetting (such as copings, railings and balusters) and exhibit severe failure due to spalling or reinforcement deterioration, may require replacement with new cast stone and can replicate deteriorated units in existing buildings.
Fortunately, a number of companies custom manufacture precast concrete units. The variables involved in manufacture are considerable, and it is wise to use a firm with experience in ornamental and custom work rather than a precast concrete firm which manufactures stock structural items, concrete pipe, or the like. Several trade organizations, including the Cast Stone Institute, the National Precast Concrete Association, and the Architectural Precast Association, have developed recommendations and/or guide specifications for the manufacture of cast stone and precast concrete. These specifications set standards for characteristics such as compressive strength and water absorptivity, and discuss additives such as air entraining agents and water reducing agents, which influence the longevity of new cast stone. Trade references and guide specifications should be consulted before contracting for replacement of historic cast stone.
Fabrication defects in new cast stone. While the cement matrix coloration and aggregate considerations previously mentioned require the most careful attention, project staff should also look for defects which are common to cast stone fabrication:

Air bubbles. Small pits on the surface of the stone may form if the unit is not given adequate vibration to release trapped air during pouring. Bubbles can also be a problem when end casting long items such as columns or railings, where it is difficult to vibrate bubbles away from the finish surface of the unit.

Surface cracking or checking. Overly wet mixes and insufficient moisture during curing can result in surface cracking of large castings, such as columns. Such cracking dramatically reduces the durability of new cast stone. Small reinforced elements, such as balusters, also frequently crack at thin "necks" in the castings.

Aggregate segregation. Cast stone formulations generally include a range of coarse aggregates (crushed stone) and fine aggregates (sand). When units are vibrated to assure compaction of the mix and liberate trapped air bubbles, coarse aggregates may begin to settle and separate from the paste of cement and sand. Aggregate segregation results in a visible concentration of coarse aggregate at one end of the casting. Segregation is more problematic when end casting long pieces such as columns.

Surface rippling or irregularity. Production molds for fabrication are often made of rubber mold facings encased in larger "mother molds" of plaster and wood. Vibration can loosen the rubber facing from the outer mold and result in rippling or irregularities on the surface of the finished casting. Even when rippling is not noticeable, irregularity caused by mold movement can make it difficult to line up surfaces of adjacent units when assembling cast stone installations.

Mold lines. Freestanding elements, such as columns, must be cast in two-part molds, which are separated to release the completed cast piece. If the mold parts do not join tightly, some leakage of cement paste will occur at the mold joint, resulting in a projecting line on the surface of the casting. This is generally tooled off before the casting completely cures. A mold line will be visible on the completed piece if the projecting material is not completely removed, or if the tooling at the mold line does not match the adjacent surface of the casting. Tooling at mold lines may also expose contrasting coarse aggregate beneath the surface of the casting.

Other Considerations for Replacement of Cast Stone

Several other considerations are worth noting when it is necessary to replace historic cast stone elements with matching new cast stone.

Reinforcement. The alkalinity of new concrete generally provides adequate protection to steel reinforcement. In exposed areas where deterioration due to rusting of reinforcement has previously been a problem, however, the use of stainless steel reinforcement is recommended.

Surface finishing. Post-fabrication surface tooling of new cast stone is not currently common. Sandblasting is typically used to remove the surface film of cement and expose the aggregate. For replacement units replicating historic cast stone pieces in highly visible locations, it is sometimes possible to make a mold of a sound or repaired existing piece to incorporate the original tooling in the casting process. If the historic unit is too deteriorated to use as a pattern, a plaster model may be made to replicate the damaged piece. This is tooled to replicate the desired surface treatment or appearance, and a production mold is then made from the plaster model.

Moist curing. Surface crystallization of soluble salts (efflorescence) during curing may lighten the surface of some precast units, especially those simulating darker stone. Some manufacturers use a series of wet/dry curing cycles or washing with acetic acid to remove soluble salts that might otherwise discolor finished surfaces. For most wet cast products, simple moist curing under a plastic cover is sufficient.

Appropriateness of Glass Fiber Reinforced Concrete as a Replacement Material

Light-Weight Alternative

GFRC is sometimes used to replicate deteriorated elements of cast or fine grained natural stone. Because the GFRC element is a rigid, but relatively thin shell, it must be supported and attached with an interior framework of steel.

The attachment hardware inside this GFRC cartouche (left) will not be visible when the unit is installed (armature visible at right). Photos: Towne House Restorations, Inc

Glass fiber reinforced concrete (GFRC) is more and more frequently encountered in building restoration and is used to replicate deteriorated stone and cast stone, and even architectural terra cotta. This is a relatively new material that uses short chopped strands of glass fiber to reinforce a matrix of sand and cement. GFRC has become a popular low cost alternative to traditional precast concrete or stone masonry for some applications. Fabricators use a spray gun to spray the mortar-like mix into a mold of the shape desired. The resulting concrete unit, typically only æ" thick, is quite rigid, but requires a metal frame or armature to secure it to the building substrate. The metal frame is joined to the GFRC unit with small "bonding pads" of GFRC. GFRC has a dramatic advantage over traditional precast concrete where the weight of the installation is a concern, such as with cornices or window hoods. Many cast stone mixes can successfully be replicated with GFRC. Where it is used to simulate natural stone, GFRC, like cast stone, is most appropriate for simulation of fine-grained sandstones or limestones.

Not for Use in Load Bearing Applications

Because the GFRC system is in effect a "skin," GFRC cannot be used for load bearing applications without provision of additional support. This makes it unsuitable for some tasks such as replacement of individual ashlar units. It is also not appropriate for small freestanding elements such as balusters, or for most columns, unless they are engaged to surrounding masonry or can be vertically seamed, which may significantly alter the historic appearance. GFRC units must also allow for expansion and contraction, and are generally separated by sealant joints, not by mortar. A sealant joint may be unacceptable for

some historic applications; however, substitution of GFRC for cast stone may be appropriate when an entire assembly, such as a cornice, roof dormer, or window hood, requires replacement. Great care must be taken when detailing a GFRC replacement for existing cast stone.

Deterioration of GFRC

Because it is a relatively new material, the long term durability of GFRC is still untested. When GFRC was first introduced, some installations experienced deterioration caused by alkaline sensitivity of the glass fiber reinforcement. Alkali resistant glass is now used for GFRC manufacture. Even when the GFRC skin is well manufactured, however, the steel armature and bonding pad system used to mount the material is vulnerable to damage from leakage at sealant joints or small cracks in wash surfaces. The use of galvanized or stainless steel armatures, and stainless steel fasteners and bonding pad anchors is advisable.

Summary and References

Cast stone-a mixture of water, sand, coarse aggregate, and cementing agents—has proven over time to be an attractive and durable building material, when properly manufactured. It gained popularity in the 1860s and, by the early decades of the 20th century, became widely accepted as an economical substitute for natural stone. Unfortunately, much historic cast stone is unnecessarily replaced when it could easily be repaired and preserved in situ, or left untreated. Appropriate repair of damaged units can extend the life of any cast stone installation. Because of the necessity of matching both matrix color and aggregate size and ratio, conservation projects which involve repair or replication of cast stone should allow adequate lead time for the assembly of materials and the preparation of test samples. Understanding which conditions require repair, which warrant replacement, and which should be accepted as normal weathering is key to selecting the most appropriate approach to the protection and care of historic cast stone.

SECTION 047200

CAST STONE MASONRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Cast-stone trim.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.
   1. For cast-stone units, include dimensions and finishes.
B. Shop Drawings: Show fabrication and installation details for cast-stone units. Include dimensions, details of reinforcement and anchorages if any, and indication of finished faces.
C. Samples:
   1. For each color and texture of cast stone required.
   2. For colored mortar.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer.
B. Material Test Reports: For each mix required to produce cast stone, based on testing according to ASTM C 1364.

1.4 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer of cast-stone units similar to those indicated for this Project, that has sufficient production capacity to manufacture required units, and is a plant certified by **the Cast Stone Institute the Architectural Precast Association or the Precast/Prestressed Concrete Institute for Group A**.

PART 2 - PRODUCTS

2.1 CAST-STONE UNITS

A. Cast-Stone Units: Comply with ASTM C 1364.
   1. Units shall be manufactured using the **vibrant dry tamp** or **wet-cast** method to best match existing.
   2. Units shall be resistant to freezing and thawing as determined by laboratory testing according to ASTM C 666/C 666M, Procedure A, as modified by ASTM C 1364.
B. Fabricate units with sharp arris and accurately reproduced details, with indicated texture on all exposed surfaces unless otherwise indicated.
   1. Slope exposed horizontal surfaces 1:12 to drain unless otherwise indicated.
   2. Provide raised fillets at backs of sills and at ends indicated to be built into jambs.
   3. Provide drips on projecting elements unless otherwise indicated.
C. Cure Units as Follows:
   1. Cure units in enclosed, moist curing room at 95 to 100 percent relative humidity and temperature of 100 deg F (38 deg C) for 12 hours or 70 deg F (21 deg C) for 16 hours.
   2. Keep units damp and continue curing to comply with one of the following:
      a. No fewer than five days at mean daily temperature of 70 deg F (21 deg C) or above.
D. Acid etch units after curing to remove cement film from surfaces to be exposed to view.
E. Colors and Textures: **Match existing units**.

2.2 ACCESSORIES

A. Anchors: Type and size indicated, fabricated from **steel complying with ASTM A 36/A 36M and hot-dip galvanized to comply with ASTM A 123/A 123M**.

B. Dowels: 1/2-inch- (12-mm-) diameter round bars, fabricated from **steel complying with ASTM A 36/A 36M and hot-dip galvanized to comply with ASTM A 123/A 123M**.

C. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cast-stone manufacturer and expressly approved by cleaner manufacturer for use on cast stone and adjacent masonry materials.

2.3 MORTAR

A. Comply with requirements in Section 042000 "Unit Masonry" for mortar mixes.
   1. For setting mortar, use **Type N**.
   2. For pointing mortar, use **Type N**.

B. Pigmented Mortar: Use colored cement product **or select and proportion pigments with other ingredients to produce color required. Do not add pigments to colored cement products**.

2.4 SOURCE QUALITY CONTROL

A. Engage a qualified independent testing agency to sample and test cast-stone units according to ASTM C 1364.
   1. Include one test for resistance to freezing and thawing.

PART 3 - EXECUTION

3.1 SETTING CAST STONE IN MORTAR

A. Install cast-stone units to comply with requirements in Section 042000 "Unit Masonry."

B. Set units in full bed of mortar with full head joints unless otherwise indicated.
   1. Fill dowel holes and anchor slots with mortar.
   2. Fill collar joints solid as units are set.
   3. Build concealed flashing into mortar joints as units are set.
   4. Keep head joints in copings and between other units with exposed horizontal surfaces open to receive sealant.
   5. Keep joints at shelf angles open to receive sealant.

C. Rake out joints for pointing with mortar to depths of not less than 3/4 inch (19 mm). Rake joints to uniform depths with square bottoms and clean sides. Scrub faces of units to remove excess mortar as joints are raked.

D. Point mortar joints by placing and compacting mortar in layers not greater than 3/8 inch (10 mm). Compact each layer thoroughly and allow it to become thumbprint hard before applying next layer.

E. Tool exposed joints slightly concave when thumbprint hard. Use a smooth plastic jointer larger than joint thickness. **Match Existing**

F. **Where indicated**, Rake out joints for pointing with sealant to depths of not less than 3/4 inch (19 mm). Scrub faces of units to remove excess mortar as joints are raked.

G. Provide sealant joints at head joints of copings and other horizontal surfaces; at expansion, control, and pressure-relieving joints; and at locations indicated.
   1. Keep joints free of mortar and other rigid materials.
   2. Prepare and apply sealant of type and at locations indicated to comply with applicable requirements in Section 079200 "Joint Sealants."

3.2 SETTING ANCHORED CAST STONE WITH SEALANT-FILLED JOINTS

A. Set cast stone as indicated on Drawings. Set units accurately in locations indicated, with edges and faces aligned according to established relationships and indicated tolerances.

1. Install anchors, supports, fasteners, and other attachments indicated or necessary to secure units in place.
2. Shim and adjust anchors, supports, and accessories to set cast stone in locations indicated with uniform joints.

B. Fill anchor holes with sealant.
1. Where dowel holes occur at pressure-relieving joints, provide compressible material at ends of dowels.

C. Set cast stone supported on clip or continuous angles on resilient setting shims. Use material of thickness required to maintain uniform joint widths. Hold shims back from face of cast stone a distance at least equal to width of joint.

D. Prepare and apply sealant of type and at locations indicated to comply with applicable requirements in Section 079200 "Joint Sealants."

3.3 INSTALLATION TOLERANCES

A. Variation from Plumb: Do not exceed 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2 inch (12 mm) maximum.

B. Variation from Level: Do not exceed 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2 inch (12 mm) maximum.

C. Variation in Joint Width: Do not vary joint thickness more than 1/8 inch in 36 inches (3 mm in 900 mm) or one-fourth of nominal joint width, whichever is less.

D. Variation in Plane between Adjacent Surfaces (Lipping): Do not vary from flush alignment with adjacent units or adjacent surfaces indicated to be flush with units by more than 1/16 inch (1.5 mm), except where variation is due to warpage of units within tolerances specified.

3.4 ADJUSTING AND CLEANING

A. Remove and replace stained and otherwise damaged units and units not matching approved Samples. Cast stone may be repaired if methods and results are approved by Architect.

B. Replace units in a manner that results in cast stone matching approved Samples, complying with other requirements, and showing no evidence of replacement.

C. In-Progress Cleaning: Clean cast stone as work progresses.
1. Remove mortar fins and smears before tooling joints.
2. Remove excess sealant immediately, including spills, smears, and spatter.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed cast stone as follows:
1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample; leave one sample uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of cast stone.
3. Protect adjacent surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.
4. Wet surfaces with water before applying cleaners; remove cleaners promptly by rinsing thoroughly with clear water.
5. Clean cast stone by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.
6. Clean cast stone with proprietary acidic cleaner applied according to manufacturer's written instructions.

END OF SECTION 047200

SECTION 05120

STRUCTURAL STEEL

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Structural steel framing members and support members.
B. Base plates.
C. Grouting under base plates.

1.02 GENERAL
A. All notes or specifications on structural drawings shall override any discrepancies listed.

1.03 SUBMITTALS
A. Submit under provisions of the General Requirements.
B. Shop Drawings:
   1. Indicate profiles, sizes, spacing, and locations of structural members, openings, attachments and fasteners.
   2. Connections and Connections not detailed.
   3. Cambers, and loads.
   4. Indicate welded connections with AWS A2.0 welding symbols. Indicate net weld lengths.
C. Welders Certificates: Certify welders employed on the Work, verifying AWS qualification within the previous 12 months.

1.04 QUALITY ASSURANCE
A. Fabricate structural steel members in accordance with AISC - Specification for the Design, Fabrication and Erection of Structural Steel for Buildings.
B. Perform Work in accordance with AISC - Specification for Architectural Exposed Structural Steel.

1.05 QUALIFICATIONS
A. Fabricator: Company specializing in performing the work of this Section with minimum 5 years' documented experience.
B. Erector: Company specializing in performing the work of this Section with minimum 5 years' documented experience.
C. Design connections not detailed on the Drawings under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State of Kansas.

1.06 FIELD MEASUREMENTS
A. Verify that field measurements are as shown on shop drawings and/or as instructed by the manufacturer.

1.07 MISCELLANEOUS ITEMS
A. All miscellaneous items required to complete the work in accordance with the intent of the Drawings and Specifications, shall be furnished and installed, regardless of whether or not specifically shown or described. Such items include masonry anchors, dovetail slots, dowels and cramps, loose or embedded items of structural shapes, plates, bars, shield, and other fastening devices which may or may not be provided with the indicated or specified items shall also be furnished and installed as required for attachment and support.

PART 2 PRODUCTS

2.01 MATERIALS
A. Reference drawings and notes on the drawings.

2.02 FINISH
A. Prepare structural component surfaces in accordance with SSPC SP 2.
B. Shop prime structural steel members. Do not prime surfaces that will be fireproofed, field welded, in contact with concrete or high strength bolts.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

3.02 ERECTION

A. Allow for erection loads, and for sufficient temporary bracing to maintain structure safe, plumb, and in true alignment until completion of erection and installation of permanent bracing.
B. Field weld components and shear studs indicated on Drawings and/or shop drawings.
C. Do not field cut or alter structural members without approval of Architect/Engineer.
D. After erection, prime welds, abrasions, and surfaces not shop primed or galvanized, except surfaces to be in contact with concrete.
E. Grout under base plates as indicated.

3.03 ERECTION TOLERANCES

A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.
B. Maximum Offset From True Alignment: 1/4 inch.

END OF SECTION 05120

SECTION 05400

COLD-FORMED METAL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Interior non-load-bearing wall framing
   2. Ceiling joist framing.

B. Related Sections include the following:
   1. Division 05 Section "Metal Fabrications" for masonry shelf angles and connections.
   2. Division 09 Section "Non-Structural Metal Framing" for interior non-load-bearing, metal-stud framing and ceiling-suspension assemblies.
   3. Division 09 Section "Gypsum Board Shaft Wall Assemblies" for interior non-load-bearing, metal-stud-framed, shaft-wall assemblies.

1.3 PERFORMANCE REQUIREMENTS

A. Structural Performance: Provide cold-formed metal framing capable of withstanding design loads within limits and under conditions indicated.
   1. Design framing system to maintain clearances at openings, to allow for construction tolerances, and to accommodate live load deflection of primary building structure as follows:
      a. Upward and downward movement of **1 inch.**

B. Cold-Formed Steel Framing, General: Design according to AISI's "Standard for Cold-Formed Steel Framing - General Provisions."
   1. Headers: Design according to AISI's "Standard for Cold-Formed Steel Framing - Header Design."
   2. Design exterior non-load-bearing wall framing to accommodate horizontal deflection without regard for contribution of sheathing materials.

1.4 SUBMITTALS

A. Product Data: For each type of cold-formed metal framing product and accessory indicated.

B. Shop Drawings: Show layout, spacings, sizes, thicknesses, and types of cold-formed metal framing; fabrication; and fastening and anchorage details, including mechanical fasteners. Show reinforcing channels, opening framing, supplemental framing, strapping, bracing, bridging, splices, accessories, connection details, and attachment to adjoining work.

1.5 QUALITY ASSURANCE

A. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code--Steel," and AWS D1.3, "Structural Welding Code--Sheet Steel."

B. Fire-Test-Response Characteristics: Where indicated, provide cold-formed metal framing identical to that of assemblies tested for fire resistance per ASTM E 119 by a testing and inspecting agency acceptable to authorities having jurisdiction.

C. AISI Specifications and Standards: Comply with AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members" and its "Standard for Cold-Formed Steel Framing - General Provisions."

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect cold-formed metal framing from corrosion, deformation, and other damage during delivery, storage, and handling.

B. Store cold-formed metal framing, protect with a waterproof covering, and ventilate to avoid condensation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering cold-formed metal framing that may be incorporated into the Work include, but are not limited to, the following:

B. Manufacturers: Subject to compliance with requirements, provide cold-formed metal framing by one of the following:

1. Allied Studco.
2. AllSteel Products, Inc.
3. California Expanded Metal Products Company.
4. Clark Steel Framing.
5. Consolidated Fabricators Corp.; Building Products Division.
6. Craco Metals Manufacturing, LLC.
7. Custom Stud, Inc.
8. Dale/Incor.
9. Design Shapes in Steel.
10. Dietrich Metal Framing; a Worthington Industries Company.
11. Formetal Co. Inc. (The).
12. Innovative Steel Systems.
13. MarinoWare; a division of Ware Industries.
14. Quail Run Building Materials, Inc.
15. SCAFCO Corporation.
16. Southeastern Stud & Components, Inc.
17. Steel Construction Systems.
18. Steeler, Inc.
19. Super Stud Building Products, Inc.
20. United Metal Products, Inc.

2.2 MATERIALS

A. Steel Sheet: ASTM A 1003/A 1003M, Structural Grade, Type H, metallic coated, of grade and coating weight as follows:

1. Grade: 50 KSI.
2. Coating: **G60**.

B. Steel Sheet for **Vertical Deflection** Clips: ASTM A 653/A 653M, structural steel, zinc coated, of grade and coating as follows:

1. Grade: **50 (340), Class 1 or 2**.
2. Coating: G60.

2.3 INTERIOR NON-LOAD-BEARING WALL FRAMING

A. Steel Studs: Manufacturer's standard C-shaped steel studs, of web depths indicated, punched, with stiffened flanges, and as follows:

1. Minimum Base-Metal Thickness: 20 gauge, 30 mil
2. Flange Width: **1-5/8 inches (41 mm)**.
3. Sizes: As indicated on drawings

B. Steel Track: Manufacturer's standard U-shaped steel track, of web depths indicated, unpunched, with unstiffened flanges, and as follows:

1. Minimum Base-Metal Thickness: **Matching steel studs**.
2. Flange Width: **1-1/4 inches (32 mm)**.

C. Vertical Deflection Clips: Manufacturer's standard **bypass** clips, capable of accommodating upward and downward vertical displacement of primary structure through positive mechanical attachment to stud web.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   a. Dietrich Metal Framing; a Worthington Industries Company.
   b. MarinoWare, a division of Ware Industries.
   c. SCAFCO Corporation
   d. The Steel Network, Inc.

D. Single Deflection Track: Manufacturer's single, deep-leg, U-shaped steel track; unpunched, with unstiffened flanges, of web depth to contain studs while allowing free vertical movement, with flanges designed to support horizontal and lateral loads and transfer them to the primary structure, and as follows:
   1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
   2. Minimum Base-Metal Thickness: **0.0428 inch (1.09 mm)**.
   3. Flange Width: 2 ½".

2.4 CEILING JOIST FRAMING

A. Steel Ceiling Joists: Manufacturer's standard C-shaped steel sections, of web depths indicated, **unpunched,** with stiffened flanges, and as follows:
   1. Minimum Base-Metal Thickness: **0.0329 inch (0.84 mm)**.
   2. Flange Width: **1-5/8 inches (41 mm).**

2.5 FRAMING ACCESSORIES

A. Fabricate steel-framing accessories from steel sheet, ASTM A 1003/A 1003M, Structural Grade, Type H, metallic coated, of same grade and coating weight used for framing members.

B. Provide accessories of manufacturer's standard thickness and configuration, unless otherwise indicated, as follows:
   1. Supplementary framing.
   2. Bracing, bridging, and solid blocking.
   3. Web stiffeners.
   4. Anchor clips.
   5. End clips.
   6. Foundation clips.
   7. Gusset plates.
   8. Stud kickers, knee braces, and girts.
   9. Joist hangers and end closures.
   10. Hole reinforcing plates.
   11. Backer plates.

2.6 ANCHORS, CLIPS, AND FASTENERS

A. Steel Shapes and Clips: ASTM A 36/A 36M, zinc coated by hot-dip process according to ASTM A 123/A 123M.

B. Anchor Bolts: ASTM F 1554, Grade **36** threaded carbon-steel **hex-headed bolts headless, hooked bolts** and carbon-steel nuts; and flat, hardened-steel washers; zinc coated by **mechanically deposition according to ASTM B 695, Class 50**.

C. Expansion Anchors: Fabricated from corrosion-resistant materials, with capability to sustain, without failure, a load equal to 5 times design load, as determined by testing per ASTM E 488 conducted by a qualified independent testing agency.

D. Power-Actuated Anchors: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with capability to sustain, without failure, a load equal to 10 times design load, as determined by testing per ASTM E 1190 conducted by a qualified independent testing agency.

E. Mechanical Fasteners: ASTM C 1513, corrosion-resistant-coated, self-drilling, self-tapping steel drill screws.
   1. Head Type: Low-profile head beneath sheathing, manufacturer's standard elsewhere.

F. Welding Electrodes: Comply with AWS standards.

2.7 MISCELLANEOUS MATERIALS

A. Galvanizing Repair Paint: **ASTM A 780**.

B. Cement Grout: Portland cement, ASTM C 150, Type I; and clean, natural sand, ASTM C 404. Mix at ratio of 1 part cement to 2-1/2 parts sand, by volume, with minimum water required for placement and hydration.

C. Nonmetallic, Nonshrink Grout: Premixed, nonmetallic, noncorrosive, nonstaining grout containing selected silica sands, portland cement, shrinkage-compensating agents, and plasticizing and water-reducing agents, complying with ASTM C 1107, with fluid consistency and 30-minute working time.

D. Shims: Load bearing, high-density multimonomer plastic, nonleaching.

E. Sealer Gaskets: Closed-cell neoprene foam, 1/4 inch (6.4 mm) thick, selected from manufacturer's standard widths to match width of bottom track or rim track members.

2.8 FABRICATION

A. Fabricate cold-formed metal framing and accessories plumb, square, and true to line, and with connections securely fastened, according to referenced AISI's specifications and standards, manufacturer's written instructions, and requirements in this Section.
   1. Fabricate framing assemblies using jigs or templates.
   2. Cut framing members by sawing or shearing; do not torch cut.
   3. Fasten cold-formed metal framing members by welding, screw fastening, clinch fastening, or riveting as standard with fabricator. Wire tying of framing members is not permitted.
      a. Comply with AWS D1.3 requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
      b. Locate mechanical fasteners and install according to Shop Drawings, with screw penetrating joined members by not less than three exposed screw threads.
   4. Fasten other materials to cold-formed metal framing by welding, bolting, or screw fastening, according to Shop Drawings.

B. Reinforce, stiffen, and brace framing assemblies to withstand handling, delivery, and erection stresses. Lift fabricated assemblies to prevent damage or permanent distortion.

C. Fabrication Tolerances: Fabricate assemblies level, plumb, and true to line to a maximum allowable tolerance variation of 1/8 inch in 10 feet (1:960) and as follows:
   1. Spacing: Space individual framing members no more than plus or minus 1/8 inch (3 mm) from plan location. Cumulative error shall not exceed minimum fastening requirements of sheathing or other finishing materials.
   2. Squareness: Fabricate each cold-formed metal framing assembly to a maximum out-of-square tolerance of 1/8 inch (3 mm).

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine supporting substrates and abutting structural framing for compliance with requirements for installation tolerances and other conditions affecting performance.
   1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Before sprayed fire-resistive materials are applied, attach continuous angles, supplementary framing, or tracks to structural members indicated to receive sprayed fire-resistive materials.

B. After applying sprayed fire-resistive materials, remove only as much of these materials as needed to complete installation of cold-formed framing without reducing thickness of fire-resistive materials below that are required to obtain fire-resistance rating indicated. Protect remaining fire-resistive materials from damage.

C. Install load bearing shims or grout between the underside of wall bottom track or rim track and the top of foundation wall or slab at stud or joist locations to ensure a uniform bearing surface on supporting concrete or masonry construction.

D. Install sealer gaskets to isolate the underside of wall bottom track or rim track and the top of foundation wall or slab at stud or joist locations.

3.3 INSTALLATION, GENERAL

A. Cold-formed metal framing may be shop or field fabricated for installation, or it may be field assembled.

B. Install cold-formed metal framing according to AISI's "Standard for Cold-Formed Steel Framing - General Provisions" and to manufacturer's written instructions unless more stringent requirements are indicated.

C. Install shop- or field-fabricated, cold-formed framing and securely anchor to supporting structure.
   1. Screw, bolt, or weld wall panels at horizontal and vertical junctures to produce flush, even, true-to-line joints with maximum variation in plane and true position between fabricated panels not exceeding 1/16 inch (1.6 mm).

D. Install cold-formed metal framing and accessories plumb, square, and true to line, and with connections securely fastened.
   1. Cut framing members by sawing or shearing; do not torch cut.
   2. Fasten cold-formed metal framing members by welding, screw fastening, clinch fastening, or riveting. Wire tying of framing members is not permitted.

a. Comply with AWS D1.3 requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
b. Locate mechanical fasteners and install according to Shop Drawings, and complying with requirements for spacing, edge distances, and screw penetration.

E. Install framing members in one-piece lengths unless splice connections are indicated for track or tension members.

F. Install temporary bracing and supports to secure framing and support loads comparable in intensity to those for which structure was designed. Maintain braces and supports in place, undisturbed, until entire integrated supporting structure has been completed and permanent connections to framing are secured.

G. Do not bridge building expansion and control joints with cold-formed metal framing. Independently frame both sides of joints.

H. Install insulation, specified in Division 07 Section "Thermal Insulation," in built-up exterior framing members, such as headers, sills, boxed joists, and multiple studs at openings, that are inaccessible on completion of framing work.

I. Fasten hole reinforcing plate over web penetrations that exceed size of manufacturer's standard punched openings.

J. Erection Tolerances: Install cold-formed metal framing level, plumb, and true to line to a maximum allowable tolerance variation of 1/8 inch in 10 feet (1:960) and as follows:
1. Space individual framing members no more than plus or minus 1/8 inch (3 mm) from plan location. Cumulative error shall not exceed minimum fastening requirements of sheathing or other finishing materials.

3.4 EXTERIOR NON-LOAD-BEARING WALL INSTALLATION

A. Install continuous tracks sized to match studs. Align tracks accurately and securely anchor to supporting structure as indicated.

B. Fasten both flanges of studs to bottom track, unless otherwise indicated. Space studs as follows:
1. Stud Spacing: **16 inches (406 mm)**.

C. Set studs plumb, except as needed for diagonal bracing or required for nonplumb walls or warped surfaces and similar requirements.

D. Isolate non-load-bearing steel framing from building structure to prevent transfer of vertical loads while providing lateral support.
1. Install single-leg deflection tracks and anchor to building structure.
2. Install double deep-leg deflection tracks and anchor outer track to building structure.
3. Connect vertical deflection clips to **infill** studs and anchor to building structure.

E. Install horizontal bridging in wall studs, spaced in rows indicated on Shop Drawings but not more than 48 inches (1220 mm) apart. Fasten at each stud intersection.
1. Top Bridging for Single Deflection Track: Install row of horizontal bridging within [**12 inches (305 mm)** of single deflection track. Install a combination of flat, taut, steel sheet straps of width and thickness indicated and stud or stud-track solid blocking of width and thickness matching studs. Fasten flat straps to stud flanges and secure solid blocking to stud webs or flanges.
a. Install solid blocking at **96-inch centers.**
2. Bridging: Cold-rolled steel channel, welded or mechanically fastened to webs of punched studs.
3. Bridging: Combination of flat, taut, steel sheet straps of width and thickness indicated and stud-track solid blocking of width and thickness to match studs. Fasten flat straps to stud flanges and secure solid blocking to stud webs or flanges.
4. Bridging: Proprietary bridging bars installed according to manufacturer's written instructions.

F. Install miscellaneous framing and connections, including stud kickers, web stiffeners, clip angles, continuous angles, anchors, fasteners, and stud girts, to provide a complete and stable wall-framing system.

3.5 JOIST INSTALLATION

A. Install perimeter joist track sized to match joists. Align and securely anchor or fasten track to supporting structure at corners, ends, and spacings indicated on Shop Drawings.

B. Install joists bearing on supporting frame, level, straight, and plumb; adjust to final position, brace, and reinforce. Fasten joists to both flanges of joist track.
1. Install joists over supporting frame with a minimum end bearing of 1-1/2 inches (38 mm).
2. Reinforce ends and bearing points of joists with web stiffeners, end clips, joist hangers, steel clip angles, or steel-stud sections as indicated on Shop Drawings.

C. Space joists not more than 2 inches (51 mm) from abutting walls, and as follows:
1. Joist Spacing: **As indicated**.

D. Frame openings with built-up joist headers consisting of joist and joist track, nesting joists, or another combination of connected joists if indicated.
E. Install joist reinforcement at interior supports with single, short length of joist section located directly over interior support, with lapped joists of equal length to joist reinforcement, or as indicated **on Shop Drawings**.
F. Install bridging at intervals indicated **on Shop Drawings**. Fasten bridging at each joist intersection as follows:
   1. Bridging: Joist-track solid blocking of width and thickness indicated, secured to joist webs.
   2. Bridging: Combination of flat, taut, steel sheet straps of width and thickness indicated and joist-track solid blocking of width and thickness indicated. Fasten flat straps to bottom flange of joists and secure solid blocking to joist webs.
G. Secure joists to load-bearing interior walls to prevent lateral movement of bottom flange.
H. Install miscellaneous joist framing and connections, including web stiffeners, closure pieces, clip angles, continuous angles, hold-down angles, anchors, and fasteners, to provide a complete and stable joist-framing assembly.

3.6 FIELD QUALITY CONTROL
A. Testing: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports, if indicated. Follow AHJ requirements for all special inspections if required.
B. Field and shop welds will be subject to testing and inspecting.
C. Testing agency will report test results promptly and in writing to Contractor and Architect.
D. Remove and replace work where test results indicate that it does not comply with specified requirements.
E. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.7 REPAIRS AND PROTECTION
A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on fabricated and installed cold-formed metal framing with galvanized repair paint according to ASTM A 780 and manufacturer's written instructions.
B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that cold-formed metal framing is without damage or deterioration at time of Substantial Completion.

END OF SECTION 05400

SECTION 05500

METAL FABRICATIONS

PART 1 GENERAL

1.01 SUMMARY

A. Section Includes:
   1. Rough Hardware
   2. Loose Bearing and Leveling Plates
   3. Loose Steel Lintels
   4. Ladders:
      a. Elevator Pit Ladder
      b. Attic & Roof Ladder
   5. Support Angles for Elevator Door Sills
   6. Elevator Sump Pit Cover
   7. Pipe Bollards
   8. Miscellaneous Metal Trim
   9. Steel Framing and Supports for Applications where framing and supports are not specified in other Sections

B. Related Sections:
   1. Section 02820 - Fences and Gates
   2. Section 09900 - Paints and Coatings
   3. Section 09960 - High Performance Coatings
   4. Section 14240 - Hydraulic Elevators

1.02 SUBMITTALS

A. General: Submit the following in accordance with Conditions of Contract and Division 1 Specification Sections.

B. Submit “Letter of Conformance” in accordance with Section 01330.
   1. Include supporting product data for products used in miscellaneous metal fabrications, including paint products and grout.

C. Submit Shop Drawings detailing fabrication and erection of each metal fabrication indicated. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items. Provide templates for anchors and bolts specified for installation under other sections.

D. Submit samples representative of materials and finished products as may be requested by Owner’s Representative.

1.03 QUALITY ASSURANCE

A. Fabricator Qualifications: Firm experienced in successfully producing metal fabrications similar to that indicated for this Project, with sufficient production capacity to produce required units without causing delay in the Work.

B. Installer Qualifications: Arrange for installation of metal fabrications specified in this Section by same firm that fabricated them.

C. Quality welding processes and welding operators in accordance with the following:
   1. AWS D1.1 "Structural Welding Code - Steel"
   2. D1.3 "Structural Welding Code - Sheet Steel"
   3. D1.2 "Structural Welding Code - Aluminum"

D. Certify that each welder has satisfactorily passed AWS qualification tests for welding processes involved and, if pertinent, has undergone recertification.

1.04 PROJECT/SITE CONDITIONS

A. Field Measurements: Check actual locations of walls and other construction to which metal fabrications must fit, by accurate field measurements before fabrication; show recorded measurements on final shop drawings. Coordinate fabrication schedule with construction progress to avoid delay of Work.

1.05 COORDINATION

A. Coordinate installation of anchorages for metal fabrications. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

PART 2 PRODUCTS

2.01 FERROUS METALS

A. Metal Surfaces, General: For metal fabrications exposed to view upon completion of the Work, provide materials selected for their surface flatness, smoothness, and freedom from surface blemishes. Do not use materials whose exposed surfaces exhibit pitting, seam marks, roller marks, rolled trade names, roughness, and, for steel sheet, variations in flatness exceeding those permitted by reference standards for stretcher-leveled sheet.
B. Steel Plates, Shapes, and Bars: ASTM A 36
C. Steel Pipe: ASTM A53
   1. Black finish, unless otherwise indicated.
   2. Galvanized finish for exterior installations, unless shown to receive special coatings.
   3. Type E, OR S, Grade B, Fy = 35 KSI, unless otherwise indicated, or another weight, type, and grade required by structural loads.
D. Gray Iron Castings: ASTM A 48, Class 30
E. Malleable Iron Castings: ASTM A 47, Grade 32510
F. Brackets, Flanges and Anchors: Cast or formed metal of the same type material and finish as supported rails, unless otherwise indicated.
G. Concrete Inserts: Threaded or wedge type; galvanized ferrous castings, either malleable iron, ASTM A 47, or cast steel, ASTM A 27. Provide bolts, washers, and shims as required, hot-dip galvanized per ASTM A 153.
H. Welding Rods: Select in accordance with AWS Specifications for the metal alloy to be welded.

2.02 FASTENERS

A. General: Provide zinc-coated fasteners for exterior use or where built into exterior walls. Select fasteners for the type, grade, and class required for each application and complying with applicable standards.
   1. Bolts and Nuts: Regular hexagon head bolts, ASTM A-307, Grade A with hex nuts ASTM A 563; and, where indicated, flat washers.
   2. Anchor Bolts: ASTM F 1554, Grade30
   3. Lag Bolts: Square head type, ASME B18.2.1
   4. Machine Screws: Cadmium plated steel, ASME B18.6.3
   5. Wood Screws: Flat head carbon steel, ASME B18.6.1
   6. Plain Washers: Round, carbon steel, ASME B18.22.1
   7. Lock Washers: Helical, spring type, carbon steel, ASME B18.21.1
   8. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to six times the load imposed when installed in unit masonry and equal to four times the load imposed when installed in concrete, as determined by testing per ASTM E 488, conducted by a qualified independent testing agency.

a. Interior Use - Material: Carbon-steel components zinc-plated to comply with ASTM B 633, Class Fe/Zn 5.
b. Exterior and Swimming Pool Use - Material: Alloy Group 1 or 2 stainless-steel bolts complying with ASTM F 593 and nuts complying with ASTM F 594.

9. Toggle Bolts: FS FF-B-588, tumble-wing type, class and style as needed.

2.03 GROUT AND ANCHORING CEMENT

A. Nonshrink Nonmetallic Grout: Premixed, factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107. Provide grout specifically recommended by manufacturer for interior and exterior heavy-duty loading applications of type specified in this Section.

B. Interior Anchoring Cement: Factory-prepackaged, nonshrink, nonstaining, hydraulic controlled expansion cement formulation for mixing with water at Project site to create pourable anchoring, patching, and grouting compound. Use for interior applications only.

C. Erosion-Resistant Anchoring Cement: Factory-prepackaged, nonshrink, nonstaining, hydraulic controlled expansion cement formulation for mixing with water at Project site to create pourable anchoring, patching, and grouting compound. Provide formulation that is resistant to erosion from water exposure without need for protection by a sealer or waterproof coating and is recommended for exterior use by manufacturer.

2.04 CONCRETE FILL AND REINFORCING MATERIALS

A. Concrete Materials and Properties: Comply with requirements of Section 03300, and as shown on Drawings, with minimum 28-day compressive strength of 3,000 PSI, unless otherwise indicated.

B. Non-slip Aggregate Finish: Factory-graded, packaged material containing fused aluminum oxide grits or crushed emery as abrasive aggregate; rustproof and non-glazing; unaffected by freezing, moisture, or cleaning materials.

C. Reinforcing Bars: ASTM A-615, Grade 60, unless noted otherwise.

2.05 PAINT

A. Shop Primer for Ferrous Metal: Manufacturer's or fabricator's standard, fast-curing, lead and chromate-free, universal modified alkyd primer selected for good resistance to normal atmospheric corrosion, for compatibility with finish paint systems indicated, and for capability to provide a sound foundation for field-applied topcoats despite prolonged exposure complying with performance requirements of FS TT-P-664.

B. Galvanizing Repair Paint: High zinc dust content paint for regalvanizing welds in galvanized steel, with dry film containing not less than 94 percent zinc dust by weight, and complying with DOD-P-21035 or SSPC-Paint-20.

C. Bituminous Paint: Cold-applied asphalt mastic complying with SSPC-Paint 12 except containing no asbestos fibers.

2.06 FABRICATION - GENERAL

A. Form metal fabrications from materials of size, thickness, and shapes indicated but not less than that needed to comply with performance requirements indicated. Work to dimensions indicated or accepted on shop drawings, using proven details of fabrication and support. Use type of materials indicated or specified for various components of each metal fabrication.

B. Allow for thermal movement resulting from the following maximum change (range) of exterior metalwork in ambient temperature in the design, fabrication, and installation of installed metal assemblies to prevent buckling, opening up of joints, and overstressing of welds and fasteners. Base design calculations on actual surface temperatures of metals due to both solar heat gain and nighttime sky heat loss. Temperature Change (Range): 120 Degrees F., ambient; 130 degrees F., material surfaces.

C. Form exposed work true to line and level with accurate angles and surfaces and straight sharp edges. Ease exposed edges to a radius of approximately 1/32 inch, unless otherwise indicated. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners wherever possible. Use exposed fasteners of type indicated or, if not indicated, Phillips flathead (countersunk) screws or bolts. Locate joints where least conspicuous.

D. Weld corners and seams continuously to comply with AWS recommendations and the following:
   1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
   2. Obtain fusion without undercut or overlap.
   3. Remove welding flux immediately.
   4. At exposed connections, finish exposed welds and surfaces smooth and blended so that no roughness shows after finishing and contour

E. Provide for anchorage of type indicated; coordinate with supporting structure. Fabricate and space anchoring devices to provide adequate support for intended use.

F. Shop Assembly: Preassemble items in shop to greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation. Cut, reinforce, drill and tap miscellaneous metal work as indicated to receive finish hardware, screws, and similar items.

G. Fabricate joints that will be exposed to weather in a manner to exclude water, or provide weep holes where water may accumulate.

2.07 ROUGH HARDWARE

A. Furnish bent or otherwise custom fabricated bolts, plates, anchors, hangers, dowels, and other miscellaneous steel and iron shapes as required for framing and supporting woodwork, and for anchoring or securing woodwork to concrete or other structures. Fabricate items to sizes, shapes, and dimensions required. Furnish malleable-iron washers for heads and nuts which bear on wood structural connections; elsewhere, furnish steel washers.

2.08 STEEL LADDERS

A. General: Fabricate ladders for the locations shown, with dimensions, spacings, and anchorages as indicated. Comply with requirements of ANSI A14.3.

B. Siderails: Continuous, steel, 1/2" x 2-1/2" flat bars, with eased edges, space 18" apart.

C. Bar Rungs: 3/4" diameter steel bars, spaced 12" o.c.

D. Fit rungs in centerline of side rails, plug weld and grind smooth on outer rail faces.

E. Support each ladder at top and bottom and at intermediate points space not more than 5' o.c. with welded or bolted steel brackets.

F. Provide nonslip surfaces on top of each rung, either by coating the rung with aluminum-oxide granules set in epoxy-resin adhesive, or by using a type of manufacture rung that is filled with aluminum-oxide grout.

G. Provide ladder safety cages where required by local codes, to comply with ANSI A14.3.

2.09 LOOSE BEARING AND LEVELING PLATES

A. Provide loose bearing and leveling plates for steel items bearing on masonry or concrete construction, made flat, free from warps or twists, and of required thickness and bearing area. Drill plates to receive anchor bolts and for grouting as required. Galvanize after fabrication.

2.10 LOOSE STEEL LINTELS

A. Fabricate loose structural steel lintels from steel angles and shapes of size indicated for openings and recesses in masonry walls and partitions at locations indicated. Weld adjoining members together to form a single unit where indicated.

B. Hot-dipped galvanize loose steel lintels located in exterior walls.

C. Size loose lintels for equal bearing of one inch per foot of clear span but not less than 8 inches bearing at each side of openings, if not indicated on Drawings.

2.11 MISCELLANEOUS FRAMING AND SUPPORTS

A. General: Provide steel framing and supports for applications indicated or which are not a part of structural steel framework, as required to complete work.

B. Fabricate units to sizes, shapes, and profiles indicated and required to receive adjacent other construction retained by framing and supports. Fabricate from structural steel shapes, plates, and steel bars of welded construction using mitered joints for field connection. Cut, drill, and tap units to receive hardware, hangers, and similar items.

1. Equip units with integrally welded anchors for casting into concrete or building into masonry. Furnish inserts if units must be installed after concrete is placed. Spacing of anchors shall not be more than 24" o.c.

2.12 PIPE BOLLARDS

A. ASTM A153 galvanized schedule 40 steel pipe with concrete fill, as detailed on Drawings. Provide smooth radius for concrete top to prevent accumulation of rainwater. Provide field painted finish.

2.13 MISCELLANEOUS STEEL TRIM

A. Provide shapes and sizes indicated for profiles shown. Unless otherwise indicated, fabricate units from structural steel shapes, plates, and steel bars, with continuously welded joints and smooth exposed edges. Use concealed field splices wherever possible. Provide cutouts, fittings, and anchorages as required for coordination of assembly and installation with other work.

1. Galvanize miscellaneous framing and supports in exterior locations and where shown to be painted.

2.14 FINISHES, GENERAL

A. Comply with NAAMM "Metal Finishes Manual" for “Architectural and Metal Products” for recommendations relative to application and designations of finishes. Finish metal fabrications after assembly.

2.15 STEEL AND IRON FINISHES

A. Galvanizing: For those items indicated for galvanizing, apply zinc-coating by the hot-dip process in compliance with the following requirements:

1. ASTM A-153 for galvanizing iron and steel hardware.
2. ASTM A-123 for galvanizing both fabricated and unfabricated iron and steel products made of uncoated rolled, pressed, and forged shapes, plates, bars, and strip 0.0299 inch thick and heavier.

B. Preparation for Shop Priming: Prepare uncoated ferrous metal surfaces to comply with minimum requirements indicated below for SSPC surface preparation specifications and environmental exposure conditions of installed metal fabrications: Interiors (SSPC Zone 1A): SSPC-SP3 "Power Tool Cleaning".

C. Apply shop primer to uncoated surfaces of metal fabrications, except those with galvanized finish or to be embedded in concrete, sprayed-on fireproofing, or masonry, unless otherwise indicated. Comply with requirements of SSPC-PA1 "Paint Application Specification No. 1" for shop painting. Stripe paint all edges, corners, crevices, bolts, welds, and sharp edges.

PART 3 EXECUTION

3.01 PREPARATION

A. Coordinate and furnish anchorages, setting drawings, diagrams, templates, instructions, and directions for installation of anchorages, including concrete inserts, sleeves, anchor bolts, and miscellaneous items having integral anchors that are to be embedded in concrete or masonry construction. Coordinate delivery of such items to project site.

B. Set sleeves in concrete with tops flush with finish surface elevations; protect sleeves from water and concrete entry.

3.02 INSTALLATION

A. Fastening to In-Place Construction: Provide anchorage devices and fasteners where necessary for securing miscellaneous metal fabrications to in-place construction; include threaded fasteners for concrete and masonry inserts, toggle bolts, through-bolts, lag bolts, wood screws, and other connectors as required.

B. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installation of miscellaneous metal fabrications. Set metal fabrication accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.

C. Provide temporary bracing or anchors in formwork for items that are to be built into concrete masonry or similar construction.

D. Field Welding: Comply with AWS Code for procedures of manual shielded metal-arc welding, appearance and quality of welds made, methods used in correctly welding work, and the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so that no roughness shows after finishing and contour of welded surface matches those adjacent.

3.03 SETTING BEARING AND LEVELING PLATES

A. Clean concrete and masonry bearing surfaces of any bond-reducing materials, and roughen to improve bond to surfaces. Clean bottom surface of plates.

B. Set leveling and bearing plates on wedges, shims, or leveling nuts. After the bearing members have been positioned and plumbed, tighten the anchor bolts. Do not remove wedges or shims, but if protruding, cut off flush with the edge of the bearing plate before packing with grout.

1. Use nonmetallic nonshrink grout, unless otherwise indicated.
2. Pack grout solidly between bearing surfaces and plates to ensure that no voids remain.

3.04 INSTALLING PIPE BOLLARDS

A. Anchor bollards in concrete with pipe sleeves preset and anchored into concrete. After bollards have been inserted into sleeves, fill annular space between bollard and sleeve solidly with nonshrink, nonmetallic grout, mixed and placed to comply with grout manufacturer's written instructions. Slope group up approximately 1/8" toward bollard.

B. Paint bollards yellow in front of dumpsters.

3.05 TOUCH-UP PAINTING: Immediately after erection, clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with same material as used for shop painting to comply with SSPC-PA1 requirements for touch-up of field painted surfaces.

A. Apply by brush or spray to provide a minimum dry film thickness of 2.0 mils.

B. For galvanized surfaces clean welds, bolted connections and abraded areas and apply galvanizing repair paint to comply with ASTM A 780.

END OF SECTION 05500

SECTION 05520

HANDRAILS AND RAILINGS

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Steel pipe, tube handrails, balusters, and fittings.

1.02 DESIGN REQUIREMENTS
A. Railing assembly, wall rails, and attachments to resist lateral force of 75 lbs. at any point without damage or permanent set.

1.03 SUBMITTALS
A. Shop Drawings: Indicate profiles, sizes, connection attachments, anchorage, size and type of fasteners, and accessories.

1.04 FIELD MEASUREMENTS
A. Verify that field measurements are as indicated on shop drawings.

PART 2 PRODUCTS

2.01 STEEL RAILING SYSTEM
A. Rails and Posts: As detailed and indicated on the drawings.
B. Fittings: Elbows, T-shapes, wall brackets, escutcheons; machined steel.
C. Mounting: Adjustable brackets and flanges, with steel inserts for casting in concrete and/or steel brackets for embedding in masonry. Prepare backing plate for mounting in wall construction.
D. Exposed Fasteners: Flush countersunk screws or bolts; consistent with design of railing.
E. Splice Connectors: Steel concealed spigots, welding collars.

2.02 FABRICATION
A. Fit and shop assemble components in largest practical sizes, for delivery to site.
B. Fabricate components with joints tightly fitted and secured.
C. Exposed Mechanical Fastenings: Flush countersunk screws or bolts; unobtrusively located; consistent with design of component, except where specifically noted otherwise.
D. Supply components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.
E. Continuously seal joined pieces by continuous welds.
F. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
G. Accurately form components to suit stairs and landings, to each other and to building structure.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify that field conditions are acceptable and are ready to receive work.
B. Beginning of installation means erector accepts existing conditions.

3.02 PREPARATION
A. Clean and strip primed steel items to bare metal where site welding is required.
B. Supply items required to be cast into concrete and/or embedded in masonry, placed in partitions with setting templates, to appropriate Sections.

3.03 INSTALLATION
A. Install in accordance with manufacturer's instructions.
B. Install components plumb and level, accurately fitted, free from distortion or defects.
C. Provide anchors, plates angles required for connecting railings to structure. Anchor railing to structure.
D. Field weld anchors as indicated on Drawings. Touch-up welds with primer. Grind welds smooth.

E. Conceal bolts and screws whenever possible. Where not concealed, use flush countersunk fastenings.

3.04 ERECTION TOLERANCES

A. Maximum Variation From Plumb: 1/4 inch per story, non-cumulative.

B. Maximum Offset From True Alignment: 1/4 inch.

END OF SECTION 05520

SECTION 06100

ROUGH CARPENTRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Framing with dimension lumber.
   2. Framing with timber.
   3. Framing with engineered wood products.
   4. Wood blocking, cants, and nailers.
   5. Utility shelving.
   6. Wood furring.
   7. Sheathing.
   8. Subflooring and underlayment.
   9. Plywood backing panels.
   10. Building wrap.

1.3 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, with the experience and capability to conduct the testing indicated, as documented according to ASTM E 548.

B. Source Limitations for Engineered Wood Products: Obtain each type of engineered wood product through one source from a single manufacturer.

C. Source Limitations for Fire-Retardant-Treated Wood: Obtain each type of fire-retardant-treated wood product through one source from a single producer.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber, plywood, and other panels; place spacers between each bundle to provide air circulation. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

A. Lumber: DOC PS 20 and applicable rules of lumber grading agencies certified by the American Lumber Standards Committee Board of Review.
   1. Factory mark each piece of lumber with grade stamp of grading agency.
   2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece.
   3. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
   4. Provide dressed lumber, S4S, unless otherwise indicated.
   5. Provide dry lumber with 19 percent maximum moisture content at time of dressing for 2-inch nominal thickness or less, unless otherwise indicated.
   6. Provide dry lumber with 15 percent maximum moisture content at time of dressing for 2-inch nominal thickness or less, unless otherwise indicated.

B. Engineered Wood Products: Provide engineered wood products acceptable to authorities having jurisdiction and for which current model code research or evaluation reports exist that show compliance with building code in effect for Project.
   1. Allowable Design Stresses: Provide engineered wood products with allowable design stresses, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

C. Wood Structural Panels:
   1. Plywood: DOC PS 1.
   2. Oriented Strand Board: DOC PS 2.

3. Thickness: As needed to comply with requirements specified but not less than thickness indicated.
4. Comply with "Code Plus" provisions in APA Form No. E30K, "APA Design/Construction Guide: Residential & Commercial."
5. Factory mark panels according to indicated standard.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

A. Preservative Treatment by Pressure Process: AWPA C2 lumber except that lumber that is not in contact with the ground and is continuously protected from liquid water may be treated according to AWPA C31 with inorganic boron (SBX).
   1. Preservative Chemicals: Acceptable to authorities having jurisdiction and one of the following:
      a. Chromated copper arsenate (CCA).
      b. Ammoniacal copper zinc arsenate (ACZA).
      c. Ammoniacal, or amine, copper quat (ACQ).
      d. Copper bis (dimethyldithiocarbamate) (CDDC).
      e. Ammoniacal copper citrate (CC).
      f. Copper azole, Type A (CBA-A).
      g. Oxine copper (copper-8-quinolinolate) in a light petroleum solvent.
   2. For exposed items indicated to receive a stained or natural finish, use chemical formulations that do not require incising, contain colorants, bleed through, or otherwise adversely affect finishes.
B. Kiln-dry material after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood. Do not use material that is warped or does not comply with requirements for untreated material.
C. Mark each treated item with the treatment quality mark of an inspection agency approved by the American Lumber Standards Committee Board of Review.
D. Application: Treat items indicated on Drawings, and the following:
   1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
   2. Wood sills, sleepers, blocking, furring, stripping, and similar concealed members in contact with masonry or concrete.
   3. Wood framing members less than 18 inches above grade.
   4. Wood floor plates that are installed over concrete slabs directly in contact with earth.

2.3 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, provide materials that comply with performance requirements in AWPA C20 lumber and AWPA C27 plywood. Identify fire-retardant-treated wood with appropriate classification marking of UL, U.S. Testing, Timber Products Inspection, or another testing and inspecting agency acceptable to authorities having jurisdiction.
   1. Use treatment for which chemical manufacturer publishes physical properties of treated wood after exposure to elevated temperatures, when tested by a qualified independent testing agency according to ASTM D 5664, for lumber and ASTM D 5516, for plywood
   2. Use treatment that does not promote corrosion of metal fasteners.
   3. Use Exterior type for exterior locations and where indicated.
   4. Use Interior Type A High Temperature (HT), unless otherwise indicated.
B. For exposed items indicated to receive a stained or natural finish, use chemical formulations that do not bleed through, contain colorants, or otherwise adversely affect finishes.

2.4 DIMENSION LUMBER

A. General: Provide dimension lumber of grades indicated according to the American Lumber Standards Committee National Grading Rule provisions of the grading agency indicated.
B. Non-Load-Bearing Interior Partitions: Construction, Stud, or No. 2 grade.
C. Exterior and Load-Bearing Walls Construction or No. 2 grade.
D. Ceiling Joists (Non-Load-Bearing): Construction or No. 2 grade.
E. Joists, Rafters, and Other Framing Not Listed Above: Construction or No. 1 grade.

2.5 MISCELLANEOUS LUMBER

A. General: Provide lumber for support or attachment of other construction, including the following:
   1. Rooftop equipment bases and support curbs.
   2. Blocking.
   3. Cants.
   4. Nailers.
   5. Furring.

6. Grounds.

B. For items of dimension lumber size, provide Construction, Stud, or No. 2 grade lumber with 15 percent maximum moisture content.

C. For exposed boards, provide lumber with 15 percent maximum moisture content.

D. For concealed boards, provide lumber with 15 percent maximum moisture content.

E. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.6 ENGINEERED WOOD PRODUCTS

A. Veneer Lumber: A composite of wood veneers with grain primarily parallel to member lengths, manufactured with an exterior-type adhesive complying with ASTM D 2559.

B. Parallel-Strand Lumber: A composite of wood strand elements with grain primarily parallel to member lengths, manufactured with an exterior-type adhesive complying with ASTM D 2559.

C. Wood I-Joists: Prefabricated units complying with APA PRI-400; depths and performance ratings not less than those indicated.

D. Rim Boards: Performance-rated product complying with APA PRR-401.

2.7 SHEATHING

A. Reference drawings, the following are minimums where sheathing is not noted on drawings.

B. Plywood Wall Sheathing: Exposure 1, Structural I sheathing.
1. Span Rating: Not less than 24/0.
2. Thickness: Not less than 1/2 inch.

C. Oriented-Strand-Board Wall Sheathing: Exposure 1, Structural I sheathing.
1. Span Rating: Not less than 24/0.
2. Thickness: Not less than 1/2 inch.

D. Glass-Mat Gypsum Wall Sheathing: ASTM C 1177/1177M.
1. Product: Subject to compliance with requirements, provide "Dens-Glass Gold" by G-P Gypsum Corp.
2. Type and Thickness: Regular, 5/8 inch thick.
3. Size: 48 by 96 inches for vertical installation.

E. Plywood Roof Sheathing: Exterior, Structural I sheathing.
1. Span Rating: Not less than 32/16.
2. Thickness: Not less than 5/8 inch.

F. Oriented-Strand-Board Roof Sheathing: Exposure 1, Structural I sheathing.
1. Span Rating: Not less than 32/16.
2. Thickness: Not less than 5/8 inch.

2.8 PLYWOOD BACKING PANELS

A. Telephone and Electrical Equipment Backing Panels: DOC PS 1, Exposure 1, C-D Plugged, fire-retardant treated, in thickness indicated or, if not indicated, not less than 1/2 inch thick.

2.9 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this Article for material and manufacture.
1. Where rough carpentry is exposed to weather, in ground contact, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.

B. Nails, Brads, and Staples: ASTM F 1667.

C. Power-Driven Fasteners: CABO NER-272.

D. Wood Screws: ASME B18.6.1.

E. Screws for Fastening to Cold-Formed Metal Framing: ASTM C 954, except with wafer heads and reamer wings, length as recommended by screw manufacturer for material being fastened.

F. Lag Bolts: ASME B18.2.1.

G. Bolts: Steel bolts complying with ASTM A 307, Grade A with ASTM A 563 hex nuts and, where indicated, flat washers.

H. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to 6 times the load imposed when installed in unit masonry assemblies and equal to 4 times the load imposed when installed in concrete as determined by testing per ASTM E 488 conducted by a qualified independent testing and inspecting agency.
1. Material: Carbon-steel components, zinc plated to comply with ASTM B 633, Class Fe/Zn 5.
2. Material: Stainless steel with bolts and nuts complying with ASTM F 593 and ASTM F 594, Alloy Group 1 or 2.

2.10 METAL FRAMING ANCHORS

A. General: Provide framing anchors made from metal indicated, of structural capacity, type, and size indicated, and as follows:
   1. Research/Evaluation Reports: Provide products acceptable to authorities having jurisdiction and for which model code research/evaluation reports exist that show compliance of metal framing anchors, for application indicated, with building code in effect for Project.
   2. Allowable Design Loads: Provide products with allowable design loads, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

B. Galvanized Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A 653/A 653M, G60 coating designation.

C. Stainless-Steel Sheet: ASTM A 666, Type 304.
   1. Use for exterior locations and where indicated.

D. Joist Hangers: U-shaped joist hangers with 2-inch- long seat and 1-1/4-inch- wide nailing flanges at least 85 percent of joist depth.
   1. Thickness: 0.050 inch.

E. I-Joist Hangers: U-shaped joist hangers with 2-inch- long seat and 1-1/4-inch- wide nailing flanges full depth of joist. Nailing flanges provide lateral support at joist top chord.
   1. Thickness: 0.050 inch.

F. Top Flange Hangers: U-shaped joist hangers, full depth of joist, formed from metal strap with tabs bent to extend over and be fastened to supporting member.
   1. Strap Width: 1-1/2 inches.
   2. Thickness: 0.050 inch.

G. Bridging: Rigid, V-section, nailless type, 0.062 inch thick, length to suit joist size and spacing.

H. Post Bases: Adjustable-socket type for bolting in place with standoff plate to raise post 1 inch above base and with 2-inch- minimum side cover, socket 0.062 inch thick, and standoff and adjustment plates 0.108 inch thick.

I. Joist Ties: Flat straps, with holes for fasteners, for tying joists together over supports.
   1. Width: 3/4 inch.
   2. Thickness: 0.050 inch.
   3. Length: 16 inches.

J. Rafter Tie-Downs: Bent strap tie for fastening rafters or roof trusses to wall studs below, 1-1/2 inches wide by 0.050 inch thick. Tie fastens to side of rafter or truss, face of top plates, and side of stud below.

K. Rafter Tie-Downs (Hurricane or Seismic Ties): Bent strap tie for fastening rafters or roof trusses to wall studs below, 2-1/4 inches wide by 0.062 inch thick. Tie fits over top of rafter or truss and fastens to both sides of rafter or truss, face of top plates, and side of stud below.

L. Floor-to-Floor Ties: Flat straps, with holes for fasteners, for tying upper floor wall studs to band joists and lower floor studs, 1-1/4 inches wide by 0.050 inch thick by 36 inches long.

M. Hold-Downs: Brackets for bolting to wall studs and securing to foundation walls with anchor bolts or to other hold-downs with threaded rods and designed with first of two bolts placed seven bolt diameters from reinforced base.

N. Wall Bracing: T-shaped bracing made for letting into studs in saw kerf, 1-1/8 inches wide by 9/16 inch deep by 0.034 inch thick with hemmed edges.

O. Wall Bracing: Angle bracing made for letting into studs in saw kerf, 15/16 by 15/16 by 0.040 inch thick with hemmed edges.

2.11 MISCELLANEOUS MATERIALS

A. Building Paper: Asphalt-saturated organic felt complying with ASTM D 226, Type I (No. 15 asphalt felt), unperforated.

B. Building Wrap: Air-retarder sheeting made from polyolefins; cross-laminated films, woven strands, or spun-bonded fibers; coated or uncoated; with or without perforations; and complying with ASTM E 1677, Type I.
   1. Thickness: Not less than 3 mils
   2. Permeance: Not less than 10 perms
   3. Flame-Spread Index: 25 or less per ASTM E 84.
   4. Allowable Exposure Time: Not less than three months.

C. Building Wrap Tape: Pressure-sensitive plastic tape recommended by building wrap manufacturer for sealing joints and penetrations in building wrap.

D. Sheathing Tape: Pressure-sensitive plastic tape for sealing joints and penetrations in sheathing and recommended by sheathing manufacturer for use with type of sheathing required.

E. Sill-Sealer Gaskets: Glass-fiber-resilient insulation, fabricated in strip form, for use as a sill sealer; 1-inch nominal thickness, compressible to 1/32 inch ; selected from manufacturer's standard widths to suit width of sill members indicated.
F. Sill-Sealer Gaskets: Closed-cell neoprene foam, 1/4 inch thick, selected from manufacturer's standard widths to suit width of sill members indicated.
G. Adhesives for Field Gluing Panels to Framing: Formulation complying with ASTM D 3498 that is approved for use with type of construction panel indicated by both adhesive and panel manufacturers.
H. Water-Repellent Preservative: NWWDA-tested and -accepted formulation containing 3-iodo-2-propynyl butyl carbamate, combined with an insecticide containing chloropyrifos as its active ingredient.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.
B. Do not use materials with defects that impair quality of rough carpentry or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
C. Apply field treatment complying with AWPA M4 to cut surfaces of preservative-treated lumber and plywood.
D. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
    1. CABO NER-272 for power-driven fasteners.
    2. Published requirements of metal framing anchor manufacturer.
    3. Table 23-II-B-1, "Nailing Schedule," and Table 23-II-B-2, "Wood Structural Panel Roof Sheathing Nailing Schedule," in the Uniform Building Code.
    4. Table 2305.2, "Fastening Schedule," in the BOCA National Building Code.
    5. Table 2306.1, "Fastening Schedule," in the Standard Building Code.
    6. Table 602.3(1), "Fastener Schedule for Structural Members," and Table 602.3(2), "Alternate Attachments," in the International One- and Two-Family Dwelling Code.
E. Use common wire nails, unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood; predrill as required.
F. Use finishing nails for exposed work, unless otherwise indicated. Countersink nail heads and fill holes with wood filler.

3.2 WOOD GROUND, SLEEPER, BLOCKING, AND NAILER INSTALLATION

A. Install where indicated and where required for screeding or attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces, unless otherwise indicated. Build anchor bolts into masonry during installation of masonry work. Where possible, secure anchor bolts to formwork before concrete placement.
C. Provide permanent grounds of dressed, pressure-preservative-treated, key-beveled lumber not less than 1-1/2 inches wide and of thickness required to bring face of ground to exact thickness of finish material. Remove temporary grounds when no longer required.

3.3 WOOD FRAMING INSTALLATION, GENERAL

A. Framing Standard: Comply with AFPA's "Manual for Wood Frame Construction," unless otherwise indicated.
B. Framing with Engineered Wood Products: Install engineered wood products to comply with manufacturer's written instructions.
C. Do not splice structural members between supports.
D. Where built-up beams or girders of 2-inch nominal- dimension lumber on edge are required, fasten together with 2 rows of 20d nails spaced not less than 32 inches o.c. Locate one row near top edge and other near bottom edge.

3.4 WALL AND PARTITION FRAMING INSTALLATION

A. General: Arrange studs so wide face of stud is perpendicular to direction of wall or partition and narrow face is parallel. Provide single bottom plate and double top plates using members of 2-inch nominal thickness whose widths equal that of studs, except single top plate may be used for non-load-bearing partitions. Anchor or nail plates to supporting construction, unless otherwise indicated.
   1. For exterior walls, provide 2-by-4-inch nominal- size wood studs spaced 16 inches o.c., unless otherwise indicated.
   2. For interior partitions and walls, provide 2-by-4-inch nominal-size wood studs spaced 16 inches o.c., unless otherwise indicated.

B. Construct corners and intersections with three or more studs. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.
   1. Provide continuous horizontal blocking at midheight of partitions more than 96 inches high, using members of 2-inch nominal thickness and of same width as wall or partitions.

C. Fire block concealed spaces of wood-framed walls and partitions at each floor level and at ceiling line of top story. Where fire blocking is not inherent in framing system used, provide closely fitted wood blocks of 2-inch nominal- thick lumber of same width as framing members.

D. Frame openings with multiple studs and headers. Provide nailed header members of thickness equal to width of studs. Set headers on edge and support on jamb studs.
   1. For non-load-bearing partitions, provide double-jamb studs with headers not less than 4-inch nominal depth for openings 48 inches and less in width, 6-inch nominal depth for openings 48 to 72 inches in width, 8-inch nominal depth for openings 72 to 120 inches in width, and not less than 10-inch nominal depth for openings 10 to 12 feet in width.
   2. For load-bearing walls, provide double-jamb studs for openings 72 inches and less in width, and triple-jamb studs for wider openings. Provide headers of depth indicated.

E. Provide bracing in exterior walls, at both walls of each external corner, full-story height, unless otherwise indicated. Provide one of the following:

F. Provide bracing in walls, at locations indicated, full-story height, unless otherwise indicated. Provide one of the following:
   1. Diagonal bracing at 45-degree angle using let-in 1-by-4-inch nominal- size boards.
   2. Diagonal bracing at 45-degree angle using metal bracing.
   3. Plywood panels not less than 48 by 96 inches applied vertically.
   4. Oriented-strand-board panels not less than 48 by 96 inches applied vertically.
   5. Particleboard sheathing panels not less than 48 by 96 inches applied vertically.
   6. In lieu of bracing at corners or at locations indicated, continuous gypsum sheathing may be provided in panels not less than 48 by 96 inches applied vertically.
   7. In lieu of bracing at corners or at locations indicated, continuous fiberboard sheathing, intermediate type, may be provided in panels not less than 48 by 96 inches applied vertically.

3.5 CEILING JOIST AND RAFTER FRAMING INSTALLATION

A. Ceiling Joists: Install ceiling joists with crown edge up and complying with requirements specified above for floor joists. Face nail to ends of parallel rafters.
   1. Where ceiling joists are at right angles to rafters, provide additional short joists parallel to rafters from wall plate to first joist; nail to ends of rafters and to top plate and nail to first joist or anchor with framing anchors or metal straps. Provide 1-by-8-inch nominal- size or 2-by-4-inch nominal- size stringers spaced 48 inches o.c. crosswise over main ceiling joists.

B. Rafters: Notch to fit exterior wall plates and use metal framing anchors. Double rafters to form headers and trimmers at openings in roof framing, if any, and support with metal hangers. Where rafters abut at ridge, place directly opposite each other and nail to ridge member or use metal ridge hangers.
   1. At valleys, provide double-valley rafters of size indicated or, if not indicated, of same thickness as regular rafters and 2 inches deeper. Bevel ends of jack rafters for full bearing against valley rafters.
   2. At hips, provide hip rafter of size indicated or, if not indicated, of same thickness as regular rafters and 2 inches deeper. Bevel ends of jack rafters for full bearing against hip rafter.

C. Provide collar beams (ties) as indicated or, if not indicated, provide 1-by-6-inch nominal-size boards between every third pair of rafters, but not more than 48 inches o.c. Locate below ridge member, at third point of rafter span. Cut ends to fit roof slope and nail to rafters.

D. Provide special framing as indicated for eaves, overhangs, dormers, and similar conditions, if any.

3.6 FIBERBOARD SHEATHING INSTALLATION

A. Fasten fiberboard sheathing panels to intermediate supports and then at edges and ends. Use galvanized roofing nails; comply with manufacturer's recommended spacing and referenced fastening schedule. Drive fasteners flush with surface of sheathing and locate perimeter fasteners at least 3/8 inch from edges and ends.

B. Install sheathing vertically with long edges parallel to, and centered over, studs. Install solid wood blocking where end joints do not occur over framing. Allow 1/8-inch open space between edges and ends of adjacent units. Stagger horizontal joints, if any.

C. Cover sheathing as soon as practical after installation to prevent deterioration from wetting.

3.7 BUILDING PAPER APPLICATION

A. Apply building paper horizontally with 2-inch overlap and 6-inch end lap; fasten to sheathing with galvanized staples or roofing nails. Cover upstanding flashing with 4-inch overlap.

3.8 BUILDING WRAP APPLICATION

A. Cover wall sheathing with building wrap as indicated.
   1. Comply with manufacturer's written instructions.
   2. Cover upstanding flashing with 4-inch overlap.
   3. Seal seams, edges, and penetrations with tape.
   4. Extend into jambs of openings and seal corners with tape.

3.9 SHEATHING TAPE APPLICATION

A. Apply sheathing tape to joints between sheathing panels and at items penetrating sheathing. Apply at upstanding flashing to overlap both flashing and sheathing.

END OF SECTION 06100

SECTION 06112

FRAMING AND SHEATHING

PART 1 – GENERAL

1.01 SECTION INCLUDES
- A. Structural roof framing.
- B. 2 x 4, 2 x 6 stud wall framing.
- C. Telephone and electrical panel boards.
- D. Concealed wood blocking for support of wall cabinets, wood trim and rails.

1.02 GENERAL
- A. All notes or specifications on street drawings shall override any discrepancies listed.

1.03 REFERENCES
- A. ALSC: American Lumber Standards Committee - Softwood, Lumber Standards.
- B. APA: American Plywood Association.
- C. NFPA: National Forest Products Association.

1.04 QUALITY ASSURANCE
- A. Perform Work in accordance with the following agencies:
  1. Lumber Grading Agency: Certified by ALSC.
  2. Plywood Grading Agency: Certified by APA.

PART 2 – PRODUCTS

2.01 LUMBER MATERIALS
- A. Lumber Grading Rules: NFPA.
- B. Truss Framing: Stress Group, Douglas Fir species, standard grade, 2” x 6” size classification, 19 percent maximum moisture content.
- C. Studding: Stress Group, Douglas Fir species, standard grade, 2” x 4” size classification, 19 percent maximum moisture content.

2.02 SHEATHING MATERIALS
- A. Reference Section 061600 Sheathing Zip System.

2.03 ACCESSORIES
- A. Fasteners and Anchors:
  1. Fasteners: Hot-dipped galvanized steel for high humidity and treated wood locations, unfinished steel elsewhere.
  2. Drywall Screws: Bugle head, hardened steel, power driven type, length three times thickness of sheathing.
  3. Anchors: Toggle bolt type for anchorage to hollow masonry. Expansion shield and lag bolt type for anchorage to solid masonry or concrete. Bolt or ballistic fastener for anchorages to steel.
- B. Sill Gasket on Top of Foundation Wall: All as approved by Architect.
- C. Building Paper: No. 15 asphalt felt.

PART 3 – EXECUTION

3.01 FRAMING
- A. Set structural members level and plumb, in correct position.
- B. Make provisions for erection loads, and for sufficient temporary bracing to maintain structure safe, plumb, and in true alignment until completion of erection and installation of permanent bracing.
- C. Place horizontal members flat, crown side up.
- D. Construct load bearing framing members full length without splices.
- E. Double members at openings over 24 inches wide. Space short studs over and under opening to stud spacing.
- F. Construct double joist headers at floor and ceiling openings and under wall stud partitions that are parallel to floor joists. Frame rigidly into joists.

G. Bridge joists framing in excess of 8 feet span as detailed at mid-span. Fit bridging at ends of members.
H. Place full width continuous sill flashings under framed walls on cementitious foundations. Lap flashing joint 4 inches.
I. Place sill gasket directly on sill flashing. Puncture gasket clean and fit tight to protruding foundation anchor bolts.

3.02 SHEATHING
A. Secure roof sheathing perpendicular to framing members with ends staggered and sheet ends over firm bearing. Use sheathing clips between sheets between roof framing members. Provide solid edge blocking between sheets.
B. Secure wall sheathing with long dimension (parallel) to wall studs, with ends over firm bearing and staggered.
C. Place building paper horizontally over wall sheathing, weather lap edges and ends.
D. Install telephone and electrical panel boards with plywood sheathing material where required. Over size the panel by 12 inches on all sides.

3.03 TOLERANCES
A. Framing Members: 1/4 inch from true position, maximum.

3.04 SCHEDULES
A. Above Grade Truss, Rafter, and Stud Framing: S/P/F species, 19 percent maximum moisture content, unless noted otherwise on drawings.
B. Blocking: S/P/F species, pressure preservative treatment.

END OF SECTION 06112

SECTION 06114

WOOD BLOCKING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Roof curbs and cants.
- B. Blocking in wall and roof openings.
- C. Wood furring and grounds.
- D. Concealed wood blocking for support of toilet and bath accessories, wall cabinets, and wood trim.
- E. Telephone and electrical panel boards.

PART 2 PRODUCTS

2.01 MATERIALS
- A. Miscellaneous Blocking: Minimum stud grade.
- B. Plywood: APA Rated Sheathing, Grade C-D; Exposure Durability 1; sanded.

2.02 ACCESSORIES
- A. Fasteners and Anchors:
  1. Fasteners: Hot-dipped galvanized steel for high humidity and treated wood locations, unfinished steel elsewhere.
  2. Anchors: Toggle bolt type for anchorage to hollow masonry. Expansion shield and lag bolt type for anchorage to solid masonry or concrete. Bolt or ballistic fastener for anchorages to steel.

PART 3 EXECUTION

3.01 FRAMING
- A. Set members level and plumb, in correct position.
- B. Place horizontal members flat, crown side up.
- C. Space framing and furring 16 inches o.c.

3.02 SHEATHING
- A. Secure sheathing to framing members with ends over firm bearing and staggered.
- B. Install telephone and electrical panel boards with plywood sheathing material where required. Over size the panel by 12 inches on all sides.

END OF SECTION 06114

SECTION 06200

FINISH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Finish carpentry items, other than shop prefabricated casework.
- B. Hardware and attachment accessories.

1.02 QUALITY ASSURANCE
- A. Perform work in accordance with AWI Custom.

1.03 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site under provisions of the General Requirements.
- B. Protect work from moisture damage.

1.04 FIELD MEASUREMENTS
- A. Verify that field measurements are as indicated on shop drawings and as instructed by the manufacturer.

1.05 COORDINATION
- A. Coordinate the work with plumbing and electrical rough-in, and installation of associated and adjacent components.

PART 2 PRODUCTS

2.01 LUMBER MATERIALS
- A. Softwood Lumber: PS 20; Graded in accordance with AWI Custom; maximum moisture content of 6 percent; suitable for prime and paint.
- B. Hardwood Lumber: Graded in accordance with AWI prime and paint.

2.02 SHEET MATERIALS
- A. Exterior Plywood: Exposed to weather shall be group 1, Exterior type, Grade A-B or A-C as required for exposure.
- B. Interior Plywood: Interior or Exterior type, Group 1 or 2, Grade B-D where concealed, Grade A-C one side exposed and Grade A-A two sides exposed.
- C. Wood Particleboard: ANSI A208.1 Type 1; AWI standard, composed of wood chips, medium density, made with high waterproof resin binders; of grade to suit application; sanded faces.

2.03 FASTENERS
- A. Fasteners: Of size and type to suit application; galvanized finish in concealed locations and brass or chrome finish in exposed locations.

2.04 FABRICATION
- A. Fabricate to AWI Custom standards.
- B. Shop assemble work for delivery to site, permitting passage through building openings.
- C. Fit exposed sheet material edges with 3/8 inch matching hardwood edging. Use one piece for full length only.
- D. When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide trim for scribing and site cutting.

2.05 SHOP FINISHING
- A. Sand work smooth and set exposed nails and screws.
- B. Apply wood filler in exposed nail and screw indentations.
- C. On items to receive transparent finishes, use wood filler which matches surrounding surfaces and of types recommended for applied finishes.
- D. Seal, stain and varnish exposed to view surfaces. Brush apply only.
- E. Prime paint. Seal surfaces in contact with cementitious materials.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify adequacy of backing and support framing.
B. Verify mechanical, electrical, and building items affecting work of this section are placed and ready to receive this work.

3.02 INSTALLATION

A. Install work in accordance with AWI Custom Quality Standard.
B. Set and secure materials and components in place, plumb and level.
C. Carefully scribe work abutting other components, with maximum gaps of 1/32 inch. Do not use additional overlay trim to conceal larger gaps.
D. Install components trim with nails, screws, bolts with blind fasteners or wall adhesive by gun application.
E. Install hardware in accordance with manufacturer's instructions.

3.03 SITE APPLIED WOOD TREATMENT

A. Apply preservative treatment in accordance with manufacturer's instructions.
B. Brush apply two coats of preservative treatment on wood in contact with cementitious materials, roofing and related metal flashings. Treat site-sawn cuts.
C. Allow preservative to dry prior to erecting members.

3.04 PREPARATION FOR SITE FINISHING

A. Site Finishing: Refer to Section 09900.
B. Before installation, prime paint surfaces of items or assemblies to be in contact with cementitious materials.

3.05 SCHEDULE

A. Interior:
   1. Trim: Primed and painted.
   2. Loose Shelving: Melamine finished, color to be selected.
   3. Window Sills: Primed and painted.
   4. Wood Base: Primed and painted.
   5. Wood Light Valance, primed and painted.

END OF SECTION 06200

SECTION 06410

CUSTOM CASEWORK

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Countertops, base and wall cabinets for Public Areas.
B. Wall Paneling
C. Cabinet hardware.
D. Prefinished surfaces and preparation for site finishing.
E. Preparation for installing utilities.

1.02 SUBMITTALS
A. Shop Drawings: Indicate materials, component profiles and elevations, assembly methods, joint details, fastening methods, accessory listings, hardware location, and schedule of finishes.

1.03 QUALIFICATIONS
A. Manufacturer: Company specializing in manufacturing the products specified in this section with minimum three years' documented experience.

1.04 DELIVERY, STORAGE, AND HANDLING
A. Deliver, store and handle products to site.
B. Protect units from moisture damage.

1.05 FIELD MEASUREMENTS
A. Verify that field measurements are as on shop drawings.

1.06 COORDINATION
A. Coordinate the work with plumbing and electrical rough-in.

PART 2 PRODUCTS

2.01 MANUFACTURERS
A. Salina Planing Mill.
B. Technique MFG
C. Crestwood MFG
D. Timberline MFG
E. Substitutions: Under provisions of the General Requirements.

2.02 WOOD MATERIALS
A. Hardwood Lumber: FS MM-L-736; graded in accordance with AWI Premium Grade; average moisture content of 6 percent; species and grade as follows: To be Selected**.**

2.03 SHEET MATERIALS
A. Hardwood Plywood: S 51; graded in accordance with AWI, core materials of veneer, and lumber, type of glue recommended for application; face veneer and cuts as follows:

ITEM	FACE SPECIES
Drawer 'Box' Construction	Per AWI Premium Grade.
Wall Paneling	Plastic Laminate (u.n.o.) - Per AWI Premium Grade.
Door Construction	Plastic Laminate and Wood - Per AWI Premium Grade.
Cabinet 'Body' Construction	Plastic Laminate and Wood - Per AWI Premium Grade.
Backs	Plastic Laminate and Wood - Per AWI Premium Grade.
Shelving	Plastic Laminate and Wood - Per AWI Premium Grade.

(Full line of colors for all plastic Laminate selected by owner.)

B. High Performance particleboard Core:
1. Particleboard to be ¾" thick of 45 lb. Density, and balanced construction with moisture content not to exceed 8%. All particleboards shall meet or exceed the requirements for its type and classification under Commercial Standard CS-236-66, Federal Specifications LLL-B-800A, and ASTM D 1037-78.
2. Particleboard shall meet the following performance requirements. Submit compliance data from the manufacturer prior to fabrication:

Screw Holding, Face	471 lbs.
Modulus of Rupture	2,400 psi.
Modulus of Elasticity	450,000 psi.
Internal Bond	90 psi.
Surface Hardness	900 lbs.

C. Hardboard: Hardboard shall meet or exceed Commercial Standards CS-251 and Federal Specifications LLL-B-00810. Tempered hardboard ¼" thick, smooth both sides.

2.04 MANUFACTURERS - PLASTIC LAMINATE
A. Wilsonart, Formica, Arborite, Pionite or Nevamar. (Full Line of all manufacturers)

2.07 LAMINATE MATERIALS
A. Plastic Laminate: AWI, 0.040 inch Post Forming 0.050 inch General Purpose quality; color, pattern, and surface texture as selected.
B. Laminate Backing Sheet: 0.020 inch Backing Sheet grade, undecorated plastic laminate.

2.08 ACCESSORIES
A. Adhesive: FS MMM-A-130 contact adhesive, type recommended by AWI and laminate manufacturer to suit application.
B. Fasteners: Size and type to suit application.
C. Bolts, Nuts, Washers, Lags, Pins, and Screws: Of size and type to suit application; approved finish in exposed locations.
D. Concealed Joint Fasteners: Threaded steel.

2.08 HARDWARE
A. Hinges: To be Selected.
B. Pulls: To be Selected.
C. Drawer Slides: To be Selected.
D. Adjustable shelf clips: To be Selected.
E. Cushion Bumpers: Hafele #356.21.428 – clear. Two on each door & drawer.
F. "Recessed" Adjustable shelf standards: Knape & Vogt, #255, zinc finish.
G. Grommets: Hafele, Series #429, full range colors. Locate per shop drawings review.
H. Catches: Amerock, #9783 magnetic.

2.09 FINISHING MATERIALS
A. Stain, Varnish and Finishing Materials: As specified in Section 09900.

2.10 FABRICATION
A. Shop assemble casework for delivery to site in units easily handled and to permit passage through building openings.
B. Fit shelves, doors, and exposed edges with .02 inch pvc. Use one piece for full length only.
C. Cap exposed plastic laminate finish edges with material of same finish and pattern.
D. Door and Drawer Fronts: 3/4 inch thick; overlay style.
E. When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide trim for scribing and site cutting.
F. Apply plastic laminate finish in full uninterrupted sheets consistent with manufactured sizes. Fit corners and joints hairline; secure with concealed fasteners. Slightly bevel arises. Locate counter butt joints minimum 2 feet from sink cut-outs.
G. Apply laminate backing sheet to reverse side of plastic laminate finished surfaces.
H. Provide cutouts for plumbing fixtures, inserts, appliances, outlet boxes, fixtures and fittings. Verify locations of cutouts from on-site dimensions. Seal contact surfaces of cut edges.

2.11 FINISHING

A. Sand work smooth and set exposed nails and screws.
B. Apply wood filler in exposed nail and screw indentations.
C. On items to receive transparent finishes, use wood filler, which matches surrounding surfaces and of types recommended for applied finishes.
D. Seal, stain and varnish exposed to view surfaces.
E. Seal, stain and varnish internal exposed to view and semi-concealed surfaces.
F. Seal surfaces in contact with cementitious materials.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify adequacy of backing and support framing.

3.02 INSTALLATION

A. Set and secure casework in place; rigid, plumb, and level.
B. Use fixture attachments in concealed locations for wall mounted components.
C. Use concealed joint fasteners to align and secure adjoining cabinet units and counter tops.
D. Carefully scribe casework abutting other components, with maximum gaps of 1/32 inch. Do not use additional overlay trim for this purpose.
E. Secure cabinet and counter bases to floor using appropriate angles and anchorages.
F. Countersink anchorage devices at exposed locations. Conceal with solid wood plugs of species to match surrounding wood; finish flush with surrounding surfaces.

3.03 ADJUSTING

A. Adjust moving or operating parts to function smoothly and correctly.

3.04 CLEANING

A. Clean casework, counters, shelves, hardware, fittings and fixtures.

3.05 SCHEDULE

A. Adjustable shelving longer than 34” to be 1” thick.
B.

END OF SECTION 06410

SECTION 07213

BATT INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Batt insulation at exterior stud walls.
- B. Batt insulation at attic space.
- C. Batt insulation for filling perimeter window and door shim spaces, crevices in exterior wall and roof.
- D. Sound batt insulation.
- E. Vapor retarder.

1.02 REFERENCES
- A. ASTM C665 - Mineral Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing.
- B. ASTM E84 - Test Method for Surface Burning Characteristics of Building Materials.

1.03 SYSTEM DESCRIPTION
- A. Materials of This Section: Provide continuity of thermal barrier at building enclosure with thermal insulating materials in attic and walls.. Overlap insulations to ensure complete thermal envelope at all exterior surfaces.

1.04 COORDINATION
- A. Coordinate the work with all related Sections for installation of vapor retarder and other forms of insulation.

PART 2 PRODUCTS

2.01 MANUFACTURERS - INSULATION MATERIALS
- A. OWENS-CORNING FIBERGLASS Product - thermal batt insulation.
- B. Substitutions: Under provisions of the General Requirements.

2.02 MATERIALS
- A. Batt Insulation, Walls: ASTM C665; preformed glass fiber batts; loose laid and taped, conforming to the following:
  1. Thermal Resistance: reference drawings
  2. Other areas as indicated in the drawings R-11.
  3. Batt Size: 3-1/2” and/or 5-1/2”.
  4. Facing: Kraft paper or unfaced as noted on wall type schedules, and as required to meet R values and code requirements.
- B. Blown Insulation, Attic: ASTM C739; Cellulose Fiber or Fiberglass type.
  1. **Thermal Value, reference drawings.**
  2. Bulk for pneumatic placement
- C. Sound Batt Insulation:
  1. Batt size: 3-1/2”.
  2. Facing: Unfaced.
- D. Tape: Self-adhering type as recommended by the manufacturer, mesh reinforced, 2 inches wide.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify site conditions.
- B. Verify that substrate, adjacent materials, and insulation are dry and ready to be installed.

3.02 INSTALLATION

A. Install insulation and vapor retarder in accordance with manufacturer's instructions.
B. Trim insulation neatly to fit spaces. Insulate miscellaneous gaps and voids.
C. Fit insulation tight in spaces and tight to exterior side of mechanical and electrical services within the plane of insulation.
D. Install with applied vapor retarder membrane facing warm side of building spaces. Lap ends and side flanges of membrane, caulk or tape.
E. Tape seal butt ends, lapped flanges, and tears or cuts in membrane.
F. Place loose-fill insulation into spaces and onto surfaces as shown, either by pouring or by machine blowing to comply with ASTM C 1015. Level horizontal applications to uniform thickness as indicated, lightly settle to uniform density, but do not compact excessively.
    1. For cellulosic loose-fill insulation, comply with the Cellulose Insulation Manufacturers Association's Special Report #3, "Standard Practice for Installing Cellulose Insulation."
    2. IECC 2015 installation requirements, follow all requirements and recommendations.

END OF SECTION 07213

SECTION 072729

LIQUID-APPLIED ROUGH OPENING FLASHING MEMBRANE
FOR RESTORATION OF EXISTING CONDITIONS

PART 1 - GENERAL

1.1 SUMMARY:
- A. Section Includes:
  1. Window and door flashing restoration, using a liquid applied air and water barrier membrane system, and accessory materials for application to existing exterior building envelope substrates, as indicated on the drawings.
- B. Related Requirements:
  1. Section 01 33 00- Submittal Procedures.
  2. Section 01 45 80- Testing Laboratory Services.
  3. Section 01 60 00- Product Requirements.
  4. Section 07 65 00- Flexible Flashing.

1.2 REFERENCES
- A. The date of the standard is that in effect as the date of receipt of bids for the project.
- B. Living Building Challenge (LBC).
- C. ASTM International (ASTM).

1.3 ADMINISTRATIVE REQUIREMENTS:
- A. Pre-installation conference: Prior to beginning installation of the fluid applied rough opening system, hold a pre-installation conference to review work to be accomplished.
  1. Owner’s Representative, Contractor, Architect, installing subcontractor, membrane system manufacturer's representative, roofing and foundation subcontractors, waterproofing subcontractors, and all subcontractors who have materials penetrating membrane system or finishes covering membrane system shall be present.
  2. Contractor shall notify Architect at least seven days prior to time for conference.
  3. Contractor shall record minutes of meeting and distribute to attending parties.
  4. Agenda: As a minimum discuss:
     a. Surface preparation of restoration area and surrounding wall interfaces.
     b. Existing substrate condition and pretreatment.
     c. Minimum curing period.
     d. Special details and/or sheet flashing for liquid applied rough opening installation.
     e. Sequence of construction, responsibilities, and schedule for subsequent repair operations.
     f. Installation procedures.
     g. Inspection procedures.
     h. Protection and repair procedures.
     i. Review and approval of all glazing applications to include the installation of the windows and related interior perimeter sealant joint.

1.4 PERFORMANCE REQUIREMENTS:
- A. Performance requirements: Comply with the specified performance requirements and characteristics as herein specified.
- B. Performance description:
  1. Wall penetrations (windows, doors, etc.) shall be constructed with a continuous, air and water barrier to control water and air leakage into and out of the conditioned space around the [existing] [new] windows and doors replacements.
  2. Joints, penetrations, and paths of water and air infiltration shall be made watertight and airtight.
  3. System shall be capable of withstanding positive and negative combined wind, stack and HVAC pressures on the rough openings and building envelope without damage or displacement.
  4. System shall be installed in an airtight and flexible manner, allowing for the relative movement of remediated systems due to thermal and moisture variations.

1.5 SUBMITTALS:

A. Product data: Submit manufacturer's product data and installation guidelines including membrane and accessory material types, technical and test data, composition, descriptions and properties, installation instructions and substrate preparation requirements.
B. Certificates:
   1. Certificates by manufacturer stating that manufacturer and installer meet qualifications as herein specified.
C. VOC Certification: Submit certification that products furnished comply with regulations controlling use of volatile organic compounds (VOC).

1.4 QUALITY ASSURANCE:

A. Applicable standards, as referenced herein: ASTM International (ASTM).
B. Manufacturer's qualifications: Air and water barrier systems shall be manufactured and marketed by a firm with an Air Barrier Association of America membership for at least five [5] years. Manufacturers proposed for use, but not named in these specifications shall submit evidence of ability to meet all requirements specified, and include certification of ABAA membership for a least five [5] years.
C. Installer's qualifications: The installer shall demonstrate qualifications to perform the work of this section by submitting the following:
   1. Verification that installer has been trained by and is approved to perform work as herein specified by air and water barrier system manufacturer.
   2. List of at least three (3) projects completed of similar scope and complexity to this project carried out by the firm and site supervisor.
D. Inspection and testing: Cooperate and coordinate with the Owner's inspection and testing agency. Do not cover installed products or assemblies until they have been inspected, tested, and approved.
E. Sole source: Obtain materials within the scope of this specification from a single manufacturer.
F. Regulations: Provide products which comply with all state and local regulations controlling use of volatile organic compounds (VOC).
G. Mock-up:
   1. Prior to installation and start of Work of the fluid applied rough opening system a field-constructed mock-up shall be applied to verify details and tie-ins, to demonstrate the required installation.
      a. Allow 72 hours for inspection and testing of mock-up before proceeding with water and air barrier work.
      b. Coordinate construction of mockups to permit inspection by [Architect] [Owner's Representative] of air barrier before beginning installation.
      c. Approved, undamaged mock-up must remain as part of the work.

1.5 DELIVERY, STORAGE, AND HANDLING:

A. Deliver materials and products in labeled packages. Store and handle in strict compliance with manufacturer's instructions and recommendations. Protect from damage, weather, excessive temperatures, and construction operations. Remove damaged material from site and dispose of in accordance with applicable regulations.
B. Protect air and water barrier components from freezing and extreme heat.
C. Sequence deliveries to avoid delays, and to minimize on-site storage.

1.6 FIELD CONDITIONS:

A. Environmental conditions:
   1. Comply with manufacturer's written instructions for substrate temperature and moisture content and other conditions affecting performance requirements.
B. Weather conditions:
   1. Perform work only when existing and forecasted weather conditions are within the limits established by the manufacturer of the materials used.
C. Proceed with installation only when the substrate construction and preparation work is complete and in condition to receive the membrane system.
D. Ultra-violet Exposure:
   1. Do not expose air barrier materials to sunlight longer than as recommended by the material manufacturer.

1.7 WARRANTY:

A. Manufacturer's warranty requirements:
   1. Submit manufacturer's five (5) year limited warranty stating:
      a. The products have been tested in accordance with national standards for air and water-resistive barriers and passed those tests with effectiveness and durability indicating their suitability for performance as an air and water-resistive barrier system when properly applied.
      b. The products shall be free from defects in material for a period of [five] years after the substantial completion of the material application.
      c. That the products will not disintegrate and will maintain their integrity over the life of the warranty.

B. Warranty period: Five (5) years from Date of Substantial Completion.

PART 2 – PRODUCTS

2.1 MANFACTURERS

A. Substitutions: [No Substitutions] [In accordance with Section 01 25 00 – Substitution Procedures].

2.2 MATERIALS

A. WATER BASED PRIMER FOR RAW GYPSUM BOARD EDGES
   1. Primer to seal the cut edges of gypsum wall boards where they are exposed in rough openings for windows and doors. The sealed edge makes a compatible surface for easy application of liquid applied fiber-reinforced fill coat and seam treatment for through-wall components.
      a. Product: PROSOCO R-Guard PorousPrep, manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
   2. Subject to compliance with the following physical and performance requirements:
      a. Breathable liquid primer.
      b. Comply with national, state and district AIM VOC regulations and be 100 g/L or less.
      c. Living Building Challenge 2.0/2.1/3.0/3.1 Red List.
      d. Total Solids: 16 percent.

B. LIQUID APPLIED FILL COAT AND SEAM FILLER
   1. High modulus, gun-grade, crack and joint filler, adhesive and detailing compound that combines the best silicone and polyurethane properties. The single-component, Silyl-Terminated-Polymer (STP) prepares open joints, seams and cracks before installing primary water and air barrier system to prevent the movement of water and air through building envelopes.
      a. Product: PROSOCO R-Guard Joint & Seam Filler, manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
   2. Subject to compliance with the following physical and performance requirements:
      a. Living Building Challenge 2.0/2.1/3.0/3.1 Red List.
      b. Comply with national, state and district AIM VOC regulations and be 30 g/L or less.
      c. Water vapor transmission: Minimum 19 perms at 20 mils when tested in accordance with ASTM E-96.
      d. Tensile strength: 70 psi when tested in accordance with ASTM D412.
      e. Elongation at break: Greater than 180 percent when tested in accordance with ASTM D412.
      f. Peel strength: Greater than 25 pli when tested in accordance with ASTM D1781.
      g. Total solids: 99 percent.

C. LIQUID-APPLIED FLASHING AND DETAILING MEMBRANE
   1. Gun-grade, spread and tool or roller apply waterproofing, adhesive and detailing compound that combines the best of silicone and polyurethane properties. The single component, Silyl-Terminated-Polymer (STP) produces a highly durable, seamless, elastomeric flashing membrane in rough openings, to fill joints and seams, to counter flash and transition waterproofing and air barrier components in new wall assemblies, and to seal around penetrations or protect countersunk fasteners.
      a. Product: PROSOCO R-Guard FastFlash manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
   2. Subject to compliance with the following physical and performance requirements:
      a. Living Building Challenge 2.0/2.1/3.0/3.1 Red List.

b. AAMA 714-12 Voluntary Specification for Liquid-Applied Flashing Used to Create a Water-Resistive Seal Around Exterior Wall Openings in Buildings.
c. ICC-ES AC 212 Acceptance Criteria for Water-Resistive Coatings Used as Water-Resistive Barriers Over Exterior Sheathing.
d. Comply with national, state and district AIM VOC regulations and be 30 g/L or less.
e. Water vapor transmission: 21 perms when tested in accordance with ASTM E96.
f. Tensile strength: Greater than 150 psi when tested in accordance with ASTM D412.
g. Elongation at break: Greater than 350 percent when tested in accordance with ASTM D412.
h. Total Solids: 99 percent.

D. SEALANT FOR INTERIOR WINDOWS AND DOORS
1. High performance, gun-grade waterproofing sealant that combines the best of silicone and polyurethane properties. Single component, Silyl-Terminated-Polymer (STP) that is durable and stops the movement of moist air through cracks surrounding windows and doors.
2. Product: PROSOCO R-Guard AirDam, manufactured by PROSOCO, Inc., Lawrence, KS, (800) 255-4255, www.prosoco.com.
Subject to compliance with the following physical and performance requirements:
a. Living Building Challenge 2.0/2.1/3.0/3.1 Red List.
b. Comply with national, state and district AIM VOC: less than 30 grams per Liter
c. Sealant Validation from Sealant Waterproofing & Restoration Institute (SWRI).
d. Elongation at break: Greater than1000 percent when tested in accordance with ASTM D412.
e. Peel strength: 25 pli when tested in accordance with ASTM C794
f. Total solids: 98 percent.
3. Backer rod: In deep joints, control sealant depth by installing closed cell backer road. Diameter of the soft-backer rod should be 25 percent greater than the joint width. Do not puncture backer rod.

PART 3 - EXECUTION

3.1 EXAMINATION AND SURFACE PREPARATION

A. Examine conditions for compliance with system manufacturer's requirements for installation, and other specific conditions affecting performance of air and water barrier system.
B. All surfaces must be sound, clean, and free of grease, dirt, excess mortar or other contaminants. Fill or bridge damaged surfaces, voids, or gaps larger than one- inch. Fill voids and gaps measuring one- inch or less with liquid applied fill coat and seam filler as necessary to ensure continuity.
1. Surfaces to receive STP fluid applied accessories must be dry, damp, or wet to the touch. Brush away any standing water present before application. The products will tolerate rain immediately after application.
C. Refer to manufacturer's product data sheets for requirements for condition of and preparation of substrates.
1. Surfaces shall be sound and free of voids, spalled areas, loose aggregate, and sharp protrusions.
2. Remove contaminants such as grease, oil and wax from exposed surfaces.
3. Remove dust, dirt, loose stone, and debris.
4. Use repair materials and methods that are acceptable to manufacturer of the air and water-resistive barrier system.
5. Refer to manufacturer's product data sheets and manufacturer's installation guidelines for additional information on preparing structural walls to receive the primary air and water resistive barrier.
D. Exterior sheathing:
1. Ensure that sheathing is properly installed with ends, corners and edges properly fastened. Remove and replace damaged sheathing.
2. Mechanical fasteners used to secure sheathing boards or penetrate sheathing boards shall be set flush with sheathing, and spot overdriven fasteners with liquid applied fill coat and seam filler.
3. Seal the cut edges of gypsum wall boards exposed in rough openings for windows and doors at corners, as recommended by manufacturer.

E. Masonry and concrete substrates:
   1. Masonry head and bed joints should be fully filled and tooled.
   2. Mechanically remove loose mortar fins, mortar accumulations and protrusions, and debris.
   3. Fill cracks, joints, and gaps with liquid applied fill coat and seam filler as herein specified.

3.2 FIBER REINFORCED FILL COAT AND SEAM FILLER

A. General: Comply with air and water barrier manufacturer's installation instructions, temperature limitations, product data and shop drawings.
B. Apply liquid applied fill coat and seam filler for seams, joints, cracks, gaps, primed rough gypsum edges at sheathing, and rough openings per manufacturer's written instructions.

3.3 LIQUID APPLIED FLASHING AT WINDOWS, DOORS OPENINGS AND PENETRATIONS

A. General: Comply with air and water barrier manufacturer's installation instructions, temperature limitations, product data and shop drawings.
B. Apply liquid flashing membrane to seal and waterproof rough openings per manufacturer's written instructions. Spread the wet product to create an opaque, monolithic flashing membrane which surrounds the rough opening and extends 4 to 6 inches over the face of the structural wall. Apply additional coats as needed to achieve void- and pinhole-free surface.

3.4 FLUID-APPLIED FLASHING TRANSITIONS

A. General: Comply with water and air barrier manufacturer's installation instructions, temperature limitations, product data and shop drawings.
B. Apply fiber reinforced fill coat and seam filler and liquid flashing membrane as a liquid flashing membrane to waterproof the transitions in rough opening and between dissimilar materials per manufacturer's written instructions.
   1. Fill any voids between the top of the flashing leg and the vertical wall with fiber reinforced fill coat and seam filler.
   2. Spread the wet liquid flashing membrane to create a monolithic "cap-flash" flashing membrane per manufacturer's written instructions.
   3. Apply additional coats as needed to achieve void- and pinhole-free surface.
   4. Allow treated surfaces to skin before installing other wall assembly, waterproofing or air barrier components.

3.5 INTERIOR SEALANT FOR WINDOWS AND DOORS INSTALLATION

A. General: Comply with air and water barrier manufacturer's installation instructions, temperature limitations, product data and shop drawings.
B. Apply interior waterproofing sealant per manufacturer's written instructions.
   1. Install Backer rod: Compressible, closed cell rod stock as recommended by manufacturer for compatibility with sealant. Install Backer Rod as necessary per manufacturer's written instructions.
   2. Apply interior waterproofing sealant in continuous beads without gaps or air pockets.

3.6 PROTECTION

A. Coordinate scheduling within installation of cover materials to ensure that fluid-applied air barrier system is not exposed to sunlight and weather longer than recommended by the system manufacturer.
B. Ensure that the top edge of the fluid-applied membrane and the existing air barrier system is sealed and protected from water intrusion. Ensure the continuity of the fluid-applied air barrier system has been achieved.

END OF SECTION 072729

SECTION 07620

SHEET METAL FLASHING AND TRIM

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Cap and sill flashings.
- B. Gutters and down spouts.
- C. Counterflashings at roof mounted equipment and vent stacks.
- D. Fascias.
- E. Miscellaneous flashings and closure pieces.

1.02 SUBMITTALS
- A. Shop Drawings: Indicate material profile, jointing pattern, jointing details, fastening methods, flashings, terminations, and installation details.

1.03 QUALITY ASSURANCE
- A. Perform work in accordance with SMACNA standard details and requirements.

1.04 QUALIFICATIONS
- A. Fabricator and Installer: Company specializing in sheet metal flashing work with three years documented experience.

1.05 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site under provisions of the General Requirements.
- B. Stack preformed and prefinished material to prevent twisting, bending, or abrasion, and to provide ventilation. Slope metal sheets to ensure drainage.
- C. Prevent contact with materials which may cause discoloration or staining.

PART 2 PRODUCTS

2.01 SHEET MATERIALS
- A. Pre-Coated Galvanized Steel: ASTM A446, Grade A, G90 zinc coating; 24 gage core steel, exposed flashings shall be shop prefinished with KYNAR coating of color as selected.

2.02 ACCESSORIES
- A. Fasteners: Galvanized steel with soft neoprene washers.
- B. Underlayment: ASTM D2178, No. 30 asphalt saturated roofing felt.
- C. Slip Sheet: Rosin sized building paper.
- D. Primer: Zinc chromate type.
- E. Sealant: Polyurethane type, specified in Section 07900.
- F. Bedding Compound: Rubber-asphalt type.
- G. Plastic Cement: ASTM D4586, Type II.
- H. Reglets: Recessed type, galvanized steel; face and ends covered with plastic tape.
- I. Gutter and Downspout Anchorage Devices: SMACNA requirements. Type recommended by fabricator.

2.03 COMPONENTS
- A. Gutters: Size and shape per drawings. Match existing as indicated in size and shape. Field verify.
- B. Downspouts: Profile to match existing. Field verify and measure.
- C. Accessories: Profiled to suit gutters and downspouts.
- D. Downspout Boots: Metal. Ref. Civil drawings for stormwater routing.

2.04 FABRICATION
- A. Form sections true to shape, accurate in size, square, and free from distortion or defects.
- B. Fabricate cleats of metal, same material as sheet, interlockable with sheet.
- C. Form pieces in longest possible lengths. Hem exposed edges on underside 1/2 inch; miter and seam corners.
- D. Form material with flat lock seams.

E. Fabricate corners from one piece with minimum 18 inch long legs; seam and/or solder for rigidity, seal with sealant.
F. Fabricate vertical faces with bottom edge formed outward 1/4 inch and hemmed to form drip.
G. Fabricate flashings to allow toe to extend 2 inches over roofing. Return and brake edges.

2.05 FINISH
A. Exposed metal shall pre-finished with Kynar finish color to be selected.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify roof openings, curbs, pipes, sleeves, ducts, or vents through roof are solidly set, reglets in place, and nailing strips located.
B. Verify roofing termination and base flashings are in place, sealed, and secure.

3.02 PREPARATION
A. Install starter and edge strips, and cleats before starting installation.
B. Install surface mounted reglets true to lines and levels. Seal top of reglets with sealant.

3.03 INSTALLATION
A. Conform to drawing details included in the SMACNA manual unless otherwise indicated on the drawings.
B. Insert flashings into reglets to form tight fit. Secure in place with lead wedges. Pack remaining spaces with lead wool. Seal flashings into reglets with sealant.
C. Apply plastic cement compound between metal flashings and felt flashings.
D. Fit flashings tight in place. Make corners square, surfaces true and straight in planes, and lines accurate to profiles.
E. Seal metal joints watertight. Secure gutters and downspouts in place using fasteners. Set splash pans under downspouts. Seal metal joints watertight.

END OF SECTION 07620

SECTION 07900

JOINT SEALERS

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Preparing substrate surfaces.
B. Sealant and joint backing.

1.02 QUALITY ASSURANCE
A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
B. Perform acoustical sealant application work in accordance with ASTM C919.

1.03 QUALIFICATIONS
A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
B. Applicator: Company specializing in performing the work of this section with minimum years documented experience.

1.04 WARRANTY
A. Provide five year warranty.
B. Warranty: Include coverage for installed sealants and accessories which fail to achieve air tight seal, water tight seal, and exhibit loss of adhesion or cohesion, or do not cure.

PART 2 PRODUCTS

2.01 SEALANTS
A. Acrylic Latex (Interior Minor Movement): ASTM C920, Single component, non-staining, non-bleeding, non-sagging; white color paintable; manufactured by Pecora AC 20 + silicone.
B. Butyl Sealant (Interior Minor Movement): ASTM C920 single component, solvent release, non-skinning, non-sagging, white, paintable; manufactured by Pecora BC 158.
C. Silicone Sealant (Exterior, Interior Major Movement and Water Resistant Areas): Single component, solvent curing, non-sagging, non-staining, fungus resistant, non-bleeding; color as selected or to match adjacent materials; manufactured by Pecora 895 silicone.
D. Bituminous Based (Paving): Single component, asphalt compound, elongation capability of 0 to 2 percent of joint width.

2.02 ACCESSORIES
A. Primer: Non-staining type, recommended by sealant manufacturer to suit application.
B. Joint Cleaner: Non-corrosive and non-staining type, recommended by sealant manufacturer; compatible with joint forming materials.
C. Joint Backing: ASTM D1056; round, closed or open cell polyethylene foam rod; oversized 30 to 50 percent larger than joint width.
D. Bond Breaker: Pressure sensitive tape recommended by sealant manufacturer to suit application.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify that substrate surfaces and joint openings are ready to receive work.
B. Verify that joint backing and release tapes are compatible with sealant.

3.02 PREPARATION
A. Remove loose materials and foreign matter which might impair adhesion of sealant.
B. Clean and prime joints in accordance with manufacturer's instructions.
C. Perform preparation in accordance with manufacturer's instructions.
D. Protect elements surrounding the work of this section from damage or disfiguration.

3.03 INSTALLATION

A. Install sealant in accordance with manufacturer's instructions.
B. Measure joint dimensions and size materials to achieve required 2:1 width/depth ratios.
C. Install joint backing to achieve a neck dimension no greater than 1/3 of the joint width.
D. Install bond breaker where joint backing is not used.
E. Install sealant free of air pockets, foreign embedded matter, ridges, and sags.
F. Apply sealant within recommended application temperature ranges. Consult manufacturer when sealant cannot be applied within these temperature ranges.

3.04 SCHEDULE

A. Interior: Caulk around all frames, windows, doors, openings, trim, etc., as required to seal or fill gaps, cracks, to make material transitions watertight and/or visually tight and finished.
B. Exterior: Caulk around all frames, windows, doors, openings, trim, material transitions etc., as required to seal or fill gaps, cracks, to make material transitions watertight and/or visually tight finished.
C. Paving: Caulk as required to seal or fill gaps, expansion joints, and cracks to make transitions watertight and/or visually tight.

END OF SECTION 07900

SECTION 08111

STANDARD STEEL DOORS AND FRAMES

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Non-rated, fire rated and thermally insulated Masonite HD Wood Edge panel doors with steel facing and metal frames.

1.02 REFERENCES
- A. ANSI A117.1 - Specifications for Making Buildings and Facilities Accessible to and Usable by Physically Handicapped People.
- B. NFPA 80 - Fire Doors and Windows.
- C. NFPA 252 - Fire Tests for Door Assemblies.
- D. UL 10B - Fire Tests of Door Assemblies.

1.03 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect, and handle products to site.
- B. Accept doors and frames on site in manufacturer's packaging. Inspect for damage.

1.04 FIELD MEASUREMENTS
- A. Verify that field measurements are as indicated on shop drawings.

PART 2 PRODUCTS

2.01 DOOR MANUFACTURERS
- A. Masonite Int. Corp
- B. Substitutions: Under provisions of the General Requirements.

2.02 DOORS
- A. Exterior Insulated Doors Non-thermally Broken: SDI-100 Grade III. Thermo-pane insulated windows where indicated.
- B. Interior Doors (Non-rated and Fire Rated): SDI-100 Grade III.

2.03 DOOR CONSTRUCTION
- A. Face: Galvanized Steel facing, .0215" min. with protective chemical coatings and primer.
- B. Core: Polyurethane or styrene foam.
- C. Thermal Insulated Door. **Insulation R value of 7.7, ASTM C236, U-Value .40 Min., SHGC .25 Min. Per 2015 IECC as required by the 2009 IEBC**
- D. Style, size, and shape as indicated on construction drawings.

2.04 FRAMES
- A. Exterior Frames: 16 gage thick material, base metal thickness.

2.05 ACCESSORIES
- A. Removable Stops: Rolled steel channel shape, mitered corners; prepared for countersink style screws.
- B. Primer: Zinc chromate type.
- C. Silencers: Resilient rubber, fitted into drilled hole.

2.06 FABRICATION
- A. Fabricate doors with hardware reinforcement welded in place.
- B. Attach fire rated label to each door unit.
- C. Close top and bottom edge of exterior doors with flush end closure. Seal joints watertight.
- D. Configure exterior doors with special profile to receive recessed weatherstripping.
- F. Fabricate frames as welded unit.
- G. Transom Bars for Glazed Lights: Fixed type, of same profiles as jamb and head.
- H. Prepare frame for silencers. Provide three single silencers for single doors and mullions of double doors on strike side. Provide two single silencers on frame head at double doors without mullions.
- L. Configure exterior frames with special profile to receive recessed weathersripping.
- M. Fabricate frames to suit masonry wall coursing with 4 or 2 inch head member.

2.07 FINISH
A. Steel Sheet: Galvanized and chemically coated and primed.
B. Primer: Baked.
C. Coat inside of frame profile with bituminous coating to a thickness of 1/16 inch.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify that opening sizes and tolerances are acceptable.

3.02 INSTALLATION
A. Install doors and frames in accordance with ANSI/SDI-100 and DHI.
B. Coordinate installation of glass and glazing.
C. Install door louvers, plumb and level.
D. Coordinate installation of doors and frames with installation of frames and hardware.
E. Coordinate with masonry and wallboard wall construction for anchor placement.
F. Install roll-formed steel reinforcement channels between two abutting frames. Anchor to structure and floor.

3.03 ERECTION TOLERANCES
A. Maximum Diagonal Distortion: 1/16 inch measured with straight edge, corner to corner.

3.04 ADJUSTING
A. Adjust door for smooth and balanced door movement.

END OF SECTION 08111

SECTION 08211

PANEL MASONITE DOORS

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Masonite Panel doors; Panel Masonite doors as indicated on the drawings; fire rated and non-rated.

1.03 QUALIFICATIONS
A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.

1.04 DELIVERY, STORAGE, AND HANDLING
A. Deliver, store, protect, and handle products to site
B. Accept doors on site in manufacturer's packaging. Inspect for damage. Do not store in damp or wet areas; or in areas where sunlight might bleach veneer. Seal top and bottom edges if stored more than one week. Break seal on-site to permit ventilation.

1.05 FIELD MEASUREMENTS
A. Verify that field measurements are as indicated on shop drawings.

1.06 COORDINATION
A. Coordinate the work with door opening construction, door frame and door hardware installation.

1.07 WARRANTY
A. Provide warranty to the following term:
    1. Interior Doors: 1 year
B. Include coverage for delamination of veneer, warping beyond specified installation tolerances, defective materials, telegraphing core construction.

PART 2 PRODUCTS

2.01 MANUFACTURERS
A. Masonite Int Corp
B. Substitutions: Under provisions of the General Requirements.

2.02 DOOR TYPES
A. Panel Interior Doors: 1-3/4 inches thick
B. Type, Size and Style per construction drawings.

2.03 DOOR CONSTRUCTION
A. Core (Solid,Non-Rated).
B. Core (Solid, Fire Rated).

2.04 ACCESSORIES
A. Glazing Stops: Masonite, of same species as door facing Masonite with metal clips for rated doors, mitered corners; prepared for countersink style screws.

2.05 FABRICATION
A. Fabricate non-rated doors in accordance with Standard requirements.
B. Fabricate fire rated doors in accordance with Standards and to UL requirements. Attach fire rating label to door.
D. Provide lock blocks at lock edge and top of door for closer hardware reinforcement.
F. Fit door edge trim to edge of stiles after applying veneer facing.
G. Bond edge banding to cores.
H. Factory machine doors for finish hardware in accordance with hardware requirements and dimensions. Do not machine for surface hardware. Provide solid blocking for through bolted hardware.
I. Factory pre-fit doors for frame opening dimensions identified on shop drawings.
J. Cut and configure exterior door edge to receive recessed weather stripping devices.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify that opening sizes and tolerances are acceptable.
- B. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.

3.02 INSTALLATION
- A. Install fire rated and non-rated doors in accordance with Standards requirements.
- B. Trim non-rated door width by cutting equally on both jamb edges.
- C. Trim door height by cutting bottom edges to a maximum of 3/4 inch (19 mm). Trim fire door height at bottom edge only, in accordance with fire rating requirements.
- D. Pilot drill screw and bolt holes. Use threaded through bolts for half surface hinges.
- E. Machine cut for hardware. Core for handsets and cylinders.
- F. Coordinate installation of glass and glazing.

3.03 INSTALLATION TOLERANCES
- A. Maximum Diagonal Distortion (Warp): 1/8 inch measured with straight edge or taught string, corner to corner, over an imaginary 36 x 84 inch surface area.
- B. Maximum Vertical Distortion (Bow): 1/8 inch measured with straight edge or taught string, top to bottom, over an imaginary 36 x 84 inch surface area.
- C. Maximum Width Distortion (Cup): 1/8 inch measured with straight edge or taught string, edge to edge, over an imaginary 36 x 84 inch surface area.

3.04 ADJUSTING
- A. Adjust door for smooth and balanced door movement.

END OF SECTION 08211

SECTION 08410

ALUMINUM ENTRANCES AND CURTAIN WALL

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Aluminum doors and frames.
- B. Curtain Wall frame and glass, (Assemblies over 12'-0" HGT)
- C. Door hardware including power operator system.
- D. IECC 2015 energy requirements **U-Value .40 Min., SHGC .25 Min. (Residential)**
- E. Integral air and vapor barrier.
- F. Perimeter sealant.

1.02 SYSTEM DESCRIPTION
- A. Aluminum entrances, storefront system and curtain wall system includes tubular aluminum sections with supplementary internal support framing, shop fabricated, factory prefinished, vision glass, related flashings, anchorage and attachment devices.

1.03 PERFORMANCE REQUIREMENTS
- A. Design and size components to withstand dead and live loads caused by positive and negative wind pressure acting normal to plane of wall as calculated in accordance with codes.
- B. Limit mullion deflection to flexure limit of glass; with full recovery of glazing materials.
- C. System to accommodate, without damage to components or deterioration of seals, movement within system, movement between system and peripheral construction, dynamic loading and release of loads, deflection of structural support framing.
- D. Limit air leakage through assembly to 0.06 cfm/min/sq. ft. of wall area, measured at a reference differential pressure across assembly of psf as measured in accordance with AAMA 501.
- E. Water Leakage: None, when measured in accordance with AAMA 501 with a test pressure difference of 2.86 lbs/sq. ft.
- F. Maintain continuous air and vapor barrier throughout assembly, primarily in line with inside pane of glass and heel bead of glazing compound.
- G. System to provide for expansion and contraction within system components caused by a cycling temperature range of 170 degrees F over a 12 hour period without causing detrimental affect to system components.
- H. Drain water entering joints, condensation occurring in glazing channels, or migrating moisture occurring within system, to the exterior by a weep drainage network.

1.04 SUBMITTALS
- A. Shop Drawings: Indicate system dimensions, framed opening requirements and tolerances, affected related Work and expansion and contraction joint location and details.

1.05 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site.
- B. Protect pre-finished aluminum surfaces. Do not use adhesive papers or sprayed coatings which bond when exposed to sunlight or weather.

1.06 ENVIRONMENTAL REQUIREMENTS
- A. Do not install sealants when ambient temperature is less than 40 degrees F during and 48 hours after installation.

1.07 FIELD MEASUREMENTS
- A. Verify that field measurements are as indicated on shop drawings.

1.08 WARRANTY
- A. Provide three year warranty.
- B. Warranty: Include coverage for complete system for failure to meet specified requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS
- A. Storefront System
  1. Manko – 2450 series, Door series 150 H Wide Style. All windows to have sub-sill, head and jamb receptors.
  2. Other acceptable manufacturers offering equivalent Products.
     a. Kawneer.
     b. Amarlite.
     c. EFCO.
  3. Substitutions: Under provisions of the General Requirements.

2.02 MATERIALS
- A. Extruded Aluminum: ANSI/ASTM B221; 6063 alloy, T5 temper. Color: **Dark Bronze, match existing.**
- B. Steel Sections: ANSI/ASTM A36; shaped to suit mullion sections.
- C. Fasteners: Galvanized steel.

2.03 COMPONENTS
- A. Storefront Frame: 4 1/2 x 2 inch nominal dimension; glazing stops; drainage holes; internal weep drainage system. **Subsill with end dams are required.**
- C. Doors: 2 inches thick, 5-inch wide top rail, 5-inch wide vertical stiles, 10-inch wide bottom rail; square glazing stops.
- D. Flashings: Aluminum, finish to match mullion sections where exposed.

2.04 GLASS AND GLAZING MATERIALS
- A. Glass and Glazing Materials: As specified in Section 08800 of types described below:
  1. Glass at Exterior and several Interior Lights (reference drawings): 1-inch insulated type (outer pane of ¼ inch **Clear exterior**, ¼ inch **Clear inner**). Tempered where required. **Low-E coating, third surface. U-Value .40 Min., SHGC .25 Min.**
  3. Spandrel Glass at some Exterior Lights (reference drawings): 1-inch insulated type, fully colored or tinted to match other, although non-visual or see-through.

2.05 SEALANT MATERIALS
- A. Sealant and Backing Materials: As specified in Section 07900.

2.06 HARDWARE
- A. Weather Stripping, Sill Sweep Strips, Thresholds, Hinges, Tubular Pull Handles, Panic Device, Closer: Manufacturers' standard type to suit application, and finish, all provided by storefront manufacturer / supplier.

2.07 FABRICATION
- A. Fabricate components with minimum clearances and shim spacing around perimeter of assembly, yet enabling installation and dynamic movement of perimeter seal.
- B. Accurately fit and secure joints and corners. Make joints flush, hairline, and weatherproof.
- C. Prepare components to receive anchor devices. Fabricate anchors.
- D. Arrange fasteners and attachments to conceal from view.
- E. Prepare components with internal reinforcement for door hardware and door operator hinge hardware.
- F. Reinforce framing members for imposed loads.

2.08 FINISHES
- A. Finish coatings to conform to AAMA
- B. **Exposed Aluminum Surfaces: Dark Bronze, match existing**.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify site opening conditions.
- B. Verify dimensions, tolerances, and method of attachment with other work.

C. Verify wall openings and adjoining air and vapor seal materials are ready to receive work of this Section.

3.02 INSTALLATION

A. Install wall system in accordance with manufacturer's instructions and AAMA - Metal Curtain Wall, Window, Store Front and Entrance - Guide Specifications Manual.
B. Attach to structure to permit sufficient adjustment to accommodate construction tolerances and other irregularities.
C. Provide alignment attachments and shims to permanently fasten system to building structure.
D. Align assembly plumb and level, free of warp or twist. Maintain assembly dimensional tolerances, aligning with adjacent work.
E. Provide thermal isolation where components penetrate or disrupt building insulation.
F. Install sill flashings and manufacturer's standard subsill, head and jamb systems.
G. Coordinate attachment and seal of perimeter air and vapor barrier materials.
H. Pack fibrous insulation in shim spaces at perimeter of assembly to maintain continuity of thermal barrier.
I. Set thresholds in bed of mastic and secure.
J. Install hardware using templates provided.
K. Install glass in accordance with Section 08800, to glazing method required to achieve performance criteria.
L. Install perimeter sealant to method required to achieve performance criteria, backing materials, and installation criteria in accordance with Section 07900.

3.03 TOLERANCES

A. Maximum Variation from Plumb: 0.06 inches every 3 ft non-cumulative or 1/16 inches per 10 feet, whichever is less.
B. Maximum Misalignment of Two Adjoining Members Abutting in Plane: 1/32 inch.

3.04 ADJUSTING

A. Adjust operating hardware and sash for smooth operation.

3.05 CLEANING

A. Remove protective material from prefinished aluminum surfaces.
B. Wash down surfaces with a solution of mild detergent in warm water, applied with soft, clean wiping cloths. Take care to remove dirt from corners. Wipe surfaces clean.
C. Remove excess sealant by method acceptable to sealant manufacturer.

3.06 PROTECTION OF FINISHED WORK

A. Protect finished Work from damage.

END OF SECTION 08410

SECTION 08520

ALUMINUM WINDOWS

PART 1 GENERAL

1.01 GENERAL PROVISIONS:

A. The conditions of the contract and all sections of Division 1, are hereby made a part of this section.

B. Coordinate work with that of all construction contractors affecting or affected by work of this contract. Cooperate with such contractors to assure the steady progress of the work.

1.02 DESCRIPTION OF WORK:

A. Work included: Provide labor, materials and equipment necessary to complete the work of the window contract and without limiting the generality thereof include:

1. Removal of existing work as required for the proper installation and operation of the units.
2. Removal from site and legal disposal of all removed materials and debris.
3. Provide new factory glazed, thermally broken aluminum windows, types as specified herein, together with necessary operating hardware, installation hardware and all other materials as required for complete installation of the windows.
4. Provide treated wood blocking, fillers and nailers as required to provide a secure installation.

1.03 SYSTEM DESCRIPTION:

A. This section includes fixed insulated aluminum framed windows for replacement of existing windows in exterior locations. Window profiles and sections to be designed to simulate original steel units in sight lines and profiles.

1.04 ENVIRONMENTAL REQUIREMENTS

A. All new exterior glazing must meet the requirements for the **2015 International Energy Conservation Code (IECC) for Climate Zone 2A (Montgomery County, TX).**

1. **U-value = 0.40 minimum**
2. **SHGC = 0.25 minimum**

1.05 QUALITY ASSURANCE:

A. Standards: Except as otherwise indicated, requirements for aluminum windows, terminology and standards of performance and fabrication of workmanship are those specified and recommended in ANSI/AAMA and applicable general recommendations published by AAMA 101-93.

B. Test Procedures and Performances:

1. Windows shall conform to all ANSI/AAMA 101-93 requirements for the window type referenced. In addition the following specific tests must be met.
2. Air Infiltration Test: With ventilators closed and locked, test unit in accordance with ASTM E283-91 at a static air pressure difference of 6.24. Air infiltration shall not exceed .10 cfm per foot of perimeter crack length.
3. Water Resistance Test: With ventilators closed and locked, test unit in accordance with ASTM E331-96 at a static air pressure of 12.0 psf. There shall be no water leakage.
4. Uniform Load Deflection Test: With ventilators closed and locked, test unit in accordance with ASTM E330-90 at a static air pressure of +/- 60.0 psf. There shall be no glass breakage, permanent damage to fasteners, hardware parts, nor any damage which would cause the window to be in-operable.
5. Life Cycle Test: In accordance with AAMA 910-93, there shall be no damage which would render the unit in-operable and supplemental air and water tests shall not exceed primary requirements.

6. Provide a Condensation Resistance Rating "CRF" of at least 54 when tested in accordance with AAMA 1502.7.
7. Provide U-Value of no more than .56 btu/hr ft F when tested in accordance with AAMA 1503.1 and subjected to a 15 mph positive wind load during testing.

1.06 SUBMITTALS:

A. Product Data: Submit manufacturer's specifications, recommendations and standard details for aluminum window units, including certified test laboratory reports as necessary to show compliance with requirements.

B. Shop Drawings: Submit shop drawings, including location floor plans or exterior wall elevations showing all window openings (if applicable and/or available), typical unit elevations at –1/2" or –3/4" = 1" scale, and full size detail sections of every typical composite member. Show anchors, hardware, operators and other components not included in manufacturer's standard data. Include glazing details and standards for factory glazed units.

C. Samples: One sample of each required aluminum finish on 6" long sections of Extrusions.

1.07 PRODUCT DELIVERY, STORAGE AND HANDLING:

A. Materials shall be packed, loaded, shipped, unloaded, stored, and protected in a manner which will avoid abuse, damage, and defacement in accordance with the recommendations contained in the AAMA Aluminum Curtain Wall Manual, Volume #10 entitled "Care and Handling of Architectural Aluminum from Shop to Site."

B. Remove all paper wrappings and inter-leavings that are wet or which could become wet when unloading and storing materials.

C. Store inside, if possible, in a clean, well drained and well ventilated area free of dust and corrosive fumes. In the event that it is not possible to store material inside, stack vertically or on edge, in accordance with the manufacturers instructions, so that water cannot accumulate on or within materials. Use wood or plastic shims between components to provide water drainage and air circulation and prevent contaminants from contacting aluminum.

D. The Contractor will be responsible for taking the steps necessary to protect stored materials from lime, mortar, run-off from concrete, copper and other corrosive materials, careless handling of tools, weld splatter, acids, roofing tar, solvents, abrasive cleaners and other items that could damage the finish or window components.

E. Items which become damaged because of non-compliance with these conditions will be cause for rejection and such items shall be replaced by the Contractor without additional costs to the owner.

1.08 WARRANTIES

A. Provide a written warranty from the window manufacturer agreeing to repair or replace any defective units or materials, to the satisfaction of and at no cost to the owner, which fail due to unsatisfactory materials or workmanship within the first 2 years of the date of the manufacture.

B. Provide a written warranty from the window installer agreeing to repair or replace window units which fail due to improper installation within the first 2 years of the date of completion. Failure includes, but is not limited to, water leakage, excessive air infiltration and improper operation of the window units due to unsatisfactory installation techniques. This warranty shall also certify that the perimeter sealant materials are suitable for each specific application and have been applied in accordance with the sealant manufacturer's recommendations for joint size, width, depth, priming, joint movement, weather conditions, bond breakers, etc.

C. Provide a written warranty from the insulated glass manufacturer agreeing to replace, at no cost to the Owner, any sealed insulating glass units which fail within the first 5 years of manufacture. Failure shall include, but is not limited to, fog, mist, condensation, or dust which appears on the #2 or #3 surfaces of the insulated glass unit.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS:

A. For purposes of creating a standard of quality, the aluminum windows as shown on drawing and specified herein are based on the Historical 500/700/800 series AW70 rated windows manufactured by Win-Vent Architectural Windows, Division of Extrusions, Inc., 2401 South Main Street, PO Box 430, Fort Scott, Kansas 66701, 800-295-3113, fax 620-223-1139.

B. To become an "or equal" submit a full size sample to the architect for approval 10 days before bid. Approved manufacturers must appear in an addendum prior to bid.

2.02 MATERIALS:

A. Aluminum Extrusions: Shall be a nominal 3" in depth of 6063T5 aluminum alloy. Wall thicknesses shall be not less than .100" at any location for frame and sash members and not less than .050 at the glazing bead.

B. Glazing (reference Spec. Section 08800)

C. Thermal Barrier: Fabricate window units with an integrally concealed low conductance thermal barrier. Material shall be poured-in-place, two-part chemically curing structural polyurethane equal to PRC (Product Research and Chemical Corporation) PR-453M. No hardware or other appurtenances shall bridge the thermal barrier in any way.

D. Fasteners: Aluminum, non-magnetic stainless steel or other material warranted by the window manufacturer to be non-corrosive and compatible with the aluminum window members, trim, hardware, anchors and other components of the window units. Do not use exposed fasteners except where unavoidable for application of operating hardware. Provide only exposed fasteners that match the finish of the hardware being used. Exposed fasteners shall be Phillips, flat, or pan-head machine screws.

E. Anchors, Clips and Window Accessories: Depending on strength and corrosion inhibiting requirements, fabricate accessories of aluminum, non-magnetic stainless steel or hot-dip zinc coated steel or iron complying with ASTM A386.

F. Compression Glazing Gaskets and Weatherstripping: At the manufacturers option, provide extruded neoprene gaskets complying with ASTM D2000 – 2BC415 to 3BC620, molded PVC gaskets complying with ASTM D2287 or molded expanded neoprene gaskets complying with ASTM C509, grade #4.

G. Window Assembly Sealant: Unless otherwise indicated, for sealants required within the fabricated window units use the type recommended by the manufacturer for joint size and movement, to remain permanently elastic, non-shrinking and non-migrating.

H. Perimeter Weather Seals: Provide a sealant which matches in color the finish of the window members. Use primers, back up material, bond breakers and cleaning agents as recommended by the sealant manufacturer. Provide product complying with AAMA Specification 803 and 808.

2.03 FABRICATED COMPONENTS:

A. Frames: All window members, sash members and muntin bars shall be nominally x" (Field verify and match existing/adjacent windows per schedule) in depth of one part construction (incorporating a thermal barrier as previously defined in this section). The four corners of the frames shall be neatly mitered and joined with reinforcing clips set in epoxy then hydraulically crimped to insure a permanent bond. Cross rails and muntin bars shall be coped and mechanically fastened to the abutting frame sections. Butyl, narrow joint seam sealer as previously specified in this section shall be applied to all intersections so as to provide a permanent and weather-tight joint. All window sections located beneath operating sash shall utilize weep holes or slots of adequate size to provide a means of drainage for water, which may accumulate.

B. Insect Screens: Screen frames shall be fabricated from solid extruded shapes finished to match the window members. Roll formed screen frames will not be acceptable. Screen cloth shall be 16 X 18 aluminum wire mesh and installed in a manner as to be easily replaceable. Hinged wickets required, sliding wickets would be unacceptable.

2.04 FINISH:

A. All exposed surfaces of window, screen and trim members shall be cleaned of all Oils and be free of serious surface defects before finishing. All aluminum shall be finished to meet the following specifications as defined in the Aluminum Association (AA) publication titled, "Designation System for Aluminum Finishes".
   1. AAMA 2605 Powder Coat Paint – Manufacturer's Standard Color
   2. AAMA 2604 Powder Coat Paint – Manufacturer's Standard Color
   3. AAMA 2603 Powder Coat Paint – Manufacturer's Standard Color
   4. Anodized Finish from Clear to Black

PART 3 EXECUTION

3.01 PREPARATION:

A. The installation contractor shall carefully remove all applicable items of the existing sash, stops, mullions, screens, storm windows and trim as shown on the drawings and as required for proper installation of the new windows. Avoid damage to the existing work that remains.

B. Existing window items that are removed from the construction shall not be reused in the new installation.

C. Existing windows, window shades, brackets, drapery that is to be disposed of, hardware or other miscellaneous items within the immediate adjacent opening surfaces which affect the installation of the new replacement window shall become the responsibility of the installation contractor who shall remove and legally dispose of same at no additional cost to the owner.

D. No window shall be removed unless it can be replaced, or the opening properly barricaded by the end of the workday. Nor shall it be removed until the opening size is confirmed to the window dimension by the General Contractor to insure the proper fit. Insofar as practical, the existing window parts shall be removed and the replacement window shall be installed in one continuous operation. Any barricades installed shall provide security against unlawful entry as well as complete weather protection.

E. Comply with all applicable laws, rules and regulations as detailed in applicable sections, Division 1 of this specification.

3.02 INSTALLATION:

A. The installation contractor and his representative shall be totally responsible for the installation of the window units.

B. Use only skilled tradesmen and complete all work in strict accordance with the manufacturers specifications and recommendations for the installation of window units, hardware, operators and other components as well as the approved project shop drawings and these project specifications.

C. Set units plumb, level and true to line without warp or rack of frames or sash. Compress fiberglass insulation between frames of new windows and construction that remains, as applicable.

D. Insulate all aluminum from direct contact with steel, masonry, concrete or other non-compatible materials with treated wood or plastic shims, or with bituminous paint or zinc chromate primer.

E. Seal all exterior perimeter joints between windows and surrounding construction in accord with the project shop drawings. Joints and other surfaces that are to receive sealants shall be clean, free from loose debris or construction stains and totally dry. In all, prepare surfaces that are to receive sealant and apply sealant according to that manufacturer's instructions.

3.03 ADJUSTMENTS, PROTECTING AND CLEANING:

A. Adjust operating sash and sash hardware to provide smooth operation and a tight fit at all contact points and at the full perimeter of weatherstripping.

B. Adjust the sash hardware so that the sash is perfectly square in the primary frame member. Lubricate hardware and all moving parts as necessary.

C. Clean aluminum surfaces promptly after installation of window units. Exercise extreme care to avoid damage to the finish. Remove excess glazing materials and sealant compounds, dirt and other substances.

D. Clean interior and exterior surfaces of glass promptly after installation of window units. Comply with the requirements of section –8800 for cleaning and maintenance of glazing materials.

E. Protect glass and window materials from contact with contaminating substances resulting from construction operations. If, despite such protection, contaminating substances do come in contact with the glass or window, work with the General Contractor to remove said substances as recommended by the window manufacturer.

F. The General Contractor shall be responsible for protection of the work from damage by other trades.

G. Final cleaning of all windows and interior and exterior surfaces of the glass shall take place not more than 5 days before the scheduled inspections intended to establish the date of final and substantial completion in each area of the project.

END OF SECTION 08520

SECTION 085400

COMPOSITE WINDOWS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes Single Hung, Fixed, and Casement Vinyl framed windows. **Design is based on MI Windows V3000**

1.3 PERFORMANCE REQUIREMENTS

A. General: Provide composite windows capable of complying with performance requirements indicated, based on testing manufacturer's windows that are representative of those specified, and that are of test size indicated below:
   1. Size required by AAMA/WDMA 101/I.S.2/NAFS
   2. Size indicated on Drawings.

B. Structural Performance: Provide composite windows capable of withstanding the effects of the following loads, based on testing units representative of those indicated for Project that pass AAMA/WDMA 101/I.S.2/NAFS, Uniform Load Structural Test:
   1. Design Wind Loads: Determine design wind loads applicable to Project from basic wind speed indicated in miles per hour (meters per second) at 33 feet (10 m) above grade, according to ASCE 7, Section 6.5, "Method 2-Analytical Procedure," based on mean roof heights above grade indicated on Drawings.
      a. Basic Wind Speed: 85 mph (38 m/s).
      b. Exposure Category: B.

C. Energy Star compliant

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An installer acceptable to vinyl window manufacturer for installation of units required for this Project.
   1. Installer's responsibilities include providing professional engineering services needed to assume engineering responsibility.
   2. Engineering Responsibility: Preparation of data for composite windows, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.

B. Manufacturer Qualifications: A manufacturer capable of fabricating composite windows that meet or exceed performance requirements indicated and of documenting this performance by inclusion in lists and by labels, test reports, and calculations.

C. Source Limitations: Obtain composite windows through one source from a single manufacturer.
Product Options: Information on Drawings and in Specifications establishes requirements for composite windows' aesthetic effects and performance characteristics. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction. Performance characteristics are indicated by criteria subject to verification by one or more methods including preconstruction testing, field testing, and in-service performance.

1.5 PROJECT CONDITIONS

A. Field Measurements: Verify composite window openings by field measurements before fabrication and indicate measurements on Shop Drawings.

1.6 WARRANTY

A. When warranties are required, verify with Owner's counsel that special warranties stated in this Article are not less than remedies available to Owner under prevailing local laws. Coordinate with Division 01 Section "Product Requirements."

B. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace composite windows that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:
   a. Failure to meet performance requirements.
   b. Structural failures including excessive deflection, water leakage, air infiltration, or condensation.
   c. Faulty operation of movable sash and hardware.
   d. Deterioration of composite material, other materials, and finishes beyond normal weathering.
   e. Failure of insulating glass.
2. Warranty Period:
   a. Non-glass parts: [10] years from date of Substantial Completion.
   b. Glass: [20] years from date of Substantial Completion.
   c. Composite Finish or color fade: [5] years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturer and Product:

1. MI Windows V3000 Vinyl: , Fixed and/or Operable as indicated on drawings. with 1-1/2" mounting fin

2.2 MATERIALS

A. Material Composition: Vinyl windows per manufacturer
B. Manufacturer Designation: Vinyl
C. Fasteners: Aluminum, nonmagnetic stainless steel, epoxy adhesive, or other materials warranted by manufacturer to be noncorrosive and compatible with vinyl window members, cladding, trim, hardware, anchors, and other components.
   1. Exposed Fasteners: Unless unavoidable for applying hardware, do not use exposed fasteners. For application of hardware, use fasteners that match finish of member or hardware being fastened, as appropriate.

D. Anchors, Clips, and Accessories: Aluminum, nonmagnetic stainless steel, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.
E. Reinforcing Members: Aluminum, or nonmagnetic stainless steel, or nickel/chrome-plated steel complying with ASTM B 456 for Type SC 3 severe service conditions, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.
F. Compression-Type Weather Stripping: Provide compressible weather stripping designed for permanently resilient sealing under bumper or wiper action, and for complete concealment when window is closed.
   1. Weather-Stripping Material: Elastomeric cellular preformed gaskets complying with ASTM C 509.
   2. Weather-Stripping Material: Dense elastomeric gaskets complying with ASTM C 864.
   3. Weather-Stripping Material: Manufacturer's standard system and materials complying with AAMA/WDMA 101/I.S.2/NAFS.
G. Replaceable Weather Seals: Comply with AAMA 701/702.
H. Window grid as noted on drawings. None

2.3 WINDOWS

A. Window Type: Single hung, fixed, casement, awning or as indicated on Drawings. **V3000 Vinyl with 1-1/2" mounting fin. Color as selected by Architect. Contractor to provide samples.**
B. AAMA/WDMA Performance Requirements: Provide composite windows of performance indicated that comply with AAMA/WDMA 101/I.S.2/NAFS.
C. Condensation-Resistance Factor (CRF): Provide composite windows tested for thermal performance according to AAMA 1503**, showing a CRF of 42**.

D. Thermal Transmittance: Provide composite windows with a whole-window, U-factor maximum indicated at 15-mph (24-km/h) exterior wind velocity and winter condition temperatures when tested according to [AAMA 1503].

2.4 PERFORMANCE & RATINGS

A. **Energy Star Compliant,**
B. **Residential IECC 2015 values**
C. **U-Value; Fixed Units, U-Factor .40 or Less, Operable Units, U-Factor .40 or Less.**
D. **Solar Heat Gain Coefficient; .25 or less.**
E. **Insulating-glass 10 Year warranty.**

2.5 HARDWARE

A. General: Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with composite material; designed to smoothly operate, tightly close, and securely lock windows, and sized to accommodate sash or ventilator weight and dimensions. Do not use aluminum in frictional contact with other metals.
B. Sill Cap/Track: of thickness, dimensions, and profile indicated; designed to comply with performance requirements indicated and to drain to the exterior.
C. Locks and Latches: Designed to allow unobstructed movement of the sash across adjacent sash in direction indicated and operated from the inside only.
D. Roller Assemblies: Low-friction design.

2.6 INSECT SCREENS

A. General: Design windows and hardware to accommodate screens in a tight-fitting, removable arrangement, with a minimum of exposed fasteners and latches. Fabricate insect screens to fully integrate with window frame.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine openings, substrates, structural support, anchorage, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work. Verify rough opening dimensions, levelness of sill plate, and operational clearances. Examine wall flashings, vapor retarders, water and weather barriers, and other built-in components to ensure a coordinated, weathertight window installation.
    1. Masonry Surfaces: Visibly dry and free of excess mortar, sand, and other construction debris.
    2. Wood Frame Walls: Dry, clean, sound, well nailed, free of voids, and without offsets at joints. Ensure that nail heads are driven flush with surfaces in opening and within 3 inches (76 mm) of opening.
    3. Metal Surfaces: Dry; clean; free of grease, oil, dirt, rust, corrosion, and welding slag; without sharp edges or offsets at joints.
    4. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Comply with Drawings, Shop Drawings, and manufacturer's written instructions for installing windows, hardware, accessories, and other components.
B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction.
C. Set sill members in bed of sealant or with gaskets, as indicated, for weathertight construction.
D. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials.

3.3 ADJUSTING, CLEANING, AND PROTECTION

A. Adjust operating sashes and ventilators, screens, hardware, and accessories for a tight fit at contact points and weather stripping for smooth operation and weathertight closure. Lubricate hardware and moving parts.

B. Clean exposed surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.

C. Clean factory-glazed glass immediately after installing windows. Comply with manufacturer's written recommendations for final cleaning and maintenance. Remove nonpermanent labels, and clean surfaces.

D. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

E. Protect window surfaces from contact with contaminating substances resulting from construction operations. In addition, monitor window surfaces adjacent to and below exterior concrete and masonry surfaces during construction for presence of dirt, scum, alkaline deposits, stains, or other contaminants. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written recommendations.

END OF SECTION 085400

SECTION 08710

DOOR HARDWARE

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Hardware for wood, hollow steel, metal insulated and aluminum doors.
- B. Locksets, Hinges, Thresholds, Closures, wall & floor stops, etc. complete sets.
- C. Weatherstriping, seals, cushions, bumpers, and door gaskets.

1.03 REFERENCES
- A. ANSI A117.1 - Specifications for Making Buildings and Facilities Accessible to and Usable by Physically Handicapped People.

1.04 OPERATION AND MAINTENANCE DATA
- A. Maintenance Data: Include data on operating hardware, lubrication requirements, and inspection procedures related to preventative maintenance.

1.05 QUALIFICATIONS
- A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum 3 years' documented experience.
- B. Hardware Supplier: Company specializing in supplying commercial door hardware with 3 years' documented experience approved by manufacturer.

1.06 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site.
- B. Package hardware items individually; label and identify each package with door opening code to match hardware schedule.
- C. Deliver keys to Owner by security shipment direct from hardware supplier.

1.07 WARRANTY
- A. Provide five year warranty.

1.08 MAINTENANCE MATERIALS
- A. Provide special wrenches and tools applicable to each different or special hardware component.
- B. Provide maintenance tools and accessories supplied by hardware component manufacturer.

PART 2 PRODUCTS

2.01 KEYING
- A. Door Locks: Master keyed. Include construction keying, and key to existing keying system.

2.02 HNGES
- A. Butts and Hinges: BHMA A156.1.
- B. Template Hinge Dimensions: BHMA A156.7.
- C. Manufacturers:
  1. Baldwin Hardware Corporation (BH).
  2. Bommer Industries, Inc. (BI).
  3. Cal-Royal Products, Inc. (CRP).
  4. Hager Companies (HAG).
  5. Lawrence Brothers, Inc. (LB).
  6. McKinney Products Company; an ASSA ABLOY Group company (MCK).
  7. PBB, Inc. (PBB).
  8. Stanley Commercial Hardware; Div. of The Stanley Works (STH).

2.03 LOCKS AND LATCHES, GENERAL

- A. Accessibility Requirements: Comply with accessibility requirements, comply with the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG)." ANSI A117.1. FED-STD- 795, "Uniform Federal Accessibility Standards."
  1. Provide operating devices that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf (22 N).

B. Latches and Locks for Means of Egress Doors: Comply with NFPA 101. Latches shall not require more than 15 lbf (67 N) to release the latch. Locks shall not require use of a key, tool, or special knowledge for operation.

2.04 MECHANICAL LOCKS AND LATCHES

A. Lock Functions: Function numbers and descriptions indicated in door hardware sets comply with the following:
1. Bored Locks: BHMA A156.2.
2. Mortise Locks: BHMA A156.13.
3. Interconnected Locks: BHMA A156.12.

B. Bored Locks:
1. Manufacturers:
a. Best Access Systems; Div. of The Stanley Works (BAS).
b. Corbin Russwin Architectural Hardware; an ASSA ABLOY Group company (CR).
c. SARGENT Manufacturing Company; an ASSA ABLOY Group company (SGT).
d. Schlage Commercial Lock Division; an Ingersoll-Rand Company (SCH).
e. Yale Commercial Locks and Hardware; an ASSA ABLOY Group company (YAL).

2.05 KEYING

A. Keying System: Factory registered, complying with guidelines in BHMA A156.28, Appendix A. Incorporate decisions made in keying conference, and as follows:
1. Master Key System: Cylinders are operated by a change key and a master key.

B. Keys: Nickel silver.
1. Quantity: In addition to one extra key blank for each lock, provide the following:
a. Cylinder Change Keys: Three.
b. Master Keys: Five.
c. Grand Master Keys: Five.
d. Great-Grand Master Keys: Five.

2.06 CLOSERS

A. Accessibility Requirements: Where handles, pulls, latches, locks, and other operating devices are indicated to comply with accessibility requirements, comply with [the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG).", ANSI A117.1., FED-STD-795, "Uniform Federal Accessibility Standards."
1. Comply with the following maximum opening-force requirements:
a. Interior, Non-Fire-Rated Hinged Doors: 5 lbf (22.2 N) applied perpendicular to door.
b. Sliding or Folding Doors: 5 lbf (22.2 N) applied parallel to door at latch.
c. Fire Doors: Minimum opening force allowable by authorities having jurisdiction.

B. Door Closers for Means of Egress Doors: Comply with NFPA 101. Door closers shall not require more than 30 lbf (133 N) to set door in motion and not more than 15 lbf (67 N) to open door to minimum required width.

C. Hold-Open Closers/Detectors: Coordinate and interface integral smoke detector and closer device with fire alarm system.

D. Flush Floor Plates: Provide finish cover plates for floor closers unless thresholds are indicated. Match door hardware finish, unless otherwise indicated.

E. Recessed Floor Plates: Provide recessed floor plates with insert of floor finish material for floor closers unless thresholds are indicated. Provide extended closer spindle to accommodate thickness of floor finish.

F. Power-Assist Closers: As specified in Division 8 Section "Automatic Door Operators" for access doors for people with disabilities or where listed in the door hardware sets.

G. Size of Units: Unless otherwise indicated, comply with manufacturer's written recommendations for size of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Provide factory-sized closers, adjustable to meet field conditions and requirements for opening force.

H. Surface Closers: Provide type of arm required for closer to be located on non-public side of door, unless otherwise indicated.
1. Manufacturers:
a. Corbin Russwin Architectural Hardware; an ASSA ABLOY Group company (CR).
b. LCN Closers; an Ingersoll-Rand Company (LCN).
c. Norton Door Controls; an ASSA ABLOY Group company (NDC).
d. SARGENT Manufacturing Company; an ASSA ABLOY Group company (SGT).
e. Yale Commercial Locks and Hardware; an ASSA ABLOY Group company (YAL).

I. Concealed Closers:
1. Manufacturers:
a. LCN Closers; an Ingersoll-Rand Company (LCN).
b. Norton Door Controls; an ASSA ABLOY Group company (NDC).
c. SARGENT Manufacturing Company; an ASSA ABLOY Group company (SGT).

2.07 STOPS AND HOLDERS

A. Stops and Bumpers:
1. Provide floor stops for doors unless wall or other type stops are scheduled or indicated. Do not mount floor stops where they will impede traffic. Where floor or wall stops are not appropriate, provide overhead holders.

B. Silencers for Wood Door Frames: BHMA A156.16, Grade 1; neoprene or rubber, minimum 5/8 by 3/4 inch (16 by 19 mm); fabricated for drilled-in application to frame.

C. Silencers for Metal Door Frames: BHMA A156.16, Grade 1; neoprene or rubber, minimum diameter 1/2 inch (13 mm); fabricated for drilled-in application to frame.

D. Manufacturers:
1. Baldwin Hardware Corporation (BH).
2. Cal-Royal Products, Inc. (CRP).
3. Glynn-Johnson; an Ingersoll-Rand Company (GJ).
4. Hager Companies (HAG).
5. Hiawatha, Inc. (HIA).
6. IVES Hardware; an Ingersoll-Rand Company (IVS).
7. Rockwood Manufacturing Company (RM).
8. SARGENT Manufacturing Company; an ASSA ABLOY Group company (SGT).
9. Stanley Commercial Hardware; Div. of The Stanley Works (STH).

2.08 DOOR GASKETING

A. General: Provide continuous weather-strip gasketing on exterior doors and provide smoke, light, or sound gasketing on interior doors where indicated or scheduled. Provide noncorrosive fasteners for exterior applications and elsewhere as indicated.
1. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.
2. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.
3. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

B. Air Leakage: Not to exceed 0.50 cfm per foot (0.000774 cu. m/s per m) of crack length for gasketing other than for smoke control, as tested according to ASTM E 283.

C. Smoke-Labeled Gasketing: Assemblies complying with NFPA 105 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for smoke-control ratings indicated, based on testing according to UL 1784.
1. Provide smoke-labeled gasketing on 20-minute-rated doors and on smoke-labeled doors.

D. Sound-Rated Gasketing: Assemblies that are listed and labeled by a testing and inspecting agency, for sound ratings indicated, based on testing according to ASTM E 1408.

E. Replaceable Seal Strips: Provide only those units where resilient or flexible seal strips are easily replaceable and readily available from stocks maintained by manufacturer.

F. Gasketing Materials: ASTM D 2000 and AAMA 701/702.

G. Manufacturers:
1. Hager Companies (HAG).
2. National Guard Products (NGP).
3. Pemko Manufacturing Co. (PEM).
4. Zero International (ZRO).

2.09 THRESHOLDS

A. Accessibility Requirements: Where thresholds are indicated to comply with accessibility requirements, comply with [the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG).", ANSI A117.1., FED-STD-795, "Uniform Federal Accessibility Standards."

B. Thresholds for Means of Egress Doors: Comply with NFPA 101. Maximum 1/2 inch (13 mm) high.

C. Manufacturers:
1. Hager Companies (HAG).
2. National Guard Products (NGP).
3. Pemko Manufacturing Co. (PEM).
4. Zero International (ZRO).

2.10 FABRICATION

A. Base Metals: Produce door hardware units of base metal, fabricated by forming method indicated, using manufacturer's standard metal alloy, composition, temper, and hardness. Furnish metals of a quality equal to or greater than that of specified door hardware units and BHMA A156.18. Do not furnish manufacturer's standard materials or forming methods if different from specified standard.

B. Fasteners: Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. Provide screws according to commercially recognized industry standards for application intended, except aluminum fasteners are not permitted. Provide Phillips flat-head screws with finished heads to match surface of door hardware, unless otherwise indicated.

1. Concealed Fasteners: For door hardware units that are exposed when door is closed, except for units already specified with concealed fasteners. Do not use through bolts for installation where bolt head or nut on opposite face is exposed unless it is the only means of securely attaching the door hardware. Where through bolts are used on hollow door and frame construction, provide sleeves for each through bolt.
2. Steel Machine or Wood Screws: For the following fire-rated applications:
   a. Mortise hinges to doors.
   b. Strike plates to frames.
   c. Closers to doors and frames.
3. Steel Through Bolts: For the following fire-rated applications unless door blocking is provided:
   a. Surface hinges to doors.
   b. Closers to doors and frames.
   c. Surface-mounted exit devices.
4. Spacers or Hex Bolts: For through bolting of hollow-metal doors.
5. Fasteners for Wood Doors: Comply with requirements in DHI WDHS.2, "Recommended Fasteners for Wood Doors."

2.11 FINISHES

A. Standard: BHMA A156.18, as indicated in door hardware sets.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that doors and frames are ready to receive work and dimensions are as indicated on shop drawings.

B. Verify that electric power is available to power operated devices and of the correct characteristics.

C. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.

D. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION

A. Install hardware in accordance with manufacturer’s instructions.

B. Use templates provided by hardware item manufacturer.

C. Mounting heights for hardware from finished floor to center line of hardware item:

1. Locksets: 40”
2. Push/Pulls: 45”
3. Dead Locks: 54”
4. Exit Devices: 42”

D. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 9 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.

1. Set units level, plumb, and true to line and location. Adjust and reinforce attachment substrates as necessary for proper installation and operation.
2. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.

E. Thresholds: Set thresholds for exterior and acoustical doors in full bed of sealant complying with requirements specified in Division 7 Section "Joint Sealants."

3.03 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.
   1. Spring Hinges: Adjust to achieve positive latching when door is allowed to close freely from an open position of 30 degrees.
   2. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.
   3. Door Closers: Unless otherwise required by authorities having jurisdiction, adjust sweep period so that, from an open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches (75 mm) from the latch, measured to the leading edge of the door requirements in paragraph below increase cost but are recommended as a good investment on substantial projects even though they may be difficult to monitor.

Occupancy Adjustment: Approximately three months after date of Substantial Completion, Installer's Architectural Hardware Consultant shall examine and readjust, including adjusting operating forces, each item of door hardware as necessary to ensure function of doors, door hardware, and electrified door hardware.

END OF SECTION 08710

SECTION 08800

GLAZING

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Glass and glazing for Sections referencing this Section for products and installation.

1.02 PERFORMANCE REQUIREMENTS
A. Glass and glazing materials of this Section shall provide continuity of building enclosure vapor and air barrier:
   1. To utilize the inner pane of multiple pane sealed units for the continuity of the air and vapor seal.
   2. Maintain continuous air and vapor barrier throughout glazed assembly from glass pane to heel bead of glazing sealant.

B. Size glass to withstand dead loads and positive and negative live loads acting normal to plane of glass as calculated in accordance with UBC 91 code.

C. Limit glass deflection to 1/200 flexure limit of glass with full recovery of glazing materials, whichever is less.

1.03 ENVIRONMENTAL REQUIREMENTS
A. Do not install glazing when ambient temperature is less than 50 degrees F.

B. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

1.04 FIELD MEASUREMENTS
A. Verify that field measurements are as indicated on shop drawings.

1.05 COORDINATION
A. Coordinate the Work with glazing frames, wall openings, and perimeter air and vapor seal to adjacent Work.

1.06 WARRANTY
A. Provide five year manufacturer’s warranty.

B. Warranty: Include coverage for sealed glass units from seal failure, interpane dusting or misting, reflective coating on mirrors, delamination of laminated glass and replacement of same.

PART 2 PRODUCTS

2.01 FLAT GLASS MATERIALS
A. Float Glass (Type FG): Clear, 1/4 inch thick minimum.

B. Safety Glass (Type SG): Clear; fully tempered with horizontal tempering 1/4 inch thick minimum at all locations where glass is less than 18 inches above finished floor.

C. Mirror Glass (Type MG): Clear with copper and silver coating, organic overcoating, beveled edges, 1/4 inch thick minimum, sizes as indicated.

2.02 SEALED INSULATING GLASS MATERIALS
A. Insulated Glass Units (Type IG): ASTM E774 and E773; 1” and ½” total thickness as detailed and noted, double pane with edge seal; outer pane of 1/4 inch glass tinted at exterior, inner pane of 1/4 inch glass.

2.03 GLAZING COMPOUNDS
A. Exterior windows not shop installed shall be glazed with vinyl or neoprene gaskets, extruded elastic polybutene tape sealant, a combination of polysulphide base compound and elastic glazing compound, or a combination of extruded polysulphide tape, polysulphide base compound elastic glazing compound.

B. Doors and interior stopped -in glass shall be glazed using putty or elastic glazing compound and stop beads.

C. Exterior glazing of steel sash shall be DAP Metal Glaze. Interior glazing of steel sash shall be DAP Steel Sash Putty.

2.04 GLAZING ACCESSORIES

A. Setting Blocks: Neoprene or Silicone, 80 - 90 Shore A durometer hardness, length of 0.1 inch for each square foot of glazing or minimum 4 inch x width of glazing rabbet space minus 1/16 inch x height to suit glazing method and pane weight and area.

B. Spacer Shims: Neoprene or Silicone, 50 - 60 Shore A durometer hardness, minimum 3 inch long x one half the height of the glazing stop x thickness to suit application, self adhesive on one face.

C. Glazing Tape: Preformed butyl compound with integral resilient tube spacing device; 10 - 15 Shore A durometer hardness; coiled on release paper.

D. Glazing Clips: Manufacturer's standard type.

E. Mirror Attachment Accessories: Mirror adhesive, chemically compatible with mirror coating and wall substrate.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that openings for glazing are correctly sized and within tolerance.

B. Verify that surfaces of glazing channels or recesses are clean, free of obstructions, and ready to receive glazing.

3.02 PREPARATION

A. Clean contact surfaces with solvent and wipe dry.

B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.

C. Prime surfaces scheduled to receive sealant.

D. Install glazing in accordance with Flat Jobbers Association Glazing Manual.

3.03 INSTALLATION - MIRRORS

A. Set mirrors with adhesive, applied in accordance with adhesive manufacturer's instructions.

B. Place plumb and level.

3.04 CLEANING

A. Remove glazing materials from finish surfaces. Remove labels after work is complete. Clean glass and mirrors.

3.05 PROTECTION OF FINISHED WORK

A. After installation, mark pane with an "X" by using removable plastic tape or paste. Do not mark heat absorbing or reflective glass units.

END OF SECTION 08800

SECTION 09016

TERRAZZO (FLOOR RESTORATION)

PART 1: GENERAL

1.01 SECTION INCLUDES
- A. Refinishing terrazzo floors.
- B. Provide all labor, material, and equipment necessary to complete the following terrazzo repair work.
- C. Preparation of all surfaces to receive patching compound
- D. Repairs to delaminated areas
- E. Repair of cracks (as per NTMA recommendations)
- F. Placement of patching compounds/terrazzo matrix
- G. Finish and curing of terrazzo

1.02 REFERENCE STANDARDS
- A. NTMA – Terrazzo Specifications; The National Terrazzo and Mosaic Association, Inc.; current edition located at www.ntma.com
- B. U.S Department of the Interior – The Secretary of the Interior's Standards for the Treatment of Historic Properties

1.03 SUBMITTALS
- A. Product Data: Provide manufacturers technical data for sealer and cleaner and grout.
- B. Cleaning products to be used and Terrazzo Maintenance Data/Protocols for facility managers
- C. Submit letter clearly identifying the terrazzo system (Epoxy, Cement, etc) and that the products are suitable/compatible

1.04 QUALITY ASSURANCE
- A. Installer Qualifications: Company specializing in performing the work of this section with not fewer than 5 years of documented experience.
  1. Installer shall be a contractor member of NTMA in good standing and shall perform all work in accordance with NTMA standards
  2. Use only skilled journeyman who are familiar and experienced with the materials and methods specified shall be used for terrazzo restoration/refinishing.
  3. Crack Repair: Prepare a sample area for each type of crack repair required (Hairline cracks 1/64" to 1/16" in size; Cracks and voids larger than 1/8") Repair shall demonstrate methods and quality of workmanship of crack repair.
  4. Patching: Prepare on-floor, a sample of patching. Patch shall demonstrate methods and quality of workmanship of patch repair

PART 2: PRODUCTS

2.01 MATERIALS
- A. Cleaner: Potable water, free of iron, all cleaners (optional) must be pH neutral
- B. Sealer: Liquid type to completely seal matrix surface; not detrimental to terrazzo components.
- C. Grout: Color to match existing matrix.
- D. Matrix: Pigmented epoxy to match sample submitted
- E. Aggregates: Aggregates to match architects approved sample

2.02 EQUIPMENT
- A. All work shall be executed with conventional terrazzo grinding equipment according to NTMA published trade practice.

PART 3: EXECUTION

3.01 GENERAL
- A. Perform work in accordance with NTMA recommendations as posted on the NTMA website (www.ntma.com)

3.02 PREPARATION
- A. Cover and protect all adjacent finished surfaces during restoration process.

3.03 CRACK REPAIR
- A. Determination
  1. The owner and contractor shall walk the entire floor and identify cracks and agree on
     - a. NA (No Action) RC (Repair Crack) or RT (Replace Terrazzo)
     - b. Hairline cracks are classified as less than 1/32" (0.030)
     - c. Replacement (RT) shall be from architectural break to architectural break
- B. RC - Repair Crack
  1. Clean crack of loose material, dirt or sealer
  2. Fill with resin/to match existing. Use aggregate in the crack if crack is wider than ¼ inch.

3.04 RT- Replace Terrazzo (if repair is not to architectural break or existing terrazzo divider strip, the joining edge shall be a saw tooth (jagged edge)
- A. Remove areas to be replaced
- B. Clean area and prepare concrete for new terrazzo
- C. Repair concrete, fill cracks in concrete substrate as needed. Fill cracks in concrete with hardening epoxy.
  1. Optional upgrade: Employ the use of a mesh (isolation membrane) to cover crack with liquid applied membrane (epoxy systems only)
- D. Fill area with epoxy or cement /cement matrix and approved aggregate mixture/blend

3.05 INITIAL GRINDING
- A. Wet or dry grind with appropriate medium diamonds/Stones

3.06 GROUTING
- A. Cleanse floor with clean water and rinse. Wet grind with 50 or higher abrasive grit medium diamonds.
- B. Remove excess water and machine or hand grout with cement or epoxy material to fill as needed.

3.07 CURING GROUT
- A. Allow grout to cure a minimum of 12 hours. Maintain ambient air temperature between 70°F (21°C) and 80°F (27°C)

3.08 FINE (Final) GRINDING
- A. Grind with 120 grit carborundum or 200 grit resin bond diamond until grout has been removed from the terrazzo surface.

3.09 CLEANING AND SEALING:
- A. Rinse with clean water and allow too thoroughly dry.
- B. Seal: Apply sealer per sealer manufacturer's written directions
- C. Remove protection and clean any adjacent surfaces effected by the refinishing process.

3.09 PROTECTION
- A. General Contractor shall protect the finish floor from all site activity until Substantial Completion.

END OF SECTION 09016

RESERVATION BRIEF 21

Repairing Historic Flat Plaster Walls and Ceilings

- Historical Background
- Common Plaster Problems
- Repairing Historic Plaster
- When Damaged Plaster Cannot be Repaired
- Patching Materials
- Summary

Plaster in a historic building is like a family album. The handwriting of the artisans, the taste of the original occupants, and the evolving styles of decoration are embodied in the fabric of the building. From modest farmhouses to great buildings, regardless of the ethnic origins of the occupants, plaster has traditionally been used to finish interior walls.

A versatile material, plaster could be applied over brick, stone, half-timber, or frame construction. It provided a durable surface that was easy to clean and that could be applied to flat or curved walls and ceilings.

Plaster could be treated in any number of ways: it could receive stenciling, decorative painting, wallpaper, or whitewash. This variety and the adaptability of the material to nearly any building size, shape, or configuration meant that plaster was the wall surface chosen for nearly all buildings until the 1930s or 40s.

Historic plaster may first appear so fraught with problems that its total removal seems the only alternative. But there are practical and historical reasons for saving it. First, three-coat plaster is unmatched in strength and durability. It resists fire and reduces sound transmission. Next, replacing plaster is expensive. A building owner needs to think carefully about the condition of the plaster that remains; plaster is often not as badly damaged as it first appears.

Of more concern to preservationists, however, original lime and gypsum plaster is part of the building's historic fabric—its smooth troweled or textured surfaces and subtle contours evoke the presence of America's earlier craftsmen. Plaster can also serve as a plain surface for irreplaceable decorative finishes. For both reasons, plaster walls and ceilings contribute to the historic character of the interior and should be left in place and repaired if at all possible.

The approaches described in this Brief stress repairs using wet plaster, and traditional materials and techniques that will best assist the preservation of historic plaster walls and ceilings—and their appearance. Dry wall repairs are not included here, but have been written about extensively in other contexts. Finally, this Brief describes a replacement option when historic plaster cannot be repaired. Thus, a veneer plaster system is discussed rather than dry wall. Veneer systems include a coat or coats of wet plaster—although thinly applied—which can, to a greater extent, simulate traditional hand-troweled or textured finish coats. This system is generally better suited to historic preservation projects than dry wall.

To repair plaster, a building owner must often enlist the help of a plasterer. Plastering is a skilled craft, requiring years of training and special tools. While minor repairs can be undertaken by building owners, most repairs will require the assistance of a plasterer.

Historical Background

Plasterers in North America have relied on two materials to create their handiwork—lime and gypsum. Until the end of the 19th century, plasterers used lime plaster. Lime plaster was made from four ingredients: lime, aggregate, fiber, and water. The lime came from ground-and-heated limestone or oyster shells; the aggregate from sand; and the fiber from cattle or hog hair. Manufacturing changes at the end of the 19th century made it possible to use gypsum as a plastering material. Gypsum and lime plasters were used in combination for the base and finish coats during the early part of the 20th century; gypsum was eventually favored because it set more rapidly and, initially, had a harder finish.

Not only did the basic plastering material change, but the method of application changed also. In early America, the windows, doors, and all other trim were installed before the plaster was applied to the wall. Generally the woodwork was prime-painted before plastering. Obtaining a plumb, level wall, while working against built-up moldings, must have been difficult. But sometime in the first half of the 19th century, builders began installing wooden plaster "grounds" around windows and doors and at the base of the wall. Installing these grounds so that they were level and plumb made the job much easier

because the plasterer could work from a level, plumb, straight surface. Woodwork was then nailed to the "grounds" after the walls were plastered. Evidence of plaster behind trim is often an aid to dating historic houses, or to discerning their physical evolution.

Lime Plaster

When building a house, plasterers traditionally mixed bags of quick lime with water to "hydrate" or "slake" the lime. As the lime absorbed the water, heat was given off. When the heat diminished, and the lime and water were thoroughly mixed, the lime putty that resulted was used to make plaster.

When lime putty, sand, water, and animal hair were mixed, the mixture provided the plasterer with "coarse stuff." This mixture was applied in one or two layers to build up the wall thickness. But the best plaster was done with three coats. The first two coats made up the coarse stuff; they were the scratch coat and the brown coat. The finish plaster, called "setting stuff," contained a much higher proportion of lime putty, little aggregate, and no fiber, and gave the wall a smooth white surface finish.

Compared to the 3/8-inch-thick layers of the scratch and brown coats, the finish coat was a mere 1/8-inch thick. Additives were used for various finish qualities. For example, fine white sand was mixed in for a "float finish." This finish was popular in the early 1900s. (If the plasterer raked the sand with a broom, the plaster wall would retain swirl marks or stipples.) Or marble dust was added to create a hard-finish white coat which could be smoothed and polished with a steel trowel. Finally, a little plaster of Paris, or "gauged stuff," was often added to the finish plaster to accelerate the setting time.

Although lime plaster was used in this country until the early 1900s, it had certain disadvantages. A plastered wall could take more than a year to dry; this delayed painting or papering. In addition, bagged quick lime had to be carefully protected from contact with air, or it became inert because it reacted with ambient moisture and carbon dioxide. Around 1900, gypsum began to be used as a plastering material.

Gypsum Plaster

Gypsum begins to cure as soon as it is mixed with water. It sets in minutes and completely dries in two to three weeks. Historically, gypsum made a more rigid plaster and did not require a fibrous binder. However it is difficult to tell the difference between lime and gypsum plaster once the plaster has cured. Despite these desirable working characteristics, gypsum plaster was more vulnerable to water damage than lime. Lime plasters had often been applied directly to masonry walls (without lathing), forming a suction bond. They could survive occasional wind-driven moisture or water winking up from the ground. Gypsum plaster needed protection from water. Furring strips had to be used against masonry walls to create a dead air space. This prevented moisture transfer.

In rehabilitation and restoration projects, one should rely on the plasterer's judgment about whether to use lime or gypsum plaster. In general, gypsum plaster is the material plasterers use today. Different types of aggregate may be specified by the architect such as clean river sand, perlite, pumice, or vermiculite; however, if historic finishes and textures are being replicated, sand should be used as the base-coat aggregate. Today, if fiber is required in a base coat, a special gypsum is available which includes wood fibers. Lime putty, mixed with about 35% gypsum (gauging plaster) to help it harden, is still used as the finish coat.

Lath

Lath provided a means of holding the plaster in place. Wooden lath was nailed at right angles directly to the structural members of the buildings (the joists and studs), or it was fastened to nonstructural spaced strips known as furring strips. Three types of lath can be found on historic buildings.

Wood Lath

Wood lath is usually made up of narrow, thin strips of wood with spaces in between. The plasterer applies a slight pressure to push the wet plaster through the spaces. The plaster slumps down on the inside of the wall, forming plaster "keys." These keys hold the plaster in place.

Metal Lath

Metal lath, patented in England in 1797, began to be used in parts of the United States toward the end of the 19th century. The steel making up the metal lath contained many more spaces than wood lath had contained. These spaces increased the number of keys; metal lath was better able to hold plaster than wood lath had been.

Rock Lath

A third lath system commonly used was rock lath (also called plaster board or gypsum-board lath). In use as early as 1900, rock lath was made up of compressed gypsum covered by a paper facing. Some

rock lath was textured or perforated to provide a key for wet plaster. A special paper with gypsum crystals in it provides the key for rock lath used today; when wet plaster is applied to the surface, a crystalline bond is achieved.
Rock lath was the most economical of the three lathing systems. Lathers or carpenters could prepare a room more quickly. By the late 1930s, rock lath was used almost exclusively in residential plastering.

Common Plaster Problems

When plaster dries, it is a relatively rigid material which should last almost indefinitely. However, there are conditions that cause plaster to crack, effloresce, separate, or become detached from its lath framewor. These include:

- Structural problems
- Poor workmanship
- Improper curing
- Moisture

Structural Problems

Overloading

Stresses within a wall, or acting on the house as a whole, can create stress cracks. Appearing as diagonal lines in a wall, stress cracks usually start at a door or window frame, but they can appear anywhere in the wall, with seemingly random starting points.
Builders of now-historic houses had no codes to help them size the structural members of buildings. The weight of the roof, the second and third stories, the furniture, and the occupants could impose a heavy burden on beams, joists, and studs. Even when houses were built properly, later remodeling efforts may have cut in a doorway or window without adding a structural beam or "header" across the top of the opening. Occasionally, load-bearing members were simply too small to carry the loads above them. Deflection or wood "creep" (deflection that occurs over time) can create cracks in plaster.
Overloading and structural movement (especially when combined with rotting lath, rusted nails, or poor quality plaster) can cause plaster to detach from the lath. The plaster loses its key. When the mechanical bond with the lath is broken, plaster becomes loose or bowed. If repairs are not made, especially to ceilings, gravity will simply cause chunks of plaster to fall to the floor.

Settlement/Vibration

Cracks in walls can also result when houses settle. Houses built on clay soils are especially vulnerable. Many types of clay (such as montmorillonite) are highly expansive.
In the dry season, water evaporates from the clay particles, causing them to contract. During the rainy season, the clay swells. Thus, a building can be riding on an unstable footing. Diagonal cracks running in opposite directions suggest that house settling and soil conditions may be at fault. Similar symptoms occur when there is a nearby source of vibration-blasting, a train line, busy highway, or repeated sonic booms.

Lath Movement

Horizontal cracks are often caused by lath movement. Because it absorbs moisture from the air, wood lath expands and contracts as humidity rises and falls. This can cause cracks to appear year after year. Cracks can also appear between rock lath panels. A nail holding the edge of a piece of lath may rust or loosen, or structural movement in the wood framing behind the lath may cause a seam to open. Heavy loads in a storage area above a rock-lath ceiling can also cause ceiling cracks.
Errors in initial building construction such as improper bracing, poor corner construction, faulty framing of doors and windows, and undersized beams and floor joists eventually "telegraph" through to the plaster surface.

Poor Workmanship

In addition to problems caused by movement or weakness in the structural framework, plaster durability can be affected by poor materials or workmanship.

Poorly Proportioned Mix

The proper proportioning and mixing of materials are vital to the quality of the plaster job. A bad mix can cause problems that appear years later in a plaster wall. Until recently, proportions of aggregate and lime were mixed on the job. A plasterer may have skimped on the amount of cementing material (lime

or gypsum) because sand was the cheaper material. Over sanding can cause the plaster to weaken or crumble. Plaster made from a poorly proportioned mix may be more difficult to repair.

Incompatible Base Coats and Finish Coats
Use of perlite as an aggregate also presented problems. Perlite is a lightweight aggregate used in the base coat instead of sand. It performs well in cold weather and has a slightly better insulating value. But if a smooth lime finish coat was applied over perlited base coats on wood or rock lath, cracks would appear in the finish coat and the entire job would have to be redone. To prevent this, a plasterer had to add fine silica sand or finely crushed perlite to the finish coat to compensate for the dramatically differing shrinkage rates between the base coat and the finish coat.

Improper Plaster Application
The finish coat is subject to "chip cracking" if it was applied over an excessively dry base coat, or was insufficiently troweled, or if too little gauging plaster was used. Chip cracking looks very much like an alligatored paint surface. Another common problem is called map cracking—fine, irregular cracks that occur when the finish coat has been applied to an over sanded base coat or a very thin base coat.

Too Much Retardant
Retarding agents are added to slow down the rate at which plaster sets, and thus inhibit hardening. They have traditionally included ammonia, glue, gelatin, starch, molasses, or vegetable oil. If the plasterer has used too much retardant, however, a gypsum plaster will not set within a normal 20 to 30 minute time period. As a result, the surface becomes soft and powdery.

Inadequate Plaster Thickness
Plaster is applied in three coats over wood lath and metal lath—the scratch, brown, and finish coats. In three-coat work, the scratch coat and brown coat were sometimes applied on successive days to make up the required wall thickness. Using rock lath allowed the plasterer to apply one base coat and the finish coat—a two-coat job.
If a plasterer skimped on materials, the wall may not have sufficient plaster thickness to withstand the normal stresses within a building. The minimum total thickness for plaster on gypsum board (rock lath) is 1/2 inch. On metal lath the minimum thickness is 5/8 inch; and for wood lath it is about 3/4 to 7/8 inch. This minimum plaster thickness may affect the thickness of trim projecting from the wall's plane.

Improper Curing
Proper temperature and air circulation during curing are key factors in a durable plaster job. The ideal temperature for plaster to cure is between 55 to 70 degrees Fahrenheit. However, historic houses were sometimes plastered before window sashes were put in. There was no way to control temperature and humidity.

Dry Outs, Freezing, and Sweat-outs
When temperatures were too hot, the plaster would return to its original condition before it was mixed with water, that is, calcined gypsum. A plasterer would have to spray the wall with alum water to reset the plaster. If freezing occurred before the plaster had set, the job would simply have to be redone. If the windows were shut so that air could not circulate, the plaster was subject to sweat-out or rot. Since there is no cure for rotted plaster, the affected area had to be removed and replastered.

Moisture
Plaster applied to a masonry wall is vulnerable to water damage if the wall is constantly wet. When salts from the masonry substrate come in contact with water, they migrate to the surface of the plaster, appearing as dry bubbles or efflorescence. The source of the moisture must be eliminated before replastering the damaged area.

Sources of Water Damage
Moisture problems occur for several reasons. Interior plumbing leaks in older houses are common. Roofs may leak, causing ceiling damage. Gutters and downspouts may also leak, pouring rain water next to the building foundation. In brick buildings, dampness at the foundation level can wick up into the above-grade walls. Another common source of moisture is splashback. When there is a paved area next to a masonry building, rainwater splashing up from the paving can dampen masonry walls. In both cases water travels through the masonry and damages interior plaster. Coatings applied to the interior are not effective over the long run. The moisture problem must be stopped on the outside of the wall.

Repairing Historic Plaster

Many of the problems described above may not be easy to remedy. If major structural problems are found to be the source of the plaster problem, the structural problem should be corrected. Some repairs can be made by removing only small sections of plaster to gain access. Minor structural problems that will not endanger the building can generally be ignored. Cosmetic damages from minor building movement, holes, or bowed areas can be repaired without the need for wholesale demolition. However, it may be necessary to remove deteriorated plaster caused by rising damp in order for masonry walls to dry out. Repairs made to a wet base will fail again.

Canvassing Uneven Wall Surfaces

Uneven wall surfaces, caused by previous patching or by partial wallpaper removal, are common in old houses. As long as the plaster is generally sound, cosmetically unattractive plaster walls can be "wallpapered" with strips of a canvas or fabric-like material. Historically, canvassing covered imperfections in the plaster and provided a stable base for decorative painting or wallpaper.

Filling Cracks

Hairline cracks in wall and ceiling plaster are not a serious cause for concern as long as the underlying plaster is in good condition. They may be filled easily with a patching material. For cracks that reopen with seasonal humidity change, a slightly different method is used. First the crack is widened slightly with a sharp, pointed tool such as a crack widener or a triangular can opener. Then the crack is filled. For more persistent cracks, it may be necessary to bridge the crack with tape. In this instance, a fiberglass mesh tape is pressed into the patching material.

After the first application of a quick setting joint compound dries, a second coat is used to cover the tape, feathering it at the edges. A third coat is applied to even out the surface, followed by light sanding. The area is cleaned off with a damp sponge, then dried to remove any leftover plaster residue or dust.

When cracks are larger and due to structural movement, repairs need to be made to the structural system before repairing the plaster. Then, the plaster on each side of the crack should be removed to a width of about 6 inches down to the lath. The debris is cleaned out, and metal lath applied to the cleared area, leaving the existing wood lath in place. The metal lath usually prevents further cracking. The crack is patched with an appropriate plaster in three layers (i.e., base coats and finish coat). If a crack seems to be expanding, a structural engineer should be consulted.

Replacing Delaminated Areas of the Finish Coat

Sometimes the finish coat of plaster comes loose from the base coat. In making this type of repair, the plasterer paints a liquid plaster-bonding agent onto the areas of base-coat plaster that will be replastered with a new lime finish coat. A homeowner wishing to repair small areas of delaminated finish coat can use the methods described in "Patching Materials."

Patching Holes in Walls

For small holes (less than 4 inches in diameter) that involve loss of the brown and finish coats, the repair is made in two applications. First, a layer of base coat plaster is troweled in place and scraped back below the level of the existing plaster. When the base coat has set but not dried, more plaster is applied to create a smooth, level surface. One-coat patching is not generally recommended by plasterers because it tends to produce concave surfaces that show up when the work is painted. Of course, if the lath only had one coat of plaster originally, then a one-coat patch is appropriate.

For larger holes where all three coats of plaster are damaged or missing down to the wood lath, plasterers generally proceed along these lines. First, all the old plaster is cleaned out and any loose lath is re-nailed. Next, a water mist is sprayed on the old lath to keep it from twisting when the new, wet plaster is applied, or better still, a bonding agent is used.

To provide more reliable keying and to strengthen the patch, expanded metal lath (diamond mesh) should be attached to the wood lath with tie wires or nailed over the wood lath with lath nails. The plaster is then applied in three layers over the metal lath, lapping each new layer of plaster over the old plaster so that old and new are evenly joined. This stepping is recommended to produce a strong, invisible patch. Also, if a patch is made in a plaster wall that is slightly wavy, the contour of the patch should be made to conform to the irregularities of the existing work. A flat patch will stand out from the rest of the wall.

Patching Holes in Ceilings

Hairline cracks and holes may be unsightly, but when portions of the ceiling come loose, a more serious problem exists. The keys holding the plaster to the ceiling have probably broken. First, the plaster around the loose plaster should be examined.

Keys may have deteriorated because of a localized moisture problem, poor quality plaster, or structural overloading; yet, the surrounding system may be intact. If the areas surrounding the loose area are in reasonably good condition, the loose plaster can be reattached to the lath using flathead wood screws and plaster washers. To patch a hole in the ceiling plaster, metal lath is fastened over the wood lath; then the hole is filled with successive layers of plaster, as described above.

Establishing New Plaster Keys

If the back of the ceiling lath is accessible (usually from the attic or after removing floor boards), small areas of bowed-out plaster can be pushed back against the lath. A padded piece of plywood and braces are used to secure the loose plaster. After dampening the old lath and coating the damaged area with a bonding agent, a fairly liquid plaster mix (with a glue size retardant added) is applied to the backs of the lath, and worked into the voids between the faces of the lath and the back of the plaster. While this first layer is still damp, plaster-soaked strips of jute scrim are laid across the backs of the lath and pressed firmly into the first layer as reinforcement. The original lath must be secure, otherwise the weight of the patching plaster may loosen it.

Loose, damaged plaster can also be re-keyed when the goal is to conserve decorative surfaces or wallpaper. Large areas of ceilings and walls can be saved. This method requires the assistance of a skilled conservator—it is not a repair technique used by most plasterers.

The conservator injects an acrylic adhesive mixture through holes drilled in the face of the plaster (or through the lath from behind, when accessible). The loose plaster is held firm with plywood bracing until the adhesive bonding mixture sets. When complete, gaps between the plaster and lath are filled, and the loose plaster is secure.

Replastering Over the Old Ceiling

If a historic ceiling is too cracked to patch or is sagging (but not damaged from moisture), plasterers routinely keep the old ceiling and simply relath and replaster over it. This repair technique can be used if lowering the ceiling slightly does not affect other ornamental features. The existing ceiling is covered with 1x3-inch wood furring strips, one to each joist, and fastened completely through the old lath and plaster using a screw gun. Expanded metal lath or gypsum board lath is nailed over the furring strips. Finally, two or three coats are applied according to traditional methods. Replastering over the old ceiling saves time, creates much less dust than demolition, and gives added fire protection.

When Damaged Plaster Cannot be Repaired—Replacement Options

Partial or complete removal may be necessary if plaster is badly damaged, particularly if the damage was caused by long-term moisture problems. Workers undertaking demolition should wear OSHA-approved masks because the plaster dust that flies into the air may contain decades of coal soot. Lead, from lead based paint, is another danger. Long-sleeved clothing and head-and-eye protection should be worn. Asbestos, used in the mid-twentieth century as an insulating and fireproofing additive, may also be present and OSHA-recommended precautions should be taken. If plaster in adjacent rooms is still in good condition, walls should not be pounded—a small trowel or pry bar is worked behind the plaster carefully in order to pry loose pieces off the wall.

When the damaged plaster has been removed, the owner must decide whether to replaster over the existing lath or use a different system. This decision should be based in part on the thickness of the original plaster and the condition of the original lath. Economy and time are also valid considerations. It is important to ensure that the wood trim around the windows and doors will have the same "reveal" as before. (The "reveal" is the projection of the wood trim from the surface of the plastered wall). A lath and plaster system that will give this required depth should be selected.

Replastering—Alternative Lath Systems for New Plaster

Replastering Old Wood Lath

When plasterers work with old lath, each lath strip is re-nailed and the chunks of old plaster are cleaned out. Because the old lath is dry, it must be thoroughly soaked before applying the base coats of plaster, or it will warp and buckle; furthermore, because the water is drawn out, the plaster will fail to set properly. As noted earlier, if new metal lath is installed over old wood lath as the base for new plaster,

many of these problems can be avoided and the historic lath can be retained. The ceiling should still be sprayed unless a vapor barrier is placed behind the metal lath.

Replastering Over New Metal Lath
An alternative to reusing the old wood lath is to install a different lathing system. Galvanized metal lath is the most expensive, but also the most reliable in terms of longevity, stability, and proper keying. When lathing over open joists, the plasterer should cover the joists with kraft paper or a polyethylene vapor barrier. Three coats of wet plaster are applied consecutively to form a solid, monolithic unit with the lath. The scratch coat keys into the metal lath; the second, or brown, coat bonds to the scratch coat and builds the thickness; the third, or finish coat, consists of lime putty and gauging plaster.

Replastering Over New Rock Lath
It is also possible to use rock lath as a plaster base. Plasterers may need to remove the existing wood lath to maintain the woodwork's reveal. Rock lath is a 16x36-inch, 1/2-inch thick, gypsum-core panel covered with absorbent paper with gypsum crystals in the paper. The crystals in the paper bond the wet plaster and anchor it securely. This type of lath requires two coats of new plaster—the brown coat and the finish coat. The gypsum lath itself takes the place of the first, or scratch, coat of plaster.

Painting New Plaster
The key to a successful paint job is proper drying of the plaster. Historically, lime plasters were allowed to cure for at least a year before the walls were painted or papered. With modern ventilation, plaster cures in a shorter time; however, fresh gypsum plaster with a lime finish coat should still be perfectly dry before paint is applied—or the paint may peel. (Plasterers traditionally used the "match test" on new plaster. If a match would light by striking it on the new plaster surface, the plaster was considered dry.) Today it is best to allow new plaster to cure two to three weeks. A good alkaline-resistant primer, specifically formulated for new plaster, should then be used. A compatible latex or oil-based paint can be used for the final coat.

A Modern Replacement System—Veneer Plaster
Using one of the traditional lath and plaster systems provides the highest quality plaster job. However, in some cases, budget and time considerations may lead the owner to consider a less expensive replacement alternative. Designed to reduce the cost of materials, a more recent lath and plaster system is less expensive than a two-or-three coat plaster job, but only slightly more expensive than drywall. This plaster system is called veneer plaster.
The system uses gypsum-core panels that are the same size as drywall (4x8 feet), and specially made for veneer plaster. They can be installed over furring channels to masonry walls or over old wood lath walls and ceilings. Known most commonly as "blue board," the panels are covered with a special paper compatible with veneer plaster. Joints between the 4-foot wide sheets are taped with fiberglass mesh, which is bedded in the veneer plaster. After the tape is bedded, a thin, 1/16-inch coat of high-strength veneer plaster is applied to the entire wall surface. A second veneer layer can be used as the "finish" coat, or the veneer plaster can be covered with a gauged lime finish-coat—the same coat that covers ordinary plaster.
Although extremely thin, a two-coat veneer plaster system has a 1,500 psi rating and is thus able to withstand structural movements in a building or surface abrasion. With either a veneer finish or a gauged lime putty finish coat, the room will be ready for painting almost immediately. When complete, the troweled or textured wall surface looks more like traditional plaster than drywall.
The thin profile of the veneer system has an added benefit, especially for owners of uninsulated masonry buildings. Insulation can be installed between the pieces of furring channel used to attach blue board to masonry walls. This can be done without having to fur out the window and door jambs. The insulation plus the veneer system will result in the same thickness as the original plaster. Occupants in the rooms will be more comfortable because they will not be losing heat to cold wall surfaces.

Patching Materials

Plasterers generally use ready-mix base-coat plaster for patching, especially where large holes need to be filled. The ready-mix plaster contains gypsum and aggregate in proper proportions. The plasterer only needs to add water.
Another mix plasterers use to patch cracks or small holes, or for finish-coat repair, is a "high gauge" lime putty (50 percent lime; 50 percent gauging plaster). This material will produce a white, smooth patch. It is especially suitable for surface repairs.

Although property owners cannot duplicate the years of accumulated knowledge and craft skills of a professional plasterer, there are materials that can be used for do-it-yourself repairs. For example, fine cracks can be filled with an all-purpose drywall joint compound. For bridging larger cracks using fiberglass tape, a homeowner can use a "quicksetting" joint compound. This compound has a fast drying time—60, 90, or 120 minutes. Quick-setting joint compound dries because of a chemical reaction, not because of water evaporation. It shrinks less than all-purpose joint compound and has much the same workability as ready-mix base-coat plaster. However, because quick-set joint compounds are hard to sand, they should only be used to bed tape or to fill large holes. All-purpose point compound should be used as the final coat prior to sanding.
Homeowners may also want to try using a ready-mix perlited base-coat plaster for scratch and brown coat repair. The plaster can be hand-mixed in small quantities, but bagged ready-mix should be protected from ambient moisture. A "millmixed pre-gauged" lime finish coat plaster can also be used by homeowners. A base coat utilizing perlite or other lightweight aggregates should only be used for making small repairs (less than 4 ft. patches). For large-scale repairs and entire room replastering, see the precautions in Table 1 for using perlite.
Homeowners may see a material sold as "patching plaster" or "plaster of Paris" in hardware stores. This dry powder cannot be used by itself for plaster repairs. It must be combined with lime to create a successful patching mixture.
When using a lime finish coat for any repair, wait longer to paint, or use an alkaline-resistant primer.

Summary

The National Park Service recommends retaining historic plaster if at all possible. Plaster is a significant part of the "fabric" of the building. Much of the building's history is documented in the layers of paint and paper found covering old plaster. For buildings with decorative painting, conservation of historic flat plaster is even more important. Consultation with the National Park Service, with State Historic Preservation Officers, local preservation organizations, historic preservation consultants, or with the Association for Preservation Technology is recommended. Where plaster cannot be repaired or conserved using one of the approaches outlined in this Brief, documentation of the layers of wallpaper and paint should be undertaken before removing the historic plaster. This information may be needed to complete a restoration plan.

Plaster Terms

Scratch coat. The first base coat put on wood or metal lath. The wet plaster is "scratched" with a scarifier or comb to provide a rough surface so the next layer of base coat will stick to it.

Brown coat. The brown coat is the second application of wet, base-coat plaster with wood lath or metal systems. With gypsum board lath (rock lath, plasterboard), it is the only base coat needed.

Finish coat. Pure lime, mixed with about 35 percent gauging plaster to help it harden, is used for the very thin surface finish of the plaster wall. Fine sand can be added for a sanded finish coat.

Casing Bead. Early casing bead was made of wood. In the 19th century, metal casing beads were sometimes used around fireplace projections, and door and window openings. Like a wood ground, they indicate the proper thickness for the plaster.
Corner Bead. Wire mesh with a rigid metal spline used on outside corners. Installing the corner bread plumb is important.

Outside corners. Installing the corner bead plumb is important.

Cornerite. Wire mesh used on inside corners of adjoining walls and ceilings. It keeps corners from cracking.

Ground. Plasterers use metal or wood strips around the edges of doors and windows and at the bottom of walls. These grounds help keep the plaster the same thickness and provide a stopping edge for the plaster. Early plaster work, however, did not use grounds. On early buildings, the woodwork was installed and primed before plastering began. Sometime in the early 19th century, a transition occurred, and plasterers applied their wall finish before woodwork was installed.

Gypsum. Once mined from large gypsum quarries near Paris (thus the name plaster of Paris), gypsum in its natural form is calcium sulfate. When calcined (or heated), one-and-a-half water molecules are

driven off, leaving a hemi-hydrate of calcium sulfate. When mixed with water, it becomes calcium sulfate again. While gypsum was used in base-coat plaster from the 1890s on, it has always been used in finish coat and decorative plaster. For finish coats, gauging plaster was added to lime putty; it causes the lime to harden. Gypsum is also the ingredient in moulding plaster, a finer plaster used to create decorative moldings in ornamental plaster work.

Lime. Found in limestone formations or shell mounds, naturally occurring lime is calcium carbonate. When heated, it becomes calcium oxide. After water has been added, it becomes calcium hydroxide. This calcium hydroxide reacts with carbon dioxide in the air to recreate the original calcium carbonate.

Screed. Screeds are strips of plaster run vertically or horizontally on walls or ceilings. They are used to plumb and straighten uneven walls and level ceilings. Metal screeds are used to separate different types of plaster finishes or to separate lime and cement plasters.

SECTION 092400

CEMENT PLASTERING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Exterior vertical plasterwork (stucco).
2. Exterior horizontal and nonvertical plasterwork (stucco).
3. Interior vertical plasterwork.
4. Interior horizontal and nonvertical plasterwork.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

C. Samples: For each type of factory-prepared finish coat and for each color and texture specified.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance Ratings: Where indicated, provide cement plaster assemblies identical to those of assemblies tested for fire resistance according to ASTM E 119 by a qualified testing agency.

2.2 METAL LATH

A. Expanded-Metal Lath: ASTM C 847, cold-rolled carbon-steel sheet with ASTM A 653/A 653M, G60 (Z180), hot-dip galvanized-zinc coating.

1. Diamond-Mesh Lath: [**Flat**] [**Self-furring**], [**2.5 lb/sq. yd. (1.4 kg/sq. m)**] Flat-Rib Lath: Rib depth of not more than 1/8 inch (3 mm), [**2.75 lb/sq. yd. (1.5 kg/sq. m)**] [3/8-Inch (10-mm) Rib Lath: [**3.4 lb/sq. yd. (1.8 kg/sq. m**

B. Wire-Fabric Lath:

1. Welded-Wire Lath: ASTM C 933; self-furring, [**1.4 lb/sq. yd. (0.8 kg/sq. m)**]
2. Woven-Wire Lath: ASTM C 1032; self-furring, with stiffener wire backing, 1.4 lb/sq. yd. (0.8 kg/sq. m).

2.3 ACCESSORIES

A. General: Comply with ASTM C 1063, and coordinate depth of trim and accessories with thicknesses and number of plaster coats required.

B. Metal Accessories:

1. Foundation Weep Screed: Fabricated from hot-dip galvanized-steel sheet, ASTM A 653/A 653M, G60 (Z180) zinc coating.
2. Cornerite: Fabricated from metal lath with ASTM A 653/A 653M, G60 (Z180), hot-dip galvanized-zinc coating.
3. External- (Outside-) Corner Reinforcement: Fabricated from metal lath with ASTM A 653/A 653M, G60 (Z180), hot-dip galvanized-zinc coating.
4. Cornerbeads: Fabricated from [**zinc**] [**or**] [**zinc-coated (galvanized) steel**].
    a. Smallnose cornerbead with expanded flanges; use unless otherwise indicated.
    b. Smallnose cornerbead with perforated flanges; use on curved corners.
    c. Smallnose cornerbead with expanded flanges reinforced by perforated stiffening rib; use on columns and for finishing unit masonry corners.

d. Bullnose cornerbead, radius 3/4 inch (19 mm) minimum, with expanded flanges; use at locations indicated on Drawings.

5. Casing Beads: Fabricated from [**zinc**] [**or**] [**zinc-coated (galvanized) steel**]; square-edged style; with expanded flanges.
6. Control Joints: Fabricated from [**zinc**] [**or**] [**zinc-coated (galvanized) steel**]; one-piece-type, folded pair of unperforated screeds in M-shaped configuration; with perforated flanges and removable protective tape on plaster face of control joint.
7. Expansion Joints: Fabricated from [**zinc**] [**or**] [**zinc-coated (galvanized) steel**]; folded pair of unperforated screeds in M-shaped configuration; with expanded flanges.
8. Two-Piece Expansion Joints: Fabricated from [**zinc**] [**or**] [**zinc-coated (galvanized) steel**]; formed to produce slip-joint and square-edged reveal that is adjustable from 1/4 to 5/8 inch (6 to 16 mm) wide; with perforated flanges.

C. Plastic Accessories: Manufactured from high-impact PVC.

1. Cornerbeads: With perforated flanges.
   a. Smallnose cornerbead; use unless otherwise indicated.
   b. Bullnose cornerbead, radius 3/4-inch (19-mm) minimum; use at locations indicated on Drawings.
2. Casing Beads: With perforated flanges in depth required to suit plaster bases indicated and flange length required to suit applications indicated.
   a. Square-edge style; use unless otherwise indicated.
   b. Bullnose style, radius 3/4-inch (19-mm) minimum; use at locations indicated on Drawings.
3. Control Joints: One-piece-type, folded pair of unperforated screeds in M-shaped configuration; with perforated flanges and removable protective tape on plaster face of control joint.
4. Expansion Joints: Two-piece type, formed to produce slip-joint and square-edged [**1/2-inch- (13-mm-)**] [**1-inch- (25-mm-)**] [**1-1/2-inch- (38-mm-)**] <**Insert dimension**> wide reveal; with perforated concealed flanges.

2.4 MISCELLANEOUS MATERIALS

A. Water for Mixing and Finishing Plaster: Potable and free of substances capable of affecting plaster set or of damaging plaster, lath, or accessories.

B. Fiber for Base Coat: Alkaline-resistant glass or polypropylene fibers, 1/2 inch (13 mm) long, free of contaminants, manufactured for use in cement plaster.

C. Bonding Compound: ASTM C 932.

D. Fasteners for Attaching Metal Lath to Substrates: ASTM C 1063.

E. Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, not less than 0.0475-inch (1.21-mm) diameter unless otherwise indicated.

F. Sound-Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.

2.5 PLASTER MATERIALS

A. Portland Cement: ASTM C 150/C 150M, Type I, Type II.

1. Color for Finish Coats: White or Gray to match existing.

B. Masonry Cement: ASTM C 91, Type N.

1. Color for Finish Coats: White or Gray to match existing.

C. Plastic Cement: ASTM C 1328.

D. Colorants for Job-Mixed Finish Coats: Colorfast mineral pigments that produce finish plaster color **to match Existing**.

E. Lime: ASTM C 206, Type S; or ASTM C 207, Type S.

F. Sand Aggregate: ASTM C 897.
G. Perlite Aggregate: ASTM C 35.
H. Ready-Mixed Finish-Coat Plaster: Mill-mixed portland cement, aggregates, coloring agents, and proprietary ingredients.
   1. Color: **Match Existing**.
I. Acrylic-Based Finish Coatings: Factory-mixed acrylic-emulsion coating systems formulated with colorfast mineral pigments and fine aggregates; for use over cement plaster base coats. Include manufacturer's recommended primers and sealing topcoats for acrylic-based finishes.
   1. Color: **Match Existing**

2.6 PLASTER MIXES
A. General: Comply with ASTM C 926 for applications indicated.
   1. Fiber Content: Add fiber to base-coat mixes after ingredients have mixed at least two minutes. Comply with fiber manufacturer's written instructions for fiber quantities in mixes, but do not exceed 1 lb of fiber/cu. yd. (0.6 kg of fiber/cu. m) of cementitious materials.
B. Base-Coat Mixes for Use over Metal Lath: Scratch and brown coats for three-coat plasterwork as follows:
   1. Portland Cement Mixes:
      a. Scratch Coat: For cementitious material, mix 1 part portland cement and [0 to 3/4] [3/4 to 1-1/2] parts lime. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
      b. Brown Coat: For cementitious material, mix 1 part portland cement and [**0 to 3/4**] [**3/4 to 1-1/2**] parts lime. Use 3 to 5 parts aggregate per part of cementitious material, but not less than volume of aggregate used in scratch coat.
   2. Masonry Cement Mixes:
      a. Scratch Coat: Mix 1 part masonry cement and 2-1/2 to 4 parts aggregate.
      b. Brown Coat: Mix 1 part masonry cement and 3 to 5 parts aggregate, but not less than volume of aggregate used in scratch coat.
   3. Portland and Masonry Cement Mixes:
      a. Scratch Coat: For cementitious material, mix 1 part portland cement and 1 part masonry cement. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
      b. Brown Coat: For cementitious material, mix 1 part portland cement and 1 part masonry cement. Use 3 to 5 parts aggregate per part of cementitious material, but not less than volume of aggregate used in scratch coat.
   4. Plastic Cement Mixes:
      a. Scratch Coat: Mix 1 part plastic cement and 2-1/2 to 4 parts aggregate.
      b. Brown Coat: Mix 1 part plastic cement and 3 to 5 parts aggregate, but not less than volume of aggregate used in scratch coat.
   5. Portland and Plastic Cement Mixes:
      a. Scratch Coat: For cementitious material, mix 1 part plastic cement and 1 part portland cement. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
      b. Brown Coat: For cementitious material, mix 1 part plastic cement and 1 part portland cement. Use 3 to 5 parts aggregate per part of cementitious material, but not less than volume of aggregate used in scratch coat.
C. Base-Coat Mixes for Use over [**Unit Masonry**] [**and**] [**Concrete**]: Single base (scratch) coat for two-coat plasterwork on low-absorption plaster bases as follows:
   1. Portland Cement Mix: For cementitious material, mix 1 part portland cement and 0 to 3/4 part lime. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
   2. Portland and Masonry Cement Mix: For cementitious material, mix 1 part portland cement and 1 part masonry cement. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
   3. Plastic Cement Mix: Use 1 part plastic cement and 2-1/2 to 4 parts aggregate.

D. Base-Coat Mixes for Use over [**Unit Masonry**] [**and**] [**Concrete**]: Single base (scratch) coat for two-coat plasterwork on high-absorption plaster bases as follows:
   1. Portland Cement Mix: For cementitious material, mix 1 part portland cement and 3/4 to 1-1/2 parts lime. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
   2. Masonry Cement Mix: Use 1 part masonry cement and 2-1/2 to 4 parts aggregate.
   3. Portland and Masonry Cement Mix: For cementitious material, mix 1 part portland cement and 1 part masonry cement. Use 2-1/2 to 4 parts aggregate per part of cementitious material.
   4. Plastic Cement Mix: Use 1 part plastic cement and 2-1/2 to 4 parts aggregate.

E. Job-Mixed Finish-Coat Mixes:
   1. Portland Cement Mix: For cementitious materials, mix 1 part portland cement and [3/4 to 1-1/2] [1-1/2 to 2] parts lime. Use 1-1/2 to 3 parts aggregate per part of cementitious material.
   2. Masonry Cement Mix: Use 1 part masonry cement and 1-1/2 to 3 parts aggregate.
   3. Portland and Masonry Cement Mix: For cementitious materials, mix 1 part portland cement and 1 part masonry cement. Use 1-1/2 to 3 parts aggregate per part of cementitious material.
   4. Plastic Cement Mix: Use 1 part plastic cement and 1-1/2 to 3 parts aggregate.

F. Factory-Prepared Finish-Coat Mixes: For **ready-mixed finish-coat plasters**, **acrylic-based finish coatings**, comply with manufacturer's written instructions.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Prepare smooth, solid substrates for plaster according to ASTM C 926.

B. Fire-Resistance-Rated Assemblies: Install components according to requirements for design designations from listing organization and publication indicated on Drawings.

C. Sound-Attenuation Blankets: Where required, install blankets before installing lath unless blankets are readily installed after lath has been installed on one side.

3.2 INSTALLING METAL LATH

A. Metal Lath: Install according to ASTM C 1063.

3.3 INSTALLING ACCESSORIES

A. Install according to ASTM C 1063 and at locations indicated on Drawings.

B. Reinforcement for External (Outside) Corners:
   1. Install lath-type, external-corner reinforcement at exterior locations.
   2. Install cornerbead at interior locations.

C. Control Joints: Locate as indicated on Drawings.

3.4 PLASTER APPLICATION

A. General: Comply with ASTM C 926.

B. Bonding Compound: Apply on **unit masonry and concrete** substrates for direct application of plaster.

C. Walls; Base-Coat Mixes for Use over Metal Lath: For scratch and brown coats, for three-coat plasterwork with 3/4-inch (19-mm) total thickness, as follows:
   1. Portland cement mixes.
   2. Masonry cement mixes.
   3. Portland and masonry cement mixes.
   4. Plastic cement mixes.
   5. Portland and plastic cement mixes.

D. Ceilings; Base-Coat Mixes for Use over Metal Lath: For scratch and brown coats, for three-coat plasterwork and having [**1/2-inch (13-mm) total thickness**] [**3/4-inch (19-mm) total thickness for metal lath on concrete**], as follows:
   1. Portland cement mixes.
   2. Masonry cement mixes.
   3. Portland and masonry cement mixes.
   4. Plastic cement mixes.
   5. Portland and plastic cement mixes.

E. Walls; Base-Coat Mix: For base (scratch) coat, for two-coat plasterwork and having [**3/8-inch (10-mm) thickness on masonry**] [**1/4-inch (6-mm) thickness on concrete**], as follows:
   1. Portland cement mix.
   2. Masonry cement mix.
   3. Portland and masonry cement mix.
   4. Plastic cement mix.
   5. Portland and plastic cement mix.

F. Ceilings; Base-Coat Mix: For base (scratch) coat, for two-coat plasterwork and having 1/4-inch (6-mm) thickness on concrete, as follows:
   1. Portland cement mix.
   2. Masonry cement mix.
   3. Portland and masonry cement mix.
   4. Plastic cement mix.
   5. Portland and plastic cement mix.

G. Plaster Finish Coats: Apply to provide finish to match Existing.

H. Acrylic-Based Finish Coatings: Apply coating system, including primers, finish coats, and sealing topcoats, according to manufacturer's written instructions.

I. Concealed Exterior Plasterwork: Where plaster application is used as a base for adhered finishes, omit finish coat.

J. Concealed Interior Plasterwork:
   1. Where plaster application is concealed behind built-in cabinets, similar furnishings, and equipment, apply finish coat.
   2. Where plaster application is concealed above suspended ceilings and in similar locations, omit finish coat.
   3. Where plaster application is used as a base for adhesive application of tile and similar finishes, omit finish coat.

3.5 PLASTER REPAIRS

A. Repair or replace work to eliminate cracks, dents, blisters, buckles, crazing and check cracking, dry outs, efflorescence, sweat outs, and similar defects and where bond to substrate has failed.

END OF SECTION 092400

SECTION 09241

GYPSUM VENEER PLASTERING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Gypsum veneer plaster and gypsum base for interior veneer plaster.
   2. Gypsum veneer plaster over interior cementitious backer units.
   3. Gypsum veneer plaster over interior masonry surfaces.
   4. Gypsum veneer plaster over interior monolithic concrete surfaces.

B. Related Requirements:
   1. Section 092216 "Non-Structural Metal Framing" for non-load-bearing steel framing.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Show locations, fabrication, and installation of control joints, reveals, and trim; include plans, elevations, sections, details of components, and attachments to other work.

C. Samples: For each trim accessory and textured finish on rigid backing.

1.3 QUALITY ASSURANCE

A. Mockups: Provide mockups of **ceilings and partitions** in sizes of at least 100 sq. ft. (9 sq. m).

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.

B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.

2.2 GYPSUM VENEER PLASTER

A. One-Component Gypsum Veneer Plaster: ASTM C 587, ready-mixed, smooth, finish-coat veneer plaster formulated for application directly over substrate without use of separate base-coat material.

B. High-Strength, One-Component Gypsum Veneer Plaster: ASTM C 587, ready-mixed, smooth, finish-coat veneer plaster containing mill-mixed, fine silica sand; with a compressive strength of 3000 psi (20 MPa) when tested according to ASTM C 472; and formulated for application directly over substrate without use of separate base-coat material.

C. Two-Component Gypsum Veneer Plaster: ASTM C 587, with separate formulations; one for base-coat application and one for finish-coat application over substrates.
   1. Base Coat:
   2. Smooth Finish Coat:
   3. Textured Finish Coat:

D. High-Strength, Two-Component Gypsum Veneer Plaster: ASTM C 587, ready-mixed, base-coat plaster and smooth finish-coat veneer plaster containing mill-mixed, fine silica sand; with a compressive strength of 3000 psi (20 MPa) when tested according to ASTM C 472.

2.3 PANEL PRODUCTS

A. Gypsum Base for Veneer Plaster: ASTM C 1396/C 1396M.
   1. Thickness: **To match existing**.

B. Gypsum Base for Veneer Plaster, Type X: ASTM C 1396/C 1396M.
   1. Thickness: **To match existing** .

C. Gypsum Base for Veneer Plaster, Type C: ASTM C 1396/C 1396M. Manufactured to have increased fire-resistive capability.
   1. Thickness: [**1/2 inch (12.7 mm)**] [**As indicated**] <**Insert dimension**>.

D. Glass-Mat Interior Gypsum Board: ASTM C 1658/C 1658M. With moisture- and mold-resistant core; [**non-rated**] [**fire-resistive rated**]; glass-mat facing on both sides of panel.
   1. Core: [**1/2 inch (12.7 mm), regular type**] [**1/2 inch (12.7 mm), Type X**] [**5/8 inch (15.9 mm), Type X**].
   2. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

E. Cementitious Backer Units: ANSI A118.9 and ASTM C 1288 and approved by backer unit manufacturer for use as veneer plaster substrate.
   1. Thickness: [**1/2 inch (12.7 mm)**] [**As indicated**] <**Insert dimension**>.
   2. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

F. Backing Panels for Multilayer Applications: ASTM C 1396/C 1396M gypsum base or gypsum board, as recommended by gypsum veneer plaster manufacturer, for application method and thicknesses indicated.
   1. Core: Matching face layer unless otherwise indicated.
   2. Thickness: Matching face layer unless otherwise indicated.

2.4 TRIM ACCESSORIES

A. Standard Trim: ASTM C 1047, approved for use in gypsum veneer plaster applications indicated.
   1. Material: [**Galvanized-steel sheet or aluminum-coated steel sheet; rolled zinc, plastic, or paper-faced galvanized-steel sheet**] [**Galvanized-steel sheet, aluminum-coated steel sheet, or rolled zinc**] [**Plastic**] [**Paper-faced, galvanized-steel sheet**].

B. Aluminum Trim: Extruded accessories of profiles and dimensions indicated.

2.5 JOINT-REINFORCING MATERIALS

A. General: Comply with joint strength requirements in ASTM C 587 and with gypsum veneer plaster manufacturer's written recommendations for each application indicated.

B. Joint Tape: [**As recommended by gypsum veneer plaster manufacturer for applications indicated**] [**Paper**] [**Open-mesh, glass fiber**].

C. Embedding Material for Joint Tape: As recommended by gypsum veneer plaster manufacturer for use with joint-tape material and gypsum veneer plaster applications indicated.

2.6 AUXILIARY MATERIALS

A. Bonding Agent: ASTM C 631 polyvinyl acetate.

B. Laminating Adhesive: Adhesive or joint compound recommended by manufacturer for directly adhering gypsum-base, face-layer panels to backing-layer panels in multilayer construction.

C. Steel Drill Screws: ASTM C 1002 unless otherwise indicated.
   1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.

D. For fastening cementitious backer units, use screws of type and size recommended by panel manufacturer.

E. Sound Attenuation Blankets: ASTM C 665, Type I; Comply with mineral-fiber requirements of assembly.

F. Acoustical Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant, complying with ASTM C 834.

G. Patching Mortar: Dry-pack patching mortar, consisting of 1 part portland cement to 2-1/2 parts fine aggregate passing a No. 16 (1.18-mm) sieve, using only enough water for handling and placing.

PART 3 - EXECUTION

3.1 INSTALLING PANELS, GENERAL

A. Gypsum Base for Veneer Plaster: Apply according to ASTM C 844 unless manufacturer's written recommendations are more stringent.
   1. Erection Tolerance: No more than 1/16-inch (1.6-mm) offsets between planes of gypsum base panels, and 1/8 inch in 8 feet (3 mm in 2.4 m) noncumulative, for level, plumb, warp, and bow.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, or mold damaged.

C. Install sound attenuation blankets before installing gypsum base for veneer plaster.

D. Cementitious Backer Units: Install according to ANSI A108.11.
   1. Where cementitious backer units abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.

E. Trim: Install trim with back flanges intended for fasteners, and attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.

F. Control Joints: Install as required and recommended by Plaster Stnadards.

G. Gypsum Base: Reinforce interior angles and flat joints with joint tape and embedding material to comply with ASTM C 843 and with gypsum veneer plaster manufacturer's written recommendations.

H. Abuse-Resistant Base: Reinforce joints between abuse-resistant panels with joint tape and embedding material according to panel manufacturer's written recommendations.

I. Glass-Mat Interior Gypsum Board: Reinforce joints between moisture- and mold-resistant panels with joint tape and embedding material according to panel manufacturer's written recommendations.

3.2 GYPSUM VENEER PLASTERING

A. Bonding Agent: Apply bonding agent on dry according to gypsum veneer plaster manufacturer's written recommendations.

B. Gypsum Veneer Plaster Mixing: Mechanically mix gypsum veneer plaster materials to comply with ASTM C 843 and with gypsum veneer plaster manufacturer's written recommendations.

C. Gypsum Veneer Plaster Application: Comply with ASTM C 843 and with veneer plaster manufacturer's written recommendations.
   1. One-Component Gypsum Veneer Plaster: Trowel apply plaster over substrate to uniform thickness. Fill all voids and imperfections. Immediately double back with same mixer batch of plaster to a uniform total thickness of 1/16 to 3/32 inch (1.6 to 2.4 mm).
   2. Two-Component Gypsum Veneer Plaster:
      a. Base Coat: Hand trowel or machine apply base coat over substrate to a uniform thickness of 1/16 to 3/32 inch (1.6 to 2.4 mm). Fill voids and imperfections.
      b. Finish Coat: Trowel apply finish-coat plaster over base-coat plaster to a uniform thickness of 1/16 to 3/32 inch (1.6 to 2.4 mm).
   3. Where gypsum veneer plaster abuts metal, including doorframes, windows and other units, groove finish coat to eliminate spalling.
   4. Do not apply veneer plaster to gypsum base if paper facing has degraded from exposure to sunlight. Before applying veneer plaster, use remedial methods to restore bonding

capability to degraded paper facing according to manufacturer's written recommendations.

D. Concealed Surfaces: Do not omit gypsum veneer plaster behind cabinets, furniture, furnishings, and similar removable items. Omit veneer plaster in the following areas where it will be concealed from view in the completed Work unless otherwise indicated or required to maintain fire-resistance and STC ratings:
   1. Above suspended ceilings.
   2. Behind wood paneling.

E. Gypsum Veneer Plaster Finish: To match existing.

END OF SECTION 092613

SECTION 092900

GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Exterior gypsum board for ceilings and soffits.
3. Tile backing panels.
4. Texture finishes.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Sustainable Design Submittals:

C. Samples: For each texture finish indicated on same backing indicated for Work.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.

B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.

2.2 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.3 INTERIOR GYPSUM BOARD

A. Gypsum Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch (15.9 mm).
2. Long Edges: **Tapered**.

B. Flexible Gypsum Board: ASTM C 1396/C 1396M. Manufactured to bend to fit radii and to be more flexible than standard regular-type gypsum board of same thickness.

1. Thickness: 1/4 inch (6.4 mm).
2. Long Edges: Tapered.

C. Mold-Resistant Gypsum Board: ASTM C 1396/C 1396M. With moisture- and mold-resistant core and paper surfaces.

1. Core:**5/8 inch (15.9 mm), Type X**.
2. Long Edges: Tapered.
3. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

2.4 TILE BACKING PANELS

A. Glass-Mat, Water-Resistant Backing Board: ASTM C 1178/C 1178M, with manufacturer's standard edges.

1. Core: **5/8 inch (15.9 mm), Type X**.
2. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

B. Cementitious Backer Units: ANSI A118.9 and ASTM C 1288 or ASTM C 1325, with manufacturer's standard edges.
   1. Thickness: **1/4 inch (6.4 mm**.
   2. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

2.5 TRIM ACCESSORIES

A. Interior Trim: ASTM C 1047.
   1. Material: [**Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized-steel sheet**] [**Galvanized or aluminum-coated steel sheet or rolled zinc**] [**Plastic**] [**Paper-faced galvanized-steel sheet**].
   2. Shapes:
      a. Cornerbead.
      b. Bullnose bead.
      c. LC-Bead: J-shaped; exposed long flange receives joint compound.
      d. L-Bead: L-shaped; exposed long flange receives joint compound.
      e. U-Bead: J-shaped; exposed short flange does not receive joint compound.
      f. Expansion (control) joint.
      g. Curved-Edge Cornerbead: With notched or flexible flanges.

B. Exterior Trim: ASTM C 1047.
   1. Material: **Hot-dip galvanized-steel sheet, plastic, or rolled zinc**.
   2. Shapes:
      a. Cornerbead.
      b. LC-Bead: J-shaped; exposed long flange receives joint compound.
      c. Expansion (Control) Joint: One-piece, rolled zinc with V-shaped slot and removable strip covering slot opening.

2.6 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:
   1. Interior Gypsum Board: Paper.
   2. Exterior Gypsum Soffit Board: Paper.
   3. Glass-Mat Gypsum Sheathing Board: 10-by-10 glass mesh.
   4. Tile Backing Panels: As recommended by panel manufacturer.

C. Joint Compound for Interior Gypsum Board: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.
   1. Prefilling: At open joints**, rounded or beveled panel edges,** and damaged surface areas, use setting-type taping compound.
   2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use **setting-type taping** compound.
      a. Use setting-type compound for installing paper-faced metal trim accessories.
   3. Fill Coat: For second coat, use **setting-type, sandable topping** compound.
   4. Finish Coat: For third coat, use **setting-type, sandable topping** compound.
   5. Skim Coat: For final coat of Level 5 finish, use **setting-type, sandable topping compound.**

D. Joint Compound for Exterior Applications:
   1. Exterior Gypsum Soffit Board: Use setting-type taping compound and setting-type, sandable topping compound.
   2. Glass-Mat Gypsum Sheathing Board: As recommended by sheathing board manufacturer.

E. Joint Compound for Tile Backing Panels:
   1. Glass-Mat, Water-Resistant Backing Panel: As recommended by backing panel manufacturer.
   2. Cementitious Backer Units: As recommended by backer unit manufacturer.

2.7 AUXILIARY MATERIALS

A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.

B. Laminating Adhesive: Adhesive or joint compound recommended for directly adhering gypsum panels to continuous substrate.

C. Steel Drill Screws: ASTM C 1002 unless otherwise indicated.

1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.

2. For fastening cementitious backer units, use screws of type and size recommended by panel manufacturer.

D. Sound-Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.

E. Acoustical Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.

F. Thermal Insulation: As specified in Section 072100 "Thermal Insulation."

G. Vapor Retarder: As specified in Section 072600 "Vapor Retarders."

2.8 TEXTURE FINISHES

A. Primer: As recommended by textured finish manufacturer.

B. Polystyrene Aggregate Ceiling Finish: Water-based, job-mixed, polystyrene aggregate finish with flame-spread and smoke-developed indexes of not more than 25 when tested according to ASTM E 84.

1. Texture: **Light spatter.**

2. Aggregate Finish: Water-based, job-mixed, aggregated, drying-type texture finish for spray application.

3. Texture: **Light spatter**.

C. Non-Aggregate Finish: Premixed, vinyl texture finish for spray application.

1. Texture**: Light Spatter**.

PART 3 - EXECUTION

3.1 APPLYING AND FINISHING PANELS

A. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

B. Comply with ASTM C 840.

C. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

D. For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.

E. Prefill open joints[**, rounded or beveled edges,**] and damaged surface areas.

F. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.

G. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:

1. Level 1: **Ceiling plenum areas, concealed areas.**

2. Level 2: **Panels that are substrate for tile**.

3. Level 4: **Panels exposed to view specifically & critical at surfaces perpendicular to Windows.**

H. Cementitious Backer Units: Finish according to manufacturer's written instructions.

3.2 APPLYING TEXTURE FINISHES

A. Surface Preparation and Primer: Prepare and apply primer to gypsum panels and other surfaces receiving texture finishes. Apply primer to surfaces that are clean, dry, and smooth.

B. Texture Finish Application: Mix and apply finish using powered spray equipment, to produce a uniform texture free of starved spots or other evidence of thin application or of application patterns.

3.3 PROTECTION

A. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.

B. Remove and replace panels that are wet, moisture damaged, and mold damaged.

END OF SECTION 092900

09300 - 40
Preserving Historic Ceramic Tile Floors

- Preservation and Maintenance
- Damage and Deterioration Problems
- Repair and Replacement
- Summary and References
- Reading List

Historic Ceramic Floor Tile: Preservation and Maintenance return to top ▲

Before undertaking any work more complicated than regular maintenance or a very simple repair on a significant historic ceramic tile floor, or on any historic tile floor where serious damage has occurred, it is recommended that a professional conservator of ceramics, an historical architect, an architectural historian, or a chemist with particular knowledge and experience in this field be consulted. This will ensure that all future work, whether it be regularly-scheduled maintenance or more technical and specialized repair and restoration, is done in accordance with *The Secretary of the Interior's Standards for the Treatment of Historic Properties*.



This tiled Presidential seal was laid in the floor of the Pension Building in 1901 at President McKinley's 2nd inaugeration. Photo: NPS files.

Cleaning Methods

Ceramic tiles are essentially a practical, low-maintenance flooring material. Yet, even glazed tiles are somewhat porous, and can get dirty and stained, especially in heavy traffic areas or where oil, fat, and grass stains are likely to occur. Although heavily soiled areas may be difficult or impossible to clean completely, in most instances, cleaning ceramic tile floors is relatively easy. Cleaning should always begin with the gentlest means possible, which may be as simple as warm water. Regular maintenance should include sweeping, or preferably dry or damp mopping or vacuuming to reduce grit. Tiles can usually be cleaned with a non-soap-based household floor cleaner, such as one of the commercial products intended for cleaning ceramic tile floors available on the market.

All cleaning and stain-removal products should always be tested on a small, inconspicuous area before using. Abrasive cleaners (including powdered cleansers and even "mildly" abrasive creams) and mechanical equipment can damage and wear away the protective surface, as well as the decorative design on the tiles, and should not be used on ceramic tile floors. Generally, acid-based cleaning solutions should also not be used on ceramic tile floors because they can damage the complex silicates in a glaze. However, there are some acid-based cleaners specially formulated for cleaning and removing coatings from ceramic tile floors that may be acceptable, but even these must be used with caution. Sometimes an acid-based cleaner may, in fact, be needed to remove discoloration or staining caused by lime or cement mortar. But, it should be

tested first, used with caution, and applied only to a thoroughly wetted tile floor from which excess water has been removed. Pre-wetting a ceramic tile floor before cleaning is a good policy to observe with all cleaners. The water saturates the porous tile and prevents chemicals or other cleaning agents from penetrating into the tile body. Floor tiles should be always rinsed thoroughly after cleaning.

Plastic pot-scrubbers may be effective in loosening and removing superficial dirt without abrading the glazed or vitrified surface of the tiles. Stubborn asphalt or oil stains, scuff marks, or soiling can sometimes be removed with ammonia or one of the household spray products intended for cleaning kitchen or bathroom tiles. If necessary, a solvent may be applied carefully to pre-wetted tiles, but it should not be left on the surface for an extended amount of time as it may cause discoloration. If possible, a stain should always be identified first in order to select the material best-suited to remove it.

Organic growth, such as mold or mildew, can be eliminated with a dilute solution of household bleach and a neutral household detergent, or a dilute (5-10%) solution of tri-sodium phosphate (TSP). After applying either of these solutions, it may be necessary to scrub the floor with a natural bristle or nylon brush, and then rinse with clear water. Even a dilute bleach solution should not be left on a ceramic tile floor for more than a few minutes, since the alkali in the bleach can lead to the formation of a white efflorescent deposit. Efflorescence (a whitish haze of water-soluble salts) may stain and streak the tile, or may even cause minor spalling around the joints.

Regular maintenance of a ceramic tile floor should always begin with vacuuming to remove loose dirt and grit. Then, a mild cleaning solution may be applied and left on the floor for 10-15 minutes, without letting it dry on the tiles. Heavily soiled areas may be scrubbed with a natural bristle or nylon brush to loosen dirt from the tile surface. Finally, the floor should be thoroughly rinsed with clean, clear water, preferably twice, and dried with terry cloth towels, if necessary. Any proprietary cleaning product should always be used in accordance with the manufacturer's directions.

Protective Coatings

In most instances, traditional ceramic tile floors probably would not have been treated or given a protective coating other than wax. In the 19th century, some encaustic tile floors were treated with linseed oil, but this is not a practice recommended today because linseed oil tends to attract dirt and discolors as it ages. Most historic ceramic tile floors simply acquired a natural "polish" or sheen through use. Because the surface of ceramic tiles is already protected with a fired skin or a glaze, an additional protective coating should generally not be needed.

Opinions differ concerning the use of protective coatings, penetrating sealers, or waxes on ceramic tile floors, and, especially, on historic ceramic tile floors. If properly applied and regularly cleaned, a coating can sometimes be an effective maintenance treatment, but only on interior floors. However, if not adequately or properly maintained, rather than facilitating maintenance of ceramic tile floors in high traffic areas, such coatings may tend to emphasize traffic patterns as they wear away or become scratched. Some coatings may also peel in spots, or cause tile to appear hazy or cloudy if the coating is not applied in accordance with the manufacturer's specifications, or if the tiles are not perfectly clean when the coating is applied. Furthermore, applying such a coating may actually increase maintenance costs, since a coating requires periodic removal and renewal. The frequent removal of a coating can also damage a ceramic tile floor if it is carried out with harsh chemicals or abrasive mechanical equipment. If any coating is considered, a traditional coating, such as floor wax, may be the most suitable. Wax is easy to remove when it becomes worn, and does not impart a high, potentially inappropriate, gloss to the surface.

On the other hand, a penetrating sealer, or *impregnator*, may be worth considering to protect patterned encaustic tiles, or painted or printed tiles featuring a design that might be worn off, particularly in public buildings with a high volume of foot traffic. For example, some manufacturers of new, reproduction encaustic tiles recommend applying a penetrating sealer to the replacement tiles, as well as to the historic tiles. Impregnators do not change the color of the tile surface and, unlike some penetrating sealers, are completely invisible after they have been applied. They can reduce the porosity or water absorption of the tile surface, and provide some

protection for the tile (and the grout) against staining. This may be particularly useful on light-colored floors. Whether to apply an impregnator to an historic ceramic tile floor, and what type or product to use, are decisions that should generally made in consultation with a conservator or ceramic tile specialist. *It may also be necessary to comply with certain safety standards and friction requirements of the ADA (Americans with Disabilities Act). The ADA Guidelines recommend "a static coefficient of friction" of 0.6 for level surfaces and 0.8 for ramps. This may require the application of a non-slip sealer or wax to historic ceramic tile floors in some public buildings.*

Despite the non-traditional shiny finish they may impart to a floor surface, two-part, acrylic-based coating systems are commonly used today on historic ceramic tile floors in many public buildings, primarily because they facilitate easy maintenance. If it is decided that a sealer is to be used, a product with a matte or dull finish may be preferable, or more appropriate, for a historic ceramic tile floor than one with a high-gloss.

In some cases, temporary protection may be the best approach until a better solution is found. Non-permanent protection for an historic ceramic tile floor may be as simple as using floor mats at doors or in heavy traffic areas.

Historic Ceramic Floor Tile: Damage and Deterioration Problems return to top ▲



Worn encaustic tiles are still serviceable, but once the design has been lost, the tiles cannot be repaired. They must be replaced in kind, to match. Photo: NPS files.

Loss of Tile Surface and Pattern

Ceramic tiles are among the most durable of historic flooring materials, but natural wear and a certain amount of deterioration or damage is inevitable. Some tiles, such as dense, close-textured quarry tiles and ceramic mosaic tiles, resist abrasion and stain absorption very well. But many others, especially patterned encaustic and geometric tiles, are extremely susceptible to abrasion. Heavy traffic can also result in uneven wear, or even cupping, in certain areas of tile floors that get more use than others, such as doorway entrances. The particular clay mix, or the dye or pigment used to color the clay, can also affect the hardness and durability of individual tiles or an entire ceramic tile floor.

Tile Glaze Failure

Occasionally some glazes can become pitted or powdery as they age. Lead glazes used in the 19th century, which were fired at low temperatures, deteriorated relatively quickly. Glazes have different physical properties from the fired clay tile body itself, and as a result may sometimes crack or craze. Unless the crazing visibly extends into the porous clay of the tile body beneath, this is not generally a serious material failure; however, dirt entering these cracks cannot be removed, and will discolor the tile. If the crazing penetrates through the glaze, it may increase the water absorption of the tile.

Tile Breakage

Ceramic floor tiles are very susceptible to damage and breakage caused when something heavy is dropped. Repeated passage of heavy objects, or carts, over a floor can also crack and break ceramic tiles, as well as heavy vibration from outside traffic.

Moisture Damage to Tile

Ceramic tile floors have been traditionally viewed as highly waterproof systems that do not require protection from moisture. In reality, however, this is not true. Water-related problems

are one of the most common causes for the deterioration and failure of historic tile floors, particularly in bathrooms and other rooms where there is a lot of moisture. Water that is allowed to sit in areas around shower stalls and bathtubs can eventually damage grout and mortar, and loosen tiles. Some of the more porous kinds of tiles that are not as hard-fired may actually begin to powder or spall if subjected to constant moisture.

Loose, Cracked, Broken or Unbonded Tile Due to Mortar Failure

The durability of ceramic tile floors depends to a great extent on a sound mortar bed and sound mortar joints. The wrong mortar type or mortar that is inadequately mixed can also spell trouble for a ceramic tile floor. Failure of a tile floor system laid over a subfloor is often the result of weakened or deteriorated grout or mortar which allows the tiles to become loose. Mortar may also be weakened or loosened by cleaning solutions that are too strong.

Proper tile-laying technique includes the use of a material that will allow for some movement of the tiles. Traditionally, a layer of asphalt (replaced by a layer of plastic or building paper in more modern construction) was inserted to separate the base and the bedding underneath. This prevents bonding between the base and the bed, and allows for some "relative" movement. It is intended to prevent the ceramic tile floor from arching or ridging, a condition in which single or entire rows of tiles can pop up to relieve tension and separate completely from the bed. When this happens, the condition will probably require taking up and relaying many or all of the tiles.

Tile Damage or Loss Caused by Systems Update

The installation of new plumbing, electrical and HVAC systems, or the attachment of new fixtures and furnishings, may be one of the most common sources of damage to an historic ceramic tile floor. Earlier remodeling projects to remove old pipes or to replace "out-dated" bathroom fixtures may have resulted in the loss of floor tiles. Different shapes and sizes of new fixtures, equipment or pipes may have exposed previously untiled areas that have been inappropriately patched with cement. Careless workers and insensitive installations can also result in damage, breakage or removal of historic floor tiles. All of these conditions will require matching replacement tile.

Historic Ceramic Floor Tile: Repair and Replacement return to top ▲

The Secretary of the Interior's Standards for the Treatment of Historic Properties emphasize the retention and preservation of historic building material. Preservation and repair treatments are always preferable to replacement.

Mortar Joint Repair

Deteriorated mortar joints and loose mortar or grout can generally be repaired. First, the entire floor should be checked for loose tiles that need to be regrouted. Damaged mortar should be carefully removed by hand and the joints wetted or a bonding agent applied in preparation for regrouting. When making mortar repairs, it is important to use grout that matches the old in color and consistency as closely as possible.

Tile Repair

Trying to remove one tile can endanger surrounding tiles. Thus, it may be better to preserve and retain an original historic tile that is only slightly damaged, rather than replace it. Sometimes cracks may be repaired, or a corner or piece of tile that has broken off may be re-attached, using an epoxy glue, or grout. If a tile is chipped or a small corner or edge is missing, a carefully executed patch of epoxy-mixed with colored enamel, or mortar tinted to blend with the tile, may be less conspicuous than trying to replace every tile that has even the slightest damage. And, it is a better preservation treatment.

In limited instances, glaze failure or surface powdering of ceramic floor tiles may sometimes be treated successfully by a conservator with a specially formulated, solvent-based, mineral densifying agent (such as silicic acid), followed by a siloxane sub-surface repellent, applied 24 hours later. Under the right circumstances, such a treatment can harden and bind the surface, and lower the absorbency of the tile, and still maintain the vapor transmission. But this is a highly complex undertaking and should only be attempted by a conservator after appropriate testing. Not only are these chemicals highly toxic and dangerous to handle, but if used improperly, they can cause greater damage to the tile!



This inappropriate ceramic tile repair is easy to spot. Photo: NPS files.

Tile Replacement

When an individual tile or a larger portion of an historic ceramic tile floor is missing or so severely damaged that it cannot be repaired, or if it has become a safety hazard, then it should be replaced. When a ceramic tile floor has deteriorated as a result of long term wear and abrasion, or from settlement or vibration damage to the setting bed, there are a number of factors that need to be considered before choosing a preservation treatment. If damage to tiles is the result of more than normal wear and tear, the source of the problem needs to be identified, and the problem corrected before replacing the damaged tiles.

Successful replacement not only depends on the availability of matching tiles, but on the condition of the substrate on which the tiles are laid. Before installing the replacement tiles, any problems, such as settlement or vibration, will have to be addressed, and the height of the new setting bed may have to be adjusted for the thickness of the new tiles.

Selective Replacement of Individual Tiles

This cautious approach, typically an attempt to replace only the most seriously damaged tiles, is often taken or considered when only a small number of tiles are involved. Unless old, matching tiles can be found and reused, replacement often requires specially fabricated reproduction tiles. In some instances, individual historic tiles that are damaged may be replaced with matching tiles salvaged from other, less prominent areas of the floor or from other buildings. This is most feasible if the tiles to be replaced are either plain, and easy to match, or decorated with a common historic floor tile pattern.

In order to replace damaged tiles, it can be helpful to identify the manufacturer and the approximate date of the tiles, if possible. However, many mass-produced tiles are not marked and give little or no information as to their origin, although stylistic similarities with other marked tiles may sometimes provide a clue as to the manufacturer. Some decorating firms seldom signed their work, while many firms made bisque tiles (plain, unglazed, once-fired tiles) for other companies, as well as their own use. Identifying marks will generally be found on the back of the tile. A mark impressed or molded into the back of the tile may give the name or initials of the company which made the tile or the bisque; sometimes a printed or painted mark indicates if it was decorated by a different company, or artist. Historic building records and construction documents may provide information about the tile company or supplier. Catalogues of the period may also be useful in identifying the tile manufacturer of unmarked tiles.

Replacing a single damaged tile is based on the ability to remove only the deteriorated tile without harming surrounding tiles. Attempts to remove one or several damaged tiles often fail because a hammer and chisel are used. The shock of the blows to the tile being removed travels through the grout into surrounding tiles and cracks them. To avoid damaging good tiles, all the

grout around the tile must be removed. This is best accomplished by an experienced tile installer using a hand tool called a grout saw or, for grout joints wider than 3/8", a dry-cutting diamond blade, mounted in an angle grinder or circular saw.

Other difficulties may be encountered when selectively replacing damaged tiles with reproduction tiles. New tiles, especially encaustic tiles, may be different in thickness and, sometimes, despite the attention to detail of the reproduction process, slightly different in color and design from historic tiles. This can cause both visual and physical problems, especially if the replacements are being laid in a piecemeal fashion.

If the setting bed does not have enough mortar to grip and hold the tile, one new tile laid among the originals will eventually come loose. If the new and old tiles are different thicknesses, the setting bed in which the new tiles are laid must be at a different height to create a level finished surface. In addition, the two levels of setting beds may be of different composition; one may be harder, stronger and less flexible than the other. This may also lead to problems, since the setting bed foundation should act and respond as a unit to the load and stresses placed upon it.

Sectional Replacement of Tiles

In some instances, the best approach may be to remove a complete section of damaged original tiles and replace that section of floor in its entirety with new reproduction tiles. Advantages of this method include the ability to lay a level setting bed, as well as achieving a finished product that is uniform in color and pattern match. Although this approach may involve replacing more original tiles with reproduction tiles than may be absolutely necessary, original tiles that remain in good condition can be saved to be reused in other sections where only a few tiles are damaged. This technique is generally most appropriate either when the section being replaced is the most damaged portion of the floor, or is in a relatively inconspicuous location and the tiles that are removed will supply enough salvaged pieces to permit in-kind repair of a more visually prominent area.

When laying a section of reproduction tiles, it may be a good idea to use contemporary materials and installation methods such as expansion joints or flexible expansion material. One of the major causes of ceramic floor tile installation failure and cracked, broken or disbonded tiles is the lack of expansion joints. Expansion joints were sometimes used in laying historic ceramic tile floors, and these are frequently the ones that have survived in the best condition. Many preservation contractors hesitate to use conventional expansion joint filler materials because of their limited range of colors. However, there are new flexible sealants in a wide range of colors that are available in either sanded or unsanded textures to match the surrounding grout joints. As a result, the expansion joints are almost invisible. A bonding agent may also be considered-if recommended by the tile manufacturer-and any drawings provided by the manufacturer should be used to guide the installation.

Each preservation technique has advantages and disadvantages that the historic property owner or manger should take into consideration before deciding which one is best suited to the particular flooring problem. For example, slight differences in the shape, size, color and the pattern between the old and the new tiles are frequently encountered. If replacing an entire section, the slightest difference in size and dimension between the original tiles and the reproduction tiles, even if it is as small as 1/8" or 1/16", can mean that the new section of tile will not fit inside an existing border. Even though drawings and photos are provided to the manufacturer, there may be some variation in the design and pattern size on the new tiles. Thus, they may not align perfectly with the original tiles, and as a result the section of the floor that has been replaced may be quite conspicuous.

SECTION 09306

FLOOR AND WALL TILE

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Ceramic tile floor finish using the thinset application method.
- B. Ceramic tile wall finish using the thinset application method.

1.02 SUBMITTALS
- A. Submit under provisions of the General Requirements.
- B. Product Data: Provide instructions for using adhesives and grouts.
- C. Samples: Submit two samples illustrating pattern, color variations, and grout color.

1.03 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site.
- B. Protect adhesives from freezing or overheating in accordance with manufacturer's instructions.

1.04 ENVIRONMENTAL REQUIREMENTS
- A. Do not install adhesives in an unventilated environment.
- B. Maintain 50 degrees F during installation of mortar materials.

PART 2 PRODUCTS

2.01 TILE MANUFACTURERS
- A. FLOOR: Ceramic Tile – Products 12x12, as selected by owner.
- B. WALL: Ceramic Tile – Products 12x12, as selected by owner.
- B. Substitutions: Under provisions of the General Requirements as equal or better.

2.02 CERAMIC TILE MATERIALS
- A. Ceramic Floor Tile: ANSI A137.1, conforming to the following:

1.	Moisture Absorption	0.5 to 3.0 percent
2.	Size	12x12 inch
3.	Shape	square/rectangular
4.	Edge	square/bullnose
5.	Surface Finish	matte glazed slip resistant
6.	Color	as selected
7.	Pattern	uncoursed

- B. Glazed Wall Tile: Flat tile as follows:
  1. Module Size: 12x12 inches.
  2. Finish: As Selected

2.03 BASE MATERIALS
- A. Base: Match floor tile for moisture absorption, surface finish, and color:

1.	Length	12 inch
2.	Height	4 inch
3.	Top Edge	bull nosed
4.	Internal Corner	coved
5.	External Corner	bullnosed

2.04 ADHESIVE MATERIALS
- A. Adhesives: thinset bond type as recommended and/or manufactured by the tile manufacturer.

2.05 MORTAR MATERIALS
- A. Mortar Materials: Portland cement, sand, latex additive, and water as recommended and/or manufactured by the tile manufacturer, color to be selected.

2.06 GROUT MIX
- A. Mix and proportion pre-mix grout materials in accordance with manufacturer's instructions.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that surfaces are ready to receive work.

3.02 PREPARATION

A. Protect surrounding work from damage or disfiguration.
B. Vacuum clean surfaces and damp clean.
C. Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.
D. Apply sealer conditioner to substrate surfaces in accordance with adhesive manufacturer's instructions.

3.03 INSTALLATION - THINSET METHOD

A. Install adhesive tile, thresholds, and grout in accordance with manufacturer's instructions and/or the TCA Handbook.
B. Lay tile to pattern indicated. Do not interrupt tile pattern through openings.
C. Place edge strips at exposed tile edges.
D. Cut and fit tile tight to penetrations through tile. Form corners and bases neatly. Align floor, base and wall joints.
E. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make joints watertight, without voids, cracks, excess mortar, or excess grout.
F. Sound tile after setting. Replace hollow sounding units.
G. Keep expansion, control joints free of adhesive or grout. Apply sealant to joints.
H. Allow tile to set for a minimum of 48 hours prior to grouting.
I. Grout tile joints.
J. Apply sealant to junction of tile and dissimilar materials and junction of dissimilar planes.
K. Install shower pan per manufacturer's instructions.

3.04 CLEANING

A. Clean tile and grout surfaces.

3.05 PROTECTION OF FINISHED WORK

A. Do not permit traffic over finished floor surface for 4 days after installation.

END OF SECTION 09306

SECTION 096400

EXISTING WOOD FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Existing wood floors to be repaired, patched, and re-finished.
   2. Sand, patch & refinish at equipment and cabinet removal to match.

1.2 SUBMITTALS

A. Product Data: For each type of product.
B. Shop Drawings: For each type of floor assembly and accessory. Include plans, sections, and attachment details. Include expansion provisions and trim details.
C. Samples: For each exposed product and for each color/stain and texture specified.
   1. Contactor to mock-up small area, or use salvaged original wood flooring pieces to create mock-up for final re-finished and stained appearance for architect's review and approval.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Flooring: Verify existing to match species, grade, and cut.

2.2 FIELD-FINISHED WOOD FLOORING

A. Solid-Wood Flooring: Provide and install to match existing.
   1. Grade and Species: Oak (Verify & Match)
   2. Cut: Verify & Match
   3. Thickness: Verify & Match
   4. Face Width: Verify & Match
B. Urethane Finish System: Complete system of compatible components to match existing.
   1. Floor Sealer: Pliable, penetrating type.
   2. Finish Coats: Formulated for multicoat application on wood flooring.
   3. Stains: Oak Natural or Golden Oak Stain – Architect to select final stain color.
C. Wood Filler: Compatible with finish system components and recommended by filler and finish manufacturers for use indicated. Match existing provide pigmented filler.

2.3 ACCESSORY MATERIALS

A. Wood Sleepers and Subfloor: As required to match existing
B. Wood Underlayment: As required to match existing
C. Asphalt-Saturated Felt: ASTM D 4869/D 4869M, Type II.
D. Wood Flooring Adhesive: Mastic recommended for application indicated.
E. Trowelable Leveling and Patching Compound: Latex-modified, hydraulic-cement-based formulation approved by wood flooring manufacturer.
F. Fasteners: As recommended for application.
G. Thresholds and Saddles: To match wood flooring. Tapered on each side.
H. Reducer Strips: To match wood flooring, tapered, and in thickness required to match height of flooring.

PART 3 - EXECUTION

3.1 EXAMINATION

3.2 PREPARATION

A. Existing floor fill, repair & patch including underlayment:
   1. Grind high spots and fill low spots to produce a maximum 1/8-inch (3-mm) deviation in any direction when checked with a 10-foot (3-m) straight edge.
   2. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
   3. Remove coatings, including curing compounds, and other substances on substrates that are incompatible with installation adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.

B. Broom or vacuum clean substrates to be covered immediately before product installation. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION

A. Comply with wood flooring standards, not less than applicable recommendations in NWFA's "Installation Guidelines."

B. Provide expansion space at walls and other obstructions and terminations of flooring.

C. Vapor Retarder: Comply with the following for vapor retarder installation:
   1. Wood Flooring Nailed to Wood Subfloor: Install flooring over a layer of asphalt-saturated felt.

D. Solid-Wood Flooring: Blind nail or staple flooring to substrate.
   1. Plank Flooring: For flooring of face width more than 3 inches (76 mm):
      a. Hardwood: Install countersunk screws at each end of each piece in addition to blind nailing. Cover screw heads with wood plugs glued flush with flooring.
      b. Softwood: Install no fewer than two countersunk nails at each end of each piece, spaced not more than 16 inches (406 mm) along length of each piece, in addition to blind nailing. Fill holes with matching wood filler.

3.4 FIELD FINISHING

A. Machine-sand flooring to remove offsets, ridges, cups, and sanding-machine marks that are noticeable after finishing. Vacuum and tack with a clean cloth immediately before applying finish.

B. Fill and repair wood flooring defects.

C. Apply floor-finish materials in number of coats recommended by finish manufacturer for application indicated, but not less than one coat of floor sealer and **three** finish coats.
   1. Apply stains to achieve an even color distribution matching approved Samples.
   2. For water-based finishes, use finishing methods recommended by finish manufacturer to minimize grain raise.

D. Cover wood flooring before finishing.

E. Do not cover wood flooring after finishing until finish reaches full cure, and not before seven days after applying last finish coat.

3.5 PROTECTION

A. Protect installed wood flooring during remainder of construction period with covering of heavy kraft paper or other suitable material. Do not use plastic sheet or film that might cause condensation.
   1. Do not move heavy and sharp objects directly over kraft-paper-covered wood flooring. Protect flooring with plywood or hardboard panels to prevent damage from storing or moving objects over flooring.

END OF SECTION 096400

SECTION 09650

RESILIENT FLOORING

PART 1 GENERAL

1.01 SECTION INCLUDES
A. Vinyl Tile Flooring, VT

1.03 DELIVERY, STORAGE, AND HANDLING
A. Deliver, store, protect and handle products to site under provisions of the General Requirements.
B. Protect roll materials from damage.

1.04 ENVIRONMENTAL REQUIREMENTS
A. Store materials for three days prior to installation in area of installation to achieve temperature stability.
B. Maintain ambient temperature required by adhesive manufacturer three days prior to, during, and 24 hours after installation of materials.

1.05 MAINTENANCE DATA
A. Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning, stripping, and re-waxing.

1.06 EXTRA MATERIALS
A. Provide 100 sq ft of flooring, 30 lineal feet of base, and stair materials of each material specified.

PART 2 PRODUCTS

2.01 MATERIALS – VINYL TILE FLOORING
A. Vinyl Composition Tile; ASTM F-1066, Tarkett Favoritt sheet flooring.
1. Total Thickness: .3.2 mm or 1/8”
2. Size; 12x24, 12x12
3. Color to be selected.
4. Manufacturer:
a) Armstrong, Mowhawk,
b) Or as approved equal.
5. Selected from, Mowhawk, Dodford 20 dry back, or Armstrong Premium Raffia & Stnd Excelon.

2.02 MATERIALS – VINYL STAIR TREADS & LANDINGS
A. Vinyl Stair Treads & matching Landings, Roppe.
1. Total Thickness: .3.2 mm or 1/8”
2. Size; as required for each stair and landing, Field Verify
3. Color to be selected.
4. Manufacturer: Roppe, or as approved equal

2.03 ACCESSORIES
A. Underlayment, install ¼” manufacturer approved underlayment as indicated and recommended.
B. Prepare for new as indicated and recommended.
C. Subfloor Filler: White premix latex; type recommended by adhesive material manufacturer.
D. Primers and Adhesives: Waterproof; types recommended by flooring manufacturer.
E. Edge Strips: Flooring material as approved.

PART 3 EXECUTION

3.01 EXAMINATION
A. Verify Floor, Stairs and landings, concrete, metal, or wood, are dry, clean, smooth & level, maximum moisture content of 7 percent, and exhibit negative alkalinity, carbonization, or dusting.
B. Verify Floors, Stairs, Risers, Stringers, and lower wall surfaces are free of substances that may impair adhesion of new adhesive and finish materials.

3.02 PREPARATION

A. Remove sub-floor ridges and bumps. Fill minor or local low spots, cracks, joints, holes, and other defects with sub-floor filler to achieve smooth, flat, hard surface.
B. Install ¼" underlayment, manufacturer approved and as indicated and recommended.
C. Prohibit traffic until filler is cured.
D. Vacuum clean substrate.
E. Apply primer as recommended by manufacturer.

3.05 INSTALLATION - TILE FLOORING

A. Install in accordance with manufacturer's instructions.
B. Spread only enough adhesive to permit installation of materials before initial set.
C. Set flooring in place, press with heavy roller to attain full adhesion.
D. Lay flooring with joints and seams parallel to building lines to produce symmetrical tile pattern.
E. Terminate flooring at centerline of door openings where adjacent floor finish is dissimilar.
F. Install resilient edge strips at unprotected or exposed edges, and where flooring terminates.
G. Scribe flooring to walls, columns, cabinets, floor outlets, and other appurtenances to produce tight joints.

3.06 CLEANING

A. Clean all work as described in the General Requirements.
B. Remove access adhesive from floor, base, and wall surfaces without damage.
C. Clean, seal, and wax floor and base surfaces in accordance with manufacturer's instructions.

3.07 PROTECTION OF FINISHED WORK

A. Protect finished Work.
B. Prohibit traffic on floor finish for 48 hours after installation.

END OF SECTION 09650

SECTION 09900

PAINTING

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Surface preparation and field application of paints and coatings.

1.02 QUALIFICATIONS
- A. Manufacturer: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.
- B. Applicator: Company specializing in performing the work of this section with minimum years documented experience and approved by manufacturer.

1.03 DELIVERY, STORAGE, AND HANDLING
- A. Deliver, store, protect and handle products to site.
- B. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- C. Container label to include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
- D. Store paint materials at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.04 ENVIRONMENTAL REQUIREMENTS
- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- B. Do not apply exterior coatings during rain or snow, or when relative humidity is outside the humidity ranges required by the paint product manufacturer.
- C. Minimum Application Temperatures for Latex Paints: 45 degrees F for interiors; 50 degrees F for exterior; unless required otherwise by manufacturer's instructions.
- D. Minimum Application Temperature for Varnish and Finishes: 65 degrees F for interior or exterior, unless required otherwise by manufacturer's instructions.
- E. Provide lighting level of 80 foot candles measured mid-height at substrate surface.

PART 2 PRODUCTS

2.01 MANUFACTURERS
- A. Manufacturer - Paint, Transparent Finishes, Stain, Primer Sealers, and Block Filler by SHERWIN-WILLIAMS or as approved equal.

2.02 MATERIALS
- A. Coatings: Ready mixed, except field catalyzed coatings. Process pigments to a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating; good flow and brushing properties; capable of drying or curing free of streaks or sags.
- B. Accessory Materials: Linseed oil, shellac, turpentine, paint thinners and other materials not specifically indicated but required to achieve the finishes specified, of commercial quality.
- C. Patching Materials: Latex filler.
- D. Fastener Head Cover Materials: Latex filler.
- E. All interior paints and primers shall comply with Green Seal standards for low VOC limits.

2.03 FINISHES
- A. Refer to schedule at end of section for surface finish schedule.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify that surfaces and substrate conditions are ready to receive work as instructed by the product manufacturer.
- B. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- C. Test shop applied primer for compatibility with subsequent cover materials.

3.02 PREPARATION

A. Remove or mask electrical plates, hardware, light fixture trim, escutcheons, and fittings prior to preparing surfaces or finishing.
B. Correct defects and clean surfaces which affect work of this section. Remove existing coatings that exhibit loose surface defects.
C. Seal with shellac and seal marks which may bleed through surface finishes.
D. Impervious Surfaces: Remove mildew by scrubbing with solution of trisodium phosphate and bleach. Rinse with clean water and allow surface to dry.
E. Aluminum Surfaces Scheduled for Paint Finish: Remove surface contamination by steam or high pressure water. Remove oxidation with acid etch and solvent washing. Apply etching primer immediately following cleaning.
F. Asphalt, Creosote, or Bituminous Surfaces Scheduled for Paint Finish: Remove foreign particles to permit adhesion of finishing materials. Apply compatible sealer or primer.
G. Insulated Coverings: Remove dirt, grease, and oil from canvas and cotton.
H. Concrete Floors: Remove contamination, acid etch, and rinse floors with clear water. Verify required acid-alkali balance is achieved. Allow to dry.
I. Copper Surfaces Scheduled for a Paint Finish: Remove contamination by steam, high pressure water, or solvent washing. Apply vinyl etch primer immediately following cleaning.
J. Copper Surfaces Scheduled for a Natural Oxidized Finish: Remove contamination by applying oxidizing solution of copper acetate and ammonium chloride in acetic acid. Rub on repeatedly for required effect. Once attained, rinse surfaces with clear water and allow to dry.
K. Gypsum Board Surfaces: Fill minor defects with filler compound. Spot prime defects after repair.
L. Galvanized Surfaces: Remove surface contamination and oils and wash with solvent. Apply coat of etching primer.
M. Concrete and Unit Masonry Surfaces Scheduled to Receive Paint Finish: Remove dirt, loose mortar, scale, salt or alkali powder, and other foreign matter. Remove oil and grease with a solution of trisodium phosphate; rinse well and allow to dry. Remove stains caused by weathering of corroding metals with a solution of sodium metasilicate after thoroughly wetting with water. Allow to dry.
N. Plaster Surfaces: Fill hairline cracks, small holes, and imperfections with latex patching plaster. Make smooth and flush with adjacent surfaces. Wash and neutralize high alkali surfaces.
O. Uncoated Steel and Iron Surfaces: Remove grease, mill scale, weld splatter, dirt, and rust. Where heavy coatings of scale are evident, remove by hand, power tool wire brushing or sandblasting; clean by washing with solvent. Apply a treatment of phosphoric acid solution, ensuring weld joints, bolts, and nuts are similarly cleaned. Spot prime paint after repairs.
P. Shop Primed Steel Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces.
Q. Interior Wood Items Scheduled to Receive Paint Finish: Wipe off dust and grit prior to priming. Seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after primer has dried; sand between coats.
R. Interior Wood Items Scheduled to Receive Transparent Finish: Wipe off dust and grit prior to sealing, seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after sealer has dried; sand lightly between coats.
S. Exterior Wood Scheduled to Receive Paint Finish: Remove dust, grit, and foreign matter. Seal knots, pitch streaks, and sappy sections. Fill nail holes with tinted exterior caulking compound after prime coat has been applied.
T. Exterior Wood Scheduled to Receive Transparent Finish: Remove dust, grit, and foreign matter; seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes with tinted exterior caulking compound after sealer has been applied.
U. Glue-Laminated Beams: Prior to finishing, wash surfaces with solvent, remove grease and dirt.
V. Wood and Metal Doors Scheduled for Painting: Seal top and bottom edges with primer.

3.03 APPLICATION

A. Apply products in accordance with manufacturer's instructions.
B. Do not apply finishes to surfaces that are not dry.
C. Apply each coat to uniform finish.
D. Apply each coat of paint slightly darker than preceding coat unless otherwise approved.
E. Sand wood and metal lightly between coats to achieve required finish.
F. Vacuum clean surfaces free of loose particles. Use tack cloth just prior to applying next coat.
G. Allow applied coat to dry before next coat is applied.
H. Where clear finishes are required, tint fillers to match wood. Work fillers into the grain before set. Wipe excess from surface.
I. Prime concealed surfaces of interior and exterior woodwork with primer paint.
J. Prime concealed surfaces of interior woodwork scheduled to receive stain or varnish finish with gloss varnish reduced 25 percent with mineral spirits.

3.04 FINISHING MECHANICAL AND ELECTRICAL EQUIPMENT

A. Remove unfinished louvers, grilles, covers, and access panels on mechanical and electrical components and paint separately.
B. Prime and paint insulated and exposed pipes, conduit, boxes, insulated and exposed ducts, hangers, brackets, collars and supports except where items are prefinished.
C. Paint interior surfaces of air ducts, and convector and baseboard heating cabinets that are visible through grilles and louvers with one coat of flat black paint, to visible surfaces. Paint dampers exposed behind louvers, grilles, and convector and baseboard cabinets to match face panels.
D. Paint exposed conduit and electrical equipment occurring in finished areas.
E. Paint both sides and edges of plywood backboards for electrical and telephone equipment before installing equipment.
F. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.05 CLEANING

A. Collect waste material which may constitute a fire hazard, place in closed metal containers and remove daily from site.

3.06 SCHEDULE

The following are for exterior and interior surfaces, and are all products of Sherwin-Williams.

EXTERIOR SURFACES

1. WOOD (Excluding Plywood)
   A. Satin Finish/Latex Base
      1st Coat: Exterior Oil Based Wood Primer
      2nd Coat: Duration, Satin
      3rd Coat: Duration, Satin

2. PLYWOOD & SIDING
   A. Satin Finish/Latex Base
      1st Coat: Exterior Oil Based Wood Primer
      2nd Coat: Duration, Satin
      3rd Coat: Duration, Satin

3. FERROUS METAL (Handrails)
   A. Painted (Gloss Finish/Alkyd Base)
      1st Coat: Kem Kromik Primer, B50N2/B50W1
      2nd Coat: Industrial Enamel, B54 Series
      3rd Coat: Industrial Enamel, B54 Series
   B. Finish on these items shall be applied to achieve polished or car finish.

4. GALVANIZED METAL
   A. Painted (Satin Finish/Latex Base)
      1st Coat: Duration, Satin
      2nd Coat: Duration, Satin

5. ALUMINUM
   A. Painted (Satin Finish/Latex Base)
      1st Coat: Duration, Satin
      2nd Coat: Duration, Satin

6. CONCRETE MASONRY UNITS
   A. Painted (Satin Finish/Latex Base)
      1st Coat: Loxon Primer/Sealer
      2nd Coat: Duration, Satin
      3rd Coat: Duration, Satin
7. CONCRETE, STUCCO, BRICK
   A. Painted (Satin Finish/Latex Base)
      1st Coat: Loxon Primer/Sealer
      2nd Coat: Duration, Satin
      3rd Coat: Duration, Satin

8. TRAFFIC AND PARKING LINE MARKING
   A. Painted (ProMar Traffic Marking Paint)
      1st Coat: B29W1-WHITE, or B29Y2-YELLOW

INTERIOR SURFACES

1. WOOD AND PLYWOOD
   A. Painted (Eg-Shel Finish/Alkyd Base)
      1st Coat: ProMar 200 Latex Primer, B49W2
      2nd Coat: ProMar 200 Latex Eg-Shel, B20W200
      3rd Coat: ProMar 200 Eg-Shel, B20W200
   B. Stained and Varnished (Clear Finish) Opened Grained Wood
      1st Coat: Interior Wood Stain, A48
      2nd Coat: Sherwood 100 Fast Dri Semi-Paste Filler D70T1
      3rd Coat: Oil Base Gloss Varnish, A66V91
      4th Coat: Oil Base Gloss Varnish, A66V91 or Oil Base Satin Varnish, A66F90

2. CONCRETE MASONRY UNITS
   A. Painted (Eg-Shel Finish/Latex Base)
      1st Coat: ProMar Block Filler, B25W1
      2nd Coat: ProMar 200 Latex Eg-Shel, B20W200
      3rd Coat: ProMar 200 Latex Eg-Shel, B20W200

3. CONCRETE, MASONRY EPOXY SYSTEM (SOLVENT BASE)
   A. Painted (Semi-Gloss Finish)
      1st Coat: Tile-Clad II Epoxy, B62W100 Series
      2nd Coat: Tile-Clad II Epoxy, B62W100 Series
      Additional Coats to ensure consistent Sheen
      (9 mils wet, 4 mils dry per coat)

3B. BRICK, CLAY TILE WALLS (SOLVENT BASE)
   A. Painted (Clear Acrylic Wall & Floor Finish)
      1st Coat: Concrete and Terrazzo Sealer B44V22 or W.R. Meadows – TIAH
      2nd Coat: Concrete and Terrazzo Sealer B44V22 or W.R. Meadows – TIAH

4. GYPSUM WALLBOARD
   A. Painted (Eg-Shel Finish/Latex Base)
      1st Coat: ProMar 200 Latex Wall Primer, B28W200
      2nd Coat: ProMar 200 Alkyd Eg-Shel Enamel, B33W200
      3rd Coat: ProMar 200 Alkyd Eg-Shel Enamel, B33W200

5. FERROUS METAL (Gloss, Handrails)
   A. Painted (Gloss Finish/Alkyd Base)
      1st Coat: Kem Kromik Metal Primer, B50N2/B50W1
      2nd Coat: Industrial Enamel, B54 Series
      3rd Coat: Industrial Enamel, B54 Series

6. GALVANIZED METAL
   A. Painted (Flat Finish/Latex Base)
      1st Coat: ProMar 200 Latex Flat Wall Paint, B30W200
      2nd Coat: ProMar 200 Latex Flat Wall Paint, B30W200

7. ALUMINUM
   A. Painted (Flat Finish/Latex Base)
      1st Coat: ProMar 200 Latex Flat Wall Paint, B30W200
      2nd Coat: ProMar 200 Latex Flat Wall Paint, B30W200

8. CONCRETE FLOORS (SEALED)
   A. Painted (Clear Acrylic Floor Finish)
      1st Coat: Concrete and Terrazzo Sealer B44V22 or W.R. Meadows – TIAH

END OF SECTION 09900

PRESERVATION BRIEF 28

Painting Historic Interiors

- Paint Investigation
- Choosing a Treatment
- Identifying Deteriorated and Damaged Paint Surface
- Choosing Modern Paint Types/Finish Coats
- Applying Interior Paints
- Summary

The paint Americans used in the past is undeniably part of a technological and commercial record. But beyond that, the colors we have chosen and continue to select for our interior living and working spaces—bright and exuberant, purposefully somber, or a combination of hues—reflect our nation's cultural influences and our individual and collective spirit. Paint color is a simple, direct expression of the time, and of taste, values, and mood. To consider paint only as a protective coating is to misunderstand its meaning as an important aspect of America's heritage.

This Brief is about historic interior paints and choosing new paints for historic interiors if repainting is necessary or desirable. It addresses a variety of materials and features: plaster walls and ceilings; wooden doors, molding, and trim; and metal items such as radiators and railings. It provides background information about some of the types of paint which were used in the past, discusses the more common causes and effects of interior paint failure, and explains the principal factors guiding decisions about repainting, including what level of paint investigation may be appropriate. Careful thought should be given to each interior paint project, depending on the history of the building and its painted surfaces. Treatments may range from protecting extant decorative surfaces, to ordering custom-made paint that replicates the original paint color, to using today's paint straight off the shelf and out of the can.

Finally, stripping old paints or applying new oil/alkyd paints poses serious health and safety concerns; the State Historic Preservation Officer should be contacted for current legal and technical information on removal, disposal, and health and safety precautions.

Paint Investigation

Understanding each project's historic preservation goal and knowing what level of information needs to be collected to achieve that goal is an important responsibility of the purchaser of the service. Before someone is hired, the owner or manager needs to decide if a thorough investigation of painted surfaces is actually needed, and how to use the results when one is done.

Specialists with both training and field experience conduct paint investigations. These experts use sophisticated instruments and procedures such as field sampling, cross-section analysis, and fluorescent and chemical staining to learn about the components and behaviors of historic paints. In addition, they utilize written documentation, verbal research, and visual information about past painting in the building in conjunction with findings in the field.

Paint investigation can make several contributions to a project. A complete analysis of the paint layers on surfaces within a structure can tell a great deal about the sequence of alterations that have occurred within a building, as well as potentially providing ranges of dates for some of these changes. By establishing a full sequence of paint layers (termed a chromochronology), together with other research, alterations of various building spaces and features can be associated with specific paint layers. It is by establishing this association that the correct layer is identified; when the correct layer has been identified, the color may be matched.

In addition to its archeological value, paint analysis can determine the types and colors of paint on a given surface (identification of thin glazes, decorative paint schemes, binders and pigments). Beyond color identification, then, paint analysis is also recommended to diagnose causes of paint failure.

Knowing a paint binder can often explain causes as well as guide appropriate preservation or conservation treatments.

Owners and managers should identify all of these needs before deciding on the extent of analysis. For example, a complete paint investigation is usually recommended as part of an historic structure report. For buildings with little documentation, additions and alterations can often be identified, and possibly dated, through analysis. Often the use of such seemingly expensive techniques can save money in the long run when determining the history of building change.

It is possible to do some analysis on site; this is a much simpler process that can be undertaken for less cost than the complex laboratory procedures described above. However, the usefulness of onsite analysis is limited and the results will not be as precise as results from samples that are analyzed in a laboratory with a good microscope. Any shortcut approaches to paint analysis that do not follow scientific procedures are generally not worth the expense. In summary, if preservation and restoration treatments are being undertaken, a complete investigation is recommended; for a rehabilitation project, onsite analysis and color matching may provide an adequate palette.

Choosing a Treatment

Most projects involve repainting. It is the historic appearance of the interior and the visual impression that will be created by new paint treatments that must be considered before choosing a particular course of action. The type and colors of paint obviously depend on the type of building and the use and interpretation of its interior spaces. A consistent approach is best.

Preservation
When the treatment goal is preservation, a building's existing historic features and finishes are maintained and repaired, saving as much of the historic paint as possible. Sometimes, cleaning and washing of painted surfaces is all that is needed. Or a coating may be applied to protect important examples of history or art. If repainting is required, the new paint is matched to existing paint colors using the safer, modern formulations. Recreating earlier surface colors and treatments is not an objective.

Rehabilitation
In a typical rehabilitation, more latitude exists in choosing both the kind of new paint as well as color because the goal is the efficient reuse of interior spaces. Decisions about new paint often weigh factors such as economy and durability—use of a high-quality standard paint from a local or national company and application by a qualified contractor. Color choices may be based on paint research reports prepared for interior rooms of comparable date and style. More often, though, current color values and taste are taken into account. Again, the safer paint formulations are used.

Interiors of institutional buildings, such as university buildings, city halls, libraries, and churches often contain rich decorative detailing. During rehabilitation, careful choices should be made to retain or restore selected portions of the decorative work as well as match some of the earlier colors to evoke the historic sense of time and place. At the least, it is important to use period typical paint color and paint placement.

Restoration
In a restoration project, the goal is to depict the property as it appeared during its period of greatest significance. This may or may not be the time of its original construction. For example, if a building dated from 1900 but historians deemed its significance to be the 1920s, the appropriate paint color match would be the 1920s layer, not the original 1900 layer.

Based on historical research, onsite collection of paint samples, and laboratory analysis, surface colors and treatments can be recreated to reflect the property at a particular period of time. It should be noted that scholarly findings may yield a color scheme that is not suited to the taste of the contemporary

owner, but is nonetheless historically accurate. In restoration, personal taste in color is not at issue; the evidence should be strictly followed.

In the restoration process, colors are custom-matched by professionals to give an accurate representation. If an artist or artisan can be found, the historically replicated paint may be applied using techniques appropriate to the period of the restoration. Although custom paint manufacture is seldom undertaken, color and glazing are capable of being customized. In some projects, paint may be custom-made using linseed oil and, if building code variances allow it, white lead. For example, the repainting of a number of rooms at Mount Vernon demonstrates that it is possible to replicate historic paints and applications in all aspects; however, as noted, replication of historic paint formulation is not practical for the majority of projects.

Identifying Deteriorated and Damaged Paint Surfaces

Because painted surfaces are subject to abrasion, soiling, water damage, sunlight, and application of incompatible paints they generally need to be repainted or at least reglazed appropriately from time to time.

Abrasion
From the baseboards up to a level of about six feet off the floor, wood trim is constantly subjected to wear from being touched and inadvertently kicked, and from having furniture pushed against it. Chair rails were in fact intended to take the wear of having chairs pushed back against them instead of against the more delicate plaster wall or expensive wallpaper. Doors in particular, sometimes beautifully grained, receive extensive handling. Baseboards get scraped by various cleaning devices, and the lower rails of windows, as well as window seats, take abuse. The paint in all of these areas tends to become abraded. Two things are important to bear in mind about areas of abraded paint. Samples taken to determine original paint colors and layer sequences will not be accurate except at undamaged edges. Also, dirt and oil or grease need to be removed before applying any new paint because new paint will not adhere to dirty, greasy surfaces.

Dirt
Soiling is another problem of interior paint. Fireplaces smoked; early coalfired furnaces put out oily black soot; gas lights and candles left dark smudges. Sometimes the dirt got deposited on plaster walls or ceilings in a way that makes the pattern of the lath behind the plaster quite clear. Another source of dirt was polluted outside air, from factories or other industries, infiltrating houses and other nearby buildings. Until smokestacks became very high, most air pollution was caused by nearby sources.

In paint investigation, dirt on the surface of paint layers; as seen under the microscope, can be very useful in suggesting the length of time a given paint layer remained exposed, and in distinguishing a finish layer from a prime or undercoat layer. This kind of soiling can happen on any painted surface in a room, but may be slightly heavier in the recesses of moldings and on upward facing horizontal edges. Using dirt as a sole measure, however, may be misleading if the surfaces have been cleaned. The fracture or bonding between paint layers is often used by professionals as a better means of indicating time differences between layers as well as indicating those layers that are part of a single decoration or painting.

Water
Water, the usual source of deterioration for many kinds of material, is also a prime cause of interior paint failure. As a liquid, it can come from roof leaks, from faulty plumbing or steam heating systems, or from fire suppression systems that have misfired. As a vapor, it may come from such human activities as breathing, showering, or cooking. Plaster walls sealed with unpigmented hide glue are notably susceptible to water damage because it forms a water-soluble layer between the plaster and the paint. This can cause the paint to lose adhesion when even small amounts of moisture come into contact with the water-soluble sealer.

Age/Sunlight

Finally, in historic interiors, especially where there is heavy paint buildup, paint can weaken and fail due to chemical or mechanical reasons. For example, the older linseed oil is, the more brittle it is. It also darkens when it is covered and gets no ultraviolet exposure. In rooms where there is more sunlight on one area than on others, the oil or even oil/alkyd paint will get discernibly darker in the less exposed areas in as short a time as six months. Painted over, the oil medium in older paints gets quite yellow-brown, thus changing the color of the paint. Prussian blue is one of the tinting pigments that is particularly vulnerable to fading.

Incompatible Paints

Understanding some basic differences in the strength of various paints helps to explain certain paint problems. Paints that dry to a stronger film are incompatible with those which are weaker. Acrylic latex paints are stronger than oil/alkyd paints. Oil or oil/alkyd paint is stronger than water based paint such as calcimine. When a stronger paint is applied over a weaker paint, it will tend to pull off any weaker paint which may have begun to lose its bond with its substrate. Thus, on many ceilings of older buildings where oil/alkyd paints have been applied over old calcimine, large strips of paint may be peeling.

Oil or varnish glazes over older paints become brittle with age, and can make removal of later paints rather easy. Sometimes it is possible to take advantage of this characteristic to reveal an earlier decorative treatment such as graining or marbleizing. Getting under the edge of the glaze with a scalpel blade can make the removal of later paints relatively simple, and relatively harmless to the fancier paint treatment. Sometimes, paints separate from each other simply due to poor surface preparation in the past or the hardening of the earlier surface paint. Use of alkaline paint strippers can cause paint to lose adhesion. When insufficiently neutralized, they leave salts in wood which cause oil or oil/alkyd paints to fail to adhere to the surface. If dirt or oily residues are not cleaned from the surfaces to be painted, new paint will not remain well adhered.

Surface Preparation

First, it is important to note that the earlier, linseed oil-based paints were penetrating type paints, forming a bond by absorption into the substrate. Often these thin oil coatings were slightly tinted with an iron oxide pigment so coverage could be seen; the next coating applied would adhere to this first oil layer. Modern paints, on the other hand, are primarily bonding paints with little ability to penetrate a substrate. For this reason, surface preparation is extremely important for today's paints.

Before preparing the interior for repainting, all moisture penetration from failing roofs or gutters or from faulty plumbing or interior heating elements should be identified and corrected. A paint job is only as good as the preparation that goes before it. The surface to be painted, old or new, wood, plaster, masonry, or metal must be made sound and capable of taking the paint to be applied.

Scraping and Sanding

The first step in preparing interior wood and plaster surfaces which are coherent and sound is to remove any loose paint (see Paint Hazards sidebar). Careful hand scraping is always advisable for historic surfaces. Use of mechanical sanders usually leaves traces of the sander's edges, visible through the new paint film. Hand sanding is also necessary to feather the edges of the firmly adhering layers down to the bare areas so that shadow lines are avoided. Preparing previously painted interior masonry for new paint is basically similar to preparing plaster. Metals elements, such as radiators, valences, or fire backs are somewhat different. In order to get a sound paint job on metal items, the work is primarily that of sanding to remove any rust before repainting. If the existing paint is well adhered over the entire metal surface, then it may be necessary only to sand lightly to roughen the existing paint, thus providing some "tooth" for the primer and new paint layer. On wood, garnet sanding papers work well. Aluminum oxide and silicon carbide sandpapers are effective on other surfaces as well as wood; emery papers should be used on metals.

Paint Removal

When should surfaces be completely stripped? Obviously, new paint is wasted when applied on old paint which is loose, that is, extensively damaged and deteriorated. Sometimes paint on an architectural feature needs to be removed if it obscures delicate detailing. For the most part, however, if the surface is intact—and the presence of lead paint has been shown to present no health dangers to building occupants—the existing paint can be overpainted.

Well-adhered, intact paint layers (in at least one area of each room) should be covered with a sturdy protective tape, then painted over with the new paint and left in place to inform future research. The next owner may be interested in the building's past history, and methods of gleaning information from old paints grow more sophisticated all the time.

Heat/Scraping

Propane torches should never be used because they can damage historic wood features. Also, charred areas of wood will not hold the new paint. Use of a heat gun or heat plate may be relatively fast, but has both health and safety drawbacks. Heat oxidizes lead paint, causing poisonous fumes. And old walls may contain fine debris which acts like tinder and smolders when heated, bursting into flame hours after the stripping. (Heat methods are best limited to those interior elements that can be safely removed from the building for stripping and reinstalled). Finally, scraping to remove heat loosened paint may gouge and scar the wood or plaster substrate if not done carefully. Rotary wire brushes cut into wood and should be avoided altogether.

Chemical Stripping

Removing paint from wood and plaster features can be done with either caustic strippers (potassium or sodium hydroxide) or solvent strippers (organic compounds such as methylene chloride, methanol, or toluol). Caustic strippers are fairly fast acting, but can weaken wood fibers if left on too long, causing them to raise and separate. They also leave alkaline residues which must be neutralized by an acidic wash (usually white vinegar which contains 4% acetic acid). It is difficult to make the neutralizing 100% effective and, when it is not, chemical reactions between the alkaline residues and the new paint may cause the paint to lose adhesion.

Methylene chloride and other organic compounds are as effective as caustic strippers, but their fumes may be both flammable and toxic. While they may leave wood and plaster surfaces free from harmful residue, the newly cleaned surface must be washed down with mineral spirits or denatured alcohol before priming in order to remove additives, such as wax, that were put in the stripper to retard its drying. All hazard warnings on the labels of chemical strippers should be heeded.

Detergent or Vinegar and Water

Water based paints can usually be scrubbed off with hot water with a detergent added. Calcimine and whitewash are difficult to remove; because of the lime or whiting content (calcium carbonate), however, they can be broken down with acids. While strong acids may work quickly, they are very dangerous. Acetic acid in its most common form, vinegar, (4% acetic acid) is often used instead. In areas where any calcimine remains and is evident as chalk, the area can be coated with white shellac, which provides a stable surface for the new paint.

Air Pressure

Air pressure of 200-500 psi is effective for flat surfaces if there is a weak substrate surface bond. A flat nozzle is inserted between the paint layer and substrate, and the air pressure simply lifts the loose paint up for easy removal. When used carefully, this method is fast and causes little damage.

Patching and Repair

Once the substrate and its surface are sound and clean, free from crumbling, loose material or dust, the next step is to undercut and fill any cracks in plaster surfaces. Plaster which has lost its key and is sagging should be reattached or replaced. Friable plaster and punky wood need to be consolidated. Wood surfaces should be made as smooth as they were historically so that the paint film will cover a relatively uniform surface. Rotted wood must be removed and new wood carefully spliced in. Finally, gypsum plaster finishes can be painted as soon as the water has evaporated; a lime putty coat or traditional finish plaster can be primed almost immediately after drying as well, using alkali resistant primers such as acrylic latex.

Priming

The importance of a primer can hardly be overstated. It is the intermediary material between the immediate substrate, which may be an old paint layer or may be bare wood, plaster, or metal (rarely stone, as around a fireplace opening), and the fresh paint itself. The primer must be capable of being

absorbed to some extent by the material underneath while being compatible and cohesive with the paint to be applied on top. Most paint manufacturers will provide explicit instructions about which primers are most compatible with their paints. Those instructions should be followed.

The question of a primer for latex paint continues to be debated. Traditionalists recommend that the primer between an old oil paint and a new latex paint be an oil primer, but the improvements to latex paint in recent years have led many experts to the conclusion that today's top grade latex primers are best for latex finish paints. If a latex primer is selected, the label on the can should specify clearly that it is one which can bond to an older oil or oil/alkyd paint.

The most important general rule to remember is that softer or weaker paints should always go over harder and stronger paints. For instance, because latex is stronger than oil, an oil or oil/alkyd paint can go over a well adhered latex, but the reverse will run the risk of failure. Using primer and finish paints by a single company is a good way to guarantee compatibility.

Choosing Modern Paint Types/Finish Coats

Most frequently today, the project goal is preservation or rehabilitation. Because of the impracticality of replicating historic paints, restoration is least often undertaken. Given current laws restricting the use of toxic ingredients, such as lead, solvents, and thinners, contemporary substitute paints using safer ingredients need to be used. Many paint companies make latex paints in colors that are close to historic colors as well as appropriate gloss levels, but contain no white lead and no hazardous volatile organic compounds.

Work on historic properties generally requires the services of a qualified paint contractor who has had at least five years of experience and who can list comparable jobs that a potential client can see. Then, too, getting a sample or a mockup of any special work may be advisable before the job starts. While less experienced workers may be acceptable for preparing and priming, it is wise to have the most experienced painters on the finish work.

Oil-based/Alkyd Paints
Today's version of oil paint has a binder that usually contains some linseed oil (read the paint can label), but also has one of the improved synthesized oils, frequently soy based, known as alkyds. They dry hard, have flexibility, and discolor far less than linseed oil. They can also be manufactured to dry with a high sheen, and can take enough tinting pigment to create even the very deep Victorian period colors. However, they all contain volatile organic compounds, and thus are forbidden by law in some parts of the United States. They are also less simple and more dangerous to use, as cleaning up involves mineral spirits.

Acrylic Waterborne Paints (latex)
Latex paints are synthetic resins carried in water. Before the paint dries or crosslinks, it can be cleaned up with water. Early in the history of latex paints, some contained styrene/butadiene resins. Now nearly all top-grade latex paints contain acrylic resins, which are superior. Also, until fairly recently, the latex paints, while offering great strength, quick drying, and water cleanup, had some disadvantages for jobs which needed to have an historic look. Today, there are latex product lines with better gloss characteristics and more historic colors from which to choose. In addition, latex paints often have excellent color retention with very little fading. Still, it is always a good idea to buy a quart and "test paint" the color chosen for the job on site before making a total commitment.

Calcimine/Whitewash
Modern water-based paints such as calcimine can be purchased today and have much the same appearance as the early ones. The same is true of modern whitewash, although today's whitewashes do not leave the same ropy surface texture as the early ones.

Glazes
Glazes were often part of historic paint treatments. Traditionally oil and turpentine, sometimes with a scant amount of pigment, today's glazes can be formulated with a water base and are relatively simple to apply by brush. An experienced decorative painter should be consulted before deciding whether to use a glaze coat rather than a high-gloss enamel. The glaze is capable of providing protection as well as a more accurate historic appearance that includes a greater depth to the finish.

Epoxies/Urethane
These were not available until relatively recently and thus are not appropriate for replication of traditional finishes.

Applying Interior Paints

Because flat wall surfaces generally dominate an interior painting job, some flexibility in applicators is suggested below:

Brushes
Natural bristle brushes now have competition from synthetic brushes made of nylon or polyester which work well for applying either oil/alkyd or latex paints. Being harder than natural bristles, they tend to last longer. Since brushes come in a wide and very specific variety of types suited to different types of work, it is important to have a painter who will use the appropriate brush for the paint selected and for each portion of the job. One strong advantage of brushing paint on is that the paint is forced onto the surface and into all of its imperfections. Thus, a good brushed on paint job may last longer if the substrate is sound and the primer and finish coats are compatible and of top quality.

Rollers
There is no harm in using a roller, or even an airless sprayer, to apply a prime coat to a large flat area. Since all contemporary commercial paints dry with a smooth surface anyway, use of a roller or sprayer is acceptable for priming, and even for a first finish coat. However, to get paint well pushed into articulated surfaces and to add some texture to larger flat surfaces, a brush is best.

Types of Modern Paint

Oil-based/alkyd: Nonvolatile oils and resins, with thinners. (Alkyds are synthetic, gelatinous resins compounded from acids and alcohol.) Accept almost any type of coloring/hiding pigments. For use on interior wood and metal.

Acrylic waterborne paints (latex): Suspension of acrylic or polyvinyl resins in water, with other resins, plus hiding and coloring pigments and extenders. Dries by evaporation. Commercially produced acrylic or latex enamels are also available in a complete range of gloss levels which are produced with the addition of various acrylic polymers. Use on interior plaster especially.

Enamels: Modern alkyd paints are adjusted with the addition of synthetic varnishes to produce a complete range of gloss levels.

Metal finishes: Paints marketed for use on metals, can either be alkyd, latex, or epoxy based, or combinations. The primers used for metals are formulated with rust inhibiting ingredients.

Special finishes: finishes such as urethane and epoxy-based paints, marketed for very high gloss surface treatments.

Finally, decorative paint work in an historic interior— whether simple or high style—is well worth preserving or restoring, and when such fancy work is being undertaken, traditional tools should always be used. To simplify by using shortcut methods or rejecting painted decoration is indeed to dismiss or skew history as well as to lose the enjoyment of a true historic finish.

Summary

First, it is most important to understand the range of approaches and treatments and to make choices with as much knowledge of the original and subsequent historic paints as possible, using the ***Secretary of the Interior's Standards for the Treatment of Historic Properties*** as a framework.

A paint's patina of age expresses decades or centuries of endurance in the face of changing climate and conditions. Documenting the sequence of interior paint layers and protecting this information for future investigation should be an integral part of any historic preservation project.

Except for the rare, scholarly restorations of historic interiors, most repainting jobs done today will employ modern paint formulations. Modern paints can recreate the appearance of historic colors, gloss and texture in varying degrees, but eliminate earlier toxic components such as white lead and volatile organic compounds.

CAUTION: Before Painting Know Paint Hazards and Take Action

Before undertaking any project involving paint removal, applicable State and Federal laws on lead paint abatement and disposal must be taken into account and carefully followed. State and Federal requirements may affect options available to owners on both paint removal and repainting. These laws, as well as any requirements prohibiting volatile organic compounds (VOCs), should be requested from the State Historic Preservation Officer in each State.

Below is a summary of the health hazards that owners, managers, and workers need to be aware of before removing paint and repainting:

Lead and other heavy metal compounds.
In virtually all paints made before 1950, the white or "hiding" pigment was a lead compound, or more rarely, zinc oxide. Work to remove lead paint such as scraping and dry sanding releases the lead—a highly damaging heavy metal—in dust. Lead dust then enters the human system through pores of the skin and through the lungs. The use of heat for stripping also creates toxic lead fumes which can be inhaled.

To mitigate the hazards of lead paint ingestion, inhalation, or contact, it is extremely important to prevent the dust from circulating by masking room openings and removing all curtains, carpeting, and upholstered furniture. Drop cloths and masking containing lead dust should be carefully enclosed in tight plastic bags before removal. Workers and others in the room should wear High Efficiency Particulate Air (HEPA) filters for lead dust (fume filters if heat stripping is being used), change clothing just outside the room leaving the work clothes inside, and avoid any contact between bare skin (hands) and the paint being removed. Workers should also not eat, drink, or smoke where lead dust is present. Finally, anyone involved in lead paint removal should undergo periodic blood testing. After work, ordinary vacuuming is not enough to remove lead dust; special HEPA vacuums are essential. The surfaces of the room must also be given a final wash with a solution of trisodium phosphate and water, changing the washing solution often and rinsing well.

In addition to lead, early oil paints also had cobalt or other heavy metal compounds in them to accelerate drying. A small amount of mercury is also included in some latex paints to help prevent mildew and mold formation.

Volatile Organic Compounds (VOCs)
Organic paint strippers, such as methylene chloride, and oil/alkyd paints have VOCs as their solvent base. Inhaling these fumes can lead to respiratory and other illnesses, and to cancer. Especially in closed spaces (but in the outdoor environment as well) these compounds pollute the air and can damage health.

SECTION 10431

SIGNAGE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Exterior ADA Parking Signs
   2. Building Numbering & Addressing
   3. Exterior Site & Amenity Signage
   4. Interior signage
   5. Building Mounted Signage – "Fin-Style" Sign (Reference Section 01019 Special Provisions, 4. Cash Allowances, item f.)

B. Contractor shall install and furnish Interior Signage: Apartments, Mechanical Rooms, Offices, Restrooms, etc. – (Tactile and Braille Signage), All Exterior Signage and ADA Parking Signage. Bid price to also include the purchase and delivery of all signage.

C. Site Signage, and Interior Signage design should reflect the historic nature of the building. Contractor to submit design options to Architect and Owner prior to Final Shop Drawing Submittal.

D. All signs are to comply with ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1. Including, but not limited to installation height and location, size and tactile & braille requirements.

1.3 DEFINITIONS

A. ADA-ABA Accessibility Guidelines: U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines."

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: Show fabrication and installation details for signs.
   1. Show sign design – should reflect the historic nature of the Lee Lofts and Building 1
   2. Show sign mounting heights, locations of supplementary supports to be provided by others, and accessories.
   3. Provide message list, typestyles, graphic elements, including tactile characters and Braille, and layout for each sign.

C. Samples for Initial Selection: Manufacturer's color charts consisting of actual units or sections of units showing the full range of colors.

D. Samples for Verification: For each of the following products and for the full range of color, texture, and sign material indicated, of sizes indicated:
   1. Plaque Casting: 6 inches (150 mm) square including border.
   2. Dimensional Characters: Full-size Samples of each type of dimensional character letter, number, and graphic element.
   3. Aluminum: For each form, finish, and color, on 6-inch- (150-mm-) long sections of extrusions and squares of sheet at least 4 by 4 inches (100 by 100 mm).

E. Maintenance Date: For signs to include maintenance manuals.

F. Warranty: Special warranty specified in this section.

1.5 SIGN SCHEDULE

1. **Building Mounted Signage** – "Fin-Style" Sign
   a. Contractor to coordinate with Architect and Owner on final design, materials, colors, size, and location.
   b. Reference Section 01019 Special Provisions, 4. Cash Allowances, item f.
2. **Exterior ADA Parking Signs**: Provide and install pole mounted handicap sign(s) with bottom of sign at 60 inches above grade. Reference site plan for type, quantity and location. Submit to Architect for approval.

3. **Other Exterior Site Signage**: Coordinate final numbering and location with architect. To include (but not limited to): Property Address, Leasing office numbers and hours; Tenant Space entry doors & information.
4. **Interior Signage**: Coordinate design, final numbering, and locations with architect. To include (but not limited to): Apartments, Leasing Office, Community Room, Restrooms, Mechanical and Electrical Rooms, Storage Rooms, Stairwells and Required Exits, Laundry, Learning Center, Basement, etc.

1.6 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.
B. Source Limitations for Signs: Obtain each sign type indicated from one source from a single manufacturer.
C. Regulatory Requirements: Comply with applicable provisions in ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

1.7 PROJECT CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit installation of signs in exterior locations to be performed according to manufacturers' written instructions and warranty requirements.
B. Field Measurements: Verify recess openings by field measurements before fabrication and indicate measurements on Shop Drawings.

1.8 COORDINATION

A. Coordinate placement of anchorage devices with templates for installing signs.

1.9 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.
1. Failures include, but are not limited to, the following:
a. Deterioration of metal and polymer finishes beyond normal weathering.
b. Deterioration of embedded graphic image colors and sign lamination.
2. Warranty Period: **Five** years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Aluminum Sheet and Plate: ASTM B 209 (ASTM B 209M), alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated, and with at least the strength and durability properties of Alloy 5005-H32.
B. Interior Signage - Tactile and Braille Signage: Manufacturer's standard process for producing text and symbols complying with ADA-ABA Accessibility Guidelines and with ICC/ANSI A117.1. Text shall be accompanied by Grade 2 Braille. Produce precisely formed characters with square-cut edges free from burrs and cut marks; Braille dots with domed or rounded shape.
1. Panel Material: **Opaque acrylic sheet**.
2. Raised-Copy Thickness: Not less than 1/32 inch (0.8 mm).

2.2 ACCESSORIES

A. Anchors and Inserts: Provide nonferrous-metal or hot-dip galvanized anchors and inserts for exterior installations and elsewhere as required for corrosion resistance. Use toothed steel or lead expansion-bolt devices for drilled-in-place anchors. Furnish inserts, as required, to be set into concrete or masonry work.

2.3 FABRICATION

A. General: Provide manufacturer's standard signs of configurations indicated.
1. Welded Connections: Comply with AWS standards for recommended practices in shop welding. Provide welds behind finished surfaces without distortion or discoloration of exposed side. Clean exposed welded surfaces of welding flux and dress exposed and contact surfaces.

2. Mill joints to tight, hairline fit. Form joints exposed to weather to exclude water penetration.
3. Preassemble signs in the shop to greatest extent possible. Disassemble signs only as necessary for shipping and handling limitations. Clearly mark units for reassembly and installation, in location not exposed to view after final assembly.
4. Conceal fasteners if possible; otherwise, locate fasteners where they will be inconspicuous.

2.4 FINISHES, GENERAL

A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.5 ACRYLIC SHEET FINISHES

A. Colored Coatings for Acrylic Sheet: For copy **and background** colors, provide colored coatings, including inks, dyes, and paints, that are recommended by acrylic manufacturers for optimum adherence to acrylic surface and that are UV and water resistant for **three** years for application intended.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.
B. Verify that items**, including anchor inserts** are sized and located to accommodate signs.
C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Locate signs and accessories where indicated, using mounting methods of types described and complying with manufacturer's written instructions.
1. Install signs level, plumb, and at heights indicated, with sign surfaces free of distortion and other defects in appearance.
2. Interior Wall Signs: Install signs on walls adjacent to latch side of door where applicable. Where not indicated or possible, such as double doors, install signs on nearest adjacent walls. Locate to allow approach within 3 inches (75 mm) of sign without encountering protruding objects or standing within swing of door.

3.3 CLEANING AND PROTECTION

A. After installation, clean soiled sign surfaces according to manufacturer's written instructions. Protect signs from damage until acceptance by Owner.

END OF SECTION 10431

SECTION 10522

FIRE EXTINGUISHERS, CABINETS, AND ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Fire extinguishers; Reference drawings –
  Cabinets with Extinguishers, where indicated on the floor plans.

1.02 SUBMITTALS
- A. Product Data: Provide extinguisher operational features, color and finish, and anchorage details.
- B. Manufacturer's Installation Instructions: Indicate special criteria and wall opening coordination requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS
- A. LARSEN'S - Architectural Series 2409-R3 & FS 2409-R3, Vertical Duo Door, baked enamel interior finish. Fire rated cabinets, FS where indicated to be installed in fire rated assemblies, Ref. CFP sheet.
- B. Substitutions: Under provisions of the General Requirements.

2.02 EXTINGUISHERS
- A. Dry Chemical Type: Larsen's MP series MP5, Cast steel tank, with pressure gage.

2.03 CABINETS
- A. Interior Metal: Formed sheet steel, baked enamel box.
- B. Configuration: Semi-recessed type, exterior nominal dimensions of 27 1/2 inch high x 13 inch wide x 5 inch deep.
- C. Trim Type: Returned to wall surface, with 2 1/2 inch projection.
- D. Exterior Door and Trim: Stainless Steel, reinforced for flatness and rigidity; latch with vertical glass.
- E. Door Glazing: Glass, clear, 1/8 inch thick tempered.
- F. Cabinet Mounting Hardware: Appropriate to cabinet.

2.04 FABRICATION
- A. Form cabinet enclosure with right angle inside corners and seams. Formed trim and door stiles.
- B. Pre-drill for anchors.
- C. Hinge doors for 180 degree opening with continuous piano hinge. Provide roller type catch.
- D. Weld, fill, and grind components smooth.
- E. Glaze doors with resilient channel gasket glazing.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify rough openings for cabinet are correctly sized and located.

3.02 INSTALLATION
- A. Install in accordance with manufacturer's instructions.
- B. Install cabinets plumb and level in wall openings, 24 inches from finished floor to inside bottom of cabinet.
- C. Secure rigidly in place.
- D. Place extinguishers in cabinets.
- E. Verify exact location with Architect.

END OF SECTION 10522

SECTION 10800

TOILET AND BATH ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES
- A. Toilet and washroom accessories.
- B. Grab bars, Towel bars
- C. Mirrors
- D. Toilet Paper, Paper Towel
- E. Shower Seat & Hardware
- E. Attachment hardware

PART 2 PRODUCTS

2.01 MANUFACTURERS
- A. BOBRICK WASHROOM EQUIPMENT INC., or BRADLEY CORPORATION.
- B. Substitutions: Under provisions of the General Requirements.

2.02 FABRICATION
- A. Weld and grind joints of fabricated components, smooth.
- B. Form exposed surfaces from single sheet of stock, free of joints. Form surfaces flat without distortion. Maintain surfaces without scratches or dents.
- C. Fabricate grab bars of tubing, free of visible joints, return to wall with end attachment flanges. Form bar with 1 1/2 inches clear of wall surface. Knurl grip surfaces.
- D. Shop assemble components and package complete with anchors and fittings.
- E. Provide steel anchor plates, adapters, and anchor components for installation.

2.03 FINISHES
- A. Galvanizing: ASTM A123 to 1.25 oz./sq. yd. Galvanize ferrous metal and fastening devices.
- B. Chrome/Nickel Plating: ASTM B456, satin finish.
- C. Stainless Steel: No. 4 satin luster finish.
- D. Back paint components where contact is made with building finishes to prevent electrolysis.

PART 3 EXECUTION

3.01 EXAMINATION
- A. Verify that site conditions are ready to receive work and dimensions are as indicated on shop drawings and instructed by the manufacturer.
- B. Verify exact location of accessories for installation. Coordinate with ADA requirements.

3.02 PREPARATION
- A. Deliver inserts and rough-in frames to site for timely installation. Provide templates and rough-in measurements as required.

3.03 INSTALLATION
- A. Install accessories in accordance with manufacturer’s instructions and Americans with Disabilities Act. Also reference ANSI A117.1.
- B. Install plumb and level, securely and rigidly anchored to substrate.

3.04 SCHEDULE
- A. Reference drawings for all required accessories and submit for approval including but not limited to:
- B. Toilet Tissue Holders: Bobrick.
- C. Towel Disp/Waste Recep. : Bobrick
- D. Towel Bar: (2 per bathroom) 24” with concealed wall bracket.
- E. Grab Bars as indicated on the drawings, Bobrick.
- F. Shower Curtain Rod: Stainless Steel Tube, 1 inch O.D., concealed attachment.
- G. Shower Seat: ADA & FH approved, submit for approval

END OF SECTION 10800

SECTION 10850

BUILDING SPECIALTIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Building specialties shall be furnished and installed as shown and herein specified. Installation shall be in accordance with the respective manufacturer's instructions. Certain manufacturer's products have been selected as a basic standard, and reference to these products has been made. Other manufacturers' products of equal capacities and design characteristics may be used, if approved by the Architect prior to the Bidding. The Contractor shall submit for approval shop drawings or standard cuts and illustrations or a combination thereof showing all items he proposes to use.

1.02 MAILBOXES

A. Manufacturer – **Florence Manufacturing Company**, front loading horizontal mailboxes for recessed mounting with snap-on outer trim kit.

B. Additional Features: Standard 5-pin cylinder tenant can lock with two keys. Engraved identification number for slots with color fill. Color: To be selected by architect.

C. Quantity and Size: (8) sections 4CADD-09 (72 Mailboxes and 16 parcel boxes total). Reference details on Sheet A8.1 of bid documents for configuration.

1.03 SITE AMENITIES

A. Benches – (1) Total – Polywood Traditional Garden 60" Bench. Color TBD

1.04 MIRRORS

A. As noted on plans. Provide number, size, and product type. For owner review and approval.

1.05 FIBERGLASS REINFORCED PLASTIC PANELING

A. Product - Class A – Minimum .090 thickness panel. Include Manufacturer's vinyl molding at all corners, transitions, joints, and tops, bottoms, etc.

B. Product shall be applied using manufacturer recommended adhesive and manufacturer recommended mechanical fasteners. Pre-drill rivet holes and silicone caulk prior to riveting.

C. Locations: install behind mop sinks

END OF SECTION 10850

SECTION 11451

RESIDENTIAL APPLIANCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Cooking equipment including: Electric ranges, Microwave ovens.
   2. Ventilation range hoods.
   3. Refrigerator/freezers; **Energy Star Compliant**.
   4. Dishwashers; **Energy Star Compliant**.
   5. Garbage Disposal; **Energy Star Compliant**
   6. Clothes washers, Clothes dryers; **Energy Star Compliant**

1.3 SUBMITTALS

A. Product Data: For each type of product indicated. Include operating characteristics, dimensions of individual appliances, and finishes for each appliance. **All appliances must be submitted and approved by the Owner/Developer prior to ordering.**

B. Samples for Verification: factory-applied **color** finishes.

C. Appliance Schedule: For appliances; use same designations indicated on Drawings.

D. Manufacturer Certificates: Signed by manufacturers certifying that products comply with requirements.

E. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for **each product**.

F. Maintenance Data: For **each product** to include in maintenance manuals.

G. Warranties: Special warranties specified in this Section.

1.4 QUALITY ASSURANCE

A. Manufacturer Qualifications: A qualified manufacturer with a service center capable of providing training, parts, and emergency maintenance repairs.

B. Product Options: Information on Drawings and in Specifications establishes requirements for product's aesthetic effects and performance characteristics. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction. Performance characteristics are indicated by criteria subject to verification by one or more methods including preconstruction testing, field testing, and in-service performance.

C. Regulatory Requirements: Comply with provisions of the following product certifications:
   1. NFPA: Provide electrical appliances listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
   2. UL and NEMA: Provide electrical components required as part of residential appliances that are listed and labeled by UL and that comply with applicable NEMA standards.
   3. ANSI: Provide gas-burning appliances that comply with ANSI Z21 Series standards.
   4. NAECA: Provide residential appliances that comply with NAECA standards.

D. Regulatory Requirements, Accessibility: Where residential appliances are indicated to comply with accessibility requirements, comply with the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG)." ANSI A117.1. FED-STD-795, "Uniform Federal Accessibility Standards."
   1. Operable Parts: Provide controls with forward reach no higher than 48 inches (1219 mm) above the floor, horizontal front reach no more than 25 inches (635 mm), horizontal side reach no more than 24 inches (610 mm), and that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf (22.2 N).
   2. Range or Cooktop: Provide knee clearance for forward approach of 27 inches (685 mm) high, 30 inches (760 mm) wide, and 11 inches (280 mm) horizontally; toe space clearance of 9 inches (230 mm) high and 17 inches (430 mm) horizontally; with insulated underside of cooktop to prevent burns, shocks, or abrasions. Provide top surface 34 inches (865 mm) above the floor, with controls that do not require reaching across burners.
   3. Refrigerator/Freezer: Provide 50 percent of freezer space within 54 inches (1370 mm) of the floor.

E. AHAM Standards: Provide appliances that comply with the following AHAM standards:
   1. Dishwashers: AHAM DW-DW1.
   2. Electric Ranges: AHAM ER-1.
   3. Clothes Dryers: AHAM HLD-1.
   4. Household Refrigerators: AHAM HRF-1.
   5. Household Freezers: AHAM HRF-1.
   6. Trash Compactors: AHAM TC-1.

F. Energy Ratings: Provide residential appliances that carry labels indicating energy-cost analysis (estimated annual operating costs) and efficiency information as required by the FTC Appliance Labeling Rule.
   1. Provide appliances that qualify for the EPA/DOE ENERGY STAR product labeling program.

G. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

1.5 WARRANTY

A. Special Warranties: Manufacturer's standard form in which manufacturer of each appliance specified agrees to repair or replace residential appliances or components that fail in materials or workmanship within specified warranty period.
   1. Electric Range: Five-year limited warranty for surface-burner elements.
   2. Microwave Oven: Five-year limited warranty fordefects in the magnetron tube.
   3. Refrigerator/Freezer: Five-year limited warranty for in-home service on the sealed refrigeration system.
   4. Freezer: Five-year limited warranty for in-home service on the sealed refrigeration system.
   5. Dishwasher: 5-year warranty for in-home service against deterioration of tub and door liner.
   6. Clothes Washer: 5-year limited warranty for the inner wash basket and outer tub, and five-year limited warranty for the balance suspension system and drive transmission.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
   1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products specified.
   2. Products: Subject to compliance with requirements, provide one of the products specified.
   3. Basis-of-Design Product: The design for each residential appliance is based on the product named. Subject to compliance with requirements, provide either the named product or a comparable product by one of the other manufacturers specified.
   4. **All appliances & finishes must be submitted and approved by the Owner/Developer prior to ordering.**
   5. **Confirm selected or submitted appliances fit in the designed space with manufacturers listed or recommended clearances.**

2.2 COOKING APPLIANCES, provide one at each unit and clubhouse as indicated.

A. Range (ADA Units, front controls), **Black**
   1. Products: 30” Free Standing with Front Controls Similar to RG below
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances, General Electric Company; Hotpoint; KitchenAid, Maytag

B. Range RG), **Black**
   1. Products: 30” Free Standing Range
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances, General Electric Company; Hotpoint; KitchenAid, Maytag

C. Microwave Oven Over Range, MO), **Black**
   1. Products: Over Range Microwave Oven 1.5 cf, 950 watt,
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

D. Microwave Oven Counter Top, MO), **Black**
   1. Products: Microwave Oven .7 cf, 700 watt,
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

E. Exhaust Hood EX), **Black, Recirculating type – Ventless.**
   1. Products: Broan 30”
   2. Acceptable manufacturers, submit equals for approval.
      a. General Electric Company; Hotpoint; KitchenAid; Maytag; Whirlpool Corp

2.3 REFRIGERATION APPLIANCES, provide one at each unit and clubhouse as indicated.

A. Refrigerator/Freezer w ice maker, RF), **Black, with Ice Maker**
   1. Products: Top-Freezer Refrigerator, **Energy Star Rated**, 18 Cu.Ft.,
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

2.4 CLEANING APPLIANCES, provide one at each unit and clubhouse as indicated.

A. Garbage Disposal – **Energy Star Rated**, Reference Mechanical drawings and schedules

B. Dishwasher DW), **Black**
   1. Products: Dishwasher, **Energy Star Rated**
   2. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

C. Clothes Washer CW, provide one at each unit as indicated.
   1. Products: Clothes Washer, **White, 3.3 CF**
   2. Size; Must fit in Laundry Closets, 27” W x 30” D max.
   3. Condensation type Dryer - Ventless
   4. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Co; Hotpoint; KitchenAid; Maytag;

D. Clothes Dryer CD, provide one at each unit as indicated.
   1. Products: Clothes Dryer, **White, 6.5 cf**
   2. Size; Must fit in Laundry Closets, 27” W x 30” D max.
   3. Verify with plans for required Side exhaust
   4. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

E. Clothes Washer (ADA Units, Frontload) , provide one at each Handicap unit as indicated.
   1. Products: Clothes Washer, **White, 3.3 cf**
   2. Size; Must fit in Laundry Closets, 27” W x 30” D max.
   3. Condensation Type Dryer – Ventless
   4. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

F. Clothes Dryer (ADA Units, Frontload) , provide one at each Handicap unit as indicated.
   1. Products: Clothes Dryer, **White, 6.5 cf**
   2. Size; Must fit in Laundry Closets, 27” W x 30” D max.
   3. Verify with plans for required Side exhaust
   4. Acceptable manufacturers, submit equals for approval.
      a. Amana Appliances; General Electric Company; Hotpoint; KitchenAid; Maytag;

2.5 FINISHES, GENERAL

A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Color-Coated Finish: Provide appliances with manufacturer's standard finish complying with manufacturer's written instructions for surface preparation including pretreatment, application, baking, color, gloss, and minimum dry film thickness for painted finishes
D. For exact finish, insert names of coating manufacturers and products.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in for piping systems to verify actual locations of piping connections before equipment installation.
B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. General: Comply with manufacturer's written instructions.
B. Built-in Equipment: Securely anchor units to supporting cabinets or countertops with concealed fasteners. Verify that clearances are adequate for proper functioning and rough openings are completely concealed.
C. Freestanding Equipment: Place units in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.
D. Utilities: Refer to Divisions 15 and 16 for plumbing and electrical requirements.

3.3 CLEANING AND PROTECTION

A. Test each item of residential appliances to verify proper operation. Make necessary adjustments.
B. Verify that accessories required have been furnished and installed.
C. Remove packing material from residential appliances and leave units in clean condition, ready for operation.

3.4 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain residential appliances. Refer to Division 1 Section "Demonstration and Training."

END OF SECTION 11451

SECTION 12356

KITCHEN CASEWORK

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:
   1. Wood-faced kitchen cabinets.
   2. Plastic-laminate-faced kitchen cabinets.
   3. Wood- and plastic-laminate-faced kitchen cabinets.
   4. Vinyl-faced kitchen cabinets.
   5. Wood-faced vanity cabinets.
   6. Plastic-laminate-faced vanity cabinets.
   7. Wood- and plastic-laminate-faced vanity cabinets.
   8. Vinyl-faced vanity cabinets.
   9. Plastic-laminate countertops.
   10. Solid-surfacing-material countertops.

B. Related Sections include the following:
   1. Division 11 Section "Residential Appliances" for appliances mounted in kitchen casework.
   2. Division 15 Section "Plumbing Fixtures" for sink units mounted in countertops.

1.3 DEFINIITIONS

A. Exposed Surfaces of Casework: Surfaces visible when doors and drawers are closed, including visible surfaces in open cabinets or behind glass doors.

B. Semiexposed Surfaces of Casework: Surfaces behind opaque doors or drawer fronts, including interior faces of doors and interiors and sides of drawers. Bottoms of wall cabinets are defined as "semiexposed."

C. Concealed Surfaces of Casework: Surfaces not usually visible after installation, including sleepers, web frames, dust panels, bottoms of drawers, and ends of cabinets installed directly against and completely concealed by walls or other cabinets. Tops of wall cabinets and utility cabinets are defined as "concealed."

1.4 SUBMITTALS

A. Product Data: For the following:

Samples and Submittals must be approved by Owner/Developer prior to ordering or production.

   1. Cabinets.
   2. Plastic-laminate countertops.
   3. Solid-surfacing material.
   4. Cabinet hardware.

B. Shop Drawings: For cabinets and countertops. Include plans, elevations, details, and attachments to other work. Show materials, finishes, filler panels, hardware, edge and backsplash profiles, cutouts for plumbing fixtures, and methods of joining countertops.

C. Samples for Initial Selection: Manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available for each type of material exposed to view.

D. Samples for Verification: For the following materials; in sets showing the full range of color, texture, and pattern variations expected:
   1. Wood-veneered panels with transparent finish, 8 by 10 inches (200 by 250 mm), for each species.
   2. Solid wood with transparent finish, 50 sq. in. (300 sq. cm), for each species.
   3. Plastic laminate for casework finish, 8 by 10 inches (200 by 250 mm).
   4. Plastic laminate for countertops, 8 by 10 inches (200 by 250 mm).
   5. Solid-surfacing material for countertops, 6 inches (150 mm) square.
   6. One unit of each type of exposed hardware.

E. Samples for Verification: As follows:
   1. One full-size, finished base cabinet complete with hardware, doors, and drawers, but without countertop.
   2. One full-size, finished wall cabinet complete with hardware, doors, and adjustable shelves.
   3. Plastic laminate for countertops, 8 by 10 inches (200 by 250 mm).
   4. Solid-surfacing material for countertops, 6 inches (150 mm) square.

F. Product Certificates: Signed by manufacturers of casework certifying that products furnished comply with requirements. **Samples and Submittals must be approved by Owner/Developer prior to ordering or production.**

1.5 QUALITY ASSURANCE

A. Source Limitations for Cabinets: Obtain cabinets through one source from a single manufacturer.

B. Product Designations: Drawings indicate size, configurations, and finish material of casework by referencing designated manufacturer's catalog numbers. Other manufacturers' casework of similar sizes, similar door and drawer configurations, same finish material, and complying with the Specifications may be considered. Refer to Division 1 Section "Substitutions."

C. Quality Standards: Unless otherwise indicated, comply with the following standards:
   1. Cabinets: KCMA A161.1.
      a. KCMA Certification: Provide cabinets with KCMA's "Certified Cabinet" seal affixed in a semiexposed location of each unit and showing compliance with the above standard.
   2. Plastic-Laminate Countertops: KCMA A161.2.

1.6 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install kitchen casework until building is enclosed, wet-work is complete, and HVAC system is operating and will maintain temperature and relative humidity at occupancy levels during the remainder of the construction period.

B. Established Dimensions: Where kitchen casework is indicated to fit to other construction, establish dimensions for areas where casework is to fit. Coordinate construction to ensure that actual dimensions correspond to established dimensions. Provide fillers and scribes to allow for trimming and fitting.

C. Field Measurements: Where kitchen casework is indicated to fit to existing construction, verify dimensions of existing construction by field measurements before fabrication and indicate measurements on Shop Drawings. Provide fillers and scribes if necessary.

D. Field Measurements for Countertops: Verify dimensions of countertops by field measurements after base cabinets are installed but before countertop fabrication is complete. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1.7 COORDINATION

A. Coordinate layout and installation of blocking and reinforcement in partitions for support of kitchen casework.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   1. Cabinets:
   2. Plastic Laminate for Countertops:
      a. Formica Corp.
      b. Laminart.
      c. Nevamar Corp.
      d. Pioneer Plastics Corp.
      e. Westinghouse Electric Corp.; Specialty Products Div.
      f. Wilson: Ralph Wilson Plastics Co.
   3. Solid-Surfacing Material for Countertops:
      a. Avonite, Inc.
      b. DuPont Polymers.
      c. Formica Corp.
      d. Nevamar Corp.
      e. Swan Corporation (The).

f. Wilson: Ralph Wilson Plastics Co.

C. Available Products: Subject to compliance with requirements, cabinets that may be incorporated into the Work include, but are not limited to, the following:

D. Products: Subject to compliance with requirements, provide one of the following:
1. Breckenridge; American Woodmark Corp.
2. Rockingham; Merillat Industries, Inc.

E. Product: Subject to compliance with requirements, provide "Cherryvale" by Shrock Cabinet Co.

2.2 COLORS, TEXTURES, AND PATTERNS

A. Colors, Textures, and Patterns: Match Architect's samples.

B. Colors, Textures, and Patterns: As indicated by referencing manufacturer's designations.

C. Colors, Textures, and Patterns: As selected by Architect from manufacturer's full range for these characteristics.

2.3 CABINET MATERIALS

A. Exposed Materials: Comply with the following:
1. Exposed Wood Species: As follows. Do not use two adjacent exposed faces that are noticeably dissimilar in color, grain, figure, or natural character markings.
a. Red oak.
b. White oak.
c. Select white birch.
d. Select red birch.
e. Natural birch.
f. Select white ash.
g. Hard maple.
h. Cherry.
2. Solid Wood: Clear hardwood lumber of species indicated, free of defects, selected for compatible grain and color, and kiln dried to 7 percent moisture content.
3. Plywood: Hardwood plywood complying with HPVA HP-1 with face veneer of species indicated, selected for compatible color and grain with Grade A faces and Grade C backs of same species as faces.
a. Edge band exposed edges with minimum 1/8-inch- (3-mm-) thick, solid-wood edging of same species as face veneer.
4. Plastic Laminate: High-pressure decorative laminate complying with NEMA LD 3, Grade VGS.
a. Where edges of solid-color plastic-laminate sheets will be visible after fabrication, provide through-color plastic laminate.
5. PVC Edge Molding: Rigid PVC extrusions, through color with satin finish, 3 mm thick at doors and drawer fronts, and 1 mm thick elsewhere.
6. Vinyl-Faced Fiberboard: Medium-density fiberboard complying with ANSI A208.2, milled to required shapes, with a thermoformed vinyl overlay applied in a vacuum or membrane press.

B. Semiexposed Materials: Unless otherwise indicated, provide the following:
1. Solid Wood: Sound hardwood lumber, selected to eliminate appearance defects and kiln dried to 7 percent moisture content. Stained to be compatible with exposed surfaces.
2. Plywood: Hardwood plywood complying with HPVA HP-1 with Grade C faces stained to be compatible with exposed surfaces and Grade 3 backs of same species as faces.
3. Plastic Laminate: High-pressure decorative laminate complying with NEMA LD 3, Grade VGS.
4. Plastic Laminate: High-pressure decorative laminate complying with NEMA LD 3, Grade CLS.
5. Thermoset Decorative Panels: Medium-density particleboard complying with ANSI A208.1, Grade M-2; with surface of thermally fused, melamine-impregnated decorative paper complying with LMA SAT-1.
a. Provide thermoset decorative overlay on both sides of shelves, dividers, drawer bodies, and other components with two semiexposed surfaces.
b. Provide PVC or polyester edge banding complying with LMA EDG-1 on components with semiexposed edges.
6. Vinyl-Faced Particleboard: Medium-density particleboard complying with ANSI A208.1, Grade M-2 with an embossed, wood-grain-patterned vinyl film adhesively bonded to particleboard.
a. Provide vinyl film on both sides of shelves, dividers, drawer bodies, and other components with two semiexposed surfaces and on semiexposed edges.

C. Concealed Materials: Comply with the following:
   1. Solid Wood or Plywood: Any hardwood or softwood species, with no defects affecting strength or utility. Hardwood and softwood lumber kiln dried to 7 and 10 percent moisture content, respectively.
   2. Particleboard: ANSI A208.1, Grade M-2.
   3. Medium-Density Fiberboard: ANSI A208.2.
   4. Hardboard: AHA A135.4, Class 1 Tempered.

2.4 COUNTERTOP MATERIALS
A. Plastic Laminate: High-pressure decorative laminate complying with NEMA LD 3.
   1. Grade: HGS.
   2. Grade: HGP.
   3. Provide through-color plastic laminate.
   4. Grade for Backer Sheet: BKL.
B. Particleboard: ANSI A208.1, Grade M-2.
C. Plywood: Exterior softwood plywood complying with PS 1, Grade C-C Plugged, touch sanded.
D. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with material and performance requirements of ANSI Z124.3, Type 5 or Type 6, without a precoated finish.
E. Solid Wood Edges and Trim: Clear hardwood lumber of species indicated, free of defects, selected for compatible grain and color, and kiln dried to 7 percent moisture content.
   1. Wood Species: Red oak.
   2. Wood Species: White oak.
   3. Wood Species: Hard maple.
   4. Wood Species: Cherry.

2.5 CASEWORK HARDWARE
A. General: Manufacturer's standard units complying with BHMA A156.9, of type, material, size, and finish as selected from manufacturer's standard choices.
B. Hinges: Decorative full-surface hinges.
C. Hinges: Concealed butt hinges.
D. Hinges: Semiconcealed (wraparound) butt hinges for overlay doors.
E. Hinges: Pivot (knife) hinges.
F. Hinges: Concealed European-style hinges.
F. Drawer Guides: Epoxy-coated-metal, self-closing drawer guides; designed to prevent rebound when drawers are closed; with nylon-tired, ball-bearing rollers; and complying with BHMA A156.9, Type B05091.

2.6 CABINET CONSTRUCTION
A. Face Style: Flush overlay; door and drawer faces cover cabinet body members or face frames with only enough space between faces for operating clearance.
B. Face Style: Reveal overlay; door and drawer faces partially cover cabinet body or face frames.
C. Face Style: Lipped overlay; door and drawer faces are rabbeted and partially inset within cabinet body or face frame with the lip of the rabbet overlapping cabinet body members or face frames.
D. Face Style: Flush inset; door and drawer faces are set within cabinet body or face frame flush with cabinet face.
E. Face Frames: Frameless.
F. Face Frames: 3/4-by-1-5/8-inch (19-by-41-mm) solid wood.
G. Face Frames: 3/4-by-1-5/8-inch (19-by-41-mm) solid wood with glued mortise and tenon or doweled joints.
H. Face Frames: 5/8-inch- (16-mm-) thick particleboard with plastic laminate on exposed and semiexposed surfaces.
I. Face Frames: 1/2-inch- (12.7-mm-) thick, vinyl-faced fiberboard with vinyl overlay on exposed and semiexposed surfaces.
J. Door and Drawer Fronts: 1/2-inch- (12.7-mm-) thick, veneer-faced plywood.
K. Door and Drawer Fronts: Solid-wood stiles and rails, 5/8 inch (16 mm) thick, with 3/4-inch- (19-mm) thick, solid-wood center panels.
L. Door and Drawer Fronts: Solid-wood stiles and rails, 3/4 inch (19 mm) thick, with 1/4-inch- (6.4-mm) thick, veneer-faced plywood center panels.
M Door and Drawer Fronts: 1/2-inch- (12.7-mm-) thick particleboard with plastic-laminate faces, backs, and edges. Provide same grade, pattern, color, and texture of plastic laminate for backs and edges as for faces.

N. Door and Drawer Fronts: 1/2-inch- (12.7-mm-) thick particleboard with plastic-laminate faces and backs, and PVC edge banding. Provide same grade, pattern, color, and texture of plastic laminate for backs as for faces.
O. Door and Drawer Fronts: 1/2-inch- (12.7-mm-) thick particleboard with plastic-laminate faces, backs, and edges, except provide continuous solid-wood pulls on one edge. Provide same grade, pattern, color, and texture of plastic laminate for backs and edges as for faces.
P. Door and Drawer Fronts: 1/2-inch- (12.7-mm-) thick, vinyl-faced fiberboard with vinyl overlay on faces, backs, and edges.
Q. Exposed Cabinet Ends: Veneer-faced plywood.
R. Exposed Cabinet Ends: Plastic-laminate-faced particleboard.
S. Exposed Cabinet Ends: Vinyl-faced fiberboard.
T. Cabinet Ends: 5/8-inch- (16-mm-) thick particleboard or 1/2-inch- (12.7-mm-) thick plywood.
U. Cabinet Ends: 1/2-inch- (12.7-mm-) thick particleboard or 3/8-inch- (9.5-mm-) thick plywood.
V. Cabinet Tops and Bottoms: 5/8-inch- (16-mm-) thick particleboard or 1/2-inch- (12.7-mm-) thick plywood, fully supported by and secured in rabbets in end panels, front frame, and back rail.
W. Cabinet Tops and Bottoms: 1/2-inch- (12.7-mm-) thick particleboard or 3/8-inch- (9.5-mm-) thick plywood, fully supported by and secured in rabbets in end panels, front frame, and back rail.
X. Back, Top, and Bottom Rails: 3/4-by-2-1/2-inch (19-by-63-mm) solid wood, interlocking with end panels and rabbeted to receive top and bottom panels. Back rails secured under pressure with glue and with mechanical fasteners.
Y. Wall-Hung Unit Back Panels: 3/16-inch- (4.8-mm-) thick plywood fastened to rear edge of end panels and to top and bottom rails.
Z. Base Unit Back Panels: 3/16-inch- (4.8-mm-) thick plywood fastened to rear edge of end panels and to top and bottom rails.
AA. Base Unit Back Panels: 1/8-inch- (3.2-mm-) thick hardboard fastened to rear edge of end panels and to top and bottom rails.
BB. Front Frame Drawer Rails: 3/4-by-1-1/4-inch (19-by-32-mm) solid wood mortised and fastened into face frame.
CC. Drawers: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.
    1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners or with glued dovetail joints.
    2. Join subfronts, backs, and sides with glued dovetail joints.
    3. Subfronts, Backs, and Sides: 3/4-inch- (19-mm-) thick solid wood.
    4. Subfronts, Backs, and Sides: 1/2-inch- (12.7-mm-) thick solid wood.
    5. Subfronts, Backs, and Sides: 1/2-inch- (12.7-mm-) thick solid wood or 3/8-inch- (9.5-mm-) thick plywood.
    6. Subfronts, Backs, and Sides: 3/8-inch- (9.5-mm-) thick particleboard.
    7. Bottoms: 1/4-inch- (6.4-mm-) thick plywood.
    8. Bottoms: 3/16-inch- (4.8-mm-) thick plywood.
    9. Bottoms: 1/4-inch- (6.4-mm-) thick hardboard.
    10. Bottoms: 1/4-inch- (6.4-mm-) thick particleboard.
DD. Shelves: 3/4-inch- (19-mm-) thick particleboard or 5/8-inch- (16-mm-) thick plywood.
EE. Shelves: 5/8-inch- (16-mm-) thick particleboard or 1/2-inch- (12.7-mm-) thick plywood.
FF. Joinery: Rabbet backs flush into end panels and secure with concealed mechanical fasteners. Connect tops and bottoms of wall cabinets and bottoms and stretchers of base cabinets to ends and dividers with mechanical fasteners. Rabbet tops, bottoms, and backs into end panels.
GG. Factory Finishing: To greatest extent possible, finish casework at factory. Defer only final touchup until after installation.

2.7 PLASTIC-LAMINATE COUNTERTOPS

A. Configuration: Provide countertops with the following front, cove (intersection of top with backsplash), backsplash, and end-splash style:
    1. Front: No drip (raised marine edge with rolled front).
    2. Front: Rolled.
    3. Front: Bevel.
    4. Front: Self-edge.
    5. Front: Wood-trimmed edge as indicated.
    6. Cove: Cove molding (one-piece postformed laminate supported at junction of top and backsplash by wood cove molding).
    7. Cove: Applied (backsplash rests on top forming seam at inside corner).
    8. Backsplash: Curved or waterfall shape with scribe.

9. Backsplash: Square edge without scribe.
10. Backsplash: Sloped top edge without scribe.
11. Backsplash: Square edge with scribe.
12. End Splash: None.
13. End Splash: Square edge without scribe.
14. End Splash: Sloped top edge without scribe.
15. End Splash: Square edge with scribe.

B. Plastic-Laminate Substrate: Particleboard not less than 3/4 inch (19 mm) thick.
1. For countertops at sinks and lavatories, use phenolic-resin particleboard or exterior-grade plywood.
2. Build up countertop thickness to 1-1/2 inches (38 mm) at front, back, and ends with additional layers of particleboard laminated to top.

C. Backer Sheet: Provide plastic-laminate backer sheet on underside of countertop substrate.

D. Paper Backing: Provide paper backing on underside of countertop substrate.

2.8 SOLID-SURFACING-MATERIAL COUNTERTOPS

A. Configuration: Provide countertops with the following front and backsplash style:
1. Front: Straight, slightly eased at top.
2. Front: Bevel.
3. Front: 3/4-inch (19-mm) bullnose.
4. Front: Radius edge with apron, 2 inches (50 mm) high with 3/8-inch (9.5-mm) radius.
5. Front: 1-1/2-inch (38-mm) laminated bullnose.
6. Front: Wood-trimmed edge as indicated.
7. Backsplash: Straight, slightly eased at corner.
8. Backsplash: Bevel.
9. Backsplash: Radius edge with 3/8-inch (9.5-mm) radius.

B. Construction: 1/2-inch- (12.7-mm-) thick, solid-surfacing-material countertops and backsplashes.

C. Construction: 3/4-inch- (19-mm-) thick, solid-surfacing-material countertops and backsplashes.

D. Construction: 3/4-inch- (19-mm-) thick, solid-surfacing-material countertops and backsplashes with front edge of countertops built up with same material.

E. Construction: 1/4-inch- (6.4-mm-) thick, solid-surfacing material laminated to 3/4-inch- (19-mm-) thick particleboard for countertops with wood-trimmed edges and 3/4-inch- (19-mm-) thick, solid-surfacing-material backsplashes.

F. Construction: 3/4-inch- (19-mm-) thick, solid-surfacing-material countertops and backsplashes with wood-trimmed edges.

G. Fabrication: Fabricate tops in one piece with shop-applied backsplashes and edges, unless otherwise indicated. Comply with solid-surfacing-material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
1. Install integral sink bowls in countertops in the shop.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install casework with no variations in flushness of adjoining surfaces; use concealed shims. Where casework abuts other finished work, scribe and cut for accurate fit. Provide filler strips, scribe strips, and moldings in finish to match casework face.

B. Install casework without distortion so doors and drawers fit openings and are aligned. Complete installation of hardware and accessories as indicated.

C. Install casework and countertop level and plumb to a tolerance of 1/8 inch in 8 feet (3 mm in 2.4 m).

D. Fasten cabinets to adjacent units and to backing.
1. Fasten wall cabinets through back, near top and bottom, at ends and not less than 24 inches (600 mm) o.c. with No. 10 wafer-head screws sized for 1-inch (25-mm) penetration into wood framing, blocking, or hanging strips.
2. Fasten wall cabinets through back, near top and bottom, at ends and not less than 24 inches (600 mm) o.c., with toggle bolts through metal backing behind gypsum board.

E. Fasten plastic-laminate countertops by screwing through corner blocks of base units into underside of countertop. Form seams using splines to align adjacent surfaces, and secure with glue and concealed clamping devices designed for this purpose.

F. Fasten solid-surfacing-material countertops by screwing through corner blocks of base units into underside of countertop. Align adjacent surfaces, and form seams to comply with manufacturer's written instructions using adhesive in color to match countertop. Carefully dress joints smooth, remove surface scratches, and clean entire surface.

3.2 ADJUSTING AND CLEANING

A. Adjust casework and hardware so doors and drawers are centered in openings and operate smoothly without warp or bind. Lubricate operating hardware as recommended by manufacturer.

B. Clean casework on exposed and semi-exposed surfaces. Touch up factory-applied finishes to restore damaged or soiled areas.

END OF SECTION 12356

SECTION 124910

HORIZONTAL LOUVER BLINDS

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes the following types of venetian blinds and accessories:
   1. Miniblinds with aluminum louver slats, Cordless.

1.2 SUBMITTALS

A. Product Data: For each type of product indicated. Include styles, material descriptions, construction details, dimensions of individual components and profiles, features, finishes, and operating instructions.
B. Shop Drawings: Show location and extent of horizontal louver blinds. Include elevations, sections, details, and dimensions not shown in Product Data. Show installation details, mountings, attachments to other Work, operational clearances, and relationship to adjoining work.
C. Samples for Initial Selection: For each colored component of each type of horizontal louver blind indicated.
   1. Include similar Samples of accessories involving color selection.
D. Window Treatment Schedule: Include horizontal louver blinds in schedule using same room designations indicated on Drawings.
E. Product Certificates: For each type of horizontal louver blind product, signed by product manufacturer.
F. Product Test Reports: For each type of horizontal louver blind product.
G. Maintenance Data: For horizontal louver blinds to include in maintenance manuals. Include the following:
   1. Methods for maintaining horizontal louver blinds and finishes.
   2. Precautions about cleaning materials and methods that could be detrimental to finishes and performance.
   3. Operating hardware.

1.3 QUALITY ASSURANCE

A. Source Limitations: Obtain horizontal louver blinds through one source from a single manufacturer.
B. Fire-Test-Response Characteristics: Provide horizontal louver blinds with the fire-test-response characteristics indicated, as determined by testing identical products per test method indicated below by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:
   1. Flame-Resistance Ratings: Passes NFPA 701.
C. Corded Window Covering Product Standard: Provide horizontal louver blinds complying with WCMA A 100.1.
D. Year 2000 Compliant: Computer hardware and software shall be capable of accurately processing, providing, and receiving date data from, into, and between the twentieth and twenty-first centuries, including leap year calculations.
E. Mockups: Build mockups to verify selections made under sample Submittals and to demonstrate aesthetic effects and qualities of materials and execution.
   1. Build mockups in the location and of the size indicated or, if not indicated, as directed by Architect.
   2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Deliver blinds in factory packages, marked with manufacturer and product name, and location of installation using same room designations indicated on Drawings and in a window treatment schedule.

1.5 PROJECT CONDITIONS

A. Environmental Limitations: Do not install horizontal louver blinds until construction and wet and dirty finish work in spaces, including painting, is complete and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

B. Field Measurements: Where horizontal louver blinds are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operable glazed units' operation hardware throughout the entire operating range. Notify Architect of discrepancies. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Horizontal Louver Blinds, Aluminum Louver Slats, Cordless:
   a. Comfortex Window Fashions.
   b. Hunter Douglas Window Fashions.
   c. Levolor Contract; a Newell Company; Levolor.
   d. Springs Window Fashions Division, Inc.; Bali.
   e. Springs Window Fashions Division, Inc.; Graber.
   f. Verosol USA, Inc.

2.2 HORIZONTAL LOUVER BLINDS, ALUMINUM LOUVER SLATS

A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:

B. Louver Slats: Aluminum, alloy and temper recommended by producer for type of use and finish indicated; with crowned profile and radiused corners.

1. Verify availability of louver widths with manufacturers. Retain one of four nominal slat widths below.
2. Nominal Slat Width: 1 inch (25 mm) for miniblinds.
3. Nominal Slat Thickness: Not less than 0.006 inch (0.15 mm).
4. Slat Finish: One color as indicated.

C. Headrail/Valance: Decorative, integrated headrail/valance not requiring a separate valance or end brackets for finished appearance; formed steel or extruded aluminum; long edges returned or rolled; fully enclosing operating mechanisms.

D. Bottom Rail: Formed-steel or extruded-aluminum tube, sealed with plastic or metal capped ends with enclosed and protected ladders and tapes to prevent their contact with sill.

E. Tilt Control: Consisting of enclosed worm gear mechanism and linkage rod, for the following operation:

F. Lift Operation**: Manual, Cordless,** lift mechanism to hold blind at any position in ascending or descending travel.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, and other conditions affecting performance. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 HORIZONTAL LOUVER BLIND INSTALLATION

A. Install blinds level and plumb and aligned with adjacent units according to manufacturer's written instructions, and located so exterior louver edges in any position are not closer than 1 inch to interior face of glass. Install intermediate support as required to prevent deflection in headrail. Allow clearances between adjacent blinds and for operating glazed opening's operation hardware, if any.

B. Flush Mounted: Install blinds with louver edges flush with finish face of opening if slats are tilted open.

C. Jamb Mounted: Install headrail flush with face of opening jamb and head.

D. Head Mounted: Install headrail on face of opening head.

E. Recessed: Install headrail concealed within blind pocket.

F. Connections: Connect motorized operators to building electrical system.

3.3 ADJUSTING

A. Adjust horizontal louver blinds to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

A. Clean blind surfaces after installation, according to manufacturer's written instructions.

B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and installer, that ensure that horizontal louver blinds are without damage or deterioration at time of Substantial Completion.

C. Replace damaged blinds that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

END OF SECTION 124910

SECTION 210500

COMMON WORK RESULTS FOR FIRE SUPPRESSION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Pipe, fittings, valves, and connections for combination sprinkler and standpipe systems.

1.2 RELATED REQUIREMENTS

A. Section 078400 - Firestopping.

B. Section 211200 - Fire-Suppression Standpipes: Standpipe design.

C. Section 211300 - Fire-Suppression Sprinkler Systems: Sprinkler systems design.

1.3 REFERENCE STANDARDS

A. ASME A112.18.1 - Plumbing Supply Fittings; 2012.

B. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Qualifications; 2015.

C. ASME B16.1 - Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250; 2010.

D. ASME B16.3 - Malleable Iron Threaded Fittings: Classes 150 and 300; 2011.

E. ASME B16.4 - Gray Iron Threaded Fittings: Classes 125 and 250; 2011.

F. ASME B16.9 - Factory-Made Wrought Buttwelding Fittings; 2012.

G. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.

H. ASTM A269/A269M - Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service; 2015.

I. ASTM A536 - Standard Specification for Ductile Iron Castings; 1984 (Reapproved 2014).

J. ASTM A795/A795M - Standard Specification for Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use; 2013.

K. ASTM C592 - Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type); 2013.

L. ASTM E814 - Standard Test Method for Fire Tests of Through-Penetration Fire Stops; 2013a.

M. ASTM F438 - Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40; 2015.

N. ASTM F439 - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80; 2013.

O. ASTM F442/F442M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR); 2013.

P. ASTM F493 - Standard Specification for Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings; 2014.

Q. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2015.

R. AWWA C105/A21.5 - Polyethylene Encasement for Ductile-Iron Pipe Systems; 2010.

S. AWWA C110/A21.10 - Ductile-Iron and Gray-Iron Fittings; 2012.

T. AWWA C111/A21.11 - Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings; 2012.

U. AWWA C151/A21.51 - Ductile-Iron Pipe, Centrifugally Cast; 2009.

V. AWWA C606 - Grooved and Shouldered Joints; 2011.

W. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

X. NFPA 14 - Standard for the Installation of Standpipe and Hose Systems; 2013.

Y. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

Z. UL 262 - Gate Valves for Fire-Protection Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

AA. UL 312 - Check Valves for Fire-Protection Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturers catalogue information. Indicate valve data and ratings.

C. Shop Drawings: Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation, layout, weights, mounting and support details, and piping connections.

D. Project Record Documents: Record actual locations of components and tag numbering.

E. Operation and Maintenance Data: Include installation instructions and spare parts lists.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.

B. Valves: Bear UL label or marking. Provide manufacturer's name and pressure rating marked on valve body.

C. Products Requiring Electrical Connection: Listed and classified as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store valves in shipping containers, with labeling in place.

B. Provide temporary protective coating on cast iron and steel valves.

C. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

PART 2 PRODUCTS

2.1 FIRE PROTECTION SYSTEMS

A. Sprinkler Systems: Conform work to NFPA 13.

B. Standpipe and Hose Systems: Conform to NFPA 14.

C. Welding Materials and Procedures: Conform to ASME Code.

2.2 BURIED PIPING

A. Steel Pipe: ASTM A53/A53M Schedule 40 or ASTM A795 Standard Weight, black, with AWWA C105 polyethylene jacket, or double layer, half-lapped polyethylene tape.
   1. Steel Fittings: ASME B16.9, wrought steel, buttwelded; with double layer, half-lapped polyethylene tape.
   2. Cast Iron Fittings: ASME B16.1, flanges and flanged fittings.
   3. Joints: Welded in accordance with AWS D1.1.

B. Cast Iron Pipe: AWWA C151/A21.51.
   1. Fittings: AWWA C110, standard thickness.
   2. Joints: AWWA C111, rubber gasket.
   3. Mechanical Couplings: Shaped composition sealing gasket, steel bolts, nuts, and washers.

2.3 ABOVE GROUND PIPING

A. Steel Pipe: ASTM A795 Schedule 10 or ASTM A53 Schedule 40, black.
   1. Steel Fittings: ASME B16.9, wrought steel, buttwelded.
   2. Cast Iron Fittings: ASME B16.1, flanges and flanged fittings and ASME B16.4, threaded fittings.
   3. Malleable Iron Fittings: ASME B16.3, threaded fittings.

4. Mechanical Grooved Couplings: Malleable iron housing clamps to engage and lock, "C" shaped elastomeric sealing gasket, steel bolts, nuts, and washers; galvanized for galvanized pipe.
5. Mechanical Formed Fittings: Carbon steel housing with integral pipe stop and O-ring pocked and O-ring, uniformly compressed into permanent mechanical engagement onto pipe.

B. CPVC Pipe: ASTM F442/F442M, SDR 13.5.
1. Fittings: ASTM F438 Schedule 40, or ASTM F439 schedule 80, CPVC.
2. Joints: Solvent welded, using ASTM F493 cement.

2.4 PIPE SLEEVES

A. Vertical Piping:
1. Sleeve Length: 1 inch above finished floor.
2. Provide sealant for watertight joint.

B. Pipe Passing Through Below Grade Exterior Walls:
1. Zinc coated or cast iron pipe.
2. Provide watertight space with link rubber or modular seal between sleeve and pipe on both pipe ends.

C. Not required for wall hydrants for fire department connections or in drywall construction.

D. Clearances:
1. Wall, Floor, Floor, Partitions, and Beam Flanges: 1 inch greater than external; pipe diameter.
2. All Rated Openings: Caulked tight with fire stopping material conforming to ASTM E814 in accordance with Firestopping section to prevent the spread of fire, smoke, and gases.

2.5 MANUFACTURED SLEEVE-SEAL SYSTEMS

A. Modular/Mechanical Seal:
1. Synthetic rubber interlocking links continuously fill annular space between pipe and wall/casing opening.
2. Provide watertight seal between pipe and wall/casing opening.
3. Elastomer element size and material in accordance with manufacturer's recommendations.
4. Glass reinforced plastic pressure end plates.

2.6 ESCUTCHEONS

A. Material:
1. Fabricate from nonferrous metal.
2. Chrome-plated except when 300 series, ASTM A269/A269M stainless steel is provided.
3. Metals and Finish: Comply with ASME A112.18.

B. Construction:
1. One-piece for mounting on chrome-plated tubing or pipe and one-piece or split-pattern type elsewhere.
2. Internal spring tension devices or setscrews to maintain a fixed position against a surface.

2.7 PIPE HANGERS AND SUPPORTS

A. Hangers for Pipe Sizes 1/2 to 1-1/2 inch: Malleable iron, adjustable swivel, split ring.

B. Hangers for Pipe Sizes 2 inches and Over: Carbon steel, adjustable, clevis.

C. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.

D. Wall Support for Pipe Sizes to 3 inches: Cast iron hook.

E. Wall Support for Pipe Sizes 4 inches and Over: Welded steel bracket and wrought steel clamp.

F. Vertical Support: Steel riser clamp.

G. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

2.8 MECHANICAL COUPLINGS

A. Rigid Mechanical Couplings for Grooved Joints:
   1. Dimensions and Testing: Comply with AWWA C606.
   2. Minimum Working Pressure: 300 psig.
   3. Housing Material: Fabricate of ductile iron conforming to ASTM A536.
   4. Housing Coating: Factory applied orange enamel.
   5. Gasket Material: EPDM suitable for operating temperature range from minus 30 degrees F to 230 degrees F.
   6. Bolts and Nuts: Hot dipped galvanized or zinc electroplated steel

2.9 GATE VALVES

A. Up to and including 2 inches:
   1. Bronze body, bronze trim, rising stem, handwheel, solid wedge or disc, threaded ends.

B. Over 2 inches:
   1. Iron body, bronze trim, rising stem pre-grooved for mounting tamper switch, handwheel, OS&Y, solid rubber covered bronze or cast iron wedge, flanged ends.

C. Over 4 inches:
   1. Iron body, bronze trim, non-rising stem with bolted bonnet, solid bronze wedge, flanged ends, iron body indicator post assembly.

2.10 GLOBE OR ANGLE VALVES

A. Up to and including 2 inches:
   1. Bronze body, bronze trim, rising stem and handwheel, inside screw, renewable rubber disc, threaded ends, with backseating capacity repackable under pressure.

B. Over 2 inches:
   1. Iron body, bronze trim, rising stem, handwheel, OS&Y, plug-type disc, flanged ends, renewable seat and disc.

2.11 BUTTERFLY VALVES

A. Bronze Body:
   1. Stainless steel disc, resilient replaceable seat, threaded or grooved ends, extended neck, handwheel and gear drive and integral indicating device, and built-in tamper proof switch rated 10 amp at 115 volt AC.

B. Cast or Ductile Iron Body
   1. Cast or ductile iron, chrome or nickel plated ductile iron or aluminum bronze disc, resilient replaceable EPDM seat, wafer, lug, or grooved ends, extended neck, handwheel and gear drive and integral indicating device, and internal tamper switch rated 10 amp at 115 volt AC.

2.12 CHECK VALVES

A. Up to and including 2 inches:
   1. Bronze body and swing disc, rubber seat, threaded ends.

B. Over 2 inches:
   1. Iron body, bronze trim, swing check with rubber disc, renewable disc and seat, flanged ends with automatic ball check.

C. 4 inches and Over:
   1. Iron body, bronze disc, stainless steel spring, resilient seal, threaded, wafer, or flanged ends.

2.13 DRAIN VALVES

A. Compression Stop:
   1. Bronze with hose thread nipple and cap.

B. Ball Valve:
   1. Brass with cap and chain, 3/4 inch hose thread.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs.

B. Remove scale and foreign material, from inside and outside, before assembly.

C. Prepare piping connections to equipment with flanges or unions.

3.2 INSTALLATION

A. Install sprinkler system and service main piping, hangers, and supports in accordance with NFPA 13.

B. The entire building shall be provided with a fire protection sprinkler system and Class I manual wet standpipe system.

C. Prepare design documents including shop drawings and hydraulic calculations in accordance with NFPA 13 and 14 and submit to Authority Having Jurisdiction for approval prior to installation. Design shall be performed by a licensed Professional Engineer.

D. Install standpipe piping, hangers, and supports in accordance with NFPA 14.

E. Route piping in orderly manner, plumb and parallel to building structure. Maintain gradient.

F. Install piping to conserve building space, to not interfere with use of space and other work.

G. Piping shall be concealed where routed in finished spaces.

H. Group piping whenever practical at common elevations.

I. Sleeve pipes passing through partitions, walls, and floors.

J. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

K. Inserts:
   1. Provide inserts for placement in concrete formwork.
   2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
   3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
   4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.

L. Pipe Hangers and Supports:
   1. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
   2. Place hangers within 12 inches of each horizontal elbow.
   3. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
   4. Support vertical piping at every other floor. Support riser piping independently of connected horizontal piping.
   5. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
   6. Support piping from top chord of bar joists. Support from deck or bottom chord is not acceptable.

M. Slope piping and arrange systems to drain at low points. Use eccentric reducers to maintain top of pipe level.

N. Prepare pipe, fittings, supports, and accessories for finish painting. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.

O. Do not penetrate building structural members unless indicated.

P. Provide sleeves when penetrating footings, floors, and walls. Seal pipe and sleeve penetrations to achieve fire resistance equivalent to fire separation required.
   1. Underground Piping: Caulk pipe sleeve watertight with lead and oakum or mechanically expandable chloroprene inserts with bitumen sealed metal components.

2. Aboveground Piping:
    a. Pack solid using mineral fiber conforming to ASTM C592.
    b. Fill space with an elastomer caulk to a depth of 0.50 inch where penetrations occur between conditioned and unconditioned spaces.
3. All Rated Openings: Caulk tight with fire stopping material conforming to ASTM E814 in accordance with Firestopping section to prevent the spread of fire, smoke, and gases.
4. Caulk exterior wall sleeves watertight with lead and oakum or mechanically expandable chloroprene inserts with mastic-sealed components.

Q. Manufactured Sleeve-Seal Systems:
1. Install manufactured sleeve-seal systems in sleeves located in grade slabs and exterior concrete walls at piping entrances into building.
2. Provide sealing elements of the size, quantity, and type required for the piping and sleeve inner diameter or penetration diameter.
3. Locate piping in center of sleeve or penetration.
4. Install field assembled sleeve-seal system components in annular space between sleeve and piping.
5. Tighten bolting for a water-tight seal.
6. Install in accordance with manufacturer's recommendations.

R. Escutcheons:
1. Install and firmly attach escutcheons at piping penetrations into finished spaces.
2. Provide escutcheons on both sides of partitions separating finished areas through which piping passes.
3. Use chrome plated escutcheons in occupied spaces and to conceal openings in construction.

S. When installing more than one piping system material, ensure system components are compatible and joined to ensure the integrity of the system. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

T. Install valves with stems upright or horizontal, not inverted. Remove protective coatings prior to installation.

U. Provide gate valves for shut-off or isolating service.

V. Provide drain valves at main shut-off valves, low points of piping and apparatus.

END OF SECTION 210500

SECTION 210523

GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION PIPING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Two-piece ball valves with indicators.

B. Bronze butterfly valves with indicators.

C. Iron butterfly valves with indicators.

D. Check valves.

E. Bronze OS&Y gate valves.

F. Iron OS&Y gate valves.

G. NRS gate valves.

H. Indicator posts.

I. Trim and drain valves.

1.2 RELATED REQUIREMENTS

A. Section 210500 - Common Work Results for Fire Suppression: Pipe and fittings.

B. Section 210553 - Identification for Fire Suppression Piping and Equipment.

C. Section 211200 - Fire-Suppression Standpipes.

D. Section 211300 - Fire Suppression Sprinklers.

E. Section 283100 - Fire Detection and Alarm.

1.3 ABBREVIATIONS AND ACRONYMS

A. EPDM: Ethylene-propylene diene monomer.

B. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.

C. NRS: Non-rising stem.

D. OS&Y: Outside screw and yoke.

E. PTFE: Polytetrafluoroethylene.

F. SBR: Styrene-butadiene rubber.

1.4 REFERENCE STANDARDS

A. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Qualifications; 2015.

B. FM 1140 - Approval Standard for Quick Opening Valves 1/4 Inch through 2 Inch Nominal Size; 1998.

C. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

D. UL 258 - Shutoff Valves for Trim and Drain Purposes for Fire Protection Service; Current Edition, Including All Revisions.

1.5 SUBMITTALS

A. Product Data: Provide data on valves including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.

B. Warranty: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

C. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, maintenance and repair data, and parts listings.

1.6 QUALITY ASSURANCE

A. Manufacturer:

1. Obtain valves for each valve type from single manufacturer.
2. Company must specialize in manufacturing products specified in this section, with not less than three years of documented experience.

B. Where listed products are specified, provide products listed, classified, and labeled by Underwriters Laboratories Inc. (UL), FM Global, or testing firm acceptable to authorities having jurisdiction as suitable for the purpose indicated.

C. Welding Materials and Procedures: Conform to ASME BPVC-IX.

D. Installer and Maintenance Contractor Qualifications:
1. Company specializing in performing the work of this section with minimum five years documented experience.
2. Trained and approved by manufacturer to design, install, test and maintain the equipment specified herein.
3. Complies with manufacturer's certification requirements.
4. Complies with manufacturer's insurance requirements.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:
1. Protect internal parts against rust and corrosion.
2. Set valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:
1. Maintain valve end protection and protect flanges and specialties from dirt.
a. Provide temporary inlet and outlet caps.
b. Maintain caps in place until installation.
2. Store valves in shipping containers and maintain in place until installation.
a. Store valves indoors and maintain at higher than ambient dew point temperature.
b. If outdoor storage is unavoidable, store valves off the ground in watertight enclosures.

C. Use the following precautions for handling:
1. Do not use operating handles or stems as lifting or rigging points.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

A. Comply with NFPA 13 and NFPA 14 for valves.

B. Valve Pressure Ratings: Not less than minimum pressure rating indicated or higher as required.

C. Valve Sizes: Same as upstream piping unless otherwise indicated.

D. Valve Actuator Types:
1. Worm-gear actuator with handwheel for quarter-turn valves, except trim and drain valves.
2. Handwheel: For other than quarter-turn trim and drain valves.
3. Hand-lever: For quarter-turn trim and drain valves 2 NPS and smaller.

2.2 TWO-PIECE BALL VALVES WITH INDICATORS

A. Description:
1. Minimum Pressure Rating: 175 psig.
2. Body Design: Two piece.
3. Body Material: Forged brass or bronze.
4. Port Size: Full or standard.
5. Seat: PTFE.
6. Stem: Bronze or stainless steel.
7. Ball: Chrome-plated brass.
8. Actuator: Worm gear or traveling nut.
9. Supervisory Switch: Internal or external.
10. End Connections: Threaded or grooved.

2.3 BRONZE BUTTERFLY VALVES WITH INDICATORS

A. Minimum Pressure Rating: 175 psig.

B. Body Material: Bronze.

C. Seat: EPDM.

D. Stem: Bronze or stainless steel.

E. Disc: Bronze with EPDM coating.

F. Actuator: Worm gear or traveling nut.

G. Supervisory Switch: Internal or external.

2.4 IRON BUTTERFLY VALVES WITH INDICATORS

A. Minimum Pressure Rating: 175 psig.

B. Body Material: Cast or ductile iron with nylon, EPDM, epoxy, or polyamide coating.

C. Seat: EPDM.

D. Stem: Stainless steel.

E. Disc: Ductile iron, nickel plated.

F. Actuator: Worm gear or traveling nut.

G. Supervisory Switch: Internal or external.

H. Body Design: Grooved-end connections.

2.5 CHECK VALVES

A. Minimum Pressure Rating: 175 psig.

B. Type: Center guided check valve.

C. Body Material: Cast iron, ductile iron.

D. Center guided check with elastomeric seal.

E. Hinge Spring: Stainless steel.

F. End Connections: Flanged, grooved, or threaded.

2.6 BRONZE OS&Y GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Bronze or brass.

C. Wedge: One-piece bronze or brass.

D. Wedge Seat: Bronze.

E. Stem: Bronze or brass.

F. Packing: Non-asbestos PTFE.

G. Supervisory Switch: External.

H. End Connections: Threaded.

2.7 IRON OS&Y GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Cast or ductile iron.

C. Wedge: Cast or ductile iron, or bronze with elastomeric coating.

D. Wedge Seat: Cast or ductile iron, or bronze with elastomeric coating.

E. Stem: Brass or bronze.

F. Packing: Non-asbestos PTFE.

G. Supervisory Switch: External.

H. End Connections: Flanged.

2.8 NRS GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Cast or ductile iron.

C. Wedge: Cast or ductile iron with elastomeric coating.

D. Stem: Brass or bronze.

E. Packing: Non-asbestos PTFE.

F. Supervisory Switch: External.

G. End Connections: Flanged.

2.9 INDICATOR POSTS

A. Type: Underground.

B. Base Barrel Material: Cast or ductile iron.

C. Cap: Cast or ductile iron.

D. Operation: Wrench.

2.10 TRIM AND DRAIN VALVES

A. Ball Valves:
   1. Description:
      a. UL 258 or FM 1140 listed.
      b. Pressure Rating: 175 psig.
      c. Body Design: Two piece.
      d. Body Material: Forged brass or bronze.
      e. Port Size: Full or standard.
      f. Seat: PTFE.
      g. Stem: Bronze or stainless steel.
      h. Ball: Chrome-plated brass.
      i. Actuator: Hand-lever.
      j. End Connections: Threaded or grooved.

B. Angle Valves:
   1. Description:
      a. UL 258 or FM 1140 listed.
      b. Pressure Rating: 175 psig.
      c. Body Material: Brass or bronze.
      d. Ends: Threaded.
      e. Stem: Bronze.
      f. Disc: Bronze.
      g. Packing: Asbestos free.
      h. Handwheel: Malleable iron, bronze, or aluminum.

C. Globe Valves:
   1. Description:
      a. UL 258 or FM 1140 listed.
      b. Pressure Rating: 175 psig.
      c. Body Material: Bronze with integral seat and screw-in bonnet.
      d. Ends: Threaded.
      e. Stem: Bronze.
      f. Disc Holder and Nut: Bronze.

g. Disc Seat: Nitrile.
h. Packing: Asbestos free.
i. Handwheel: Malleable iron, bronze, or aluminum.

PART 3 EXECUTION

3.1 EXAMINATION

A. Confirm valve interior to be free of foreign matter and corrosion.

B. Remove packing materials.

C. Examine guides and seats by operating valves from the fully open position to the fully closed position.

D. Examine valve threads and mating pipe for form and cleanliness.

3.2 INSTALLATION

A. Comply with specific valve installation requirements and application in the following Sections:

B. Install listed fire protection shutoff valves supervised-open, located to control sources of water supply except from fire department connections.
   1. Install permanent identification signs indicating portion of system controlled by each valve.

C. Install check valve in water supply connections and backflow preventer at potable water supply connections.

D. Valves in horizontal piping installed with stem at or above the pipe center.

E. Position valves to allow full stem movement.

F. Install valve tags. Comply with Section 210553 requirements for valve tags, schedules, and signs on surfaces concealing valves; and the appropriate NFPA standard applying to the piping system in which valves are installed.

END OF SECTION 210523

SECTION 210553

IDENTIFICATION FOR FIRE SUPPRESSION PIPING AND EQUIPMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Nameplates.

B. Tags.

C. Stencils.

D. Pipe Markers.

1.2 REFERENCE STANDARDS

1.3 SUBMITTALS

A. List: Submit list of wording, symbols, letter size, and color coding for mechanical identification.

B. Chart and Schedule: Submit valve chart and schedule, including valve tag number, location, function, and valve manufacturer's name and model number.

C. Product Data: Provide manufacturers catalog literature for each product required.

PART 2 PRODUCTS

2.1 NAMEPLATES

A. Description: Laminated three-layer plastic with engraved letters.

2.2 TAGS

A. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inch diameter.

B. Metal Tags: Brass with stamped letters; tag size minimum 1-1/2 inch diameter with smooth edges.

C. Valve Tag Chart: Typewritten letter size list in anodized aluminum frame.

2.3 STENCILS

A. Stencils: With clean cut symbols and letters of following size:

1. 3/4 to 1-1/4 inch Outside Diameter of Insulation or Pipe: 8 inch long color field, 1/2 inch high letters.
2. 1-1/2 to 2 inch Outside Diameter of Insulation or Pipe: 8 inch long color field, 3/4 inch high letters.
3. 2-1/2 to 6 inch Outside Diameter of Insulation or Pipe: 12 inch long color field, 1-1/4 inch high letters.
4. Equipment: 2-1/2 inch high letters.

2.4 PIPE MARKERS

A. Plastic Pipe Markers: Factory fabricated, flexible, semi- rigid plastic, preformed to fit around pipe or pipe covering; minimum information indicating flow direction arrow and identification of fluid being conveyed.

B. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

C. Underground Plastic Pipe Markers: Bright colored continuously printed plastic ribbon tape, minimum 6 inches wide by 4 mil thick, manufactured for direct burial service.

2.5 CEILING TACKS

A. Description: Steel with 3/4 inch diameter color coded head.

PART 3 EXECUTION

3.1 PREPARATION

A. Degrease and clean surfaces to receive adhesive for identification materials.

3.2 INSTALLATION

A. Install nameplates with corrosive-resistant mechanical fasteners, or adhesive. Apply with sufficient adhesive to ensure permanent adhesion and seal with clear lacquer.

B. Install tags with corrosion resistant chain.

C. Install plastic pipe markers in accordance with manufacturer's instructions.

D. Install plastic tape pipe markers complete around pipe in accordance with manufacturer's instructions.

E. Install underground plastic pipe markers 6 to 8 inches below finished grade, directly above buried pipe.

F. Use tags on piping 3/4 inch diameter and smaller.

G. Locate ceiling tacks to locate valves above T-bar type panel ceilings. Locate in corner of panel closest to equipment.

END OF SECTION 210553

SECTION 211300

FIRE SUPPRESSION SPRINKLERS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Wet-pipe sprinkler system.

B. System design, installation, and certification.

C. Fire department connections.

1.2 RELATED REQUIREMENTS

A. Section 210500 - Common Work Results for Fire Suppression: Pipe, fittings, and valves.

B. Section 220553 - Identification for Plumbing Piping and Equipment.

1.3 REFERENCE STANDARDS

A. FM P7825 - Approval Guide; Factory Mutual Research Corporation; current edition.

B. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2012.

C. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2012.

D. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2013.

E. ICC-ES AC308 - Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements; 2013.

F. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.

C. Shop Drawings:

1. Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation. Additionally, indicate general routing of piping for review by Architect.
2. Indicate hydraulic calculations, detailed pipe layout, hangers and supports, sprinklers, components and accessories. Indicate system controls.
3. Submit shop drawings, product data, and hydraulic calculations to authority having jurisdiction for approval. Drawings and calculations shall be stamped by a licenced professional engineer.
4. Installation shall be fully coordinated with structure and all other trades. Coordination shall be performed with installed conditions, not just the construction drawings. Rework of sprinkler piping due to conflicts with field conditions shall be performed without cost to the Owner or Engineer.

D. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.

E. Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.

1.5 QUALITY ASSURANCE

A. Maintain one copy of referenced design and installation standard on site.

B. Conform to UL requirements.

C. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed by the State.

D. Equipment and Components: Provide products that bear UL label or marking.

E. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

1.7 EXTRA MATERIALS

A. Provide extra sprinklers of type and size matching those installed, in quantity required by referenced NFPA design and installation standard.

B. Provide suitable wrenches for each sprinkler type.

C. Provide metal storage cabinet located adjacent to alarm valve.

PART 2 PRODUCTS

2.1 SPRINKLER SYSTEM

A. Sprinkler System: Provide coverage for entire building.

B. Occupancy: Comply with NFPA 13.

C. Water Supply: Determine volume and pressure from water flow test data.

D. Interface system with building fire and smoke alarm system.

E. Provide fire department connections at locations coordinated with Fire Department.

F. Storage Cabinet for Spare Sprinklers and Tools: Steel, located adjacent to alarm valve.

G. Pipe Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
5. Concrete Adhesive Type Anchors: Complying with ICC-ES AC308.
6. Other Types: As required.

2.2 SPRINKLERS

A. Suspended Ceiling Type: Semi-recessed or concealed pendant type with matching push on escutcheon or cover plate.
1. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

B. Exposed Area Type: Standard upright type with guard.
1. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

C. Sidewall Type: Semi-recessed horizontal sidewall type with matching push on escutcheon plate .
1. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

D. Guards: Finish to match sprinkler finish.
1. Provide guards at all heads in basement, mechanical rooms, and storage rooms.
2. Provide guards at all heads installed below 8' AFF.

E. Finish:
1. Heads and escutcheons in historic areas, rooms 101, 102, 103, 104, 106, and 107 shall have brass finish.
2. Heads and escutcheons in all other areas shall have black finish.

2.3 PIPING SPECIALTIES

A. Dry Pipe Sprinkler Alarm Valve: Check type valve with divided seat ring, rubber faced clapper to automatically actuate water motor alarm, accelerator, and with the following additional capabilities and features:
1. Activate electric alarm.

2. Test and drain valve.
3. Externally resettable.
4. Replaceable internal components without removing valve from installed position.

B. Wet Pipe Sprinkler Alarm Valve: Check type valve with divided seat ring, rubber faced clapper to automatically actuate water motor alarm and electric alarm, with pressure retard chamber and variable pressure trim; with test and drain valve.

C. Backflow Preventer: Double check valve assembly backflow preventer with drain and OS & Y gate valve on each end. Coordinate requirements with Authority Having Jurisdiction.

D. Test Connections:
1. Inspector's Test Connection for Preaction Systems:
a. Provide test connections approximately 6 ft above floor for each or portion of each sprinkler system equipped with an alarm device, located at the most remote part of each system.
b. Route test connection to an open-site drain location, excluding janitor sinks, accepting full flow without negative consequences.
c. Supply discharge orifice with same size as corresponding sprinkler orifice.
2. Backflow Preventer Test Connection:
a. Provide downstream of the backflow prevention assembly, listed hose valves with 2.5 inch National Standard male hose threads with cap and chain.

E. Electric Alarm: Electrically operated chrome plated gong with pressure alarm switch.

F. Water Flow Switch: Vane type switch for mounting horizontal or vertical, with two contacts; rated 10 amp at 125 volt AC and 2.5 amp at 24 volt DC.

G. Fire Department Connections:
1. Type: Flush mounted wall type with brass finish.
2. Outlets: Two way with thread size to suit fire department hardware; threaded dust cap and chain of matching material and finish.
3. Drain: 3/4 inch automatic drip, outside.
4. Label: "Auto. Sprinkler Standpipe".

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with referenced NFPA design and installation standard.

B. Install equipment in accordance with manufacturer's instructions.

C. Install buried shut-off valves in valve box. Provide post indicator.

D. Provide approved backflow preventer assembly at sprinkler system water source connection.

E. Locate fire department connection with sufficient clearance from walls, obstructions, or adjacent siamese connectors to allow full swing of fire department wrench handle. Coordinate with Authority Having Jurisdiction.

F. Place pipe runs to minimize obstruction to other work.

G. Place piping in concealed spaces above finished ceilings.

H. Center sprinklers in two directions in ceiling tile and provide piping offsets as required.

I. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.

J. Flush entire piping system of foreign matter.

K. Install guards on sprinklers where subject to damage..

L. Hydrostatically test entire system.

M. Required tests must be witnessed by authority having jurisdiction.

N. Provide concealed or sidewall heads in lobby. Other public areas must have concealed or recessed heads. Exposed ceiling or sidewall heads may be used in apartments.

O. Piping serving historic lobby shall be concealed as much as possible. Route piping between sleepers at floor above if required to conceal piping. Coordinate final routing with Architect prior to installation.

P. Areas subject to freezing shall be provided with dry type heads.

3.2 INTERFACE WITH OTHER PRODUCTS

A. Ensure required devices are installed and connected as required to fire alarm system.

END OF SECTION 211300

SECTION 213000

FIRE PUMPS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Fire pump package, including electric motor drive, controller, and accessories.

B. Electric jockey pump.

C. System maintenance.

1.2 RELATED REQUIREMENTS

A. Section 210500 - Common Work Results for Fire Suppression: Fire protection piping.

B. Section 283100 - Fire Detection and Alarm.

1.3 REFERENCE STANDARDS

A. FM (AG) - FM Approval Guide; Factory Mutual Research Corporation; current edition.

B. NEMA MG 1 - Motors and Generators; 2014.

C. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

D. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

E. NFPA 20 - Standard for the Installation of Stationary Pumps for Fire Protection; 2016.

F. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

G. UL 448 - Centrifugal Stationary Pumps for Fire-Protection Service; Current Edition, Including All Revisions.

H. UL 1478 - Fire Pump Relief Valves; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. See Administrative for submittal procedures.

B. Product Data: Provide manufacturers literature including general assembly, pump curves showing performance characteristics with pump and system, operating point indicated, NPSH curve, controls, wiring diagrams, and service connections.

C. Shop Drawings: Indicate layout, general assembly, components, dimensions, weights, clearances, and methods of assembly.

D. Certificates: Certify that fire pumps meet or exceed requirements at operating conditions and that installation complies with regulatory requirements.

E. Test Reports: Indicate results of hydrostatic test and field acceptance tests.

F. Manufacturer's Instructions: Indicate support details, connection requirements, for fire pump system.

G. Project Record Documents: Record actual locations of components and accessories.

H. Operation Data: Include manufacturers instructions, start-up data, trouble-shooting check lists, for pumps, drivers, and controllers.

I. Maintenance Data: Include manufacturers literature, cleaning procedures, replacement parts lists, and repair data for pumps, drivers and controllers.

J. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. Extra Pump Gaskets/Screens/Seals: One set for each different pump model.

1.5 QUALITY ASSURANCE

A. Comply with NFPA 20 and NFPA 13; where requirements differ comply with most stringent.

B. Maintain on site at all times one copy of each design and installation standard referenced.

C. Design fire pump system under direct supervision of a Professional Engineer experienced in design of this Work and licensed at the State in which the Project is located.

D. Equipment and Components: Bearing UL (DIR) label or marking.

E. Products Requiring Electrical Connection: Listed and classified by UL (DIR) as suitable for the purpose specified and indicated.

F. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum three years documented experience.

G. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years of documented experience.

H. Provide certificate of compliance from authority have jurisdiction indicating approval of field acceptance tests.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver fire pumps and components in factory packing. Comply with manufacturer's rigging and installation instructions.

B. Protect fire pumps and components from physical damage including effects of weather, water, and construction debris.

C. Provide temporary inlet and outlet caps, and maintain in place until installation.

PART 2 PRODUCTS

2.1 FIRE PUMPS

A. Fire Pumps: Vertical in-line type; UL 448; single stage, close coupled, radially or horizontally split casing, for in-line mounting, for 250 psi.
   1. Casing: Cast or ductile iron, with suction and discharge gage port, casing wear ring, seal flush connection, drain plug, flanged suction and discharge.
   2. Impeller: Bronze, fully enclosed, keyed directly to motor shaft.
   3. Shaft: Solid alloy steel with bronze sleeve.
   4. Seal: Packing gland with minimum four rings graphite impregnated packing and bronze lantern rings, 230 degrees F maximum continuous operating temperature.
   5. Performance to be determined by fire sprinkler/standpipe designer.
      a. For bidding purposes, assume motor to be 20 hp, 208 volt, three phase, 60 Hz.

B. Fire Pump Accessories:
   1. Eccentric suction reducer and OS&Y gate valve on suction side of pump.
   2. Concentric increaser and check valve in pump discharge and OS&Y gate or butterfly valve on system side of check valve.
   3. Fire pump bypass fitted with OS&Y gate or butterfly valves and check valve.
   4. Main relief valve, UL 1478, and enclosed type waste cone.
   5. Suction pressure gage, 4-1/2 inch diameter dial with snubber, valve cock and lever handle.
   6. Discharge pressure gage mounted on board attached to pump, with snubber, valve cock and lever handle.
   7. 3/4 inch casing relief valve.
   8. Float operated 3/4 inch automatic air release valve.
   9. Hose valve manifold with 2-1/2 inch hose gate valves with caps and chains.
   10. Flow metering system for closed loop testing.

2.2 ELECTRIC MOTOR DRIVE

A. Motor: Squirrel cage induction type, NEMA MG 1; in open drip proof NEMA 250 enclosure, 3500 rpm.

B. Controller: Full service type with across-the-line starter, in NEMA 250 enclosure, including the following:
   1. Disconnect Switch: Externally operable, quick break type.
   2. Circuit Breaker: Comply with NFPA 20; minimum 10,000 amperes interrupting capacity.

3. Motor Starter: Energized automatically through pressure switch or manually by externally operable handle.
4. Pilot Lamp: Indicates circuit breaker closed and power available.
5. Alarm Relay: Energizes alarm to indicate circuit breaker open or power failure.
6. Switch Relay: For remote start.
7. Manual Selector Station: On enclosure marked "Automatic" and "Non-Automatic."

2.3 PRESSURE BOOSTER (JOCKEY) PUMP

A. Electrically operated, vertical multi-stage pump.

B. Control by automatic jockey pump controller with full voltage starter and minimum run timer to start pump on pressure drop in system and stay in operation for minimum period of time. Fire pump shall start automatically on further pressure drop or on jockey pump failure.

2.4 REMOTE PUMP ALARM PANEL

A. Provide a remote annunciator panel in accordance with NFPA 20, Paragraph 10.4.7.

B. Panel shall indicate the following information:
1. Pump or Motor Running: Signal shall actuate whenever the controller has operated into a motor-running condition. This signal circuit shall be energized by a separate, reliable supervised power source, or from the pump motor power, reduced to not more than 125V.
2. Loss of Phase: The fire pump alarm shall actuate whenever any phase at the line terminals of the motor contactor is lost. All phases shall be monitored. Such monitoring shall detect loss of phase whether the motor is running or at rest.
3. Phase Reversal: This fire pump alarm circuit shall be energized by a separate reliable supervised power source or from the pump motor power, reduced to not more than 125V. The fire pump alarm shall actuate whenever the three-phase power at the line terminals of the motor contactor is reversed.

C. Provide all required power and signal wiring. Coordinate requirements with electrical contractor.

PART 3 EXECUTION

3.1 INSTALLATION

A. Provide system analysis to determine if fire pump is required. For bidding purposes, it is anticipated that the facility will require a fire pump. Submit hydraulic calculations supporting design.

B. Install in accordance with NFPA 20.

C. Provide access space around pumps for service; no less than minimum as recommended by manufacturer.

D. Install piping in accordance with Section 210500. Decrease from line size with long radius reducing elbows or reducers. Support piping adjacent to pump such that no weight is carried on pump casings. For base mounted pumps, provide supports under elbows on pump suction and discharge.

E. Provide drains for bases and seals, piped to and discharging into floor drains.

F. Provide for connection to electrical service. Refer to Division 26.

G. Lubricate pumps before start-up.

H. Provide supervisory alarm notifications using auxiliary dry contacts interconnected into fire alarm system for monitoring by Owner-designated central or off-site point of constant attendance; see Section 283100.

3.2 FIELD QUALITY CONTROL

A. Perform field acceptance tests as specified in NFPA 20.

B. Perform field acceptance tests in the presence of Fire Marshal.

3.3 CLOSEOUT ACTIVITIES

A. Demonstrate automatic operation of system including verification of pressure switch set points.

3.4 MAINTENANCE

A. Provide service and maintenance of equipment installed under this section for one year from Date of Substantial Completion.

END OF SECTION 213000

SECTION 220501

PLUMBING DEMOLITION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Plumbing demolition.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify field measurements, pipe, and equipment arrangements for new work as shown on Drawings.

B. Prior to submitting bid, visit site and become familiar with scope of demolition work required to accommodate new work.

C. Refer to Architectural Drawings for additional clarification of scope of demolition and new work.

D. Report discrepancies to Architect before disturbing existing installation.

3.2 PREPARATION

A. Remove all piping, fixtures, and other plumbing installation from entire building.

3.3 DEMOLITION AND EXTENSION OF EXISTING PLUMBING WORK

A. Remove all equipment, controls, piping, fixtures, and other plumbing installation from the entire building. Piping to be removed to source of supply.

B. Repair adjacent construction and finishes damaged during demolition and extension work.

END OF SECTION 220501

SECTION 220553

IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Nameplates.

B. Tags.

C. Pipe Markers.

1.2 REFERENCE STANDARDS

A. ASME A13.1 - Scheme for the Identification of Piping Systems; The American Society of Mechanical Engineers; 2007.

1.3 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. List: Submit list of wording, symbols, letter size, and color coding for mechanical identification.

C. Chart and Schedule: Submit valve chart and schedule, including valve tag number, location, function, and valve manufacturer's name and model number.

D. Product Data: Provide manufacturers catalog literature for each product required.

E. Project Record Documents: Record actual locations of tagged valves.

PART 2 PRODUCTS

2.1 PLUMBING COMPONENT IDENTIFICATION GUIDELINE

A. Pipe Markers: 3/4 inch diameter and higher.

2.2 NAMEPLATES

A. Description: Laminated three-layer plastic with engraved letters.
   1. Letter Color: White.
   2. Letter Height: 1/4 inch.
   3. Background Color: Black.

2.3 TAGS

A. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inch diameter.

B. Metal Tags: Brass with stamped letters; tag size minimum 1-1/2 inch diameter with smooth edges.

C. Chart: Typewritten letter size list in anodized aluminum frame.

2.4 PIPE MARKERS

A. Comply with ASME A13.1.

B. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install plastic nameplates with corrosive-resistant mechanical fasteners, or adhesive. Apply with sufficient adhesive to ensure permanent adhesion and seal with clear lacquer.

B. Install tags with corrosion resistant chain.

C. Install plastic pipe markers in accordance with manufacturer's instructions.

D. Install plastic tape pipe markers complete around pipe in accordance with manufacturer's instructions.

E. Identify equipment with plastic nameplates. Small devices, such as in-line pumps, may be identified with tags.

F. Identify control panels and major control components outside panels with plastic nameplates.

G. Identify valves in main and branch piping with tags.

H. Identify piping, concealed or exposed, with plastic pipe markers. Use tags on piping 3/4 inch diameter and smaller. Identify service, flow direction, and pressure. Install in clear view and align with axis of piping. Locate identification not to exceed 20 feet on straight runs including risers and drops, adjacent to each valve and Tee, at each side of penetration of structure or enclosure, and at each obstruction.

END OF SECTION 220553

SECTION 220719

PLUMBING PIPING INSULATION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Piping insulation.

B. Jackets and accessories.

1.2 REFERENCE STANDARDS

A. ASTM C177 - Standard Test Method for Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus; 2013.

B. ASTM C195 - Standard Specification for Mineral Fiber Thermal Insulating Cement; 2007 (Reapproved 2013).

C. ASTM C449 - Standard Specification for Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement; 2007 (Reapproved 2013).

D. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2014.

E. ASTM C547 - Standard Specification for Mineral Fiber Pipe Insulation; 2015.

F. ASTM C795 - Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel; 2008 (Reapproved 2013).

G. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2015a.

H. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2014.

I. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.3 SUBMITTALS

A. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service

B. Manufacturer's Instructions: Indicate installation procedures that ensure acceptable workmanship and installation standards will be achieved.

PART 2 PRODUCTS

2.1 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread index/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84 or UL 723.

2.2 GLASS FIBER

A. Manufacturers:
   1. Knauf Insulation: www.knaufusa.com.
   2. Johns Manville Corporation: www.jm.com.
   3. Owens Corning Corp: www.owenscorning.com.
   4. CertainTeed Corporation: www.certainteed.com.

B. Insulation: ASTM C547 and ASTM C795; rigid molded, noncombustible.
   1. 'K' value: ASTM C177, 0.24 at 75 degrees F.
   2. Maximum service temperature: 250 degrees F.
   3. Maximum moisture absorption: 0.2 percent by volume.

C. Insulation: ASTM C547 and ASTM C795; semi-rigid, noncombustible, end grain adhered to jacket.
   1. 'K' value: ASTM C177, 0.24 at 75 degrees F.
   2. Maximum service temperature: 250 degrees F.
   3. Maximum moisture absorption: 0.2 percent by volume.

D. Vapor Barrier Jacket: White Kraft paper with glass fiber yarn, bonded to aluminized film; moisture vapor transmission when tested in accordance with ASTM E96/E96M of 0.02 perm-inches.

E. Vapor Barrier Lap Adhesive:
   1. Compatible with insulation.

F. Insulating Cement/Mastic:
   1. ASTM C195; hydraulic setting on mineral wool.

G. Fibrous Glass Fabric:
   1. Cloth: Untreated; 9 oz/sq yd weight.
   2. Blanket: 1.0 lb/cu ft density.
   3. Weave: 5x5.

H. Indoor Vapor Barrier Finish:
   1. Cloth: Untreated; 9 oz/sq yd weight.
   2. Vinyl emulsion type acrylic, compatible with insulation, black color.

I. Insulating Cement:
   1. ASTM C449/C449M.

2.3 FLEXIBLE ELASTOMERIC CELLULAR INSULATION

A. Manufacturer:
   1. Armacell International: www.armacell.com/#sle.
   2. K-Flex USA: www.kflexusa.com.

B. Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534 Grade 1; use molded tubular material wherever possible.
   1. Minimum Service Temperature: -40 degrees F.
   2. Maximum Service Temperature: 220 degrees F.
   3. Connection: Waterproof vapor barrier adhesive.

C. Elastomeric Foam Adhesive: Air dried, contact adhesive, compatible with insulation.

2.4 JACKETS

A. PVC Plastic.
   1. Jacket: One piece molded type fitting covers and sheet material, off-white color.
      a. Minimum Service Temperature: 0 degrees F.
      b. Maximum Service Temperature: 150 degrees F.
      c. Moisture Vapor Permeability: 0.002 perm inch, maximum, when tested in accordance with ASTM E96/E96M.
      d. Thickness: 10 mil.
      e. Connections: Brush on welding adhesive.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that piping has been tested before applying insulation materials.

B. Verify that surfaces are clean and dry, with foreign material removed.

3.2 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Exposed Piping: Locate insulation and cover seams in least visible locations.

C. Insulated pipes conveying fluids below ambient temperature: Insulate entire system including fittings, valves, unions, flanges, strainers, flexible connections, pump bodies, and expansion joints.

D. Glass fiber insulated pipes conveying fluids below ambient temperature:
   1. Provide vapor barrier jackets, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive.

2. Insulate fittings, joints, and valves with molded insulation of like material and thickness as adjacent pipe. Finish with glass cloth and vapor barrier adhesive or PVC fitting covers.

E. Glass fiber insulated pipes conveying fluids above ambient temperature:
1. Provide standard jackets, with or without vapor barrier, factory-applied or field-applied. Secure with self-sealing longitudinal laps and butt strips with pressure sensitive adhesive.
2. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe. Finish with glass cloth and adhesive or PVC fitting covers.

F. Inserts and Shields:
1. Application: Piping 2-1/2 inches diameter or larger.
2. Shields: Galvanized steel between pipe hangers or pipe hanger rolls and inserts.
3. Insert location: Between support shield and piping and under the finish jacket.

G. Continue insulation through walls, sleeves, pipe hangers, and other pipe penetrations. Finish at supports, protrusions, and interruptions. At fire separations, refer to Firestopping Section.

H. Exterior Applications: Provide vapor barrier jacket. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe. Provide PVC jacket.

3.3 SCHEDULES

A. Domestic Hot and Recirculated Hot Water:
1. Glass Fiber Insulation:
a. Pipe Size Range: 1/2 through 1-1/4 inch.
b. Thickness: 1 inch.
2. Glass Fiber Insulation:
a. Pipe Size Range: Above 1-1/4 inch
b. Thickness: 1-1/2 inch

B. Domestic Cold Water:
1. Glass Fiber Insulation:
a. Pipe Size Range: 1/2 through 1-1/4 inch.
b. Thickness: 1/2 inch.
2. Glass Fiber Insulation:
a. Pipe Size Range: Above 1-1/4 inch
b. Thickness: 1 inch

C. Other Systems:
1. Drains from water coolers: 1/2" elastomeric

END OF SECTION 220719

SECTION 221005

PLUMBING PIPING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Pipe, pipe fittings, valves, and connections for piping systems.
   1. Sanitary sewer.
   2. Domestic water.
   3. Flanges, unions, and couplings.
   4. Pipe hangers and supports.
   5. Valves.
   6. Flow controls.
   7. Check valves.
   8. Water pressure reducing valves.
   9. Relief valves.
   10. Sleeves
   11. Sleeve seals
   12. Grout
   13. Escutcheons

1.2 RELATED REQUIREMENTS

A. Section - Firestopping.

B. Section 220553 - Identification for Plumbing Piping and Equipment.

C. Section 220719 - Plumbing Piping Insulation.

1.3 REFERENCE STANDARDS

A. ANSI Z21.22 - American National Standard for Relief Valves and Automatic Gas Shutoff Devices for Hot Water Supply Systems; 1999, and addenda A&B (R2004).

B. ANSI Z223.1 - National Fuel Gas Code; 2015.

C. ASME B16.18 - Cast Copper Alloy Solder Joint Pressure Fittings; 2012.

D. ASME B16.22 - Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings; 2013.

E. ASME B31.9 - Building Services Piping; 2014.

F. ASSE 1003 - Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems; 2009.

G. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.

H. ASTM A74 - Standard Specification for Cast Iron Soil Pipe and Fittings; 2015.

I. ASTM B32 - Standard Specification for Solder Metal; 2008 (Reapproved 2014).

J. ASTM B42 - Standard Specification for Seamless Copper Pipe, Standard Sizes; 2015a.

K. ASTM B88 - Standard Specification for Seamless Copper Water Tube; 2014.

L. ASTM B813 - Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube; 2010.

M. ASTM B828 - Standard Practice for Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings; 2002 (Reapproved 2010).

N. ASTM D2564 - Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems; 2012.

O. ASTM D2665 - Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings; 2014.

P. ASTM D2729 - Standard Specification for Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings; 2011.

Q. ASTM D2855 - Standard Practice for Making Solvent-Cemented Joints with Poly(Vinyl Chloride) (PVC) Pipe and Fittings; 1996 (Reapproved 2010).

R. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2015a.

S. ASTM F876 - Standard Specification for Crosslinked Polyethylene (PEX) Tubing; 2013a.

T. ASTM F877 - Standard Specification for Crosslinked Polyethylene (PEX) Plastic Hot- and Cold-Water Distribution Systems; 2011.

U. ASTM F708 - Standard Practice for Design and Installation of Rigid Pipe Hangers; 1992 (Reapproved 2008).

V. ASTM F 2389-06 - Standard Specification for Pressure-rated Polypropylene (PP) Piping Systems

W. CSA B137.11 - Polypropylene (PP-R) Pipe and Fittings for Pressure Applications

X. NSF/ANSI 14 - Plastic Piping System Components and Related Materials

Y. NSF/ANSI 61 - Drinking Water Systems Components - Health Effects

Z. AWWA C550 - Protective Interior Coatings for Valves and Hydrants; 2013.

AA. AWWA C651 - Disinfecting Water Mains; 2005.

AB. CISPI 301 - Standard Specification for Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste and Vent Piping Applications; 2009.

AC. CISPI 310 - Specification for Coupling for Use in Connection with Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications; 2011.

AD. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2012.

AE. MSS SP-58 - Pipe Hangers and Supports - Materials, Design, Manufacture, Selection, Application, and Installation; 2009.

AF. MSS SP-67 - Butterfly Valves; 2011.

AG. MSS SP-70 - Cast Iron Gate Valves, Flanged and Threaded Ends; 2011.

AH. MSS SP-71 - Cast Iron Swing Check Valves, Flanged and Threaded Ends; 2011.

AI. MSS SP-78 - Cast Iron Plug Valves, Flanged and Threaded Ends; 2011.

AJ. MSS SP-80 - Bronze Gate, Globe, Angle and Check Valves; 2013.

AK. MSS SP-110 - Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends; 2010.

AL. NSF 372 - Drinking Water System Components - Lead Content; 2011.

AM. PPI TR-4 - PPI Listing of Hydrostatic Design Basis (HDB), Hydrostatic Design Stress (HDS), Strength Design Basis (SDB), Pressure Design Basis (PDB), and Minimum Required Strength (MRS) Ratings For Thermoplastic Piping Materials or Pipe; 2013.

AN. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. See Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on pipe materials, pipe fittings, valves, and accessories. Provide manufacturers catalog information. Indicate valve data and ratings.

C. Project Record Documents: Record actual routing of piping. Record actual locations of valves.

1.5 QUALITY ASSURANCE

A. Perform work in accordance with adopted standards of local municipality.

B. Where joining systems specific to a piping manufacturer are used, personnel shall receive factory authorized training prior to installation, and submit evidence of such training for review.

C. Valves: Manufacturer's name and pressure rating marked on valve body.

D. Welding Materials and Procedures: Conform to ASME BPVC-IX and applicable state labor regulations.

E. Welder Qualifications: Certified in accordance with ASME BPVC-IX.

F. Identify pipe with marking including size, ASTM material classification, ASTM specification, potable water certification, water pressure rating.

1.6 REGULATORY REQUIREMENTS

A. Perform work in accordance with adopted standards of local municipality.

B. Conform to applicable code for installation of backflow prevention devices.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Accept valves on site in shipping containers with labeling in place. Inspect for damage.

B. Provide temporary protective coating on cast iron and steel valves.

C. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

D. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the work, and isolating parts of completed system.

1.8 FIELD CONDITIONS

A. Do not install underground piping when bedding is wet or frozen.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

A. Potable Water Supply Systems: Provide piping, pipe fittings, and solder and flux (if used), that comply with NSF 61 and NSF 372 for maximum lead content; label pipe and fittings.

B. Plenum-Installed Acid Waste Piping: Flame-spread index equal or below 25 and smoke-spread index equal or below 50 according to ASTM E84 or UL 723 tests.

C. Reference PART 3 EXECUTION for product applications. Listing of products herein does not imply acceptance of use in all sizes or locations.

2.2 SANITARY SEWER PIPING, BURIED WITHIN 5 FEET OF BUILDING

A. PVC Pipe: ASTM D2665 or ASTM D3034.
   1. Fittings: PVC.
   2. Joints: Solvent welded, with ASTM D2564 solvent cement.

2.3 SANITARY SEWER PIPING, ABOVE GRADE

A. Cast Iron Pipe: CISPI 301, hubless, service weight.
   1. Fittings: Cast iron.
   2. Joints: CISPI 310, neoprene gaskets and stainless steel clamp-and-shield assemblies.

B. PVC Pipe: ASTM D2729.
   1. Fittings: PVC.
   2. Joints: Solvent welded, with ASTM D2564 solvent cement.

2.4 WATER PIPING, BURIED WITHIN 5 FEET OF BUILDING

A. Copper Pipe: ASTM B42, hard drawn.
   1. Fittings: ASME B16.18, cast copper alloy or ASME B16.22 wrought copper and bronze.
   2. Joints: ASTM B 32, alloy Sn95 solder.

B. PE Pipe: ASTM D2239, or ASTM D2447 Schedule 40.
   1. Fittings: ASTM D2609, PE.
   2. Joints: Mechanical with stainless steel clamp.

2.5 WATER PIPING, ABOVE GRADE

A. Copper Tube: ASTM B88 (ASTM B88M), Type L (B), Drawn (H).
   1. Fittings: ASME B16.18, cast copper alloy or ASME B16.22, wrought copper and bronze.
   2. Joints: ASTM B32, alloy Sn95 solder.

B. Cross-Linked Polyethylene (PEX) Pipe: ASTM F876 or ASTM F877.
   1. Manufacturers:
      a. Zurn Industries, LLC
      b. Viega
   2. PPI TR-4 Pressure Design Basis:

C. Polypropylene Pipe (PP-R): Pipe shall be manufactured from a PP-R resin meeting the short-term properties and long-term strength requirements of ASTM F 2389. The pipe shall contain no rework or recycled materials except that generated in the manufacturer's own plant from resin of the same specification from the same raw material. All pipe shall be made in a three layer extrusion process. Domestic hot water shall contain a fiber layer (faser) to restrict thermal expansion. All pipe shall comply with the rated pressure requirements of ASTM F 2389. All pipe shall be certified by NSF International as complying with NSF 14, NSF 61, and ASTM F 2389 or CSA B137.11.
   1. Pipe shall be aquatherm® Greenpipe®, Faser®, or available from Aquatherm, Inc.. Piping specifications and ordering information are available at www.aquathermpipe.com.
   2. Fittings shall be manufactured from a PP-R resin meeting the short-term properties and long-term strength requirements of ASTM F 2389. The fittings shall contain no rework or recycled materials except that generated in the manufacturer's own plant from resin of the same specification from the same raw material. All fittings shall be certified by NSF International as complying with NSF 14, NSF 61, and ASTM F 2389 or CSA B137.11.
   3. Valves with PP-R bodies shall be manufactured from a PP-R resin meeting the short-term properties and long-term strength requirements of ASTM F 2389. The valves shall contain no rework or recycled materials except that generated in the manufacturer's own plant from resin of the same specification from the same raw material.
   4. Manufacturer shall warrantee pipe and fittings for 10 years to be free of defects in materials or workmanship. Warrantee shall cover labor and material costs of repairing and/or replacing defective materials and repairing any incidental damage caused by failure of the piping system do to defects in materials or workmanship.
   5. Where up to 1 inch of standard insulation is indicated on the drawings or in these specifications, a field installed, thermal (radiant, conductive, and convective) and vapor barrier insulation shall be provided for all straight lengths of pipe. The thick wall, self insulating fittings do not require an additional vapor barrier for the piping system to meet this performance level. Where up to 1.5 inches of standard inches of insulation is indicated on the drawings or in these specifications, a field installed, thermal (radiant, conductive, and convective) and vapor barrier insulation shall be provided for all straight lengths of pipe and all fittings. The thermal barrier is UV resistant, CFC-free, non-porous, non-fibrous, and resist mold growth. The pipe with the integral thermal barrier with standard unprotected fittings shall meet the ASTM E84 and the CSA/ULc S102 requirements for a Flame Spread Rating of 25 and Smoke Development rating of 50.

D. Mechanical joint system: Manufacturer's fittings and joining methods, for pipe materials and sizes.
   1. Viega

2.6 FLANGES, UNIONS, AND COUPLINGS

A. Unions for Pipe Sizes 3 Inches and Under:
   1. Ferrous pipe: Class 150 malleable iron threaded unions.
   2. Copper tube and pipe: Class 150 bronze unions with soldered joints.

B. Dielectric Connections: Union with galvanized or plated steel threaded end, copper solder end, water impervious isolation barrier.

2.7 PIPE HANGERS AND SUPPORTS

A. Provide hangers and supports that comply with MSS SP-58.
   1. If type of hanger or support for a particular situation is not indicated, select appropriate type using MSS SP-58 recommendations.
   2. Overhead Supports: Individual steel rod hangers attached to structure or to trapeze hangers.
   3. Trapeze Hangers: Welded steel channel frames attached to structure.
   4. Vertical Pipe Support: Steel riser clamp.

B. Plumbing Piping - Drain, Waste, and Vent:
   1. Conform to ASME B31.9.
   2. Hangers for Pipe Sizes 1/2 Inch to 1-1/2 Inches: Carbon steel, adjustable swivel, split ring.
   3. Hangers for Pipe Sizes 2 Inches and Over: Carbon steel, adjustable, clevis.
   4. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.
   5. Wall Support for Pipe Sizes to 3 Inches: Cast iron hook.
   6. Wall Support for Pipe Sizes 4 Inches and Over: Welded steel bracket and wrought steel clamp.
   7. Vertical Support: Steel riser clamp.

C. Plumbing Piping - Water:
   1. Conform to ASME B31.9.
   2. Hangers for Pipe Sizes 1/2 Inch to 1-1/2 Inches: Malleable iron, adjustable swivel, split ring.
   3. Hangers for Cold Pipe Sizes 2 Inches and Over: Carbon steel, adjustable, clevis.
   4. Hangers for Hot Pipe Sizes 2 Inches to 4 Inches: Carbon steel, adjustable, clevis.
   5. Multiple or Trapeze Hangers: Steel channels with welded supports or spacers and hanger rods.
   6. Multiple or Trapeze Hangers for Hot Pipe Sizes 6 Inches and Over: Steel channels with welded supports or spacers and hanger rods, cast iron roll.
   7. Wall Support for Pipe Sizes to 3 Inches: Cast iron hook.
   8. Wall Support for Pipe Sizes 4 Inches and Over: Welded steel bracket and wrought steel clamp.
   9. Vertical Support: Steel riser clamp.

D. Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
   1. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
   2. Other Types: As required.

2.8 GATE VALVES

A. Manufacturers:
   1. Tyco Flow Control: www.tycoflowcontrol.com.
   2. Conbraco Industries: www.conbraco.com.
   3. Nibco, Inc: www.nibco.com.
   4. Milwaukee Valve Company: www.milwaukeevalve.com.
   5. Substitutions: See Section 016000 - Product Requirements.

B. Up To and Including 3 Inches:
   1. 1, Class 125, bronze body, bronze trim, rising stem, handwheel, inside screw, solid wedge disc, solder ends.

C. 2 Inches and Larger:
   1. 1, Class 125, iron body, bronze trim, outside screw and yoke, handwheel, solid wedge disc, flanged ends. Provide chain-wheel operators for valves 6 inches and larger mounted over 8 feet above floor.

2.9 BALL VALVES

A. Manufacturers:
   1. Tyco Flow Control: www.tycoflowcontrol.com.
   2. Conbraco Industries: www.conbraco.com.
   3. Nibco, Inc: www.nibco.com.
   4. Milwaukee Valve Company: www.milwaukeevalve.com.

5. Substitutions: See Section 016000 - Product Requirements.

B. Construction, 4 Inches and Smaller: MSS SP-110, Class 150, 400 psi CWP, bronze, two piece body, chrome plated brass ball, regular port, teflon seats and stuffing box ring, blow-out proof stem, lever handle with balancing stops, solder ends with union.

2.10 PLUG VALVES

A. Construction 2-1/2 Inches and Larger: 1, 175 psi CWP, cast iron body and plug, pressure lubricated, teflon or Buna N packing, flanged or grooved ends. Provide lever operator with set screw.

2.11 BUTTERFLY VALVES

A. Manufacturers:
1. Tyco Flow Control: www.tycoflowcontrol.com.
2. Hammond Valve: www.hammondvalve.com.
3. Crane Co.: www.cranevalve.com.
4. Milwaukee Valve Company: www.milwaukeevalve.com.
5. Substitutions: See Section 016000 - Product Requirements.

B. Construction 1-1/2 Inches and Larger: MSS SP-67, 200 psi CWP, cast or ductile iron body, nickel-plated ductile iron disc, resilient replaceable EPDM seat, wafer ends, extended neck, 10 position lever handle.

C. Provide gear operators for valves 8 inches and larger, and chain-wheel operators for valves mounted over 8 feet above floor.

2.12 FLOW CONTROLS

A. Manufacturers:
1. Tyco Flow Control: www.tycoflowcontrol.com.
2. ITT Bell & Gossett: www.bellgossett.com.
3. Griswold Controls: www.griswoldcontrols.com.
4. Taco, Inc: www.taco-hvac.com.

B. Construction: Class 125, Brass or bronze body with union on inlet and outlet, temperature and pressure test plug on inlet and outlet, blowdown/backflush drain.

C. Calibration: Control flow within 5 percent of selected rating, over operating pressure range of 10 times minimum pressure required for control, maximum minimum pressure 3.5 psi.

2.13 SWING CHECK VALVES

A. Manufacturers:
1. Tyco Flow Control: www.tycoflowcontrol.com.
2. Hammond Valve: www.hammondvalve.com.
3. Nibco, Inc: www.nibco.com.
4. Milwaukee Valve Company: www.milwaukeevalve.com.
5. Substitutions: See Section 016000 - Product Requirements.

B. Up to 2 Inches:
1. 1, Class 125, bronze body and cap, bronze swing disc with rubber seat, solder ends.

C. Over 2 Inches:
1. 1, Class 125, iron body, bronze swing disc, renewable disc seal and seat, flanged or grooved ends.

2.14 SPRING LOADED CHECK VALVES

A. Manufacturers:
1. Tyco Flow Control: www.tycoflowcontrol.com.
2. Hammond Valve: www.hammondvalve.com.
3. Crane Co.: www.cranevalve.com.
4. Milwaukee Valve Company: www.milwaukeevalve.com.

B. Class 125, iron body, bronze trim, stainless steel springs, bronze disc, Buna N seals, wafer style ends.

2.15 WATER PRESSURE REDUCING VALVES

A. Manufacturers:
   1. Amtrol Inc: www.amtrol.com.
   2. Cla-Val Co: www.cla-val.com.
   3. Watts Regulator Company: www.wattsregulator.com.

B. Up to 2 Inches:
   1. ASSE 1003, bronze body, stainless steel, and thermoplastic internal parts, fabric reinforced diaphragm, strainer, threaded single union ends.

C. Over 2 Inches:
   1. ASSE 1003, cast iron body with interior lining complying with AWWA C550, bronze fitted, elastomeric diaphragm and seat disc, flanged.

2.16 RELIEF VALVES

A. Temperature and Pressure Relief:
   1. Manufacturers:
      a. Cla-Val Co: www.cla-val.com.
      b. Henry Technologies: www.henrytech.com.
      c. Watts Regulator Company: www.wattsregulator.com.
   2. AGA Z21.22 certified, bronze body, teflon seat, stainless steel stem and springs, automatic, direct pressure actuated, temperature relief maximum 210 degrees F, capacity ASME (BPV IV) certified and labelled.

2.17 SLEEVES

A. Galvanized-Steel-Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends.

2.18 SLEEVE-SEAL SYSTEMS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

B. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.
   1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
   2. Pressure Plates: Carbon steel.
   3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, of length required to secure pressure plates to sealing elements.

2.19 GROUT

A. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.

B. Characteristics: Nonshrink; recommended for interior and exterior applications.

C. Design Mix: 5000-psi, 28-day compressive strength.

D. Packaging: Premixed and factory packaged.

2.20 ESCUTCHEONS

A. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.

B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with chrome-plated finish and spring-clip fasteners.

C. One-Piece, Stamped-Steel Type: With chrome-plated finish and spring-clip fasteners.

D. Split-Casting Brass Type: With polished, chrome-plated finish and with concealed hinge and setscrew.

E. Split-Plate, Stamped-Steel Type: With chrome-plated finish, exposed-rivet hinge, and spring-clip fasteners.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that excavations are to required grade, dry, and not over-excavated.

B. Coordinate locatios of slab penetrations with Structural Engineer prior to core drilling.

3.2 PREPARATION

A. Ream pipe and tube ends. Remove burrs.

B. Remove scale and dirt, on inside and outside, before assembly.

C. Prepare piping connections to equipment with flanges or unions.

3.3 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Provide non-conducting dielectric connections wherever jointing dissimilar metals.

C. Route piping in orderly manner and maintain gradient. Route parallel and perpendicular to walls.

D. Install piping to maintain headroom, conserve space, and not interfere with use of space.

E. Group piping whenever practical at common elevations.

F. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

G. Provide clearance in hangers and from structure and other equipment for installation of insulation and access to valves and fittings. Refer to Section 220719.

H. Provide access where valves and fittings are not exposed.

I. Install vent piping penetrating roofed areas to maintain integrity of roof assembly.

J. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.

K. Provide support for utility meters in accordance with requirements of utility companies.

L. TRENCHING

1. Notify Architect of unexpected subsurface conditions and discontinue affected Work in area until notified to resume work.
2. Slope banks of excavations deeper than 4 feet to angle of repose or less until shored.
3. Do not interfere with 45 degree bearing splay of foundations.
4. Cut trenches wide enough to allow inspection of installed utilities.
5. Hand trim excavations. Remove loose matter.
6. Remove large stones and other hard matter that could damage piping or impede consistent backfilling or compaction.
7. Remove excavated material from site.

M. BACKFILLING

1. Fill up to subgrade elevations unless otherwise indicated.
2. Employ a placement method that does not disturb or damage other work.
3. Systematically fill to allow maximum time for natural settlement. Do not fill over porous, wet, frozen or spongy subgrade surfaces.
4. Maintain optimum moisture content of fill materials to attain required compaction density.
5. Utilize sand for fill. Place and compact materials in equal continuous layers not exceeding 6 inches compacted depth.

N. Install bell and spigot pipe with bell end upstream.

O. Install valves with stems upright or horizontal, not inverted.

P. Pipe vents from gas pressure reducing valves to outdoors and terminate in weather proof hood.

Q. Install water piping to ASME B31.9.

R. Copper Pipe and Tube: Make soldered joints in accordance with ASTM B828, using specified solder, and flux meeting ASTM B813; in potable water systems use flux also complying with NSF 61 and NSF 372.

S. PVC Pipe: Make solvent-welded joints in accordance with ASTM D2855.

T. Do not use PVC piping in return air plenums.

U. Do not use PVC piping exposed in dwelling units.

V. Do not use PEX piping exposed in dwelling units.

W. PP Piping: Install fittings and joints using socket-fusion, elecrofusion, or butt-fusion as applicable for the fitting type. All fusion-well joints shall be made in accordance with the pipe and fitting manufacturer's specifications and product standards.

X. The use of PEX piping shall be limited to 1" and smaller unless noted otherwise.

Y. SLEEVE INSTALLATION
   1. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
   2. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
      a. Sleeves are not required for core-drilled holes.
   3. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
      a. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
      b. Cut sleeves to length for mounting flush with both surfaces.
         1) Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
      c. Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.
   4. Install sleeves for pipes passing through interior partitions.
      a. Cut sleeves to length for mounting flush with both surfaces.
      b. Install sleeves that are large enough to provide 1/4-inchannular clear space between sleeve and pipe or pipe insulation.
      c. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in other sections.
   5. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in other sections.

Z. SLEEVE-SEAL-SYSTEM INSTALLATION
   1. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.
   2. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

AA. ESCUTCHEONS
   1. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
   2. Install escutcheons with ID to closely fit around pipe, tube, and insulation of insulated piping and with OD that completely covers opening.
      a. Escutcheons Schedule:
         1) Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.

2) Insulated Piping: One-piece, stamped-steel type or split-plate, stamped-steel type with exposed-rivet hinge.
3) Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass or split-casting brass type with polished, chrome-plated finish.
4) Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece, cast-brass or split-casting brass type with polished, chrome-plated finish.
5) Bare Piping in Unfinished Service Spaces: One-piece, stamped-steel type or split-plate, stamped-steel type with exposed-rivet hinge.
6) Bare Piping in Equipment Rooms: One-piece, stamped-steel type or split-plate, stamped-steel type with exposed-rivet hinge.

AB. Inserts:
1. Provide inserts for placement in concrete formwork.
2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.

AC. Pipe Hangers and Supports:
1. Install in accordance with ASME B31.9.
2. Support horizontal piping as scheduled.
3. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
4. Place hangers within 12 inches of each horizontal elbow.
5. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
6. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
7. Provide copper plated hangers and supports for copper piping.
8. Provide hangers adjacent to motor driven equipment with vibration isolation; refer to Section 220548.
9. Support cast iron drainage piping at every joint.

3.4 APPLICATION

A. Install unions downstream of valves and at equipment or apparatus connections.

B. Install brass male adapters each side of valves in copper piped system. Solder adapters to pipe.

C. Install gate or ball valves for shut-off and to isolate equipment, part of systems, or vertical risers.

D. Provide spring loaded check valves on discharge of water pumps.

E. Provide flow controls in water recirculating systems where indicated.

3.5 TOLERANCES

A. Drainage Piping: Establish invert elevations within 1/2 inch vertically of location indicated and slope to drain at minimum of 1/8 inch per foot slope.

3.6 DISINFECTION OF DOMESTIC WATER PIPING SYSTEM

A. Prior to starting work, verify system is complete, flushed and clean.

B. Ensure Ph of water to be treated is between 7.4 and 7.6 by adding alkali (caustic soda or soda ash) or acid (hydrochloric).

C. Inject disinfectant, free chlorine in liquid, powder, tablet or gas form, throughout system to obtain 50 to 80 mg/L residual.

D. Bleed water from outlets to ensure distribution and test for disinfectant residual at minimum 15 percent of outlets.

E. Maintain disinfectant in system for 24 hours.

F. If final disinfectant residual tests less than 25 mg/L, repeat treatment.

G. Flush disinfectant from system until residual equal to that of incoming water or 1.0 mg/L.

H. Take samples no sooner than 24 hours after flushing, from 10 percent of outlets and from water entry, and analyze in accordance with AWWA C651.

3.7 SERVICE CONNECTIONS

A. Provide new sanitary sewer services. Before commencing work check invert elevations required for sewer connections, confirm inverts and ensure that these can be properly connected with slope for drainage and cover to avoid freezing.

B. Provide new domestic water service.

3.8 SCHEDULES

A. Pipe Hanger Spacing:
   1. Metal Piping:
      a. Pipe size: 1/2 inches to 1-1/4 inches:
         1) Maximum hanger spacing: 6.5 ft.
         2) Hanger rod diameter: 3/8 inches.
      b. Pipe size: 1-1/2 inches to 2 inches:
         1) Maximum hanger spacing: 10 ft.
         2) Hanger rod diameter: 3/8 inch.
      c. Pipe size: 2-1/2 inches to 3 inches:
         1) Maximum hanger spacing: 10 ft.
         2) Hanger rod diameter: 1/2 inch.
      d. Pipe size: 4 inches to 6 inches:
         1) Maximum hanger spacing: 10 ft.
         2) Hanger rod diameter: 5/8 inch.
   2. Plastic Piping:
      a. All Sizes:
         1) Maximum hanger spacing: 6 ft.
         2) Hanger rod diameter: 3/8 inch.

B. Pipe Materials:
   1. Domestic Water:
      a. Basis of design is copper. If PEX is used, sizes shall be adjusted to provide equivalent hydraulic diameter.
      b. Stubouts to fixtures shall be copper.
      c. Pipe sizes 1/2" to 1": Any material listed for use in Part 2.
      d. Pipe sizes 1-1/4" and larger: Any material listed for use in Part 2, except PEX is not acceptable.
      e. PEX shall not be used where exposed in dwelling units.
   2. Sanitary Drain and Vent: Any material listed for use in Part 2.
      a. PVC shall not be used in return air plenums.
      b. PVC shall not be used where exposed in dwelling units.

END OF SECTION 221005

SECTION 221006

PLUMBING PIPING SPECIALTIES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Cleanouts.

B. Water hammer arrestors.

C. Mixing valves.

D. Interceptors.

E. Thermostatic mixing valves.

1.2 REFERENCE STANDARDS

A. ADA Standards - Americans with Disabilities Act (ADA) Standards for Accessible Design; 2010.

B. ASSE 1012 - Backflow Preventer with Intermediate Atmospheric Vent; 2009.

C. PDI-WH 201 - Water Hammer Arresters; 2010.

1.3 SUBMITTALS

A. Product Data: Provide component sizes, rough-in requirements, service sizes, and finishes.

B. Certificates: Certify that grease interceptors meet or exceed specified requirements.

PART 2 PRODUCTS

2.1 CLEANOUTS

A. Manufacturers:
   1. Jay R. Smith Manufacturing Company: www.jayrsmith.com/#sle.
   2. Josam Company: www.josam.com/#sle.
   3. Zurn Industries, Inc: www.zurn.com/#sle.
   4. Sioux Chief Manufacturing.

B. Cleanouts at Exterior Surfaced Areas:
   1. Round cast nickel bronze access frame and non-skid cover.

C. Cleanouts at Exterior Unsurfaced Areas:
   1. Line type with lacquered cast iron body and round epoxy coated gasketed cover.

D. Cleanouts at Interior Finished Floor Areas (FFCO):
   1. Lacquered cast iron body with anchor flange, threaded top assembly, and round gasketed scored cover in service areas and round gasketed depressed cover to accept floor finish in finished floor areas.

E. Cleanouts at Interior Finished Wall Areas (FWCO):
   1. Line type with lacquered cast iron body and round epoxy coated gasketed cover, and round stainless steel access cover secured with machine screw.

F. Cleanouts at Interior Unfinished Accessible Areas: Caulked or threaded type.

2.2 BACKFLOW PREVENTERS

A. Manufacturers:
   1. Conbraco Industries: www.conbraco.com/#sle.
   2. Watts Regulator Company: www.wattsregulator.com/#sle.
   3. Zurn Industries, Inc: www.zurn.com.

B. Reduced Pressure Backflow Preventers:
   1. ASSE 1013; bronze body with bronze internal parts and stainless steel springs; two independently operating, spring loaded check valves; diaphragm type differential pressure relief valve located between check valves; third check valve that opens under back pressure in case of diaphragm failure; non-threaded vent outlet; assembled with two gate valves, strainer, and four test cocks.

2.3 DOUBLE CHECK VALVE ASSEMBLIES

A. Manufacturers:
   1. Conbraco Industries: www.conbraco.com/#sle.
   2. Watts Regulator Company: www.wattsregulator.com/#sle.
   3. Zurn Industries, Inc: www.zurn.com/#sle.

B. Double Check Valve Assemblies:
   1. ASSE 1012; Bronze body with corrosion resistant internal parts and stainless steel springs; two independently operating check valves with intermediate atmospheric vent.

2.4 WATER HAMMER ARRESTORS

A. Manufacturers:
   1. Sioux Chief Manufacturing

B. Water Hammer Arrestors:
   1. Stainless steel or Copper construction, piston type sized in accordance with PDI-WH 201, precharged suitable for operation in temperature range 34 to 250 degrees F and maximum 150 psi working pressure.

2.5 MIXING VALVES

A. Thermostatic Mixing Valves:
   1. Accessories:
      a. Check valve on inlets.
      b. Volume control shut-off valve on outlet.
      c. Stem thermometer on outlet.
      d. Strainer stop checks on inlets.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Extend cleanouts to finished floor or wall surface. Lubricate threaded cleanout plugs with mixture of graphite and linseed oil. Ensure clearance at cleanout for rodding of drainage system.

C. Encase exterior cleanouts in concrete flush with grade.

D. Install floor cleanouts at elevation to accommodate finished floor.

E. Install approved portable water protection devices on plumbing lines where contamination of domestic water may occur.

F. Pipe relief from backflow preventer to nearest drain.

G. Install water hammer arrestors on cold water supply piping to flush valve or solenoid operated fixtures.
.

H. Install cleanouts at locations required by the International Plumbing Code (IPC), whether or not specifically indicated on the drawings. Such locations include, but are not limited to the following:
   1. Base of waste or soil stacks.
   2. Junction of building drain and building sewer (utilize 2-way cleanout at this location).

END OF SECTION 221006

SECTION 223000

PLUMBING EQUIPMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Diaphragm-type compression tanks.

B. Sump pumps.

C. Sanitary Sewage Pumps:
   1. Centrifugal solids handling.

D. Water heaters.

E. Pumps.
   1. Circulators.

F. Water pressure booster system.

1.2 REFERENCE STANDARDS

A. ABMA STD 9 - Load Ratings and Fatigue Life for Ball Bearings; 2015.

B. ABMA STD 11 - Load Ratings and Fatigue Life for Roller Bearings; 2014.

1.3 REFERENCE STANDARDS

A. ASME BPVC-VIII-1 - Boiler and Pressure Vessel Code, Section VIII, Division 1 - Rules for Construction of Pressure Vessels; The American Society of Mechanical Engineers; 2013.

B. ICC (IPC) - International Plumbing Code; 2012.

C. UL 174 - Standard for Household Electric Storage Tank Water Heaters; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

D. UL 778 - Standard for Motor-Operated Water Pumps; Current Edition, Including All Revisions.

E. UL 1453 - Standard for Electric Booster and Commercial Storage Tank Water Heaters; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. Product Data:
   1. Product Data: Provide manufacturer's literature and data sheets for each product. Include information on materials of fabrication, assembly of components, dimensions, weights, capabilities, performance, electrical characteristics, location and sizes of connections, service and access locations, and manufacturer-provided and field-installed accessories.
   2. Provide dimension drawings of water heaters indicating components and connections to other equipment and piping.
   3. Indicate pump type, capacity, power requirements.
   4. Provide certified pump curves showing pump performance characteristics with pump and system operating point plotted. Include NPSH curve when applicable.
   5. Provide electrical characteristics and connection requirements.

B. Shop Drawings:
   1. Provide plans and elevations showing equipment assembly, including fabrication and installation details. Show location and sizes of connections.
   2. Indicate clearances required for service, access, maintenance, and replacement of internal components.
   3. Indicate dimensions of tanks, tank lining methods, anchors, attachments, lifting points, tappings, and drains.

C. Project Record Documents: Record actual locations of components.

D. Operation and Maintenance Data: Include operation, maintenance, and inspection data, replacement part numbers and availability, and service depot location and telephone number.

E. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section, with minimum three years of documented experience.

B. Identification: Provide pumps with manufacturer's name, model number, and rating/capacity identified by permanently attached label.

C. Performance: Ensure pumps operate at specified system fluid temperatures without vapor binding and cavitation, are non-overloading in parallel or individual operation, operate within 25 percent of midpoint of published maximum efficiency curve.

1.6 CERTIFICATIONS

A. Water Heaters: NSF approved.

B. Electric Water Heaters: UL listed and labeled to UL 174 or UL 1453.

C. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

1.8 WARRANTY

A. Provide five year manufacturer warranty for domestic water heaters.

PART 2 PRODUCTS

2.1 WATER HEATER MANUFACTURERS

A. A.O. Smith Water Products Co: www.hotwater.com.

B. Rheem Manufacturing Company: www.rheem.com.

2.2 ELECTRIC WATER HEATERS

A. Type: Automatic, electric, vertical storage.

B. Electrical Characteristics:
1. 208 volts, single phase.

C. Tank: Glass lined welded steel, thermally insulated with one inch thick glass fiber; encased in corrosion-resistant steel jacket; baked-on enamel finish.

D. Controls: Automatic water thermostat with externally adjustable temperature range from 120 to 170 degrees F, flanged or screw-in nichrome elements, enclosed controls and electrical junction box .

E. Accessories: Provide:
1. Water Connections: Brass.
2. Dip tube: Brass.
3. Drain Valve.
4. Anode: Magnesium

2.3 DIAPHRAGM-TYPE COMPRESSION TANKS

A. Manufacturers:
1. Amtrol Inc: www.amtrol.com/#sle.
2. ITT Bell & Gossett: www.bellgossett.com.
3. Taco, Inc: www.taco-hvac.com.

B. Construction: Welded steel, tested and stamped in accordance with ASME BPVC-VIII-1; supplied with National Board Form U-1, rated for working pressure of 125 psig, with flexible EPDM diaphragm sealed into tank, and steel legs or saddles.

C. Accessories: Pressure gage and air-charging fitting, tank drain; precharge to 12 psig.

2.4 IN-LINE CIRCULATOR PUMPS

A. Casing: Bronze, rated for 125 psig working pressure, with stainless steel rotor assembly.

B. Impeller: Bronze.

C. Shaft: Alloy steel with integral thrust collar and two oil lubricated bronze sleeve bearings.

D. Seal: Carbon rotating against a stationary ceramic seat.

E. Drive: Flexible coupling.

2.5 PRESSURE BOOSTER SYSTEMS

A. System: Packaged with two pumps, factory assembled, tested, and adjusted; shipped to site as integral unit; consisting of pumps, variable frequency drives, valves, and piping, with control panel assembled on fabricated steel base with structural steel framework.

B. Controls and Instruments: Locate in NEMA 250 Type 1 general purpose enclosure with main disconnect interlocked with door, fused circuit for each motor, variable frequency drives, control circuit transformer with fuse protection, selector switch for each pump, low limit pressure switch, low pressure alarm light, running lights, current sensing devices, minimum run timers, manual alternation, and suction and discharge pressure gages.

C. Lead Pump: Operate continuously with lag pump operating on system demand. Should lead pump fail to operate, next pump in sequence shall start automatically.

D. Time Delay Relay: Prevent lag pump short cycling on fluctuating demands.

E. Thermal Bleed Circuit with Solenoid Valve: Prevent overheating during low demand.

F. Low Pressure Control: Stop pump operation if incoming water pressure drops to atmospheric.

G. Pump Switch: Permit manual or automatic operation.

H. Valving: Each pump outlet combination pressure reducing and check valve to maintain constant system pressure. Provide gate or butterfly valves on suction and discharge of each pump. Provide check valve on each pump discharge.

I. Performance: On drawings

2.6 SUBMERSIBLE SUMP PUMPS

A. Type: Completely submersible, vertical, centrifugal.

B. Casing: Cast iron pump body and oil filled motor chamber.

C. Impeller: Cast iron; open non-clog, stainless steel shaft.

D. Bearings: Ball bearings.

E. Sump: Fiberglass basin with steel cover plate, dimensions as indicated on drawings.

F. Accessories: Oil resistant 6 foot cord and plug with three-prong connector for connection to electric wiring system including grounding connector.

2.7 SANITARY SEWAGE PUMPS

A. Centrifugal Solids Handling:
   1. General: Non-clogging centrifugal type suitable for pumping solids up to 3 inches in diameter without internal interstices that can collect stringy materials and solids resulting in clogging.
   2. Casing:
      a. Capable of withstanding operating pressures 50 percent greater than the maximum operating pressure.
      b. Plugged and tapped holes for draining and venting pump.
      c. Volute to consist of smooth passages.
      d. Configuration to permit removal of impeller without disturbing discharge and suction connections.

e. Handhole to allow cleaning and inspection of pump interior.
f. Lifting eyes to facilitate handling of pump.

3. Impeller:
   a. Design to consist of smooth passages to prevent clogging and pass fibrous or stringy material.
   b. Securely keyed to shaft with locking arrangement preventing loosening by torque from either forward or reverse direction.
   c. Balance statically, dynamically, and hydraulically within the operating range and to the first critical speed at 150 percent of the maximum operating speed.
4. Wearing Rings:
   a. Provide renewable wearing rings on the casing and impeller with wearing surfaces normal to the axis of rotation.
   b. Construction: Cast iron.
   c. Factory designed for simple maintenance and secured to prevent rotation.
   d. In lieu of wearing rings on impeller and casing, replaceable steel wear plates fastened to casing may be used.
5. Pump Shaft:
   a. Provide with adequate size and strength to transmit full driver horsepower with liberal safety factor.
   b. Fabricate from stainless steel.
6. Pump Shaft Sleeve:
   a. Fabricate from stainless steel.
   b. Seal joint between shaft and sleeve to prevent leakage.
   c. Stuffing Box:
      1) Factory designed for minimum 5 rings of packing with removable split type glands.
      2) Fabricate from same material as casing and water sealed.
7. Mechanical Seal System:
   a. Furnish single seals to seal pump shaft against leakage.
   b. Each seal to be held in place by its own spring system, supplemented by external liquid pressures.
   c. System to be readily removable from the shaft.
8. Bearings:
   a. Provide ball type designed to handle all thrust loads in either direction.
   b. Furnish with a L-10 life of minimum 50,000 hours as required by ABMA 9 or ABMA 11.
   c. Pumps depending only on hydraulic balance and thrust are not acceptable.
9. Lubrication:
   a. Bearing:
10. Pump Support:
11. Coupling:
   a. Provide heavy duty, flexible type, locked to the shaft.
   b. Disconnection of the coupling possible without removing the driver half or the pump half of the coupling from the shaft.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install plumbing equipment in accordance with manufacturer's instructions, as required by code, and complying with conditions of certification, if any.

B. Coordinate with plumbing piping and related fuel piping work to achieve operating system.

C. Pumps:
   1. Provide line sized isolating valve and strainer on suction and line sized soft seated check valve and balancing valve on discharge.

2. Decrease from line size with long radius reducing elbows or reducers. Support piping adjacent to pump such that no weight is carried on pump casings. Provide supports under elbows on pump suction and discharge line sizes 4 inches and over.
3. Ensure pumps operate at specified system fluid temperatures without vapor binding and cavitation, are non-overloading in parallel or individual operation, and operate within 25 percent of midpoint of published maximum efficiency curve.

END OF SECTION 223000

SECTION 224000

PLUMBING FIXTURES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Fixtures

1.2 RELATED REQUIREMENTS

A. Section 221005 - Plumbing Piping.

B. Section 221006 - Plumbing Piping Specialties.

1.3 REFERENCE STANDARDS

A. ASHRAE Std 18 - Methods of Testing for Rating Drinking-Water Coolers with Self-Contained Mechanical Refrigeration; 2008.

B. ASME A112.6.1M - Supports for Off-the-Floor Plumbing Fixtures for Public Use; 1997 (Reaffirmed 2002).

C. ASME A112.18.1 - Plumbing Supply Fittings; 2012.

D. ASME A112.19.2 - Ceramic Plumbing Fixtures; 2013.

E. ASME A112.19.3 - Stainless Steel Plumbing Fixtures (Designed for Residential Use); 2008 (R2013).

F. ASME A112.19.5 - Flush Valves and Spuds for Water Closets, Urinals, and Tanks; 2011.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide catalog illustrations of fixtures, sizes, rough-in dimensions, utility sizes, trim, and finishes.

C. Manufacturer's Instructions: Indicate installation methods and procedures.

D. Maintenance Data: Include fixture trim exploded view and replacement parts lists.

E. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.

1. Extra Faucet Washers: Two sets of each type and size.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Accept fixtures on site in factory packaging. Inspect for damage.

B. Protect installed fixtures from damage by securing areas and by leaving factory packaging in place to protect fixtures and prevent use.

1.6 WARRANTY

A. Provide five year manufacturer warranty for electric water cooler.

PART 2 PRODUCTS

2.1 FIXTURES

A. Scheduled on drawings

B. Substitutions permitted, provided products are functionally and materially equivalent to those scheduled. Substitutions must be approvded by Engineer.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that walls and floor finishes are prepared and ready for installation of fixtures.

B. Verify that electric power is available and of the correct characteristics.

C. Confirm that millwork is constructed with adequate provision for the installation of counter top lavatories and sinks.

3.2 PREPARATION

A. Rough-in fixture piping connections in accordance with minimum sizes indicated in fixture rough-in schedule for particular fixtures.

3.3 INSTALLATION

A. Install each fixture with trap, easily removable for servicing and cleaning.

B. Provide chrome plated rigid or flexible supplies to fixtures with loose key stops, reducers, and escutcheons.

C. Install components level and plumb.

D. Install and secure fixtures in place with wall supports and bolts.

E. Seal fixtures to wall and floor surfaces with sealant, color to match fixture.

3.4 INTERFACE WITH WORK OF OTHER SECTIONS

A. Review millwork shop drawings. Confirm location and size of fixtures and openings before rough-in and installation.

3.5 ADJUSTING

A. Adjust stops or valves for intended water flow rate to fixtures without splashing, noise, or overflow.

3.6 CLEANING

A. Clean plumbing fixtures and equipment.

3.7 PROTECTION

A. Protect installed products from damage due to subsequent construction operations.

B. Do not permit use of fixtures by construction personnel.

C. Repair or replace damaged products before Date of Substantial Completion.

3.8 SCHEDULES

A. On Drawings

END OF SECTION 224000

SECTION 230001

MECHANICAL DEMOLITION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Mechanical demolition.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 EXAMINATION

A. Prior to submitting bid, visit site and become familiar with scope of demolition work required to accommodate new work.

B. Refer to Architectural Drawings for additional clarification of scope of demolition and new work.

C. Verify that abandoned equipment and associated mechanical installation serve only abandoned facilities.

D. Should the contractor encounter any existing conditions related to the project area that prevent the work from being performed as indicated or described, contact the Architect immediately.

E. Report discrepancies to Architect before disturbing existing installation.

F. Beginning of demolition means installer accepts existing conditions.

3.2 PREPARATION

A. Remove ductwork, piping, controls, and all other mechanical installation from entire building.

3.3 DEMOLITION OF EXISTING MECHANICAL WORK

A. Remove existing installations in their entirety.

B. Remove abandoned equipment, controls, air devices, ductwork, piping, fixtures, and other mechanical installation. Piping and ductwork to be removed to source of supply.

C. Repair adjacent construction and finishes damaged during demolition and extension work.

END OF SECTION 230001

SECTION 230593

TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Testing, adjustment, and balancing of air systems.

B. Measurement of final operating condition of HVAC systems.

1.2 REFERENCE STANDARDS

A. AABC MN-1 - AABC National Standards for Total System Balance; Associated Air Balance Council; 2002.

B. NEBB (TAB) - Procedural Standards for Testing Adjusting Balancing of Environmental Systems; 2005, Seventh Edition.

1.3 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Qualifications: Submit name of adjusting and balancing agency and TAB supervisor for approval within 30 days after award of Contract.

C. Final Report: Indicate deficiencies in systems that would prevent proper testing, adjusting, and balancing of systems and equipment to achieve specified performance.

1. Submit to the Construction Manager within two weeks after completion of testing, adjusting, and balancing.
2. Revise TAB plan to reflect actual procedures and submit as part of final report.
3. Provide reports in soft cover, letter size, 3-ring binder manuals, complete with index page and indexing tabs, with cover identification at front and side. Include set of reduced drawings with air outlets and equipment identified to correspond with data sheets, and indicating thermostat locations.
4. Include actual instrument list, with manufacturer name, serial number, and date of calibration.
5. Form of Test Reports: Where the TAB standard being followed recommends a report format use that; otherwise, follow ASHRAE Std 111.
6. Units of Measure: Report data in I-P (inch-pound) units only.
7. Include the following on the title page of each report:
    a. Name of Testing, Adjusting, and Balancing Agency.
    b. Address of Testing, Adjusting, and Balancing Agency.
    c. Telephone number of Testing, Adjusting, and Balancing Agency.
    d. Project name.
    e. Project location.
    f. Report date.

D. Project Record Documents: Record actual locations of flow measuring stations and balancing valves and rough setting.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

A. Perform total system balance in accordance with one of the following:

1. AABC MN-1, AABC National Standards for Total System Balance.
2. ASHRAE Std 111, Practices for Measurement, Testing, Adjusting and Balancing of Building Heating, Ventilation, Air-Conditioning, and Refrigeration Systems.
3. NEBB Procedural Standards for Testing Adjusting Balancing of Environmental Systems.

B. Begin work after completion of systems to be tested, adjusted, or balanced and complete work prior to Substantial Completion of the project.

C. Where HVAC systems and/or components interface with life safety systems, including fire and smoke detection, alarm, and control, coordinate scheduling and testing and inspection procedures with the authorities having jurisdiction.

D. TAB Agency Qualifications:
   1. Company specializing in the testing, adjusting, and balancing of systems specified in this section.
   2. Having minimum of three years documented experience.
   3. Certified by one of the following:
      a. AABC, Associated Air Balance Council: www.aabchq.com; upon completion submit AABC National Performance Guaranty.
      b. NEBB, National Environmental Balancing Bureau: www.nebb.org/#sle.

E. TAB Supervisor Qualifications: Professional Engineer licensed in Oklahoma.

3.2 EXAMINATION

A. Verify that systems are complete and operable before commencing work. Ensure the following conditions:
   1. Systems are started and operating in a safe and normal condition.
   2. Temperature control systems are installed complete and operable.
   3. Proper thermal overload protection is in place for electrical equipment.
   4. Final filters are clean and in place. If required, install temporary media in addition to final filters.
   5. Duct systems are clean of debris.
   6. Fans are rotating correctly.
   7. Fire and volume dampers are in place and open.
   8. Air coil fins are cleaned and combed.
   9. Access doors are closed and duct end caps are in place.
   10. Air outlets are installed and connected.
   11. Duct system leakage is minimized.

B. Submit field reports. Report defects and deficiencies that will or could prevent proper system balance.

C. Beginning of work means acceptance of existing conditions.

3.3 PREPARATION

A. Hold a pre-balancing meeting at least one week prior to starting TAB work.
   1. Require attendance by all installers whose work will be tested, adjusted, or balanced.

B. Provide instruments required for testing, adjusting, and balancing operations. Make instruments available to Architect to facilitate spot checks during testing.

C. Provide additional balancing devices as required.

3.4 ADJUSTMENT TOLERANCES

A. Air Handling Systems: Adjust to within plus or minus 10 percent of design for supply systems and plus or minus 10 percent of design for return and exhaust systems.

B. Air Outlets and Inlets: Adjust total to within plus 10 percent and minus 10 percent of design to space. Adjust outlets and inlets in space to within plus or minus 10 percent of design.

3.5 RECORDING AND ADJUSTING

A. Field Logs: Maintain written logs including:
   1. Running log of events and issues.
   2. Discrepancies, deficient or uncompleted work by others.
   3. Contract interpretation requests.
   4. Lists of completed tests.

B. Ensure recorded data represents actual measured or observed conditions.

C. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.

D. After adjustment, take measurements to verify balance has not been disrupted or that such disruption has been rectified.

E. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring thermostats to specified settings.

3.6 AIR SYSTEM PROCEDURE

A. Adjust air handling and distribution systems to provide required or design supply, return, and exhaust air quantities .

B. Make air quantity measurements in ducts by Pitot tube traverse of entire cross sectional area of duct.

C. Measure air quantities at air inlets and outlets.

D. Adjust distribution system to obtain uniform space temperatures free from objectionable drafts and noise.

E. Use volume control devices to regulate air quantities only to extent that adjustments do not create objectionable air motion or sound levels. Effect volume control by duct internal devices such as dampers and splitters.

F. Vary total system air quantities by adjustment of fan speeds. Provide drive changes required. Vary branch air quantities by damper regulation.

G. Provide system schematic with required and actual air quantities recorded at each outlet or inlet.

H. Measure static air pressure conditions on air supply units, including filter and coil pressure drops, and total pressure across the fan. Make allowances for 50 percent loading of filters.

I. Adjust outside air automatic dampers, outside air, return air, and exhaust dampers for design conditions.

J. Measure temperature conditions across outside air, return air, and exhaust dampers to check leakage.

K. Where modulating dampers are provided, take measurements and balance at extreme conditions.

3.7 SCOPE

A. Test, adjust, and balance the following:
   1. Air Handling Units
   2. Fans
   3. Air Inlets and Outlets
   4. Energy Recovery Ventilators

3.8 MINIMUM DATA TO BE REPORTED

A. Electric Motors:
   1. Manufacturer
   2. Model/Frame
   3. HP/BHP
   4. Phase, voltage, amperage; nameplate, actual, no load
   5. RPM
   6. Service factor
   7. Starter size, rating, heater elements
   8. Sheave Make/Size/Bore

B. V-Belt Drives:
   1. Identification/location
   2. Required driven RPM
   3. Driven sheave, diameter and RPM
   4. Belt, size and quantity
   5. Motor sheave diameter and RPM
   6. Center to center distance, maximum, minimum, and actual

C. Air Cooled Condensers:
   1. Location
   2. Manufacturer
   3. Model number

D. Electric Duct Heaters:
   1. Manufacturer
   2. Identification/number
   3. Location
   4. Design kW
   5. Number of stages
   6. Phase, voltage, amperage
   7. Test voltage (each phase)
   8. Test amperage (each phase)
   9. Air flow, specified and actual
   10. Temperature rise, specified and actual

E. Air Moving Equipment:
   1. Location
   2. Manufacturer
   3. Model number
   4. Air flow, specified and actual
   5. Total static pressure (total external), specified and actual

F. Exhaust Fans:
   1. Location
   2. Manufacturer
   3. Model number
   4. Air flow, specified and actual
   5. Total static pressure (total external), specified and actual

G. Air Distribution Tests:
   1. Room number/location
   2. Terminal type
   3. Design air flow
   4. Test (final) air flow
   5. Percent of design air flow

END OF SECTION 230593

SECTION 230713

DUCT INSULATION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Duct insulation.

B. Duct Liner.

1.2 REFERENCE STANDARDS

A. ASTM C518 - Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2010.

B. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2014.

C. ASTM C553 - Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013.

D. ASTM C916 - Standard Specification for Adhesives for Duct Thermal Insulation; 2014.

E. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2015a.

F. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2014.

G. ASTM G21 - Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi; 2015.

H. NFPA 255 - Standard Method of Test of Surface Burning Characteristics of Building Materials; National Fire Protection Association; 2006.

I. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005.

J. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.3 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.

C. Manufacturer's Instructions: Indicate installation procedures necessary to ensure acceptable workmanship and that installation standards will be achieved.

1.4 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing products of the type specified in this section with not less than three years of documented experience.

B. Applicator Qualifications: Company specializing in performing the type of work specified in this section, with minimum three years of experienceand approved by manufacturer.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Accept materials on site in original factory packaging, labelled with manufacturer's identification, including product density and thickness.

B. Protect insulation from weather and construction traffic, dirt, water, chemical, and mechanical damage, by storing in original wrapping.

1.6 FIELD CONDITIONS

A. Maintain ambient temperatures and conditions required by manufacturers of adhesives, mastics, and insulation cements.

B. Maintain temperature during and after installation for minimum period of 24 hours.

PART 2 PRODUCTS

2.1 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84, NFPA 255, or UL 723.

2.2 GLASS FIBER, FLEXIBLE

A. Manufacturer:
   1. Knauf Insulation: www.knaufusa.com.
   2. Johns Manville Corporation: www.jm.com/#sle.
   3. Owens Corning Corp: www.owenscorning.com/#sle.
   4. CertainTeed Corporation; : www.certainteed.com/#sle.

B. Insulation: ASTM C553; flexible, noncombustible blanket.
   1. 'K' value: 0.25 at 75 degrees F, when tested in accordance with ASTM C518.
   2. Maximum Water Vapor Sorption: 5.0 percent by weight.

C. Vapor Barrier Jacket:
   1. Kraft paper with glass fiber yarn and bonded to aluminized film.
   2. Moisture Vapor Permeability: 0.02 perm inch, when tested in accordance with ASTM E96/E96M.
   3. Secure with pressure sensitive tape.

D. Vapor Barrier Tape:
   1. Kraft paper reinforced with glass fiber yarn and bonded to aluminized film, with pressure sensitive rubber based adhesive.

2.3 DUCT LINER

A. Manufacturers:
   1. Armacell LLC; AP Coilflex: www.armacell.us/#sle.

B. Elastomeric Foam Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534/C534M Grade 1, in sheet form.
   1. Minimum Service Temperature: Minus 40 degrees F.
   2. Maximum Service Temperature: 180 degrees F.
   3. Fungal Resistance: No growth when tested according to ASTM G21.
   4. Apparent Thermal Conductivity: Maximum of 0.28 at 75 degrees F.
   5. Minimum Noise Reduction Coefficients:
      a. 1/2 inch Thickness: 0.30.
      b. 1 inch Thickness: 0.40.
   6. Connection: Waterproof vapor barrier adhesive.

C. Elastomeric Foam Adhesive: Air dried, contact adhesive, compatible with insulation. Comply with ASTM C916.

D. Liner Fasteners: Galvanized steel, self-adhesive pad, impact applied, or welded with integral or press-on head.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that ducts have been tested before applying insulation materials.

B. Verify that surfaces are clean, foreign material removed, and dry.

3.2 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Insulated ducts:
   1. Provide insulation with vapor barrier jackets.

2. Finish with tape and vapor barrier jacket.
3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
4. Insulate entire system including fittings, joints, flanges, fire dampers, flexible connections, and expansion joints.

C. External Duct Insulation Application:
1. Secure insulation with vapor barrier with wires and seal jacket joints with vapor barrier adhesive or tape to match jacket.
2. Secure insulation without vapor barrier with staples, tape, or wires.
3. Install without sag on underside of duct. Use adhesive or mechanical fasteners where necessary to prevent sagging. Lift duct off trapeze hangers and insert spacers.
4. Seal vapor barrier penetrations by mechanical fasteners with vapor barrier adhesive.
5. Stop and point insulation around access doors and damper operators to allow operation without disturbing wrapping.

D. Duct and Plenum Liner Application:
1. Adhere insulation with adhesive for 90 percent coverage.
2. Secure insulation with mechanical liner fasteners. Refer to SMACNA HVAC Duct Construction Standards for spacing.
3. Seal and smooth joints. Seal and coat transverse joints.
4. Seal liner surface penetrations with adhesive.
5. Duct dimensions indicated are net inside dimensions required for air flow. Increase duct size to allow for insulation thickness.

3.3 SCHEDULES

A. Ductwork located in basement: Flexible glass fiber duct insulation, 1-1/2" thick.

B. Outside Air Intake Ducts: Flexible glass fiber duct insulation, 1-1/2" thick.

C. Supply ducts from space heating and cooling equipment: Flexible glass fiber duct insulation, 1-1/2" thick.
1. Omit duct wrap on fresh air and exhaust ducts connected to ERV.
2. Omit duct wrap on exposed spiral ductwork.

D. Supply and return ducts within 5`of energy recovery ventilators and blower coil equipment: Elastomeric Duct Liner, 1/2" thick.

END OF SECTION 230713

SECTION 230719

HVAC PIPING INSULATION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Piping insulation.

B. Jackets and accessories.

1.2 REFERENCE STANDARDS

A. ASTM C534/C534M - Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form; 2014.

B. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2015a.

C. ASTM E96/E96M - Standard Test Methods for Water Vapor Transmission of Materials; 2014.

D. NFPA 255 - Standard Method of Test of Surface Burning Characteristics of Building Materials; National Fire Protection Association; 2006.

E. UL 723 - Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.

1.3 SUBMITTALS

A. Product Data: Provide product description, thermal characteristics, list of materials and thickness for each service, and locations.

PART 2 PRODUCTS

2.1 REQUIREMENTS FOR ALL PRODUCTS OF THIS SECTION

A. Surface Burning Characteristics: Flame spread/Smoke developed index of 25/50, maximum, when tested in accordance with ASTM E84, NFPA 255, or UL 723.

2.2 FLEXIBLE ELASTOMERIC CELLULAR INSULATION

A. Manufacturer:
   1. Armacell LLC: www.armacell.us/#sle.

B. Insulation: Preformed flexible elastomeric cellular rubber insulation complying with ASTM C534 Grade 1; use molded tubular material wherever possible.
   1. Minimum Service Temperature: -40 degrees F.
   2. Maximum Service Temperature: 220 degrees F.
   3. Connection: Waterproof vapor barrier adhesive.

C. Elastomeric Foam Adhesive: Air dried, contact adhesive, compatible with insulation.

2.3 JACKETS

A. PVC Plastic.
   1. Jacket: One piece molded type fitting covers and sheet material, off-white color.
      a. Minimum Service Temperature: 0 degrees F.
      b. Maximum Service Temperature: 150 degrees F.
      c. Moisture Vapor Permeability: 0.002 perm inch, maximum, when tested in accordance with ASTM E96/E96M.
      d. Thickness: 10 mil.
      e. Connections: Brush on welding adhesive.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that piping has been tested before applying insulation materials.

B. Verify that surfaces are clean and dry, with foreign material removed.

3.2 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Exposed Piping: Locate insulation and cover seams in least visible locations.

C. Inserts and Shields:
   1. Application: Piping 1-1/2 inches diameter or larger.
   2. Shields: Galvanized steel between pipe hangers or pipe hanger rolls and inserts.
   3. Insert location: Between support shield and piping and under the finish jacket.
   4. Insert Configuration: Minimum 6 inches long, of same thickness and contour as adjoining insulation; may be factory fabricated.
   5. Insert Material: Hydrous calcium silicate insulation or other heavy density insulating material suitable for the planned temperature range.

D. Continue insulation through walls, sleeves, pipe hangers, and other pipe penetrations. Finish at supports, protrusions, and interruptions. At fire separations, refer to "Firestopping" Section.

E. Pipe Exposed in Mechanical Equipment Rooms or Finished Spaces (less than 10 feet above finished floor): Finish with canvas jacket sized for finish painting.

F. Exterior Applications: Provide PVC jacket.

3.3 SCHEDULE

A. Cooling Systems:
   1. Condensate Drains from Cooling Coils: 1/2" Flexible Elastomeric
   2. Refrigerant Suction: 1" Flexible Elastomeric
   3. Refrigerant Liquid/hot gas: Per system manufacturer's recommendations

END OF SECTION 230719

SECTION 232100

GENERAL REQUIREMENTS FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Sleeves.
   2. Sleeve-seal systems.
   3. Grout.
   4. Escutcheons.

PART 2 - PRODUCTS

2.1 SLEEVES

A. Cast-Iron Wall Pipes: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.

B. Galvanized-Steel Wall Pipes: ASTM A 53/A 53M, Schedule 40, with plain ends and welded steel collar; zinc coated.

C. Galvanized-Steel-Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, with plain ends.

D. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.

E. Galvanized-Steel-Sheet Sleeves: 0.0239-inchminimum thickness; round tube closed with welded longitudinal joint.

F. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.

G. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.

2.2 SLEEVE-SEAL SYSTEMS

A. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.
   1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
   2. Pressure Plates: Stainless steel.
   3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, of length required to secure pressure plates to sealing elements.

2.3 GROUT

A. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.

B. Characteristics: Nonshrink; recommended for interior and exterior applications.

C. Design Mix: 5000-psi, 28-day compressive strength.

D. Packaging: Premixed and factory packaged.

2.4 ESCUTCHEONS

A. One-Piece, Stamped-Steel Type: With chrome-plated finish and spring-clip fasteners.

B. Split-Plate, Stamped-Steel Type: With chrome-plated finish, concealed or exposed-rivet hinge, and spring-clip fasteners.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION

A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.

B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
   1. Sleeves are not required for core-drilled holes.

C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
   1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
   2. Cut sleeves to length for mounting flush with both surfaces.
      a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
   3. Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.

D. Install sleeves for pipes passing through interior partitions.
   1. Cut sleeves to length for mounting flush with both surfaces.
   2. Install sleeves that are large enough to provide 1/4-inchannular clear space between sleeve and pipe or pipe insulation.
   3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in other sections.

E. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in other sections.

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.

B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

3.3 ESCUTCHEON INSTALLATION

A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.

B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of piping and with OD that completely covers opening.
   1. Escutcheon Schedule:
      a. Bare Piping in Unfinished Service Spaces: One-piece, stamped-steel type or split-plate, stamped-steel type with exposed-rivet hinge.
      b. Bare Piping in Equipment Rooms: One-piece, stamped-steel type or split-plate, stamped-steel type with exposed-rivet hinge.

END OF SECTION 232100

SECTION 232300

REFRIGERANT PIPING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Piping.

B. Refrigerant.

1.2 RELATED REQUIREMENTS

A. Section 230719 - HVAC Piping Insulation.

1.3 REFERENCE STANDARDS

A. ASHRAE Std 15 - Safety Standard for Refrigeration Systems; 2013.

B. ASHRAE Std 34 - Designation and Safety Classification of Refrigerants; 2013.

C. ASME B16.22 - Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings; 2013.

D. ASME B31.5 - Refrigeration Piping and Heat Transfer Components; 2013.

E. ASTM B280 - Standard Specification for Seamless Copper Tube for Air Conditioning and Refrigeration Field Service; 2013.

F. AWS A5.8M/A5.8 - Specification for Filler Metals for Brazing and Braze Welding; 2011-AMD 1.

1.4 SYSTEM DESCRIPTION

A. Where more than one piping system material is specified ensure system components are compatible and joined to ensure the integrity of the system is not jeopardized. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

B. Provide pipe hangers and supports in accordance with ASME B31.5 unless indicated otherwise.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store piping and specialties in shipping containers with labeling in place.

B. Protect piping and specialties from entry of contaminating material by leaving end caps and plugs in place until installation.

C. Dehydrate and charge components such as piping and receivers, seal prior to shipment, until connected into system.

PART 2 PRODUCTS

2.1 PIPING

A. Copper Tube: ASTM B280, H58 hard drawn .
   1. Fittings: ASME B16.22 wrought copper.
   2. Joints: Braze, AWS A5.8 BCuP silver/phosphorus/copper alloy.

B. Pipe Supports and Anchors:
   1. Conform to ASME B31.5.
   2. Hangers for Pipe Sizes 1/2 to 1-1/2 Inch: Malleable iron adjustable swivel, split ring.
   3. Hangers for Pipe Sizes 2 Inches and Over: Carbon steel, adjustable, clevis.
   4. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.
   5. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
   6. Copper Pipe Support: Carbon steel ring, adjustable, copper plated.
   7. Hanger Rods: Mild steel threaded both ends, threaded one end, or continuous threaded.
   8. Inserts: Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

2.2 REFRIGERANT

A. Refrigerant: R-454B as defined in ASHRAE Std 34.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.

B. Remove scale and dirt on inside and outside before assembly.

C. Prepare piping connections to equipment with flanges or unions.

3.2 INSTALLATION

A. Install refrigerant piping and accessories in accordance with split system manufacturer's recommendations.

B. Install refrigeration specialties in accordance with manufacturer's instructions.

C. Route piping in orderly manner, with plumbing parallel to building structure, and maintain gradient.

D. Where piping must be exposed, obtain approval of routing from Architect prior to installation.

E. Install piping to conserve building space and avoid interference with use of space.

F. Group piping whenever practical at common elevations and locations. Slope piping per manufacturer's recommendations.

G. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

H. Pipe Hangers and Supports:
   1. Install in accordance with ASME B31.5.
   2. Support horizontal piping as scheduled.
   3. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
   4. Place hangers within 12 inches of each horizontal elbow.
   5. Support vertical piping at every floor. Support riser piping independently of connected horizontal piping.
   6. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
   7. Provide copper plated hangers and supports for copper piping.

I. Arrange piping to return oil to compressor. Provide traps and loops in piping, and provide double risers as required. Slope horizontal piping 0.40 percent in direction of flow.

J. Provide clearance for installation of insulation and access to valves and fittings.

K. Provide access to concealed valves and fittings. Coordinate with General Contractor.

L. Flood piping system with nitrogen when brazing.

M. Where pipe support members are welded to structural building frame, brush clean, and apply one coat of zinc rich primer to welding.

N. Follow ASHRAE Std 15 procedures for charging and purging of systems and for disposal of refrigerant.

O. Fully charge completed system with refrigerant after testing.

P. Penetrations of roofs shall be made using manufactured roof penetration systems with curbs and pipe fittings. The use of "pitch pan" or similar installations is not acceptable.

3.3 FIELD QUALITY CONTROL

A. Test refrigeration system in accordance with ASME B31.5, and in accordance with VRFZ system manufacturer's recommendations.

3.4 SCHEDULES

A. Hanger Spacing for Copper Tubing.

1. 1/2 inch, 5/8 inch, and 7/8 inch OD: Maximum span, 5 feet; minimum rod size, 1/4 inch.
2. 1-1/8 inch OD: Maximum span, 6 feet; minimum rod size, 1/4 inch.
3. 1-3/8 inch OD: Maximum span, 7 feet; minimum rod size, 3/8 inch.
4. 1-5/8 inch OD: Maximum span, 8 feet; minimum rod size, 3/8 inch.

END OF SECTION 232300

SECTION 233100

HVAC DUCTS AND CASINGS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Metal ductwork.

B. Duct cleaning.

1.2 RELATED REQUIREMENTS

A. Section 230713 - Duct Insulation: External insulation and duct liner.

B. Section 233300 - Air Duct Accessories.

C. Section 230593 - Testing, Adjusting, and Balancing for HVAC.

1.3 REFERENCE STANDARDS

A. ASHRAE (FUND) - ASHRAE Handbook - Fundamentals; 2013.

B. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2015.

C. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2015a.

D. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005.

1.4 PERFORMANCE REQUIREMENTS

A. No variation of duct configuration or sizes permitted except by written permission. Size round ducts installed in place of rectangular ducts in accordance with ASHRAE table of equivalent rectangular and round ducts.

1.5 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Project Record Documents: Record actual locations of ducts and duct fittings. Record changes in fitting location and type. Show additional fittings used.

1.6 FIELD CONDITIONS

A. Do not install duct sealants when temperatures are less than those recommended by sealant manufacturers.

B. Maintain temperatures within acceptable range during and after installation of duct sealants.

PART 2 PRODUCTS

2.1 DUCT ASSEMBLIES

2.2 MATERIALS

A. Galvanized Steel for Ducts: Hot-dipped galvanized steel sheet, ASTM A653/A653M FS Type B, with G60/Z180 coating.

B. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant.

1. Type: Heavy mastic or liquid used alone or with tape, suitable for joint configuration and compatible with substrates, and recommended by manufacturer for pressure class of ducts.
2. Surface Burning Characteristics: Flame spread of zero, smoke developed of zero, when tested in accordance with ASTM E84.

C. Joint Sealers and Sealants: Non-hardening, water resistant, mildew and mold resistant.

2.3 DUCTWORK FABRICATION

A. Fabricate and support in accordance with SMACNA HVAC Duct Construction Standards and as indicated.

B. No variation of duct configuration or size permitted except by written permission.

C. Provide duct material, gages, reinforcing, and sealing for operating pressures indicated.

D. Construct T's, bends, and elbows with radius of not less than 1-1/2 times width of duct on centerline. Where not possible and where rectangular elbows must be used, provide air foil turning vanes of perforated metal with glass fiber insulation.

E. Provide turning vanes of perforated metal with glass fiber insulation when acoustical lining is indicated.

F. Provide air foil turning vanes when rectangular elbows must be used.

G. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible; maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream.

H. Fabricate continuously welded round and oval duct fittings in accordance with SMACNA HVAC Duct Construction Standards.

I. Provide standard 45 degree lateral wye takeoffs unless otherwise indicated where 90 degree conical tee connections may be used.

J. Where ducts are connected to exterior wall louvers and duct outlet is smaller than louver frame, provide blank-out panels sealing louver area around duct. Use same material as duct, painted black on exterior side; seal to louver frame and duct.

2.4 MANUFACTURED DUCTWORK AND FITTINGS

A. Manufacture in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, and as indicated. Provide duct material, gages,reinforcing, and sealing for operating pressures indicated.

B. Spiral Ducts: Machine made from round spiral lockseam duct, steel with mill phosphatized finish.
   1. Manufacturers:
      a. Wesco
      b. Wichita Sheet Metal.

C. Double Wall Insulated Spiral Ducts: Machine made from round spiral lockseam duct, steel outer wall with mill phosphatized finish or PVC coating, 1 inch thick fiberglass insulation, perforated galvanized steel inner wall; fittings manufactured with solid inner wall.
   1. Manufacturers:
      a. Wesco
      b. Wichita Sheet Metal.

D. Transverse Duct Connection System: SMACNA "E" rated rigidly class connection, interlocking angle and duct edge connection system with sealant, gasket, cleats, and corner clips.
   1. Manufacturers:

PART 3 EXECUTION

3.1 INSTALLATION

A. Install, support, and seal ducts in accordance with SMACNA HVAC Duct Construction Standards.

B. Spiral ductwork in exposed locations shall be installed with aircraft cable and manufactured cam type hangers.

C. Install in accordance with manufacturer's instructions.

D. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.

E. Duct sizes indicated are inside clear dimensions. For lined ducts, maintain sizes inside lining.

F. Install and seal metal and flexible ducts in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible.

G. Provide openings in ductwork where required to accommodate thermometers and controllers. Provide pilot tube openings where required for testing of systems, complete with metal can with spring device or

screw to ensure against air leakage. Where openings are provided in insulated ductwork, install insulation material inside a metal ring.

H. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.

I. Use crimp joints with or without bead for joining round duct sizes 8 inch and smaller with crimp in direction of air flow.

J. Use double nuts and lock washers on threaded rod supports.

K. Connect flexible ducts to metal ducts with draw bands plus sheet metal screws and adhesive. Use a maximum of 5' of flexible duct, at final connection to diffusers only, free of kinks. Do not install above inaccessible ceilings. Do not use flexible ductwork in exposed areas.

L. During construction provide temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.

M. At exterior wall louvers, seal duct to louver frame and install blank-out panels.

3.2 CLEANING

A. Clean duct system and force air at high velocity through duct to remove accumulated dust. To obtain sufficient air, clean half the system at a time. Protect equipment that could be harmed by excessive dirt with temporary filters, or bypass during cleaning.

3.3 SCHEDULES

A. Ductwork Material:
   1. Low Pressure Supply (Heating Systems): Steel.
   2. Low Pressure Supply (System with Cooling Coils): Steel.
   3. Return and Relief: Steel.
   4. General Exhaust: Steel.
   5. Outside Air Intake: Steel.

B. Ductwork Pressure Class:
   1. Supply (System with Cooling Coils): 1 inch.
   2. Return and Relief: 1 inch.
   3. General Exhaust: 1/2 inch.

C. Round ductwork shall be spiral where exposed. Concealed round ductwork may be spiral, double or single wall, or fabricated.
   1. Base bid: Exposed ductwork shall be single wall spiral.
   2. Alternate bid: Exposed ductwork shall be double wall spiral.

END OF SECTION 233100

SECTION 233300

AIR DUCT ACCESSORIES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Air turning devices/extractors.

B. Backdraft dampers.

C. Combination fire and smoke dampers.

D. Duct access doors.

E. Duct test holes.

F. Fire dampers.

G. Flexible duct connections.

H. Smoke dampers.

I. Volume control dampers.

1.2 RELATED REQUIREMENTS

A. Section 233100 - HVAC Ducts and Casings.

1.3 REFERENCE STANDARDS

A. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.

B. NFPA 92 - Standard for Smoke Control Systems; 2015.

C. NFPA 96 - Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations; 2014.

D. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible; 2005.

E. UL 33 - Safety Heat Responsive Links for Fire-Protection Service; Current Edition, Including All Revisions.

F. UL 555 - Standard for Fire Dampers; Current Edition, Including All Revisions.

G. UL 555S - Standard for Smoke Dampers; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide for shop fabricated assemblies including volume control dampers. Include electrical characteristics and connection requirements.

C. Shop Drawings: Indicate for shop fabricated assemblies including volume control dampers.

D. Manufacturer's Installation Instructions: Provide instructions for fire dampers.

E. Project Record Drawings: Record actual locations of access doors and test holes.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect dampers from damage to operating linkages and blades.

PART 2 PRODUCTS

2.1 AIR TURNING DEVICES/EXTRACTORS

A. Multi-blade device with blades aligned in short dimension; steel construction; with individually adjustable blades, mounting straps.

2.2 BACKDRAFT DAMPERS

A. Gravity Backdraft Dampers, Size 24 inches or Smaller, Furnished with Air Moving Equipment: Air moving equipment manufacturer's standard construction.

2.3 COMBINATION FIRE AND SMOKE DAMPERS

A. Fabricate in accordance with NFPA 90A, UL 555, UL 555S, and as indicated.

B. Provide factory sleeve and collar for each damper.

C. Multiple Blade Dampers: Fabricate with 16 gage galvanized steel frame and blades, oil-impregnated bronze or stainless steel sleeve bearings and plated steel axles, stainless steel jamb seals, 1/8 x 1/2 inch plated steel concealed linkage, stainless steel closure spring, blade stops, and lock, and 1/2 inch actuator shaft.

D. Operators: UL listed and labelled spring return electric type suitable for 120 volts, single phase, 60 Hz. Locate damper operator on exterior of duct and link to damper operating shaft.

2.4 DUCT ACCESS DOORS

A. Fabrication: Rigid and close-fitting of galvanized steel with sealing gaskets and quick fastening locking devices. For insulated ducts, install minimum 1 inch thick insulation with sheet metal cover.
   1. Less Than 12 inches Square: Secure with sash locks.
   2. Up to 18 inches Square: Provide two hinges and two sash locks.
   3. Up to 24 x 48 inches: Three hinges and two compression latches with outside and inside handles.
   4. Larger Sizes: Provide an additional hinge.

2.5 DUCT TEST HOLES

A. Temporary Test Holes: Cut or drill in ducts as required. Cap with neat patches, neoprene plugs, threaded plugs, or threaded or twist-on metal caps.

B. Permanent Test Holes: Factory fabricated, air tight flanged fittings with screw cap. Provide extended neck fittings to clear insulation.

2.6 FIRE DAMPERS

A. Fabricate in accordance with NFPA 90A and UL 555, and as indicated.

B. Ceiling Dampers: Galvanized steel, 22 gage frame and 16 gage flap, two layers 0.125 inch ceramic fiber on top side and one layer on bottom side for round flaps, with locking clip.

C. Horizontal Dampers: Galvanized steel, 22 gage frame, stainless steel closure spring, and lightweight, heat retardant non-asbestos fabric blanket.

D. Curtain Type Dampers: Galvanized steel with interlocking blades. Provide stainless steel closure springs and latches for horizontal installations. Configure with blades out of air stream except for 1.0 inch pressure class ducts up to 12 inches in height.

E. Multiple Blade Dampers: 16 gage galvanized steel frame and blades, oil-impregnated bronze or stainless steel sleeve bearings and plated steel axles, 1/8 x 1/2 inch plated steel concealed linkage, stainless steel closure spring, blade stops, and lock.

F. Fusible Links: UL 33, separate at 160 degrees F with adjustable link straps for combination fire/balancing dampers.

2.7 FLEXIBLE DUCT CONNECTIONS

A. Fabricate in accordance with SMACNA HVAC Duct Construction Standards and as indicated.

B. Flexible Duct Connections: Fabric crimped into metal edging strip.
   1. Fabric: UL listed fire-retardant neoprene coated woven glass fiber fabric to NFPA 90A, minimum density 30 oz per sq yd.
      a. Net Fabric Width: Approximately 2 inches wide.
   2. Metal: 3 inches wide, 24 gage thick galvanized steel.

C. Leaded Vinyl Sheet: Minimum 0.55 inch thick, 0.87 lbs per sq ft, 10 dB attenuation in 10 to 10,000 Hz range.

2.8 SMOKE DAMPERS

A. Fabricate in accordance with NFPA 90A and UL 555S, and as indicated.

B. Dampers: UL Class 1 multiple blade type fire damper, normally closed automatically operated by 120 VAC electric actuator.

C. Electro Thermal Link: Fusible link melting at 165 degrees F; 120 volts, single phase, 60 Hz; UL listed and labeled.

2.9 VOLUME CONTROL DAMPERS

A. Fabricate in accordance with SMACNA HVAC Duct Construction Standards and as indicated.

B. Splitter Dampers:
   1. Material: Same gage as duct to 24 inches size in either direction, and two gages heavier for sizes over 24 inches.
   2. Blade: Fabricate of single thickness sheet metal to streamline shape, secured with continuous hinge or rod.
   3. Operator: Minimum 1/4 inch diameter rod in self aligning, universal joint action, flanged bushing with set screw .

C. Single Blade Dampers: Fabricate for duct sizes up to 6 x 30 inch.

D. Multi-Blade Damper: Fabricate of opposed blade pattern with maximum blade sizes 8 x 72 inch. Assemble center and edge crimped blades in prime coated or galvanized channel frame with suitable hardware.

E. End Bearings: Except in round ducts 12 inches and smaller, provide end bearings. On multiple blade dampers, provide oil-impregnated nylon or sintered bronze bearings.

F. Quadrants:
   1. Provide locking, indicating quadrant regulators on single and multi-blade dampers.
   2. On insulated ducts mount quadrant regulators on stand-off mounting brackets, bases, or adapters.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install accessories in accordance with manufacturer's instructions, NFPA 90A, and follow SMACNA HVAC Duct Construction Standards. Refer to Section 233100 for duct construction and pressure class.

B. Provide backdraft dampers on exhaust fans or exhaust ducts nearest to outside and where indicated.

C. Provide duct access doors for inspection and cleaning before and after filters, coils, fans, automatic dampers, at fire dampers, combination fire and smoke dampers, and elsewhere as indicated. Provide for cleaning kitchen exhaust ducts in accordance with NFPA 96. Provide minimum 8 x 8 inch size for hand access, size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.

D. Provide duct access doors for inspection and cleaning before and after filters, coils, fans, automatic dampers, at fire dampers, combination fire and smoke dampers, and elsewhere as indicated. Provide minimum 8 x 8 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated. Provide 4 x 4 inch for balancing dampers only. Review locations prior to fabrication.

E. Provide duct test holes where indicated and required for testing and balancing purposes.

F. Provide fire dampers, combination fire and smoke dampers, and smoke dampers at locations indicated, where ducts and outlets pass through fire rated components, and where required by authorities having jurisdiction. Install with required perimeter mounting angles, sleeves, breakaway duct connections, corrosion resistant springs, bearings, bushings and hinges.

G. Install smoke dampers and combination smoke and fire dampers in accordance with NFPA 92.

H. Install smoke damper motors in locations to allow service/replacement without removal of permenant building components.

I. Demonstrate re-setting of fire dampers to Owner's representative.

J. At fans and motorized equipment associated with ducts, provide flexible duct connections immediately adjacent to the equipment.

K. Provide balancing dampers at points on supply, return, and exhaust systems where branches are taken from larger ducts as required for air balancing. Install minimum 2 duct widths from duct take-off.

L. Provide balancing dampers on duct take-off to diffusers, grilles, and registers, regardless of whether dampers are specified as part of the diffuser, grille, or register assembly. Omit dampers only where noted on drawings.

M. Where dampers or other accessories that require adjustment or maintenance are located above hard ceilings, provide access panel in ceiling. Coordinate with G.C.

END OF SECTION 233300

SECTION 233700

AIR OUTLETS AND INLETS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Diffusers.

B. Registers/grilles.

C. Louvers.

1.2 REFERENCE STANDARDS

A. ASHRAE Std 70 - Method of Testing the Performance of Air Outlets and Inlets; 2006 (R2011).

1.3 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data for equipment required for this project. Review outlets and inlets as to size, finish, and type of mounting prior to submission. Submit schedule of outlets and inlets showing type, size, location, application, and noise level.

1.4 QUALITY ASSURANCE

A. Test and rate air outlet and inlet performance in accordance with ASHRAE Std 70.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Hart & Cooley, Inc: www.hartandcooley.com.

B. Krueger: www.krueger-hvac.com/#sle.

C. Price Industries: www.price-hvac.com/#sle.

D. Titus: www.titus-hvac.com/#sle.

2.2 DIFFUSERS, REGISTERS, AND GRILLES

A. Type and performance are scheduled on the drawings.

B. Coordinate finish of all devices with Architect.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with manufacturer's instructions.

B. Check location of outlets and inlets and make necessary adjustments in position to conform with architectural features, symmetry, and lighting arrangement.

C. Install diffusers to ductwork with air tight connection.

D. Provide balancing dampers on duct take-off to diffusers, and grilles and registers, despite whether dampers are specified as part of the diffuser, or grille and register assembly. Omit dampers where drawings specifically indicate devices are to be provided without dampers.

E. Paint ductwork visible behind air outlets and inlets matte black. Coordinate with G.C.

END OF SECTION 233700

SECTION 234000

HVAC AIR CLEANING DEVICES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Disposable, extended area panel filters.

B. Disposable panel filters.

1.2 REFERENCE STANDARDS

A. ASHRAE Std 52.2 - Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size; 2012, with 2015 amendments.

B. UL 900 - Standard for Air Filter Units; Current Edition, Including All Revisions.

1.3 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on filter media, filter performance data, filter assembly and filter frames, dimensions, motor locations and electrical characteristics and connection requirements.

C. Shop Drawings: Indicate filter assembly and filter frames, dimensions, motor locations, and electrical characteristics and connection requirements.

1.4 EXTRA MATERIALS

A. Provide one set of disposable panel filters. Filters shall be delivered to Owner.

PART 2 PRODUCTS

2.1 FILTER MANUFACTURERS

A. American Filtration Inc: www.americanfiltration.com/#sle.

B. AAF International/American Air Filter: www.aafintl.com/#sle.

C. Camfil Farr Company: www.camfilfarr.com/#sle.

2.2 DISPOSABLE, EXTENDED AREA PANEL FILTERS

A. Media: UL 900 Class 1, pleated, lofted, non-woven, reinforced cotton fabric; supported and bonded to welded wire grid by corrugated aluminum separators.
   1. Frame: Non-flammable.
   2. Nominal thickness: 2 inches.

B. Minimum Efficiency Reporting Value (MERV): 8, when tested in accordance with ASHRAE 52.2.

2.3 DISPOSABLE PANEL FILTERS

A. Media: UL 900 Class 2, fiber blanket, factory sprayed with flameproof, non-drip, non-volatile adhesive.
   1. Thickness: 1 inch.

B. Performance Rating:
   1. Face Velocity: 500 FPM.
   2. Initial Resistance: 0.15 inch WG.
   3. Recommended Final Resistance: 0.50 inches WG.

C. Casing: Cardboard frame.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install air cleaning devices in accordance with manufacturer's instructions.

B. Prevent passage of unfiltered air around filters with felt, rubber, or neoprene gaskets.

C. Do not operate fan system until filters (temporary or permanent) are in place. Replace temporary filters used during construction and testing, with clean set.

D. Ensure that filters are easily removable from equipment, and that access is not blocked by other installations.

END OF SECTION 234000

SECTION 237210

AIR-TO-AIR ENERGY RECOVERY EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes static plate rooftop air to air energy recovery ventilators.

PART 2 - PRODUCTS

2.1 AIR TO AIR ENERGY RECOVERY VENTILATORS

A. Manufacturers:
   1. Renewaire
   2. Lossnay
   3. Approved substitute

B. Quality Assurance
   1. The energy recovery cores used in these products shall be certified by ARI under its Standard 1060 for Energy Recovery Ventilators. ARI published certifications shall confirm manufacture's published performance for airflow, static pressure, temperature and total effectiveness, purge air (OACF) and exhaust air leakage (EATR). Products that are not currently ARI Certified will not be accepted.
   2. Manufacturer shall be able to provide evidence of independent testing of the core by Underwriters Laboratory (UL), verifying a maximum flame spread index (FSI) of 25 and a maximum smoke developed index (SDI) of 50 thereby meeting NFPA 90A and NFPA 90B requirements for materials in a compartment handling air intended for circulation through a duct system. The method of test shall be UL Standard 723.
   3. Unit shall be listed under UL 1812 Standard for Ducted Air to Air Heat Exchangers.
   4. The cores shall be warranted to be free of manufacturing defects and to retain its functional characteristics, under circumstances of normal use, for a period of ten years from the date of purchase. Balance of Unit shall be warranted to be free of manufacturing defects and to retain its functional characteristics, under circumstances of normal use, for a period of two years from the date of purchase.

C. Energy Transfer
   1. Shall be capable of transferring both sensible and latent energy between air streams. Latent energy transfer shall be accomplished by direct water vapor transfer from one airstream to the other, without exposing transfer media in succeeding cycles directly to the exhaust air and then to the fresh air.

D. Passive Frost Control
   1. Energy-transfer element shall perform without condensing or frosting under normal operating conditions (defined as outside temperatures above -10°F and inside relative humidity below 40%). Occasional extreme conditions shall not affect the usual function or performance of the element. No condensate drains will be allowed.

E. Continuous Ventilation
   1. Unit shall have the capacity to operate continuously without the need for bypass, recirculation, preheaters, or defrost cycles under normal operating conditions.

F. Positive Airstream Separation
   1. Water vapor transfer shall be through molecular transport by hydroscopic resin and shall not be accomplished by “porous plate” mechanisms. Exhaust and fresh airstreams shall at all times travel in separate passages, and airstreams shall not mix.

G. Laminar Flow
   1. Airflow through the energy exchange element shall be laminar, avoiding deposition of particulates on the interior of the energy exchange plate material.

H. Construction

1. Fixed-plate energy-exchange element. Energy-exchange module shall be of fixed-plate cross-flow construction, with no moving parts.
2. No condensate drain pans or drains shall be allowed and unit shall be capable of operating in winter and summer conditions without generating condensate.
3. Housing shall be constructed of galvanized, 20-gauge steel, with lapped corners, and gasketed, zinc plated screw fasteners.
4. Unit shall have single-point power connection.
5. Flange components shall be provided suitable for connection of ductwork.
6. Access door shall provide easy access to blowers, energy transfer elements, and filters. Panel shall be gasketed to provide air-tight seal.
7. Case walls and doors shall be insulated with 1" FSK high-density board insulation, eliminating the possibility of exposing the fresh air to glass fibers.
8. Energy-exchange element shall be protected by 30% efficient 2" nominal pleated, disposable filters.
9. Blowers shall be direct drive.
10. Units shall be provided for single point wiring connection.

PART 3 - EXECUTION

3.1 MANUFACTURER'S DIRECTIONS:

A. Delivery, Storage and Handling - Equipment shall be stored and handled according to the manufacturer's recommendation.

B. Install equipment in strict accordance with manufacturer's recommendations and requirements of other Sections.

3.2 CONNECTIONS

A. Connect ductwork at fresh air and exhaust connections on unit.

B. Provide flexible duct connector at each connection.

C. Provide power wiring and connect controls.

END OF SECTION 237210

SECTION 237413

PACKAGED OUTDOOR CENTRAL-STATION AIR-HANDLING UNITS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Packaged roof top unit.

B. Unit controls.

C. Roof mounting curb and base.

1.2 RELATED REQUIREMENTS

A. Section 230548 - Vibration Controls for HVAC Piping and Equipment.

B. Section 234000 - HVAC Air Cleaning Devices.

C. Section 253519 - Integrated Automation Control Valves.

D. Section 262717 - Equipment Wiring: Installation and wiring of thermostats and other controls components; wiring from unit terminal strip to remote panel.

1.3 REFERENCE STANDARDS

A. AHRI 210/240 - Standard for Performance Rating of Unitary Air-Conditioning and Air-Source Heat Pump Equipment; 2008.

B. AHRI 270 - Sound Performance Rating of Outdoor Unitary Equipment; 2008.

C. ASHRAE Std 135 - BACnet - A Data Communication Protocol for Building Automation and Control Networks; 2024, with Errata (2025).

D. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.

1.4 SUBMITTALS

A. See Section 013000 - Administrative Requirements for submittal procedures.

B. Product Data: Provide capacity and dimensions of manufactured products and assemblies required for this project. Indicate electrical service with electrical characteristics and connection requirements, and duct connections.

C. Shop Drawings: Indicate capacity and dimensions of manufactured products and assemblies required for this project. Indicate electrical service with electrical characteristics and connection requirements, and duct connections.

D. Manufacturer's Instructions: Indicate assembly, support details, connection requirements, and include start-up instructions.

E. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, installation instructions, maintenance and repair data, and parts listing.

F. Warranty: Submit manufacturer's warranty and ensure forms have been filled out in Owner's name and registered with manufacturer.

1.5 WARRANTY

A. See Section 017800 - Closeout Submittals for additional warranty requirements.

B. Provide a five year warranty to include coverage for refrigeration compressors.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Daikin

B. Trane

C. Carrier

2.2 PERFORMANCE REQUIREMENTS

A. Performance shall be as scheduled on drawings.

2.3 MANUFACTURED UNITS

A. General: Roof mounted units having gas burner and electric refrigeration.

B. Description: Self-contained, packaged, factory assembled and prewired, consisting of cabinet and frame, supply fan, heat exchanger and burner, controls, air filters, refrigerant cooling coil and compressor, condenser coil and condenser fan.

2.4 FABRICATION

A. Cabinet: Steel with baked enamel finish, including access doors with piano hinges and locking handle.

B. Heat Exchangers: Aluminized steel, of welded construction.

C. Supply Fan: Forward curved centrifugal type, resiliently mounted with V-belt drive, adjustable variable pitch motor pulley, and rubber isolated hinge mounted high efficiency motor or direct drive as indicated.

2.5 BURNER

A. Gas Burner: Induced draft type burner with adjustable combustion air supply, pressure regulator, gas valves, manual shut-off, intermittent spark or glow coil ignition, flame sensing device, and automatic 100 percent shut-off pilot.

B. Gas Burner Safety Controls: Energize ignition, limit time for establishment of flame, prevent opening of gas valve until pilot flame is proven, stop gas flow on ignition failure, energize blower motor, and after airflow proven and slight delay, allow gas valve to open.

2.6 ELECTRIC HEATING COIL

A. Finned tube heating elements easily accessible with automatic reset thermal cut-out, built-in magnetic contactors, galvanized steel frame, control circuit transformer and fuse, manual reset thermal cut-out, airflow proving device, toggle switch (pilot duty), load fuses.

B. Controls: Start supply fan before electric elements are energized and continue operating until air temperature reaches minimum setting, with switch for continuous fan operation.

2.7 INDOOR COIL

A. Provide copper tube aluminum fin coil assembly with galvanized drain pan and connection.

B. Provide capillary tubes or thermostatic expansion valves for units of 6 Tons of refrigeration capacity and less, and thermostatic expansion valves and alternate row circuiting for units 7.5 Tons of refrigeration cooling capacity and larger.

2.8 COMPRESSOR

A. Provide scroll compressors, resiliently mounted with positive lubrication, crankcase heater, high and low pressure safety controls, motor overload protection, suction and discharge service valves and gauge ports, and filter drier.

B. For heat pump units, provide reversing valve, suction line accumulator, discharge muffler, flow control check valve, and solid-state defrost control utilizing thermistors.

2.9 OUTDOOR COIL

A. Provide copper tube aluminum fin coil assembly with subcooling rows and coil guard.

B. Provide direct drive propeller fans, resiliently mounted with fan guard, motor overload protection, wired to operate with compressor. Provide high efficiency fan motors.

2.10 OPERATING CONTROLS

A. Provide microprocessor controller with thermostat interface board. Reference controls drawings and specifications.

B. BAS, SCADA, or other Integrated Automation Link: ASHRAE Std 135, BACnet MS/TP.

C. Control Valves: Field-installed, modulating, ball type with position tracking; see Section 253519.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that roof is ready to receive work and opening dimensions are as indicated on shop drawings.

B. Verify that proper power supply is available.

3.2 INSTALLATION

A. Install in accordance with manufacturer's instructions.

3.3 SYSTEM STARTUP

A. Prepare and start equipment. Adjust for proper operation.

END OF SECTION 237413

SECTION 238127

MINI-SPLIT HEAT PUMP SYSTEMS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Air-source heat pumps.

B. Indoor ductless fan & coil units.

C. Controls.

1.2 RELATED REQUIREMENTS

A. Section 233100 - HVAC Ducts and Casings.

B. Section 262717 - Equipment Wiring: Electrical characteristics and wiring connections and installation and wiring of thermostats and other controls components.

1.3 REFERENCE STANDARDS

A. AHRI 210/240 - Standard for Performance Rating of Unitary Air-Conditioning and Air-Source Heat Pump Equipment; 2008.

B. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.

C. NFPA 90B - Standard for the Installation of Warm Air Heating and Air-Conditioning Systems; 2015.

D. UL 207 - Standard for Refrigerant-Containing Components and Accessories, Nonelectrical; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. Product Data: Provide rated capacities, weights, accessories, electrical nameplate data, and wiring diagrams.

B. Shop Drawings: Indicate assembly, required clearances, and location and size of field connections.

C. Design Data: Indicate refrigerant pipe sizing.

D. Manufacturer's Instructions: Indicate rigging, assembly, and installation instructions.

E. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, installation instructions, maintenance and repair data, and parts listing.

F. Warranty: Submit manufacturers warranty and ensure forms have been filled out in Owner s name and registered with manufacturer.

1.5 WARRANTY

A. Provide five year manufacturers warranty for heat exchangers.

B. Provide five year manufacturers warranty for compressors.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Mitsubishi

B. Approved substitute.

2.2 SYSTEM DESIGN

A. Split-System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed.

1. Heating and Cooling: Air-source electric heat pump located in outdoor unit with evaporator.
2. Provide refrigerant lines internal to units and between indoor and outdoor units, factory cleaned, dried, pressurized and sealed, with insulated suction line.

B. Performance Requirements: See Drawings for additional requirements.

2.3 INDOOR UNITS FOR DUCTLESS SYSTEMS

A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, supply fan, evaporator coil, and controls; wired for single power connection with control transformer.
   1. Location: High-wall.
   2. Cabinet: Plastic.
      a. Finish: White.
   3. Fan: Line-flow fan direct driven by a single motor.
   4. Filter return air with washable, antioxidant pre-filter and a pleated anti-allergy enzyme filter.

B. Evaporator Coils: Copper tube aluminum fin assembly, galvanized or polymer drain pan sloped in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.
   1. Construction and Ratings: In accordance with AHRI 210/240 and UL 207.
   2. Manufacturer: System manufacturer.

C. Remote Actuators:

2.4 OUTDOOR UNITS

A. The outdoor unit shall be equipped with an electronic control board that interfaces with the indoor unit to perform all necessary operation functions.

B. The outdoor unit shall be completely factory assembled, piped, and wired. Each unit must be test run at the factory.

C. Cabinet
   1. The casing shall be constructed from galvanized steel plate, finished with an electrostatically applied, thermally fused acrylic or polyester powder coating for corrosion protection and have a Munsell 3Y 7.8/1.1 finish.
   2. Mounting feet shall be provided and shall be welded to the base of the cabinet and be of sufficient size to afford reliable equipment mount and stability.
   3. Easy access shall be afforded to all serviceable parts by means of removable panel sections.
   4. The fan grill shall be of ABS plastic.

D. Fan
   1. The fan blades shall be of high performance, aerodynamic design for quiet operation, and the fan motor bearings shall be permanently lubricated.
   2. The outdoor unit shall have horizontal discharge airflow. The fan shall be mounted in front of the coil, pulling air across it from the rear and dispelling it through the front. The fans shall be provided with a raised guard to prevent external contact with moving parts.

E. Coil
   1. The L shaped condenser coil shall be of copper tubing with flat aluminum fins to reduce debris build up and allow maximum airflow. The coil shall be protected with an integral metal guard.
   2. Refrigerant flow from the condenser shall be controlled by means of an electronic linear expansion valve (LEV) metering device. The LEV shall be controlled by a microprocessor controlled step motor.
   3. All refrigerant lines between outdoor and indoor units shall be of annealed, refrigeration grade copper tubing, ARC Type, meeting ASTM B280 requirements, individually insulated in twin-tube, flexible, closed-cell, CFC-free (ozone depletion potential of zero), elastomeric material for the insulation of refrigerant pipes and tubes with thermal conductivity equal to or better than 0.27 BTU-inch/hour per Sq Ft / °F, a water vapor transmission equal to or better than 0.08 Perm-inch and superior fire ratings such that insulation will not contribute significantly to fire and up to 1” thick insulation shall have a - Flame-Spread Index of less than 25 and a Smoke-development Index of less than 50 as tested by ASTM E 84 and CAN / ULC S-102. All refrigerant line connections shall be flare type sized as required and tightened to manufacturers specified torque value.

F. Compressor
   1. The compressor for shall be a Mitsubishi Electric, injection port equipped, Frame Compliant Scroll compressor with Variable Speed Inverter Drive Technology.
   2. The compressor shall be driven by inverter circuit to control compressor speed. The compressor speed shall dynamically vary to match the room loads, increasing the efficiency of the system which shall result in significant energy savings.
   3. To prevent liquid from accumulating in the compressor during the off cycle, a minimal amount of current shall be automatically, intermittently applied to the compressor motor windings to maintain sufficient heat to vaporize any refrigerant. No crankcase heater is to be used.
   4. The outdoor unit shall have an accumulator and high pressure safety switch. The compressor shall be mounted to avoid the transmission of vibration.

G. Electrical
   1. The electrical power of the unit shall be 208volts or 230 volts, single phase, 60 hertz. The unit shall be capable of satisfactory operation within voltage limits of 187 volts to 253 volts.
   2. Power for the indoor unit shall be supplied from the outdoor unit via Mitsubishi Electric A-Control using three (3) fourteen (14) gauge AWG conductors plus ground wire connecting the units.
   3. The outdoor unit shall be controlled by the microprocessor located in the indoor unit.
   4. The control signal between the indoor unit and the outdoor unit shall be pulse signal 24 volts DC.
   5. The unit shall have Pulse Amplitude Modulation circuit to utilize 98% of input power supply.

2.5 ACCESSORY EQUIPMENT

A. Room Thermostat: Wall-mounted, wired, electric solid state microcomputer based room thermostat with remote sensor to maintain temperature setting; low-voltage; with following features:
   1. Automatic switching from heating to cooling.
   2. Preferential rate control to minimize overshoot and deviation from setpoint.
   3. Set-up for four separate temperatures per day.
   4. Programming based on weekdays, Saturday and Sunday.
   5. Thermostat display:
      a. Actual room temperature.
      b. Programmed temperature.
      c. System mode indication: heating, cooling, fan auto, off, and on, auto or on, off.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with manufacturer's instructions and requirements of local authorities having jurisdiction.

B. Install in accordance with NFPA 90A and NFPA 90B.

END OF SECTION 238127

SECTION 238128

SMALL SPLIT-SYSTEM HEATING AND COOLING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Air cooled condensing units.

B. Indoor air handler (fan & coil) units for duct connection.

C. Controls.

1.2 RELATED REQUIREMENTS

A. Section 233100 - HVAC Ducts and Casings.

B. Section 262717 - Equipment Wiring: Electrical characteristics and wiring connections and installation and wiring of thermostats and other controls components.

1.3 REFERENCE STANDARDS

A. AHRI 210/240 - Standard for Performance Rating of Unitary Air-Conditioning and Air-Source Heat Pump Equipment; 2008.

B. AHRI 520 - Performance Rating of Positive Displacement Condensing Units; 2004.

C. ASHRAE Std 15 - Safety Standard for Refrigeration Systems; 2013.

D. ASHRAE Std 23.1 - Methods of Testing for Rating Positive Displacement Refrigerant Compressors and Condensing Units; 2010.

E. NEMA MG 1 - Motors and Generators; 2014.

F. NFPA 54 - National Fuel Gas Code; 2015.

G. NFPA 90A - Standard for the Installation of Air-Conditioning and Ventilating Systems; 2015.

H. NFPA 90B - Standard for the Installation of Warm Air Heating and Air-Conditioning Systems; 2015.

I. NFPA 211 - Guide for Smoke and Heat Venting; 2013, Including All Amendments.

J. UL 207 - Standard for Refrigerant-Containing Components and Accessories, Nonelectrical; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. Product Data: Provide rated capacities, weights, accessories, electrical nameplate data, and wiring diagrams.

B. Shop Drawings: Indicate assembly, required clearances, and location and size of field connections.

C. Design Data: Indicate refrigerant pipe sizing.

D. Manufacturer's Instructions: Indicate rigging, assembly, and installation instructions.

E. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, installation instructions, maintenance and repair data, and parts listing.

F. Warranty: Submit manufacturers warranty and ensure forms have been filled out in Owner s name and registered with manufacturer.

G. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.

1. See Section 016000 - Product Requirements, for additional provisions.
2. Extra Filters: One for each unit.

1.5 WARRANTY

A. Provide five year manufacturers warranty for heat exchangers.

B. Provide five year manufacturers warranty for compressors.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Carrier Corporation: www.carrier.com.

B. Approved substitute.

2.2 SYSTEM DESIGN

A. Split-System Heating and Cooling Units: Self-contained, packaged, matched factory-engineered and assembled, pre-wired indoor and outdoor units; UL listed.
   1. Heating: Electric resistance heating.
   2. Cooling: Outdoor electric condensing unit with evaporator coil in central ducted indoor unit.
   3. Provide refrigerant lines internal to units and between indoor and outdoor units, factory cleaned, dried, pressurized and sealed, with insulated suction line.
      a. Pipe sizes for each unit shall be sized per the manufacturer's recommendations and account for line length and suction lift requirements. Provide manufacturer's confirmation for each unit that proposed installation and line sizes will provide proper system operation.

B. Performance Requirements: See Drawings for additional requirements.

2.3 INDOOR UNITS FOR DUCTED SYSTEMS

A. Indoor Units: Self-contained, packaged, factory assembled, pre-wired unit consisting of cabinet, supply fan, heating and cooling element(s), controls, and accessories; wired for single power connection with control transformer.
   1. Air Flow Configuration: As indicated on drawings.
   2. Cabinet: Steel with baked enamel finish, easily removed and secured access doors with safety interlock switches, glass fiber insulation with reflective liner.

B. Supply Fan: Centrifugal type rubber mounted with direct or belt drive with adjustable variable pitch motor pulley.
   1. Motor: NEMA MG 1; 1750 rpm single speed, permanently lubricated, hinge mounted.
   2. Motor Electrical Characteristics:

C. Air Filters: 1 inch thick urethane, washable type arranged for easy replacement.

D. Evaporator Coils: Copper tube aluminum fin assembly, galvanized or polymer drain pan sloped in all directions to drain, drain connection, refrigerant piping connections, restricted distributor or thermostatic expansion valve.
   1. Construction and Ratings: In accordance with AHRI 210/240 and UL 207.
   2. Manufacturers: System manufacturer.

2.4 OUTDOOR UNITS

A. Outdoor Units: Self-contained, packaged, pre-wired unit consisting of cabinet, with compressor and condenser.
   1. Refrigerant: R-454B.
   2. Construction and Ratings: In accordance with AHRI 210/240 with testing in accordance with ASHRAE Std 23 and UL listed.

B. Compressor: Scroll, 3600 rpm, AHRI 520 resiliently mounted integral with condenser, with positive lubrication, crankcase heater, high pressure control, motor overload protection, service valves and drier. Provide time delay control to prevent short cycling.

C. Air Cooled Condenser: ARI 520; Aluminum fin and copper tube coil, with direct drive axial propeller fan resiliently mounted, galvanized fan guard.

D. Accessories: Filter drier, high pressure switch (manual reset), low pressure switch (automatic reset), service valves and gage ports, thermometer well (in liquid line).
   1. Provide thermostatic expansion valves.

E. Operating Controls:

1. Control by programmable room thermostat to maintain room temperature setting.

2.5 ELECTRIC FURNACE COMPONENTS

A. Electric Heater: Helix wound bare nichrome wire heating elements arranged in incremental stages of 5 kW each, with porcelain insulators.

B. Operating Controls:
   1. Heater stages energized in sequence with pre-determined delay between heating stages.
   2. High limit temperature control to de-energize heating elements, with automatic reset.

2.6 ACCESSORY EQUIPMENT

A. Room Thermostat: Wall-mounted, electric solid state microcomputer based room thermostat with sensor to maintain temperature setting; low-voltage; with following features:
   1. Automatic switching from heating to cooling.
   2. Preferential rate control to minimize overshoot and deviation from setpoint.
   3. Set-up for four separate temperatures per day.
   4. Programming based on weekdays, Saturday and Sunday.
   5. Thermostat display:
      a. Actual room temperature.
      b. Programmed temperature.
      c. System mode indication: heating, cooling, fan auto, off, and on, auto or on, off.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with NFPA 90A and NFPA 90B.

B. Install gas fired furnaces in accordance with NFPA 54.

C. Provide combustion air and vent connections in accordance with manufacturer's recommendations.

D. Install refrigeration systems in accordance with ASHRAE Std 15.

END OF SECTION 238128

SECTION 260501

ELECTRICAL DEMOLITION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Electrical demolition.

PART 3 EXECUTION

2.1 EXAMINATION

A. Verify that abandoned wiring and equipment serve only abandoned facilities.

B. Report discrepancies to Architect before disturbing existing installation.

C. Beginning of demolition means installer accepts existing conditions.

2.2 PREPARATION

A. Disconnect and remove electrical systems throughout entire building.

2.3 DEMOLITION OF ELECTRICAL WORK

A. Remove existing installations in their entirety.

B. Remove abandoned wiring.

C. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. Cut conduit flush with walls and floors, and patch surfaces.

D. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if conduit servicing them is abandoned and removed.

E. Disconnect and remove abandoned panelboards and distribution equipment.

F. Disconnect and remove electrical devices and equipment serving utilization equipment that has been removed.

G. Disconnect and remove abandoned luminaires. Remove brackets, stems, hangers, and other accessories.

H. Repair adjacent construction and finishes damaged during demolition.

I. Remove all abandoned knob insulators and other appurtances from the building.

END OF SECTION 260501

SECTION 260519

LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Single conductor building wire.

B. Metal-clad cable.

C. Power and control tray cable.

D. Wiring connectors.

E. Electrical tape.

F. Oxide inhibiting compound.

G. Wire pulling lubricant.

H. Cable ties.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems: Additional requirements for grounding conductors and grounding connectors.

B. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

C. Section 283100 - Fire Detection and Alarm: Fire alarm system conductors and cables.

1.3 REFERENCE STANDARDS

A. ASTM B3 - Standard Specification for Soft or Annealed Copper Wire; 2013.

B. ASTM B8 - Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft; 2011.

C. ASTM B33 - Standard Specification for Tin-Coated Soft or Annealed Copper Wire for Electrical Purposes; 2010 (Reapproved 2014).

D. ASTM B787/B787M - Standard Specification for 19 Wire Combination Unilay-Stranded Copper Conductors for Subsequent Insulation; 2004 (Reapproved 2014).

E. ASTM B800 - Standard Specification for 8000 Series Aluminum Alloy Wire for Electrical Purposes - Annealed and Intermediate Tempers; 2005 (Reapproved 2011).

F. ASTM B801 - Standard Specification for Concentric-Lay-Stranded Conductors of 8000 Series Aluminum Alloy Wire for Subsequent Covering of Insulation; 2007 (Reapproved 2012).

G. ASTM D3005 - Standard Specification for Low-Temperature Resistant Vinyl Chloride Plastic Pressure-Sensitive Electrical Insulating Tape; 2010.

H. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

I. NECA 104 - Recommended Practice for Installing Aluminum Building Wire and Cable; 2012.

J. NECA 120 - Standard for Installing Armored Cable (AC) and Metal-Clad Cable (MC); 2012.

K. NEMA WC 70 - Nonshielded Power Cable 2000 V or Less for the Distribution of Electrical Energy; 2009.

L. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

M. UL 44 - Thermoset-Insulated Wires and Cables; Current Edition, Including All Revisions.

N. UL 83 - Thermoplastic-Insulated Wires and Cables; Current Edition, Including All Revisions.

O. UL 486A-486B - Wire Connectors; Current Edition, Including All Revisions.

P. UL 486C - Splicing Wire Connectors; Current Edition, Including All Revisions.

Q. UL 510 - Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape; Current Edition, Including All Revisions.

R. UL 1277 - Electrical Power and Control Tray Cables with Optional Optical-Fiber Members; Current Edition, Including All Revisions.

S. UL 1569 - Metal-Clad Cables; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Coordinate sizes of raceways, boxes, and equipment enclosures installed under other sections with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
   2. Coordinate with electrical equipment installed under other sections to provide terminations suitable for use with the conductors to be installed.
   3. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets for conductors and cables, including detailed information on materials, construction, ratings, listings, and available sizes, configurations, and stranding.

C. Design Data: Indicate voltage drop and ampacity calculations for aluminum conductors substituted for copper conductors. Include proposed modifications to raceways, boxes, wiring gutters, enclosures, etc. to accommodate substituted conductors.

D. Project Record Documents: Record actual installed circuiting arrangements. Record actual routing for underground circuits.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store conductors and cables in accordance with manufacturer's instructions.

1.8 FIELD CONDITIONS

A. Do not install or otherwise handle thermoplastic-insulated conductors at temperatures lower than 14 degrees F, unless otherwise permitted by manufacturer's instructions. When installation below this temperature is unavoidable, notify Architect and obtain direction before proceeding with work.

PART 2 PRODUCTS

2.1 CONDUCTOR AND CABLE APPLICATIONS

A. Do not use conductors and cables for applications other than as permitted by NFPA 70 and product listing.

B. Provide single conductor building wire installed in suitable raceway unless otherwise indicated, permitted, or required.

C. Nonmetallic-sheathed cable is not permitted.

D. Underground feeder and branch-circuit cable is not permitted.

E. Service entrance cable is not permitted.

F. Metal-clad cable is permitted only as follows:
   1. Where not otherwise restricted, may be used:

a. Where concealed above accessible ceilings for final connections from junction boxes to luminaires.
1) Maximum Length: 6 feet.
b. Where concealed in hollow stud walls, under raised floors, and above ceilings for branch circuits and feeders to dwelling units.

2. In addition to other applicable restrictions, may not be used:
a. Unless approved by Owner.
b. Where not approved for use by the authority having jurisdiction.
c. Where exposed to view.
d. Where exposed to damage.
e. For damp, wet, or corrosive locations.

2.2 CONDUCTOR AND CABLE MANUFACTURERS

A. AFC Cable Systems: www.afcweb.com

B. Alan Wire Company: www.alanwire.com.

C. Cerro Wire LLC: www.cerrowire.com.

D. Encore Wire Corporation: www.encorewire.com.

E. Southwire Company: www.southwire.com.

F. Substitutions: See Section 016000 - Product Requirements.

2.3 ALL CONDUCTORS AND CABLES

A. Provide products that comply with requirements of NFPA 70.

B. Provide products listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose indicated.

C. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, etc. as required for a complete operating system.

D. Comply with NEMA WC 70.

E. Thermoplastic-Insulated Conductors and Cables: Listed and labeled as complying with UL 83.

F. Thermoset-Insulated Conductors and Cables: Listed and labeled as complying with UL 44.

G. Conductor Material:
1. Provide copper conductors except where aluminum conductors are specifically indicated. Substitution of aluminum conductors for copper is not permitted. Conductor sizes indicated are based on copper unless specifically indicated as aluminum. Conductors designated with the abbreviation "AL" indicate aluminum.
2. Copper Conductors: Soft drawn annealed, 98 percent conductivity, uncoated copper conductors complying with ASTM B3, ASTM B8, or ASTM B787/B 787M unless otherwise indicated.
3. Tinned Copper Conductors: Comply with ASTM B33.
4. Aluminum Conductors (only where specifically indicated or permitted for substitution): AA-8000 series aluminum alloy conductors recognized by ASTM B800 and compact stranded in accordance with ASTM B801 unless otherwise indicated.

H. Minimum Conductor Size:
1. Branch Circuits: 12 AWG.
a. Exceptions:
1) 20 A, 120 V circuits longer than 75 feet: 10 AWG, for voltage drop.
2) 20 A, 120 V circuits longer than 150 feet: 8 AWG, for voltage drop.
3) 20 A, 277 V circuits longer than 150 feet: 10 AWG, for voltage drop.
2. Control Circuits: 14 AWG.

I. Conductor Color Coding:

1. Color code conductors as indicated unless otherwise required by the authority having jurisdiction. Maintain consistent color coding throughout project.
2. Color Coding Method: Integrally colored insulation.
    a. Conductors size 4 AWG and larger may have black insulation color coded using vinyl color coding electrical tape.
3. Color Code:
    a. 208Y/120 V, 3 Phase, 4 Wire System:
        1) Phase A: Black.
        2) Phase B: Red.
        3) Phase C: Blue.
        4) Neutral/Grounded: White.
    b. Equipment Ground, All Systems: Green.
    c. Travelers for 3-Way and 4-Way Switching: Pink.
    d. For control circuits, comply with manufacturer's recommended color code.

2.4 SINGLE CONDUCTOR BUILDING WIRE

A. Description: Single conductor insulated wire.

B. Conductor Stranding:
1. Feeders and Branch Circuits:
    a. Size 10 AWG and Smaller: Solid.
    b. Size 8 AWG and Larger: Stranded.
2. Control Circuits: Stranded.

C. Insulation Voltage Rating: 600 V.

D. Insulation:
1. Copper Building Wire: Type THHN/THWN or THHN/THWN-2.
2. Aluminum Building Wire (only where specifically indicated or permitted for substitution): Type XHHW-2.

2.5 METAL-CLAD CABLE

A. Description: NFPA 70, Type MC cable listed and labeled as complying with UL 1569, and listed for use in classified firestop systems to be used.

B. Conductor Stranding:
1. Size 10 AWG and Smaller: Solid.
2. Size 8 AWG and Larger: Stranded.

C. Insulation Voltage Rating: 600 V.

D. Insulation: Type THHN, THHN/THWN, or THHN/THWN-2.

E. Grounding: Full-size integral equipment grounding conductor.

F. Armor: Aluminum or steel, interlocked tape.

G. Provide PVC jacket applied over cable armor where indicated or required for environment of installed location.

2.6 WIRING CONNECTORS

A. Description: Wiring connectors appropriate for the application, suitable for use with the conductors to be connected, and listed as complying with UL 486A-486B or UL 486C as applicable.

B. Wiring Connectors for Splices and Taps:
1. Copper Conductors Size 8 AWG and Smaller: Use twist-on insulated spring connectors.
2. Copper Conductors Size 6 AWG and Larger: Use mechanical connectors or compression connectors.

C. Wiring Connectors for Terminations:

1. Provide terminal lugs for connecting conductors to equipment furnished with terminations designed for terminal lugs.
2. Provide compression adapters for connecting conductors to equipment furnished with mechanical lugs when only compression connectors are specified.
3. Where over-sized conductors are larger than the equipment terminations can accommodate, provide connectors suitable for reducing to appropriate size, but not less than required for the rating of the overcurrent protective device.
4. Copper Conductors Size 8 AWG and Larger: Use mechanical connectors or compression connectors where connectors are required.
5. Stranded Conductors Size 10 AWG and Smaller: Use crimped terminals for connections to terminal screws.
6. Conductors for Control Circuits: Use crimped terminals for all connections.

D. Do not use insulation-piercing or insulation-displacement connectors designed for use with conductors without stripping insulation.

E. Do not use push-in wire connectors as a substitute for twist-on insulated spring connectors.

F. Twist-on Insulated Spring Connectors: Rated 600 V, 221 degrees F for standard applications and 302 degrees F for high temperature applications; pre-filled with sealant and listed as complying with UL 486D for damp and wet locations.

G. Mechanical Connectors: Provide bolted type or set-screw type.

H. Compression Connectors: Provide circumferential type or hex type crimp configuration.

I. Crimped Terminals: Nylon-insulated, with insulation grip and terminal configuration suitable for connection to be made.

2.7 WIRING ACCESSORIES

A. Electrical Tape:
1. Manufacturers:
a. 3M: www.3m.com/#sle.
b. Plymouth Rubber Europa: www.plymouthrubber.com/#sle.
2. Vinyl Color Coding Electrical Tape: Integrally colored to match color code indicated; listed as complying with UL 510; minimum thickness of 7 mil; resistant to abrasion, corrosion, and sunlight; suitable for continuous temperature environment up to 221 degrees F.
3. Vinyl Insulating Electrical Tape: Complying with ASTM D3005 and listed as complying with UL 510; minimum thickness of 7 mil; resistant to abrasion, corrosion, and sunlight; conformable for application down to 0 degrees F and suitable for continuous temperature environment up to 221 degrees F.

B. Oxide Inhibiting Compound: Listed; suitable for use with the conductors or cables to be installed.

C. Wire Pulling Lubricant: Listed; suitable for use with the conductors or cables to be installed and suitable for use at the installation temperature.

D. Cable Ties: Material and tensile strength rating suitable for application.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that interior of building has been protected from weather.

B. Verify that work likely to damage wire and cable has been completed.

C. Verify that raceways, boxes, and equipment enclosures are installed and are properly sized to accommodate conductors and cables in accordance with NFPA 70.

D. Verify that field measurements are as shown on the drawings.

E. Verify that conditions are satisfactory for installation prior to starting work.

3.2 PREPARATION

A. Clean raceways thoroughly to remove foreign materials before installing conductors and cables.

3.3 INSTALLATION

A. Circuiting Requirements:
   1. Unless dimensioned, circuit routing indicated is diagrammatic.
   2. When circuit destination is indicated and routing is not shown, determine exact routing required.
   3. Arrange circuiting to minimize splices.
   4. Include circuit lengths required to install connected devices within 10 ft of location shown.
   5. Maintain separation of Class 1, Class 2, and Class 3 remote-control, signaling, and power-limited circuits in accordance with NFPA 70.
   6. Circuiting Adjustments: Unless otherwise indicated, when branch circuits are shown as separate, combining them together in a single raceway is permitted, under the following conditions:
      a. Provide no more than six current-carrying conductors in a single raceway. Dedicated neutral conductors are considered current-carrying conductors.
   7. Common Neutrals: Unless otherwise indicated, sharing of neutral/grounded conductors among single phase branch circuits of different phases installed in the same raceway is not permitted. Provide dedicated neutral/grounded conductor for each individual branch circuit.

B. Install products in accordance with manufacturer's instructions.

C. Install conductors and cable in a neat and workmanlike manner in accordance with NECA 1.

D. Install metal-clad cable (Type MC) in accordance with NECA 120.

E. Installation in Raceway:
   1. Tape ends of conductors and cables to prevent infiltration of moisture and other contaminants.
   2. Pull all conductors and cables together into raceway at same time.
   3. Do not damage conductors and cables or exceed manufacturer's recommended maximum pulling tension and sidewall pressure.
   4. Use suitable wire pulling lubricant where necessary, except when lubricant is not recommended by the manufacturer.

F. Paralleled Conductors: Install conductors of the same length and terminate in the same manner.

G. Secure and support conductors and cables in accordance with NFPA 70 using suitable supports and methods approved by the authority having jurisdiction. Provide independent support from building structure. Do not provide support from raceways, piping, ductwork, or other systems.
   1. Installation Above Suspended Ceilings: Do not provide support from ceiling support system. Do not provide support from ceiling grid or allow conductors and cables to lay on ceiling tiles.

H. Terminate cables using suitable fittings.
   1. Metal-Clad Cable (Type MC):
      a. Use listed fittings.
      b. Cut cable armor only using specialized tools to prevent damaging conductors or insulation. Do not use hacksaw or wire cutters to cut armor.
      c. Do not use direct-bearing set-screw type fittings for cables with aluminum armor.

I. Install conductors with a minimum of 12 inches of slack at each outlet.

J. Neatly train and bundle conductors inside boxes, wireways, panelboards and other equipment enclosures.

K. Make wiring connections using specified wiring connectors.
   1. Make splices and taps only in accessible boxes. Do not pull splices into raceways or make splices in conduit bodies or wiring gutters.
   2. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors.
   3. Do not remove conductor strands to facilitate insertion into connector.

4. Clean contact surfaces on conductors and connectors to suitably remove corrosion, oxides, and other contaminates. Do not use wire brush on plated connector surfaces.
5. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
6. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.

L. Insulate splices and taps that are made with uninsulated connectors using methods suitable for the application, with insulation and mechanical strength at least equivalent to unspliced conductors.
1. Dry Locations: Use insulating covers specifically designed for the connectors, electrical tape, or heat shrink tubing.
a. For taped connections, first apply adequate amount of rubber splicing electrical tape or electrical filler tape, followed by outer covering of vinyl insulating electrical tape.
2. Damp Locations: Use insulating covers specifically designed for the connectors, electrical tape, or heat shrink tubing.
a. For connections with insulating covers, apply outer covering of moisture sealing electrical tape.
b. For taped connections, follow same procedure as for dry locations but apply outer covering of moisture sealing electrical tape.
3. Wet Locations: Use heat shrink tubing.

M. Insulate ends of spare conductors using vinyl insulating electrical tape.

N. Field-Applied Color Coding: Where vinyl color coding electrical tape is used in lieu of integrally colored insulation as permitted in Part 2 under "Color Coding", apply half overlapping turns of tape at each termination and at each location conductors are accessible.

O. Identify conductors and cables in accordance with Section 260553.

P. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.

Q. Unless specifically indicated to be excluded, provide final connections to all equipment and devices, including those furnished by others, as required for a complete operating system.

3.4 FIELD QUALITY CONTROL

A. Perform inspection, testing, and adjusting in accordance with Section 014000.

B. Correct deficiencies and replace damaged or defective conductors and cables.

END OF SECTION 260519

SECTION 260526

GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Grounding and bonding requirements.

B. Conductors for grounding and bonding.

C. Connectors for grounding and bonding.

D. Ground bars.

E. Ground rod electrodes.

F. Grounding and bonding components.

G. Provide all components necessary to complete the grounding system(s) consisting of:
   1. Metal underground water pipe.
   2. Metal underground gas piping system.
   3. Rod electrodes.

1.2 REFERENCE STANDARDS

A. IEEE 81 - IEEE Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Grounding System; 2012.

B. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

C. NEMA GR 1 - Grounding Rod Electrodes and Grounding Rod Electrode Couplings; 2007.

D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

E. UL 467 - Grounding and Bonding Equipment; Current Edition, Including All Revisions.

1.3 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Verify exact locations of underground metal water service pipe entrances to building.
   2. Coordinate the work with other trades to provide steel reinforcement complying with specified requirements for concrete-encased electrode.
   3. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

B. Sequencing:
   1. Do not install ground rod electrodes until final backfill and compaction is complete.

1.4 PERFORMANCE REQUIREMENTS

A. Grounding System Resistance: 25 ohms.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements for submittals procedures.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets for grounding and bonding system components.

C. Test Reports: Indicate overall resistance to ground .

D. Project Record Documents: Record actual locations of grounding electrode system components and connections.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

C. Installer Qualifications for Signal Reference Grids: Company with minimum five years documented experience with high frequency grounding systems.

D. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 GROUNDING AND BONDING REQUIREMENTS

A. Do not use products for applications other than as permitted by NFPA 70 and product listing.

B. Unless specifically indicated to be excluded, provide all required components, conductors, connectors, conduit, boxes, fittings, supports, accessories, etc. as necessary for a complete grounding and bonding system.

C. Where conductor size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.

D. Grounding System Resistance:
   1. Achieve specified grounding system resistance under normally dry conditions unless otherwise approved by Architect. Precipitation within the previous 48 hours does not constitute normally dry conditions.
   2. Grounding Electrode System: Not greater than 25 ohms to ground, when tested according to IEEE 81 using "fall-of-potential" method.

E. Grounding Electrode System:
   1. Provide connection to required and supplemental grounding electrodes indicated to form grounding electrode system.
      a. Provide continuous grounding electrode conductors without splice or joint.
      b. Install grounding electrode conductors in raceway where exposed to physical damage. Bond grounding electrode conductor to metallic raceways at each end with bonding jumper.
   2. Metal Underground Water Pipe(s):
      a. Provide connection to underground metal domestic and fire protection (where present) water service pipe(s) that are in direct contact with earth for at least 10 feet at an accessible location not more than 5 feet from the point of entrance to the building.
      b. Provide bonding jumper(s) around insulating joints/pipes as required to make pipe electrically continuous.
      c. Provide bonding jumper around water meter of sufficient length to permit removal of meter without disconnecting jumper.
   3. Metal Building or Structure Frame:
      a. Provide connection to metal building or structure frame effectively grounded in accordance with NFPA 70 at nearest accessible location.
   4. Concrete-Encased Electrode:
      a. Provide connection to concrete-encased electrode consisting of not less than 20 feet of either steel reinforcing bars or bare copper conductor not smaller than 4 AWG embedded within concrete foundation or footing that is in direct contact with earth in accordance with NFPA 70.
   5. Ground Rod Electrode(s):
      a. Provide single electrode unless otherwise indicated or required.
      b. Space electrodes not less than 10 feet from each other and any other ground electrode.
      c. Where location is not indicated, locate electrode(s) at least 5 feet outside building perimeter foundation as near as possible to electrical service entrance; where possible, locate in softscape (uncovered) area.

6. Provide additional ground electrode(s) as required to achieve specified grounding electrode system resistance.
7. Ground Bar: Provide ground bar, separate from service equipment enclosure, for common connection point of grounding electrode system bonding jumpers as permitted in NFPA 70. Connect grounding electrode conductor provided for service-supplied system grounding to this ground bar.

F. Service-Supplied System Grounding:
1. For each service disconnect, provide grounding electrode conductor to connect neutral (grounded) service conductor to grounding electrode system. Unless otherwise indicated, make connection at neutral (grounded) bus in service disconnect enclosure.
2. For each service disconnect, provide main bonding jumper to connect neutral (grounded) bus to equipment ground bus where not factory-installed. Do not make any other connections between neutral (grounded) conductors and ground on load side of service disconnect.

G. Bonding and Equipment Grounding:
1. Provide bonding for equipment grounding conductors, equipment ground busses, metallic equipment enclosures, metallic raceways and boxes, device grounding terminals, and other normally non-current-carrying conductive materials enclosing electrical conductors/equipment or likely to become energized as indicated and in accordance with NFPA 70.
2. Provide insulated equipment grounding conductor in each feeder and branch circuit raceway. Do not use raceways as sole equipment grounding conductor.
3. Where circuit conductor sizes are increased for voltage drop, increase size of equipment grounding conductor proportionally in accordance with NFPA 70.
4. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.
5. Terminate branch circuit equipment grounding conductors on solidly bonded equipment ground bus only. Do not terminate on neutral (grounded) or isolated/insulated ground bus.
6. Provide bonding jumper across expansion or expansion/deflection fittings provided to accommodate conduit movement.
7. Provide bonding for interior metal piping systems in accordance with NFPA 70. This includes, but is not limited to:
   a. Metal water piping where not already effectively bonded to metal underground water pipe used as grounding electrode.
   b. Metal gas piping.

H. Communications Systems Grounding and Bonding:
1. Provide bonding jumper in raceway from intersystem bonding termination to each communications room or backboard and provide ground bar for termination.
   a. Bonding Jumper Size: As indicated.
   b. Raceway Size: 3/4 inch unless otherwise indicated or required.
   c. Ground Bar Size: 1/4 by 2 by 12 inches unless otherwise indicated or required.
   d. Ground Bar Mounting Height: 18 inches above finished floor unless otherwise indicated.

I. Pole-Mounted Luminaires: Also comply with Section 265600.

2.2 GROUNDING AND BONDING COMPONENTS

A. General Requirements:
1. Provide products listed, classified, and labeled by Underwriter's Laboratories Inc. (UL) or testing firm acceptable to authority having jurisdiction as suitable for the purpose indicated.
2. Provide products listed and labeled as complying with UL 467 where applicable.

B. Conductors for Grounding and Bonding, in addition to requirements of Section 260519:
1. Use insulated copper conductors unless otherwise indicated.
   a. Exceptions:
      1) Use bare copper conductors where installed underground in direct contact with earth.

2) Use bare copper conductors where directly encased in concrete (not in raceway).

C. Connectors for Grounding and Bonding:
1. Description: Connectors appropriate for the application and suitable for the conductors and items to be connected; listed and labeled as complying with UL 467.
2. Unless otherwise indicated, use exothermic welded connections for underground, concealed and other inaccessible connections.
3. Unless otherwise indicated, use mechanical connectors, compression connectors, or exothermic welded connections for accessible connections.
a. Exceptions:
1) Use exothermic welded connections for connections to metal building frame.
4. Manufacturers - Mechanical and Compression Connectors:
a. Burndy: www.burndy.com.
b. Thomas & Betts Corporation: www.tnb.com/#sle.
5. Manufacturers - Exothermic Welded Connections:
a. Burndy: www.burndy.com.
b. Cadweld, a brand of Erico International Corporation: www.erico.com/#sle.
c. ThermOweld, a brand of Continental Industries, Inc: www.thermoweld.com/#sle.

D. Ground Bars:
1. Description: Copper rectangular ground bars with mounting brackets and insulators.
2. Size: As indicated.
3. Holes for Connections: As indicated or as required for connections to be made.

E. Ground Rod Electrodes:
1. Comply with NEMA GR 1.
2. Material: Copper-bonded (copper-clad) steel.
3. Size: 3/4 inch diameter by 10 feet length, unless otherwise indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that work likely to damage grounding and bonding system components has been completed.

B. Verify that field measurements are as shown on the drawings.

C. Verify that conditions are satisfactory for installation prior to starting work.

D. Verify existing conditions prior to beginning work.

E. Verify that final backfill and compaction has been completed before driving rod electrodes.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install grounding and bonding system components in a neat and workmanlike manner in accordance with NECA 1.

C. Ground Rod Electrodes: Unless otherwise indicated, install ground rod electrodes vertically. Where encountered rock prohibits vertical installation, install at 45 degree angle or bury horizontally in trench at least 30 inches (750 mm) deep in accordance with NFPA 70 or provide ground plates.
1. Outdoor Installations: Unless otherwise indicated, install with top of rod 6 inches below finished grade.

D. Make grounding and bonding connections using specified connectors.
1. Remove appropriate amount of conductor insulation for making connections without cutting, nicking or damaging conductors. Do not remove conductor strands to facilitate insertion into connector.
2. Remove nonconductive paint, enamel, or similar coating at threads, contact points, and contact surfaces.

3. Exothermic Welds: Make connections using molds and weld material suitable for the items to be connected in accordance with manufacturer's recommendations.
4. Mechanical Connectors: Secure connections according to manufacturer's recommended torque settings.
5. Compression Connectors: Secure connections using manufacturer's recommended tools and dies.

E. Identify grounding and bonding system components in accordance with Section 260553.

3.3 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Perform ground electrode resistance tests under normally dry conditions. Precipitation within the previous 48 hours does not constitute normally dry conditions.

C. Investigate and correct deficiencies where measured ground resistances do not comply with specified requirements.

END OF SECTION 260526

SECTION 260529

HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Support and attachment components for equipment, conduit, cable, boxes, and other electrical work.

1.2 REFERENCE STANDARDS

A. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2009.

B. MFMA-4 - Metal Framing Standards Publication; 2004.

C. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.3 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer’s catalog data for fastening systems.

1.4 QUALITY ASSURANCE

A. Comply with NFPA 70.

B. Comply with applicable building code.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store products in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 SUPPORT AND ATTACHMENT COMPONENTS

A. General Requirements:
   1. Comply with the following. Where requirements differ, comply with most stringent.
      a. NFPA 70.
      b. Requirements of authorities having jurisdiction.
   2. Provide all required hangers, supports, anchors, fasteners, fittings, accessories, and hardware as necessary for the complete installation of electrical work.
   3. Provide products listed, classified, and labeled by Underwriter's Laboratories Inc. (UL) or testing firm acceptable to authority having jurisdiction as suitable for the purpose indicated, where applicable.
   4. Where support and attachment component types and sizes are not indicated, select in accordance with manufacturer's application criteria as required for the load to be supported. Include consideration for vibration, equipment operation, and shock loads where applicable.
   5. Do not use products for applications other than as permitted by NFPA 70 and product listing.
   6. Steel Components: Use corrosion resistant materials suitable for the environment where installed.
      a. Zinc-Plated Steel: Electroplated in accordance with ASTM B633.
      b. Galvanized Steel: Hot-dip galvanized after fabrication in accordance with ASTM A123/A123M or ASTM A153/A153M.

B. Conduit and Cable Supports: Straps, clamps, etc. suitable for the conduit or cable to be supported.
   1. Conduit Straps: One-hole or two-hole type; steel or malleable iron.
   2. Conduit Clamps: Bolted type unless otherwise indicated.

C. Outlet Box Supports: Hangers, brackets, etc. suitable for the boxes to be supported.

D. Metal Channel (Strut) Framing Systems: Factory-fabricated continuous-slot metal channel (strut) and associated fittings, accessories, and hardware required for field-assembly of supports.

1. Comply with MFMA-4.

E. Hanger Rods: Threaded zinc-plated steel unless otherwise indicated.

F. Anchors and Fasteners:
1. Unless otherwise indicated and where not otherwise restricted, use the anchor and fastener types indicated for the specified applications.
2. Concrete: Use preset concrete inserts, expansion anchors, or screw anchors.
3. Solid or Grout-Filled Masonry: Use expansion anchors or screw anchors.
4. Hollow Masonry: Use toggle bolts.
5. Hollow Stud Walls: Use toggle bolts.
6. Steel: Use beam clamps, machine bolts, or welded threaded studs.
7. Sheet Metal: Use sheet metal screws.
8. Wood: Use wood screws.
9. Preset Concrete Inserts: Continuous metal channel (strut) and spot inserts specifically designed to be cast in concrete ceilings, walls, and floors.
   a. Comply with MFMA-4.
   b. Channel Material: Use galvanized steel.
   c. Manufacturer: Same as manufacturer of metal channel (strut) framing system.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install support and attachment components in a neat and workmanlike manner in accordance with NECA 1.

C. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.

D. Unless specifically indicated or approved by Architect, do not provide support from suspended ceiling support system or ceiling grid.

E. Unless specifically indicated or approved by Architect, do not provide support from roof deck.

F. Do not penetrate or otherwise notch or cut structural members without approval of Structural Engineer.

G. Equipment Support and Attachment:
1. Use metal fabricated supports or supports assembled from metal channel (strut) to support equipment as required.
2. Use metal channel (strut) secured to studs to support equipment surface-mounted on hollow stud walls when wall strength is not sufficient to resist pull-out.
3. Use metal channel (strut) to support surface-mounted equipment in wet or damp locations to provide space between equipment and mounting surface.
4. Securely fasten floor-mounted equipment. Do not install equipment such that it relies on its own weight for support.

H. Preset Concrete Inserts: Use manufacturer provided closure strips to inhibit concrete seepage during concrete pour.

I. Secure fasteners according to manufacturer's recommended torque settings.

J. Remove temporary supports.

3.2 FIELD QUALITY CONTROL

A. Inspect support and attachment components for damage and defects.

B. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.

C. Correct deficiencies and replace damaged or defective support and attachment components.

END OF SECTION 260529

SECTION 260534

CONDUIT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Galvanized steel rigid metal conduit (RMC).

B. Intermediate metal conduit (IMC).

C. Flexible metal conduit (FMC).

D. Liquidtight flexible metal conduit (LFMC).

E. Electrical metallic tubing (EMT).

F. Rigid polyvinyl chloride (PVC) conduit.

G. Conduit fittings.

H. Accessories.

1.2 RELATED REQUIREMENTS

A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260529 - Hangers and Supports for Electrical Systems.

D. Section 260537 - Boxes.

E. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

F. Section 271005 - Structured Cabling for Voice and Data - Inside-Plant: Additional requirements for communications systems conduits.

1.3 REFERENCE STANDARDS

A. ANSI C80.1 - American National Standard for Electrical Rigid Steel Conduit (ERSC); 2005.

B. ANSI C80.3 - American National Standard for Steel Electrical Metallic Tubing (EMT); 2005.

C. ANSI C80.6 - American National Standard for Electrical Intermediate Metal Conduit (EIMC); 2005.

D. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

E. NECA 101 - Standard for Installing Steel Conduits (Rigid, IMC, EMT); 2013.

F. NEMA FB 1 - Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2012.

G. NEMA TC 2 - Electrical Polyvinyl Chloride (PVC) Conduit; 2013.

H. NEMA TC 3 - Polyvinyl Chloride (PVC) Fittings for Use with Rigid PVC Conduit and Tubing; 2015.

I. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

J. UL 1 - Flexible Metal Conduit; Current Edition, Including All Revisions.

K. UL 6 - Electrical Rigid Metal Conduit-Steel; Current Edition, Including All Revisions.

L. UL 360 - Liquid-Tight Flexible Steel Conduit; Current Edition, Including All Revisions.

M. UL 514B - Conduit, Tubing, and Cable Fittings; Current Edition, Including All Revisions.

N. UL 651 - Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings; Current Edition, Including All Revisions.

O. UL 797 - Electrical Metallic Tubing-Steel; Current Edition, Including All Revisions.

P. UL 1242 - Electrical Intermediate Metal Conduit-Steel; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Coordinate minimum sizes of conduits with the actual conductors to be installed, including adjustments for conductor sizes increased for voltage drop.
   2. Coordinate the arrangement of conduits with structural members, ductwork, piping, equipment and other potential conflicts installed under other sections or by others.
   3. Verify exact conduit termination locations required for boxes, enclosures, and equipment installed under other sections or by others.
   4. Coordinate the work with other trades to provide roof penetrations that preserve the integrity of the roofing system and do not void the roof warranty.
   5. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

B. Sequencing:
   1. Do not begin installation of conductors and cables until installation of conduit is complete between outlet, junction and splicing points.

1.5 SUBMITTALS

A. Product Data: Provide manufacturer's standard catalog pages and data sheets for conduits and fittings.

B. Project Record Documents: Record actual routing for conduits installed underground, conduits embedded within concrete slabs, and conduits 2 inch (53 mm) trade size and larger.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store conduit and fittings in accordance with manufacturer's instructions.

PART 2 PRODUCTS

2.1 CONDUIT APPLICATIONS

A. Do not use conduit and associated fittings for applications other than as permitted by NFPA 70 and product listing.

B. Unless otherwise indicated and where not otherwise restricted, use the conduit types indicated for the specified applications. Where more than one listed application applies, comply with the most restrictive requirements. Where conduit type for a particular application is not specified, use galvanized steel rigid metal conduit.

C. Underground:
   1. Under Slab on Grade: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or rigid PVC conduit.
   2. Exterior, Direct-Buried: Use galvanized steel rigid metal conduit, intermediate metallic conduit (IMC), or rigid PVC conduit.
   3. Exterior, Embedded Within Concrete: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or rigid PVC conduit.
   4. Where rigid polyvinyl (PVC) conduit is provided, transition to galvanized steel rigid metal conduit where emerging from underground.
   5. Where rigid polyvinyl (PVC) conduit larger than 2 inch (53 mm) trade size is provided, use galvanized steel rigid metal conduit elbows for bends.
   6. Where steel conduit is installed in direct contact with earth where soil has a resistivity of less than 2000 ohm-centimeters or is characterized as severely corrosive based on soils report or local experience, use corrosion protection tape to provide supplementary corrosion protection.
   7. Where steel conduit emerges from concrete into soil, use corrosion protection tape to provide supplementary corrosion protection for a minimum of 4 inches on either side of where conduit emerges.

D. Embedded Within Concrete:
   1. Within Slab on Grade: Not permitted.
   2. Within Slab Above Ground: Not permitted.
   3. Within Concrete Walls Above Ground: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or rigid PVC conduit.
   4. Where rigid polyvinyl (PVC) conduit is provided, transition to galvanized steel rigid metal conduit where emerging from concrete.

E. Concealed Within Masonry Walls: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or electrical metallic tubing (EMT).

F. Concealed Within Hollow Stud Walls: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or electrical metallic tubing (EMT).

G. Concealed Above Accessible Ceilings: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or electrical metallic tubing (EMT).

H. Interior, Damp or Wet Locations: Use galvanized steel rigid metal conduit or intermediate metal conduit (IMC).

I. Exposed, Interior, Not Subject to Physical Damage: Use galvanized steel rigid metal conduit, intermediate metal conduit (IMC), or electrical metallic tubing (EMT).

J. Exposed, Interior, Subject to Physical Damage: Use galvanized steel rigid metal conduit or intermediate metal conduit (IMC).
   1. Locations subject to physical damage include, but are not limited to:
      a. Where exposed below 8 feet, except within electrical and communication rooms or closets.
      b. Where exposed below 20 feet in warehouse areas.

K. Exposed, Exterior: Use galvanized steel rigid metal conduit or intermediate metal conduit (IMC).

L. Concealed, Exterior, Not Embedded in Concrete or in Contact With Earth: Use galvanized steel rigid metal conduit or intermediate metal conduit (IMC).

M. Connections to Luminaires Above Accessible Ceilings: Use flexible metal conduit.
   1. Maximum Length: 6 feet.

N. Connections to Vibrating Equipment:
   1. Dry Locations: Use flexible metal conduit.
   2. Damp, Wet, or Corrosive Locations: Use liquidtight flexible metal conduit.
   3. Maximum Length: 6 feet unless otherwise indicated.
   4. Vibrating equipment includes, but is not limited to:
      a. Transformers.
      b. Motors.

2.2 CONDUIT REQUIREMENTS

A. Electrical Service Conduits: Also comply with Section 262701.

B. Communications Systems Conduits: Also comply with Section 271005.

C. Provide all conduit, fittings, supports, and accessories required for a complete raceway system.

D. Provide products listed, classified, and labeled by Underwriter's Laboratories Inc. (UL) or testing firm acceptable to authority having jurisdiction as suitable for the purpose indicated.

E. Minimum Conduit Size, Unless Otherwise Indicated:
   1. Branch Circuits: 1/2 inch (16 mm) trade size.
   2. Control Circuits: 1/2 inch (16 mm) trade size.
   3. Flexible Connections to Luminaires: 1/2 inch (16 mm) trade size.
   4. Underground, Interior: 3/4 inch (21 mm) trade size.
   5. Underground, Exterior: 1 inch (27 mm) trade size.

F. Where conduit size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.

2.3 GALVANIZED STEEL RIGID METAL CONDUIT (RMC)

A. Manufacturers:
1. Allied Tube & Conduit: www.alliedeg.com/#sle.
2. Republic Conduit: www.republic-conduit.com/#sle.
3. Wheatland Tube Company: www.wheatland.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type RMC galvanized steel rigid metal conduit complying with ANSI C80.1 and listed and labeled as complying with UL 6.

C. Fittings:
1. Non-Hazardous Locations: Use fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
2. Material: Use steel or malleable iron.
a. Do not use die cast zinc fittings.
3. Connectors and Couplings: Use threaded type fittings only. Threadless set screw and compression (gland) type fittings are not permitted.

2.4 INTERMEDIATE METAL CONDUIT (IMC)

A. Manufacturers:
1. Allied Tube & Conduit: www.alliedeg.com/#sle.
2. Republic Conduit: www.republic-conduit.com/#sle.
3. Wheatland Tube Company: www.wheatland.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type IMC galvanized steel intermediate metal conduit complying with ANSI C80.6 and listed and labeled as complying with UL 1242.

C. Fittings:
1. Non-Hazardous Locations: Use fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
2. Material: Use steel or malleable iron.
a. Do not use die cast zinc fittings.
3. Connectors and Couplings: Use threaded type fittings only. Threadless set screw and compression (gland) type fittings are not permitted.

2.5 FLEXIBLE METAL CONDUIT (FMC)

A. Manufacturers:
1. AFC Cable Systems, Inc: www.afcweb.com/#sle.
2. Electri-Flex Company: www.electriflex.com/#sle.
3. International Metal Hose: www.metalhose.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type FMC standard wall steel or standard wall aluminum flexible metal conduit listed and labeled as complying with UL 1, and listed for use in classified firestop systems to be used.

C. Fittings:
1. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
2. Material: Use steel or malleable iron.
a. Do not use die cast zinc fittings.

2.6 LIQUIDTIGHT FLEXIBLE METAL CONDUIT (LFMC)

A. Manufacturers:

1. AFC Cable Systems, Inc: www.afcweb.com/#sle.
2. Electri-Flex Company: www.electriflex.com/#sle.
3. International Metal Hose: www.metalhose.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type LFMC polyvinyl chloride (PVC) jacketed steel or aluminum flexible metal conduit listed and labeled as complying with UL 360.

C. Fittings:
1. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
2. Material: Use steel or malleable iron.
a. Do not use die cast zinc fittings.

2.7 ELECTRICAL METALLIC TUBING (EMT)

A. Manufacturers:
1. Allied Tube & Conduit: www.alliedeg.com/#sle.
2. Republic Conduit: www.republic-conduit.com/#sle.
3. Wheatland Tube Company: www.wheatland.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type EMT steel electrical metallic tubing complying with ANSI C80.3 and listed and labeled as complying with UL 797.

C. Fittings:
1. Description: Fittings complying with NEMA FB 1 and listed and labeled as complying with UL 514B.
2. Material: Use steel or malleable iron.
a. Do not use die cast zinc fittings.
3. Connectors and Couplings: Use compression (gland) or set-screw type.
a. Do not use indenter type connectors and couplings.

2.8 RIGID POLYVINYL CHLORIDE (PVC) CONDUIT

A. Manufacturers:
1. Cantex Inc: www.cantexinc.com/#sle.
2. Carlon, a brand of Thomas & Betts Corporation: www.carlon.com/#sle.
3. JM Eagle: www.jmeagle.com/#sle.
4. Substitutions: See Section 016000 - Product Requirements.

B. Description: NFPA 70, Type PVC rigid polyvinyl chloride conduit complying with NEMA TC 2 and listed and labeled as complying with UL 651; Schedule 40 unless otherwise indicated, Schedule 80 where subject to physical damage; rated for use with conductors rated 90 degrees C.

C. Fittings:
1. Manufacturer: Same as manufacturer of conduit to be connected.
2. Description: Fittings complying with NEMA TC 3 and listed and labeled as complying with UL 651; material to match conduit.

2.9 ACCESSORIES

A. Corrosion Protection Tape: PVC-based, minimum thickness of 20 mil.

B. Conduit Joint Compound: Corrosion-resistant, electrically conductive; suitable for use with the conduit to be installed.

C. Solvent Cement for PVC Conduit and Fittings: As recommended by manufacturer of conduit and fittings to be installed.

D. Pull Strings: Use nylon cord with average breaking strength of not less than 200 pound-force.

E. Sealing Compound for Sealing Fittings: Listed for use with the particular fittings to be installed.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on drawings.

B. Verify that mounting surfaces are ready to receive conduits.

C. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install conduit in a neat and workmanlike manner in accordance with NECA 1.

C. Install galvanized steel rigid metal conduit (RMC) in accordance with NECA 101.

D. Install intermediate metal conduit (IMC) in accordance with NECA 101.

E. Install rigid polyvinyl chloride (PVC) conduit in accordance with NECA 111.

F. Conduit Routing:
   1. Unless dimensioned, conduit routing indicated is diagrammatic.
   2. When conduit destination is indicated and routing is not shown, determine exact routing required.
   3. Conceal all conduits unless specifically indicated to be exposed.
   4. Conduits in the following areas may be exposed, unless otherwise indicated:
      a. Electrical rooms.
      b. Mechanical equipment rooms.
      c. Within joists in areas with no ceiling.
   5. Unless otherwise approved, do not route conduits exposed:
      a. Across floors.
      b. Across roofs.
      c. Across top of parapet walls.
      d. Across building exterior surfaces.
   6. Conduits installed underground or embedded in concrete may be routed in the shortest possible manner unless otherwise indicated. Route all other conduits parallel or perpendicular to building structure and surfaces, following surface contours where practical.
   7. Arrange conduit to maintain adequate headroom, clearances, and access.
   8. Arrange conduit to provide no more than the equivalent of four 90 degree bends between pull points.
   9. Route conduits above water and drain piping where possible.
   10. Arrange conduit to prevent moisture traps. Provide drain fittings at low points and at sealing fittings where moisture may collect.
   11. Maintain minimum clearance of 6 inches between conduits and piping for other systems.
   12. Maintain minimum clearance of 12 inches between conduits and hot surfaces. This includes, but is not limited to:
      a. Heaters.
      b. Hot water piping.
      c. Flues.
   13. Group parallel conduits in the same area together on a common rack.

G. Conduit Support:
   1. Secure and support conduits in accordance with NFPA 70 and Section 260529 using suitable supports and methods approved by the authority having jurisdiction.
   2. Provide independent support from building structure. Do not provide support from piping, ductwork, or other systems.
   3. Installation Above Suspended Ceilings: Do not provide support from ceiling support system. Do not provide support from ceiling grid or allow conduits to lay on ceiling tiles.
   4. Use conduit strap to support single surface-mounted conduit.

a. Use clamp back spacer with conduit strap for damp and wet locations to provide space between conduit and mounting surface.

5. Use metal channel (strut) with accessory conduit clamps to support multiple parallel surface-mounted conduits.
6. Use conduit clamp to support single conduit from beam clamp or threaded rod.
7. Use trapeze hangers assembled from threaded rods and metal channel (strut) with accessory conduit clamps to support multiple parallel suspended conduits.

H. Connections and Terminations:
1. Use approved zinc-rich paint or conduit joint compound on field-cut threads of galvanized steel conduits prior to making connections.
2. Where two threaded conduits must be joined and neither can be rotated, use three-piece couplings or split couplings. Do not use running threads.
3. Use suitable adapters where required to transition from one type of conduit to another.
4. Provide drip loops for liquidtight flexible conduit connections to prevent drainage of liquid into connectors.
5. Terminate threaded conduits in boxes and enclosures using threaded hubs or double lock nuts for dry locations and raintight hubs for wet locations.
6. Where spare conduits stub up through concrete floors and are not terminated in a box or enclosure, provide threaded couplings equipped with threaded plugs set flush with finished floor.
7. Provide insulating bushings or insulated throats at all conduit terminations to protect conductors.
8. Secure joints and connections to provide maximum mechanical strength and electrical continuity.

I. Penetrations:
1. Do not penetrate or otherwise notch or cut structural members, including footings and grade beams, without approval of Structural Engineer.
2. Make penetrations perpendicular to surfaces unless otherwise indicated.
3. Provide sleeves for penetrations as indicated or as required to facilitate installation. Set sleeves flush with exposed surfaces unless otherwise indicated or required.
4. Conceal bends for conduit risers emerging above ground.
5. Seal interior of conduits entering the building from underground at first accessible point to prevent entry of moisture and gases.
6. Where conduits penetrate waterproof membrane, seal as required to maintain integrity of membrane.
7. Make penetrations for roof-mounted equipment within associated equipment openings and curbs where possible to minimize roofing system penetrations. Where penetrations are necessary, seal as indicated or as required to preserve integrity of roofing system and maintain roof warranty. Include proposed locations of penetrations and methods for sealing with submittals.
8. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.

J. Underground Installation:
1. Provide trenching and backfilling in accordance with specifications.
2. Minimum Cover, Unless Otherwise Indicated or Required:
a. Underground, Exterior: 24 inches.
b. Under Slab on Grade: 12 inches to bottom of slab.
3. Provide underground warning tape in accordance with Section 260553 along entire conduit length for service entrance where not concrete-encased.

K. Concrete Encasement: Where conduits not otherwise embedded within concrete are indicated to be concrete-encased, provide concrete in accordance with Section 033000 with minimum concrete cover of 3 inches on all sides unless otherwise indicated.

L. Conduit Movement Provisions: Where conduits are subject to movement, provide expansion and expansion/deflection fittings to prevent damage to enclosed conductors or connected equipment. This includes, but is not limited to:

1. Where conduits cross structural joints intended for expansion, contraction, or deflection.
2. Where conduits are subject to earth movement by settlement or frost.

M. Conduit Sealing:
1. Use foam conduit sealant to prevent entry of moisture and gases. This includes, but is not limited to:
   a. Where conduits enter building from outside.
   b. Where service conduits enter building from underground distribution system.
   c. Where conduits enter building from underground.
   d. Where conduits may transport moisture to contact live parts.
2. Where conduits cross barriers between areas of potential substantial temperature differential, use foam conduit sealant at accessible point near penetration to prevent condensation. This includes, but is not limited to:
   a. Where conduits pass from outdoors into conditioned interior spaces.
   b. Where conduits pass from unconditioned interior spaces into conditioned interior spaces.

N. Condensation Prevention: Where conduits cross barriers between areas of potential substantial temperature differential, provide sealing fitting or approved sealing compound at an accessible point near the penetration to prevent condensation. This includes, but is not limited to:
1. Where conduits pass from outdoors into conditioned interior spaces.
2. Where conduits pass from unconditioned interior spaces into conditioned interior spaces.

O. Provide pull string in all empty conduits and in conduits where conductors and cables are to be installed by others. Leave minimum slack of 12 inches at each end.

P. Provide grounding and bonding in accordance with Section 260526.

Q. Identify conduits in accordance with Section 260553.

R. Conduit in exposed areas will be painted. Coordinate with G.C. Entire conduit system, including boxes and coverplates shall be installed prior to painting.

3.3 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Repair cuts and abrasions in galvanized finishes using zinc-rich paint recommended by manufacturer. Replace components that exhibit signs of corrosion.

C. Correct deficiencies and replace damaged or defective conduits.

3.4 CLEANING

A. Clean interior of conduits to remove moisture and foreign matter.

3.5 PROTECTION

A. Immediately after installation of conduit, use suitable manufactured plugs to provide protection from entry of moisture and foreign material and do not remove until ready for installation of conductors.

END OF SECTION 260534

SECTION 260537

BOXES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Outlet and device boxes up to 100 cubic inches, including those used as junction and pull boxes.

B. Cabinets and enclosures, including junction and pull boxes larger than 100 cubic inches.

C. Pull and junction boxes.

1.2 RELATED REQUIREMENTS

A. Section 083100 - Access Doors and Panels: Panels for maintaining access to concealed boxes.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260529 - Hangers and Supports for Electrical Systems.

D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

E. Section 262726 - Wiring Devices:
   1. Wall plates.

F. Section 262716 - Electrical Cabinets and Enclosures.

G. Section 262726 - Wiring Devices: Wall plates in finished areas.

1.3 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.

C. NEMA FB 1 - Fittings, Cast Metal Boxes, and Conduit Bodies for Conduit, Electrical Metallic Tubing, and Cable; 2012.

D. NEMA OS 1 - Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports; 2013.

E. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

F. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

G. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.

H. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.

I. UL 508A - Industrial Control Panels; Current Edition, Including All Revisions.

J. UL 514A - Metallic Outlet Boxes; Current Edition, Including All Revisions.

K. UL 514C - Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Coordinate the work with other trades to avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and working clearances for electrical equipment required by NFPA 70.
   2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
   3. Coordinate minimum sizes of boxes with the actual installed arrangement of conductors, clamps, support fittings, and devices, calculated according to NFPA 70.
   4. Coordinate minimum sizes of pull boxes with the actual installed arrangement of connected conduits, calculated according to NFPA 70.

5. Coordinate the placement of boxes with millwork, furniture, devices, equipment, etc. installed under other sections or by others.
6. Coordinate the work with other trades to preserve insulation integrity.
7. Coordinate the work with other trades to provide walls suitable for installation of flush-mounted boxes where indicated.
8. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Project Record Documents: Record actual locations and mounting heights of outlet, pull, and junction boxes on project record documents.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

PART 2 PRODUCTS

2.1 BOXES

A. General Requirements:
1. Do not use boxes and associated accessories for applications other than as permitted by NFPA 70 and product listing.
2. Provide all boxes, fittings, supports, and accessories required for a complete raceway system and to accommodate devices and equipment to be installed.
3. Provide products listed, classified, and labeled by Underwriter's Laboratories Inc. (UL) or testing firm acceptable to authority having jurisdiction as suitable for the purpose indicated.
4. Where box size is not indicated, size to comply with NFPA 70 but not less than applicable minimum size requirements specified.
5. Provide grounding terminals within boxes where equipment grounding conductors terminate.

B. Outlet and Device Boxes Up to 100 cubic inches, Including Those Used as Junction and Pull Boxes:
1. Use sheet-steel boxes for dry locations unless otherwise indicated or required.
2. Use cast iron boxes or cast aluminum boxes for damp or wet locations unless otherwise indicated or required; furnish with compatible weatherproof gasketed covers.
3. Use suitable concrete type boxes where flush-mounted in concrete.
4. Use suitable masonry type boxes where flush-mounted in masonry walls.
5. Use raised covers suitable for the type of wall construction and device configuration where required.
6. Use shallow boxes where required by the type of wall construction.
7. Do not use "through-wall" boxes designed for access from both sides of wall.
8. Sheet-Steel Boxes: Comply with NEMA OS 1, and list and label as complying with UL 514A.
9. Cast Metal Boxes: Comply with NEMA FB 1, and list and label as complying with UL 514A; furnish with threaded hubs.
10. Nonmetallic Boxes: Comply with NEMA OS 2, and list and label as complying with UL 514C. Use of nometallic boxes shall be limited to new framed walls.
11. Boxes for Supporting Luminaires and Ceiling Fans: Listed as suitable for the type and weight of load to be supported; furnished with fixture stud to accommodate mounting of luminaire where required.
12. Boxes for Ganged Devices: Use multigang boxes of single-piece construction. Do not use field-connected gangable boxes.
13. Wall Plates: Comply with Section 262726.

C. Cabinets and Enclosures, Including Junction and Pull Boxes Larger Than 100 cubic inches:
1. Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E, or UL 508A.
2. NEMA 250 Environment Type, Unless Otherwise Indicated:

3. Junction and Pull Boxes Larger Than 100 cubic inches:
    a. Provide screw-cover or hinged-cover enclosures unless otherwise indicated.
4. Finish for Painted Steel Enclosures: Manufacturer's standard grey unless otherwise indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on drawings.

B. Verify that mounting surfaces are ready to receive boxes.

C. Verify that conditions are satisfactory for installation prior to starting work.

D. Verify locations of outlets in offices and work areas prior to rough-in.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Perform work in a neat and workmanlike manner in accordance with NECA 1 and, where applicable, NECA 130, including mounting heights specified in those standards where mounting heights are not indicated.

C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.

D. Flush-mount boxes in finished areas unless specifically indicated to be surface-mounted.

E. Box Locations:
1. Locate boxes to be accessible. Provide access panels in accordance with Section 083100 as required where approved by the Architect.
2. Unless dimensioned, box locations indicated are approximate.
3. Locate boxes as required for devices installed under other sections or by others.
4. Locate boxes so that wall plates do not span different building finishes.
5. Locate boxes so that wall plates do not cross masonry joints.

F. Box Supports:
1. Secure and support boxes in accordance with NFPA 70 and Section 260529 using suitable supports and methods approved by the authority having jurisdiction.
2. Provide independent support from building structure except for cast metal boxes (other than boxes used for fixture support) supported by threaded conduit connections in accordance with NFPA 70. Do not provide support from piping, ductwork, or other systems.

G. Install boxes plumb and level.

H. Flush-Mounted Boxes:
1. Install boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that front edge of box or associated raised cover is not set back from finished surface more than 1/4 inch or does not project beyond finished surface.
2. Install boxes in combustible materials such as wood so that front edge of box or associated raised cover is flush with finished surface.
3. Repair rough openings around boxes in noncombustible materials such as concrete, tile, gypsum, plaster, etc. so that there are no gaps or open spaces greater than 1/8 inch at the edge of the box.

I. Install boxes as required to preserve insulation integrity.

J. Install permanent barrier between ganged wiring devices when voltage between adjacent devices exceeds 300 V.

K. Install firestopping to preserve fire resistance rating of partitions and other elements, using materials and methods specified in Section 078400.

L. Close unused box openings.

M. Install blank wall plates on junction boxes and on outlet boxes with no devices or equipment installed or designated for future use.

N. Provide grounding and bonding in accordance with Section 260526.

O. Install boxes securely, in a neat and workmanlike manner, as specified in NECA 1.

P. Install in locations as shown on Drawings, and as required for splices, taps, wire pulling, equipment connections, and as required by NFPA 70.

Q. Coordinate installation of outlet boxes for equipment connected under Section 262717.

R. Set wall mounted boxes at elevations to accommodate mounting heights indicated.

S. Electrical boxes are shown on Drawings in approximate locations unless dimensioned.
   1. Adjust box locations up to 10 feet if required to accommodate intended purpose.

T. Orient boxes to accommodate wiring devices oriented as specified in Section 262726.

U. Maintain headroom and present neat mechanical appearance.

V. Install pull boxes and junction boxes above accessible ceilings and in unfinished areas only.

W. Inaccessible Ceiling Areas: Install outlet and junction boxes no more than 6 inches from ceiling access panel or from removable recessed luminaire.

X. Coordinate mounting heights and locations of outlets mounted above counters, benches, and backsplashes.

Y. Locate outlet boxes to allow luminaires positioned as shown on reflected ceiling plan.

Z. Align adjacent wall mounted outlet boxes for switches, thermostats, and similar devices.

AA. Use flush mounting outlet box in finished areas.

AB. Locate flush mounting box in masonry wall to require cutting of masonry unit corner only. Coordinate masonry cutting to achieve neat opening.

AC. Unless otherwise indicated, provide separate boxes for line voltage and low voltage systems.

AD. Locate outlet boxes so that wall plates do not span different building finishes.

AE. Do not install flush mounting box back-to-back in walls; provide minimum 6 inches separation.

AF. Secure flush mounting box to interior wall and partition studs. Accurately position to allow for surface finish thickness.

AG. Use stamped steel bridges to fasten flush mounting outlet box between studs.

AH. Install flush mounting box without damaging wall insulation or reducing its effectiveness.

AI. Use adjustable steel channel fasteners for hung ceiling outlet box.

AJ. Do not fasten boxes to ceiling support wires.

AK. Support boxes independently of conduit, except cast box that is connected to two rigid metal conduits both supported within 12 inches of box.

AL. Use gang box where more than one device is mounted together. Do not use sectional box.

AM. Use gang box with plaster ring for single device outlets.

AN. Use cast outlet box in exterior locations exposed to the weather and wet locations.

AO. Large Pull Boxes: Use hinged enclosure in interior dry locations, surface-mounted cast metal box in other locations.

AP. Identify boxes in accordance with Section 260553.

3.3 ADJUSTING

A. Adjust flush-mounting outlets to make front flush with finished wall material.

B. Install knockout closures in unused box openings.

3.4 CLEANING

A. Clean interior of boxes to remove dirt, debris, plaster and other foreign material.

END OF SECTION 260537

SECTION 260553

IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Electrical identification requirements.

B. Identification nameplates and labels.

C. Wire and cable markers.

D. Underground warning tape.

E. Warning signs and labels.

1.2 RELATED REQUIREMENTS

A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables: Color coding for power conductors and cables 600 V and less; vinyl color coding electrical tape.

B. Section 262726 - Wiring Devices: Device and wallplate finishes; factory pre-marked wallplates.

1.3 REFERENCE STANDARDS

A. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

B. UL 969 - Marking and Labeling Systems; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Verify final designations for equipment, systems, and components to be identified prior to fabrication of identification products.

B. Sequencing:
   1. Do not conceal items to be identified, in locations such as above suspended ceilings, until identification products have been installed.
   2. Do not install identification products until final surface finishes and painting are complete.

1.5 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.6 FIELD CONDITIONS

A. Do not install adhesive products when ambient temperature is lower than recommended by manufacturer.

PART 2 PRODUCTS

2.1 IDENTIFICATION REQUIREMENTS

A. Identification for Equipment:
   1. Use identification nameplate to identify each piece of electrical distribution and control equipment and associated sections, compartments, and components.
      a. Switchboards:
         1) Identify voltage and phase.
         2) Use identification nameplate to identify main overcurrent protective device.
         3) Use identification nameplate to identify load(s) served for each branch device.
      b. Panelboards:
         1) Identify ampere rating.
         2) Identify voltage and phase.
         3) Use typewritten circuit directory to identify load(s) served for panelboards with a door.
         4) For power panelboards without a door, use identification nameplate to identify load(s) served for each branch device. Do not identify spares and spaces.

c. Enclosed switches:
1) Identify voltage and phase.
2) Identify load(s) served. Include location when not within sight of equipment.
d. Enclosed Contactors:
1) Identify coil voltage.
2) Identify load(s) and associated circuits controlled. Include location.

2. Service Equipment:
a. Use identification nameplate to identify each service disconnecting means.

3. Use identification label or handwritten text using indelible marker on inside of door at each fused switch to identify required NEMA fuse class and size.

4. Use field-painted floor markings, floor marking tape, or warning labels to identify required equipment working clearances where indicated or where required by the authority having jurisdiction.

5. Arc Flash Hazard Warning Labels: Use warning labels to identify arc flash hazards for switchboards and panelboards.
a. Legend: Include orange header that reads "WARNING", followed by the word message "Arc Flash and Shock Hazard; Appropriate PPE Required; Do not operate controls or open covers without appropriate personal protection equipment; Failure to comply may result in injury or death; Refer to NFPA 70E for minimum PPE requirements" or approved equivalent.

B. Identification for Conductors and Cables:
1. Color Coding for Power Conductors 600 V and Less: Comply with Section 260519.
2. Identification for Communications Conductors and Cables: Comply with Section 271005.
3. Use identification nameplate or identification label to identify color code for ungrounded and grounded power conductors inside door or enclosure at each piece of feeder or branch-circuit distribution equipment.

C. Identification for Raceways:
1. Use identification labels or plastic marker tags to identify spare conduits at each end. Identify purpose and termination location.
2. Use underground warning tape to identify underground raceways.

D. Identification for Boxes:
1. Use color coded boxes to identify systems other than normal power system.
a. Color-Coded Boxes: Field-painted in accordance with Section 099000 per the following color code:.
1) Fire Alarm System: Red.

E. Identification for Devices:
1. Identification for Communications Devices: Comply with Section 271005.
2. Wiring Device and Wallplate Finishes: Comply with Section 262726.
3. Use identification label or engraved wallplate to identify load controlled for wall-mounted control devices controlling loads that are not visible from the control location and for multiple wall-mounted control devices installed at one location.
4. Use identification label to identify receptacles protected by upstream GFI protection, where permitted.

2.2 IDENTIFICATION NAMEPLATES AND LABELS

A. Identification Nameplates:
1. Materials:
a. Indoor Clean, Dry Locations: Use plastic nameplates.
b. Outdoor Locations: Use plastic, stainless steel, or aluminum nameplates suitable for exterior use.

2. Plastic Nameplates: Two-layer or three-layer laminated acrylic or electrically non-conductive phenolic with beveled edges; minimum thickness of 1/16 inch; engraved text.

a. Exception: Provide minimum thickness of 1/8 inch when any dimension is greater than 4 inches.

3. Stainless Steel Nameplates: Minimum thickness of 1/32 inch; engraved or laser-etched text.
4. Aluminum Nameplates: Anodized; minimum thickness of 1/32 inch; engraved or laser-etched text.
5. Mounting Holes for Mechanical Fasteners: Two, centered on sides for sizes up to 1 inch high; Four, located at corners for larger sizes.

B. Identification Labels:
1. Manufacturers:
2. Materials: Use self-adhesive laminated plastic labels; UV, chemical, water, heat, and abrasion resistant.
a. Use only for indoor locations.
3. Text: Use factory pre-printed or machine-printed text. Do not use handwritten text unless otherwise indicated.

C. Format for Equipment Identification:
1. Minimum Size: 1 inch by 2.5 inches.
2. Legend:
a. Equipment designation or other approved description.
b. Other information as indicated.
3. Text: All capitalized unless otherwise indicated.
4. Minimum Text Height:
a. Equipment Designation: 1/2 inch.
b. Other Information: 1/4 inch.
5. Color:
a. Normal Power System: White text on black background.
b. Fire Alarm System: White text on red background.

D. Format for General Information and Operating Instructions:
1. Minimum Size: 1 inch by 2.5 inches.
2. Legend: Include information or instructions indicated or as required for proper and safe operation and maintenance.
3. Text: All capitalized unless otherwise indicated.
4. Minimum Text Height: 1/4 inch.
5. Color: Black text on white background unless otherwise indicated.
a. Exceptions:
1) Provide white text on red background for general information or operational instructions for fire alarm systems.

E. Format for Caution and Warning Messages:
1. Minimum Size: 2 inches by 4 inches.
2. Legend: Include information or instructions indicated or as required for proper and safe operation and maintenance.
3. Text: All capitalized unless otherwise indicated.
4. Minimum Text Height: 1/2 inch.
5. Color: Black text on yellow background unless otherwise indicated.

F. Format for Control Device Identification:
1. Minimum Size: 3/8 inch by 1.5 inches.
2. Legend: Load controlled or other designation indicated.
3. Text: All capitalized unless otherwise indicated.
4. Minimum Text Height: 3/16 inch.
5. Color: Black text on clear background.

2.3 WIRE AND CABLE MARKERS

A. Markers for Conductors and Cables: Use wrap-around self-adhesive vinyl cloth, wrap-around self-adhesive vinyl self-laminating, heat-shrink sleeve, plastic sleeve, plastic clip-on, or vinyl split sleeve type markers suitable for the conductor or cable to be identified.

B. Markers for Conductor and Cable Bundles: Use plastic marker tags secured by nylon cable ties.

C. Legend: Power source and circuit number or other designation indicated.

D. Text: Use factory pre-printed or machine-printed text, all capitalized unless otherwise indicated.
   1. Do not use handwritten text.

E. Minimum Text Height: 1/8 inch.

F. Color: Black text on white background unless otherwise indicated.

2.4 UNDERGROUND WARNING TAPE

A. Materials: Use non-detectable type polyethylene tape suitable for direct burial, unless otherwise indicated.
   1. Exception: Use foil-backed detectable type tape where required by serving utility.

B. Non-detectable Type Tape: 3 inches wide, with minimum thickness of 4 mil.

C. Foil-backed Detectable Type Tape: 3 inches wide, with minimum thickness of 5 mil, unless otherwise required for proper detection.

D. Legend: Type of service, continuously repeated over full length of tape.

E. Color:
   1. Tape for Buried Power Lines: Black text on red background.
   2. Tape for Buried Communication, Alarm, and Signal Lines: Black text on orange background.

2.5 WARNING SIGNS AND LABELS

A. Comply with ANSI Z535.2 or ANSI Z535.4 as applicable.

B. Warning Signs:
   1. Materials:
      a. Indoor Dry, Clean Locations: Use factory pre-printed rigid plastic or self-adhesive vinyl signs.
      b. Outdoor Locations: Use factory pre-printed rigid aluminum signs.
   2. Rigid Signs: Provide four mounting holes at corners for mechanical fasteners.
   3. Minimum Size: 7 by 10 inches unless otherwise indicated.

C. Warning Labels:
   1. Materials: Use factory pre-printed or machine-printed self-adhesive polyester or self-adhesive vinyl labels; UV, chemical, water, heat, and abrasion resistant; produced using materials recognized to UL 969.
   2. Machine-Printed Labels: Use thermal transfer process printing machines and accessories recommended by label manufacturer.
   3. Minimum Size: 2 by 4 inches unless otherwise indicated.

PART 3 EXECUTION

3.1 PREPARATION

A. Clean surfaces to receive adhesive products according to manufacturer's instructions.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install identification products to be plainly visible for examination, adjustment, servicing, and maintenance. Unless otherwise indicated, locate products as follows:
   1. Surface-Mounted Equipment: Enclosure front.

2. Flush-Mounted Equipment: Enclosure front.
3. Free-Standing Equipment: Enclosure front; also enclosure rear for equipment with rear access.
4. Elevated Equipment: Legible from the floor or working platform.
5. Branch Devices: Adjacent to device.
6. Interior Components: Legible from the point of access.
7. Conduits: Legible from the floor.
8. Boxes: Outside face of cover.
9. Conductors and Cables: Legible from the point of access.
10. Devices: Outside face of cover.

C. Install identification products centered, level, and parallel with lines of item being identified.

D. Secure nameplates to exterior surfaces of enclosures using stainless steel screws and to interior surfaces using self-adhesive backing or epoxy cement.
1. Do not use adhesives on exterior surfaces except where substrate can not be penetrated.

E. Install self-adhesive labels and markers to achieve maximum adhesion, with no bubbles or wrinkles and edges properly sealed.

F. Install underground warning tape above buried lines with one tape per trench at 12 inch(es) below finished grade.

G. Secure rigid signs using stainless steel screws.

H. Mark all handwritten text, where permitted, to be neat and legible.

3.3 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Replace self-adhesive labels and markers that exhibit bubbles, wrinkles, curling or other signs of improper adhesion.

END OF SECTION 260553

SECTION 260919

ENCLOSED CONTACTORS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Lighting contactors.

1.2 RELATED REQUIREMENTS

A. Section 260529 - Hangers and Supports for Electrical Systems.

B. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

1.3 REFERENCE STANDARDS

A. NEMA ICS 2 - Industrial Control and Systems Controllers, Contactors and Overload Relays Rated 600 Volts; 2000 (R2005), with errata, 2008.

B. NEMA ICS 6 - Industrial Control and Systems: Enclosures; 1993 (R2011).

C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.4 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide dimensions, size, voltage ratings and current ratings.

C. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

1.5 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

B. Products: Listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. General Electric Company: www.geindustrial.com

B. Eaton Corporation; Cutler-Hammer Products: www.eaton.com/#sle.

C. Schneider Electric; Square D Products: www.schneider-electric.us/#sle.

D. Siemens Industry Inc.: www.sea.siemens.com

E. Substitutions: See Section 016000 - Product Requirements.

2.2 LIGHTING CONTACTORS

A. Description: NEMA ICS 2, magnetic lighting contactor.

B. Configuration: Electrically held.

C. Coil operating voltage: 120 volts, 60 Hertz.

D. Poles: As required to match circuit configuration and control function.

E. Contact Rating: Match branch circuit overcurrent protection, considering derating for continuous loads.

F. Enclosure: NEMA ICS 6, Type 1.

G. Accessories:

1. Selector Switch: ON/OFF/AUTOMATIC.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install enclosed contactors where indicated, in accordance with manufacturer's instructions.

B. Install enclosed contactors plumb. Provide supports in accordance with Section 260529.

C. Identify enclosed contactors in accordance with Section 260553.

END OF SECTION 260919

SECTION 260923

LIGHTING CONTROL DEVICES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Occupancy sensors.

B. Time switches.

C. Outdoor photo controls.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems.

B. Section 260529 - Hangers and Supports for Electrical Systems.

C. Section 260537 - Boxes.

D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

E. Section 260919 - Enclosed Contactors: Lighting contactors.

F. Section 265100 - Interior Lighting.

G. Section 265600 - Exterior Lighting.

1.3 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.

C. NEMA 410 - Performance Testing for Lighting Controls and Switching Devices with Electronic Drivers and Discharge Ballasts; 2011.

D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

E. UL 773A - Nonindustrial Photoelectric Switches for Lighting Control; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the placement of wall switch occupancy sensors with actual installed door swings.
2. Coordinate the placement of occupancy sensors with millwork, furniture, equipment or other potential obstructions to motion detection coverage installed under other sections or by others.
3. Notify Architect of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.

B. Sequencing:

1. Do not install lighting control devices until final surface finishes and painting are complete.

1.5 SUBMITTALS

A. Product Data: Include ratings, configurations, standard wiring diagrams, dimensions, colors, service condition requirements, and installed features.

1. Occupancy Sensors: Include detailed motion detection coverage range diagrams.

B. Manufacturer's Installation Instructions: Include application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

C. Operation and Maintenance Data: Include detailed information on device programming and setup.

D. Project Record Documents: Record actual installed locations and settings for lighting control devices.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND PROTECTION

A. Store products in a clean, dry space in original manufacturer's packaging in accordance with manufacturer's written instructions until ready for installation.

1.8 FIELD CONDITIONS

A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.9 WARRANTY

A. Provide five year manufacturer warranty for all occupancy sensors.

PART 2 PRODUCTS

2.1 ALL LIGHTING CONTROL DEVICES

A. Provide products listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

B. Unless specifically indicated to be excluded, provide all required conduit, wiring, connectors, hardware, components, accessories, etc. as required for a complete operating system.

C. Products for Switching of Electronic Fluorescent Ballasts: Tested and rated to be suitable for peak inrush currents specified in NEMA 410.

2.2 OCCUPANCY SENSORS

A. Manufacturers:
   1. Hubbell Building Automation, Inc; : www.hubbellautomation.com
   2. Sensor Switch Inc; : www.sensorswitch.com/#sle.
   3. WattStopper; : www.wattstopper.com/#sle.
   4. Substitutions: See Section 016000 - Product Requirements.

B. All Occupancy Sensors:
   1. Description: Factory-assembled commercial specification grade devices for indoor use capable of sensing both major motion, such as walking, and minor motion, such as small desktop level movements, according to published coverage areas, for automatic control of load indicated.
   2. Sensor Technology:
      a. Passive Infrared (PIR) Occupancy Sensors: Designed to detect occupancy by sensing movement of thermal energy between zones.
      b. Passive Infrared/Ultrasonic Dual Technology Occupancy Sensors: Designed to detect occupancy using a combination of both passive infrared and ultrasonic technologies.
   3. Provide LED to visually indicate motion detection with separate color LEDs for each sensor type in dual technology units.
   4. Operation: Unless otherwise indicated, occupancy sensor to turn load on when occupant presence is detected and to turn load off when no occupant presence is detected during an adjustable turn-off delay time interval.
   5. Dual Technology Occupancy Sensors: Field configurable turn-on and hold-on activation with settings for activation by either or both sensing technologies.
   6. Passive Infrared Lens Field of View: Field customizable by addition of factory masking material, adjustment of integral blinders, or similar means to block motion detection in selected areas.
   7. Turn-Off Delay: Field adjustable, up to a maximum time delay setting of not less than 5 minutes and not more than 30 minutes.
   8. Sensitivity: Field adjustable.
   9. Adaptive Technology: Field selectable; capable of self-adjusting sensitivity and time delay according to conditions.

10. Compatibility: Suitable for controlling incandescent lighting, low-voltage lighting with electronic and magnetic transformers, fluorescent lighting with electronic and magnetic ballasts, and fractional motor loads, with no minimum load requirements.
11. Load Rating for Line Voltage Occupancy Sensors: As required to control the load indicated on drawings.

C. Wall Switch Occupancy Sensors:
1. All Wall Switch Occupancy Sensors:
a. Description: Occupancy sensors designed for installation in standard wall box at standard wall switch mounting height with a field of view of 180 degrees, integrated manual control capability, and no leakage current to load in off mode.
b. Unless otherwise indicated or required to control the load indicated on drawings, provide line voltage units with self-contained relay.
c. Where indicated, provide two-circuit units for control of two separate lighting loads, with separate manual controls and separately programmable operation for each load.
d. Occupancy sensor to be field selectable as either manual-on/automatic-off or automatic on/off.
e. Manual-Off Override Control: When used to turn off load while in automatic-on mode, unit to revert back to automatic mode after no occupant presence is detected during the delayed-off time interval.
f. Finish: Match finishes specified for wiring devices in Section 262726, unless otherwise indicated.
2. Passive Infrared/Ultrasonic Dual Technology Wall Switch Occupancy Sensors: Capable of detecting motion within an area of 300 square feet for minor motion and 1050 square feet for major motion.
a. Products:
1) Wattstopper #DW-100-G.
2) Substitutions: See Section 016000 - Product Requirements.

D. Ceiling Mounted Occupancy Sensors:
1. All Ceiling Mounted Occupancy Sensors:
a. Description: Low profile occupancy sensors designed for ceiling installation.
b. Unless otherwise indicated or required to control the load indicated on the drawings, provide line voltage units with self-contained relay.
c. Occupancy sensor to be field selectable as either manual-on/automatic-off or automatic on/off.
d. Finish: White unless otherwise indicated.
2. Passive Infrared/Ultrasonic Dual Technology Ceiling Mounted Occupancy Sensors:
a. Standard Range Sensors: Capable of detecting motion within an area of 1000 square feet at a mounting height of 9 feet, with a field of view of 360 degrees.
1) Products:
(a) Wattstopper #DT-355.
(b) Substitutions: See Section 016000 - Product Requirements.

2.3 TIME SWITCHES

A. Manufacturers:
1. Intermatic, Inc; _____: www.intermatic.com/#sle.
2. Paragon, a brand of Invensys Controls; _____: www.invensyscontrols.com.
3. Tork, a division of NSI Industries LLC; _____: www.tork.com/#sle.

B. Digital Electronic Time Switches:
1. Description: Factory-assembled solid state programmable controller with LCD display, listed and labeled as complying with UL 916 or UL 917.
2. Program Capability:

a. 7-Day Time Switches: Single channel, capable of different schedule for each day of the week with additional holiday schedule available to override normal schedule for selected days.

3. Schedule Capacity: Not less than 16 programmable on/off operations.
4. Provide automatic daylight savings time and leap year compensation.
5. Provide power outage backup to retain programming and maintain clock.
6. Manual override: Capable of overriding current schedule both permanently and temporarily until next scheduled event.
7. Input Supply Voltage: As indicated on the drawings.
8. Provide lockable enclosure; environmental type per NEMA 250 as specified for the following installation locations:
   a. Indoor clean, dry locations: Type 1.

2.4 OUTDOOR PHOTO CONTROLS

A. Manufacturers:
   1. Intermatic, Inc; : www.intermatic.com/#sle.
   2. Kele; www.kele.com
   3. Paragon, a brand of Invensys Controls; : www.invensyscontrols.com.
   4. Tork, a division of NSI Industries LLC; : www.tork.com/#sle.
   5. Substitutions: See Section 016000 - Product Requirements.
   6. Source Limitations: Furnish products produced by a single manufacturer and obtained from a single supplier.

B. Stem-Mounted Outdoor Photo Controls:
   1. Description: Direct-wired photo control unit with threaded conduit mounting stem and field-adjustable swivel base, listed and labeled as complying with UL 773A.
   2. Housing: Weatherproof, impact resistant polycarbonate.
   3. Photo Sensor: Cadmium sulfide.
   4. Provide external sliding shield for field adjustment of light level activation.
   5. Light Level Activation: 1 to 5 footcandles turn-on and 3 to 1 turn-off to turn-on ratio with delayed turn-off.
   6. Voltage: 120 V unless otherwise indicated.
   7. Failure Mode: Fails to the on position.
   8. Load Rating: 1,800 W for tungsten load or 1,000 VA for ballast load.
   9. Products:
      a. Intermatic #K4221C
      b. Substitutions: See Section 01600 - Product Requirements

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.

C. Verify that openings for outlet boxes are neatly cut and will be completely covered by devices or wall plates.

D. Verify that final surface finishes are complete, including painting.

E. Verify that branch circuit wiring installation is completed, tested, and ready for connection to lighting control devices.

F. Verify that the service voltage and ratings of lighting control devices are appropriate for the service voltage and load requirements at the location to be installed.

G. Verify that conditions are satisfactory for installation prior to starting work.

3.2 PREPARATION

A. Provide extension rings to bring outlet boxes flush with finished surface.

B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.3 INSTALLATION

A. Perform work in a neat and workmanlike manner in accordance with NECA 1 and, where applicable, NECA 130.

B. Coordinate locations of outlet boxes provided under Section 260537 as required for installation of lighting control devices provided under this section.
   1. Mounting Heights: As indicated on the drawings.
   2. Orient outlet boxes for vertical installation of lighting control devices unless otherwise indicated.

C. Install lighting control devices in accordance with manufacturer's instructions.

D. Unless otherwise indicated, connect lighting control device grounding terminal or conductor to branch circuit equipment grounding conductor and to outlet box with bonding jumper.

E. Install lighting control devices plumb and level, and held securely in place.

F. Where required and not furnished with lighting control device, provide wall plate in accordance with Section 262726.

G. Provide required supports in accordance with Section 260529.

H. Where applicable, install lighting control devices and associated wall plates to fit completely flush to mounting surface with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.

I. Occupancy Sensor Locations:
   1. Location Adjustments: Within the design intent, reasonably minor adjustments to locations may be made in order to optimize coverage and avoid conflicts or problems affecting coverage.
   2. Locate dual technology passive infrared/ultrasonic occupancy sensors a minimum of 4 feet from air supply ducts or other sources of heavy air flow and as per manufacturer's recommendations, in order to minimize false triggers.

J. Outdoor Photo Control Locations:
   1. Where possible, locate outdoor photo controls with photo sensor facing north. If north facing photo sensor is not possible, install with photo sensor facing east, west, or down.
   2. Locate outdoor photo controls so that photo sensors do not face artificial light sources, including light sources controlled by the photo control itself.

K. Install outdoor photo controls so that connections are weatherproof. Do not install photo controls with conduit stem facing up in order to prevent infiltration of water into the photo control.

L. Unless otherwise indicated, install power packs for lighting control devices above accessible ceiling or above access panel in inaccessible ceiling near the sensor location.

M. Unless otherwise indicated, install switches on load side of power packs so that switch does not turn off power pack.

3.4 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Inspect each lighting control device for damage and defects.

C. Test occupancy sensors to verify proper operation, including time delays and ambient light thresholds where applicable. Verify optimal coverage for entire room or area.

D. Test outdoor photo controls to verify proper operation, including time delays where applicable.

E. Correct wiring deficiencies and replace damaged or defective lighting control devices.

3.5 ADJUSTING

A. Adjust devices and wall plates to be flush and level.

B. Adjust occupancy sensor settings to minimize undesired activations while optimizing energy savings, and to achieve desired function as indicated or as directed by Architect.

C. Where indicated or as directed by Architect, install factory masking material or adjust integral blinders on dual technology occupancy sensor lenses to block undesired motion detection.

D. Adjust external sliding shields on outdoor photo controls under optimum lighting conditions to achieve desired turn-on and turn-off activation as indicated or as directed by Architect.

3.6 CLEANING

A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.

3.7 CLOSEOUT ACTIVITIES

A. Training: Train owner's personnel on operation, adjustment, programming, and maintenance of lighting control devices.
   1. Use operation and maintenance manual as training reference, supplemented with additional training materials as required.
   2. Provide minimum of two hours of training.
   3. Instructor: Qualified contractor familiar with the project and with sufficient knowledge of the installed lighting control devices.
   4. Location: At project site.

END OF SECTION 260923

SECTION 262100

LOW-VOLTAGE ELECTRICAL SERVICE ENTRANCE

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Electrical service requirements.

1.2 RELATED REQUIREMENTS

A. Section 260519 - Low-Voltage Electrical Power Conductors and Cables.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260529 - Hangers and Supports for Electrical Systems.

D. Section 260534 - Conduit.

E. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

F. Section 262413 - Switchboards: Service entrance equipment.

G. Section 262818 - Enclosed Switches: Service entrance equipment.

1.3 REFERENCE STANDARDS

A. IEEE C2 - National Electrical Safety Code; 2012.

B. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Verify the following with Utility Company representative:
      a. Utility Company requirements, including division of responsibility.
      b. Exact location and details of utility point of connection.
      c. Utility easement requirements.
      d. Utility Company charges associated with providing service.
   2. Coordinate the work with other trades to avoid placement of other utilities or obstructions within the spaces dedicated for electrical service and associated equipment.
   3. Coordinate arrangement of service entrance equipment with the dimensions and clearance requirements of the actual equipment to be installed.
   4. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

B. Arrange for Utility Company to provide permanent electrical service. Prepare and submit documentation required by Utility Company.

C. Utility Company charges associated with providing permanent service to be paid by Owner.

D. Preinstallation Meeting: Convene one week prior to commencing work of this section to review service requirements and details with Utility Company representative.

E. Scheduling:
   1. Arrange for inspections necessary to obtain Utility Company approval of installation.

1.5 QUALITY ASSURANCE

A. Comply with the following:
   1. IEEE C2 (National Electrical Safety Code).
   2. NFPA 70 (National Electrical Code).
   3. The requirements of the Utility Company.

PART 2 PRODUCTS

2.1 ELECTRICAL SERVICE REQUIREMENTS

A. Provide new electrical service consisting of all required conduits, conductors, equipment, metering provisions, supports, accessories, etc. as necessary for connection between Utility Company point of supply and service entrance equipment.

B. Electrical Service Characteristics:
   1. Service Type: Underground.
   2. Service Voltage: 208Y/120 V, 3 phase, 60 Hz.

C. Utility Company: As indicated on drawings.

D. Division of Responsibility: As indicated on drawings.

E. Products Furnished by Contractor: Comply with Utility Company requirements.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install products in accordance with manufacturer's instructions and Utility Company requirements.

B. Perform work in accordance with NECA 1 (general workmanship).

C. Arrange equipment to provide minimum clearances and required maintenance access.

D. Provide required support and attachment components in accordance with Section 260529.

E. Provide grounding and bonding for service entrance equipment in accordance with Section 260526.

F. Identify service entrance equipment, including main service disconnect(s) in accordance with Section 260553.

END OF SECTION 262100

SECTION 262413

SWITCHBOARDS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Switchboards.

1.2 RELATED REQUIREMENTS

A. Section 033000 - Cast-in-Place Concrete: Concrete for supporting foundations and pads.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260529 - Hangers and Supports for Electrical Systems.

D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

1.3 REFERENCE STANDARDS

A. FS W-C-375 - Circuit Breakers, Molded Case; Branch Circuit and Service; Federal Specification; Revision E, 2013.

B. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

C. NECA 400 - Standard for Installing and Maintaining Switchboards; 2007.

D. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

E. NEMA PB 2 - Deadfront Distribution Switchboards; 2011.

F. NEMA PB 2.1 - General Instructions for Proper Handling, Installation, Operation, and Maintenance of Deadfront Distribution Switchboards Rated 600 Volts or Less; 2013.

G. NETA ATS - Acceptance Testing Specifications for Electrical Power Equipment and Systems; 2013.

H. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

I. UL 489 - Molded-Case Circuit Breakers, Molded-Case Switches and Circuit Breaker Enclosures; Current Edition, Including All Revisions.

J. UL 869A - Reference Standard for Service Equipment; Current Edition, Including All Revisions.

K. UL 891 - Switchboards; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the work with other trades to avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and working clearances required by NFPA 70.
2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
3. Verify with manufacturer that conductor terminations are suitable for use with the conductors to be installed.
4. Coordinate with manufacturer to provide shipping splits suitable for the dimensional constraints of the installation.
5. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. Product Data: Provide manufacturer's standard catalog pages and data sheets for switchboards, enclosures, overcurrent protective devices, and other installed components and accessories.

B. Shop Drawings: Indicate dimensions, voltage, bus ampacities, overcurrent protective device arrangement and sizes, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.

C. Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store in a clean, dry space having a uniform temperature to prevent condensation (including outdoor switchboards, which are not weatherproof until completely and properly installed). Where necessary, provide temporary enclosure space heaters or temporary power for permanent factory-installed space heaters.

1.8 FIELD CONDITIONS

A. Maintain field conditions within required service conditions during and after installation.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Switchboards:
1. Schneider Electric; Square D Products: www.schneider-electric.us/#sle.
2. Siemens Industry, Inc: www.usa.siemens.com/#sle.

B. Source Limitations: Furnish switchboards and associated components produced by the same manufacturer as the other electrical distribution equipment used for this project and obtained from a single supplier.

2.2 SWITCHBOARDS

A. Provide switchboards consisting of all required components, control power transformers, instrumentation and control wiring, accessories, etc. as necessary for a complete operating system.

B. Provide products listed, classified, and labeled as suitable for the purpose intended.

C. Description: Dead-front switchboard assemblies complying with NEMA PB 2, and listed and labeled as complying with UL 891; ratings, configurations and features as indicated on the drawings.

D. Front-Connected Switchboards:
1. Main Device(s): Individually-mounted.
2. Feeder Devices: Panel/group-mounted.
3. Arrangement: Front accessible only (not rear accessible), rear aligned.

E. Service Entrance Switchboards:
1. Listed and labeled as suitable for use as service equipment according to UL 869A.
2. For solidly-grounded wye systems, provide factory-installed main bonding jumper between neutral and ground busses, and removable neutral disconnecting link for testing purposes.
3. Comply with Utility Company requirements for electrical service.
4. Provide switchboard with phase loss protection.
5. Utility Metering Provisions: Provide separate barriered compartment complying with Utility Company requirements where indicated or where required by Utility Company. Include hinged sealable door and provisions for Utility Company current transformers (CTs), potential transformers (PTs), or potential taps as required.

F. Service Conditions:
1. Provide switchboards and associated components suitable for operation under the following service conditions without derating:
a. Altitude: Less than 6,600 feet.
b. Ambient Temperature:
1) Switchboards Containing Molded Case or Insulated Case Circuit Breakers: Between 23 degrees F and 104 degrees F.

G. Short Circuit Current Rating:

1. Provide switchboards with listed short circuit current rating not less than the available fault current at the installed location as indicated on the drawings.

H. Main Devices: Configure for top or bottom incoming feed as indicated or as required for the installation. Provide separate pull section and/or top-mounted pullbox as indicated or as required to facilitate installation of incoming feed.

I. Bussing: Sized in accordance with UL 891 temperature rise requirements.
1. Through bus (horizontal cross bus) to be fully rated through full length of switchboard (non-tapered). Tapered bus is not permitted.
2. Provide fully rated neutral bus unless otherwise indicated, with a suitable lug for each feeder or branch circuit requiring a neutral connection.
3. Provide solidly bonded equipment ground bus through full length of switchboard, with a suitable lug for each feeder and branch circuit equipment grounding conductor.
4. Phase and Neutral Bus Material: Aluminum.
5. Ground Bus Material: Aluminum.

J. Conductor Terminations: Suitable for use with the conductors to be installed.
1. Line Conductor Terminations:
a. Main and Neutral Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
b. Main and Neutral Lug Type: Mechanical.
2. Load Conductor Terminations:
a. Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
b. Lug Type:

K. Enclosures:
1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
a. Indoor Clean, Dry Locations: Type 1 or Type 2 (drip-proof).
2. Finish: Manufacturer's standard unless otherwise indicated.

L. Future Provisions:
1. Prepare designated spaces for future installation of devices including bussing, connectors, mounting hardware and all other required provisions.
2. Equip distribution sections with full height vertical bussing to accommodate maximum utilization of space for devices.

M. Surge Protective Devices: Where factory-installed, internally mounted surge protective devices are provided in accordance with Section 264300, list switchboards as a complete assembly including surge protective device.

N. Description: NEMA PB 2 switchboard with electrical ratings and configurations as indicated and specified.

O. Bus Connections: Bolted, accessible from front for maintenance.

P. Ground Bus: Extend length of switchboard.

2.3 OVERCURRENT PROTECTIVE DEVICES

A. Circuit Breakers:
1. Interrupting Capacity:
a. Provide circuit breakers with interrupting capacity as required to provide the short circuit current rating indicated, but not less than specified minimum requirements.
b. Fully Rated Systems: Provide circuit breakers with interrupting capacity not less than the short circuit current rating indicated.
2. Molded Case Circuit Breakers:

a. Description: Quick-make, quick-break, over center toggle, trip-free, trip-indicating circuit breakers; listed and labeled as complying with UL 489, and complying with FS W-C-375 where applicable; ratings, configurations, and features as indicated on the drawings.
b. Thermal Magnetic Circuit Breakers: For each pole, furnish thermal inverse time tripping element for overload protection and magnetic instantaneous tripping element for short circuit protection.
    1) Provide field-adjustable magnetic instantaneous trip setting for circuit breaker frame sizes 225 amperes and larger.
c. Electronic Trip Circuit Breakers: Furnish solid state, microprocessor-based, true rms sensing trip units.
    1) Provide the following field-adjustable trip response settings:
        (a) Long time pickup, adjustable by replacing interchangeable trip unit or by setting dial.
        (b) Long time delay.
        (c) Short time pickup and delay.
        (d) Instantaneous pickup.

2.4 SURGE PROTECTIVE DEVICES

A. See Section 264300 for factory-installed, internally mounted surge protective devices. List and label switchboards containing surge protective devices as a complete assembly including surge protective device.

2.5 SOURCE QUALITY CONTROL

A. Factory test switchboards according to NEMA PB 2, including the following production (routine) tests on each switchboard assembly or component:
    1. Dielectric tests.
    2. Mechanical operation tests.
    3. Grounding of instrument transformer cases test.
    4. Electrical operation and control wiring tests, including polarity and sequence tests.
    5. Ground-fault sensing equipment test.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that the ratings and configurations of the switchboards and associated components are consistent with the indicated requirements.

C. Verify that mounting surfaces are ready to receive switchboards.

D. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install switchboards in accordance with NECA 1 (general workmanship), NECA 400, and NEMA PB 2.1.

C. Where switchboard is indicated to be mounted with inaccessible side against wall, provide minimum clearance of 1/2 inch between switchboard and wall.

D. Provide required support and attachment components in accordance with Section 260529.

E. Install switchboards plumb and level.

F. Unless otherwise indicated, mount switchboards on properly sized 4 inch high concrete pad constructed in accordance with Section 033000.

G. Provide grounding and bonding in accordance with Section 260526.

H. Install all field-installed devices, components, and accessories.

I. Where accessories are not self-powered, provide control power source as indicated or as required to complete installation.

J. Set field-adjustable ground fault protection pickup and time delay settings as indicated.

K. Provide filler plates to cover unused spaces in switchboards.

L. Identify switchboards in accordance with Section 260553.

M. Install switchboard in locations shown on drawings, according to NEMA PB 2.1.

N. Install in a neat and workmanlike manner, as specified in NECA 400.

O. Tighten accessible bus connections and mechanical fasteners after placing switchboard.

3.3 FIELD QUALITY CONTROL

A. Disconnect surge protective devices (SPDs) prior to performing any high potential testing. Replace SPDs damaged by performing high potential testing with SPDs connected.

B. Perform field inspection and testing in accordance with Section 014000.

C. Inspect and test in accordance with NETA ATS, except Section 4.

D. Perform inspections and tests listed in NETA ATS, Section 7.1.

E. Molded Case and Insulated Case Circuit Breakers: Perform inspections and tests listed in NETA ATS, Section 7.6.1.1 for all main circuit breakers. Tests listed as optional are not required.

3.4 ADJUSTING

A. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.

B. Adjust alignment of switchboard covers and doors.

C. Adjust all operating mechanisms for free mechanical movement.

D. Tighten bolted bus connections in accordance with manufacturer's instructions.

3.5 CLEANING

A. Clean dirt and debris from switchboard enclosures and components according to manufacturer's instructions.

B. Touch up scratched or marred surfaces to match original finish.

3.6 PROTECTION

A. Protect installed switchboards from subsequent construction operations.

END OF SECTION 262413

SECTION 262416

PANELBOARDS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Lighting and appliance panelboards.

B. Load centers.

C. Overcurrent protective devices for panelboards.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260529 - Hangers and Supports for Electrical Systems.

D. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

E. Section 264300 - Surge Protective Devices.

1.3 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NECA 407 - Standard for Installing and Maintaining Panelboards; 2009.

C. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

D. NEMA PB 1 - Panelboards; 2011.

E. NEMA PB 1.1 - General Instructions for Proper Installation, Operation and Maintenance of Panelboards Rated 600 Volts or Less; 2013.

F. NETA ATS - Acceptance Testing Specifications for Electrical Power Equipment and Systems; 2013.

G. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

H. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.

I. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.

J. UL 67 - Panelboards; Current Edition, Including All Revisions.

K. UL 489 - Molded-Case Circuit Breakers, Molded-Case Switches and Circuit Breaker Enclosures; Current Edition, Including All Revisions.

L. UL 869A - Reference Standard for Service Equipment; Current Edition, Including All Revisions.

M. UL 943 - Ground-Fault Circuit-Interrupters; Current Edition, Including All Revisions.

N. UL 1699 - Arc-Fault Circuit-Interrupters; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the work with other trades to avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and working clearances for electrical equipment required by NFPA 70.
2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
3. Coordinate the work with other trades to provide walls suitable for installation of flush-mounted panelboards where indicated.
4. Verify with manufacturer that conductor terminations are suitable for use with the conductors to be installed.

5. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. Product Data: Provide manufacturer's standard catalog pages and data sheets for panelboards, enclosures, overcurrent protective devices, and other installed components and accessories.
   1. Include characteristic trip curves for each type and rating of overcurrent protective device upon request.

B. Shop Drawings: Indicate outline and support point dimensions, voltage, main bus ampacity, overcurrent protective device arrangement and sizes, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.
   1. Clearly indicate whether proposed short circuit current ratings are fully rated or, where acceptable, series rated systems.
   2. Include documentation of listed series ratings upon request.

C. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

D. Project Record Documents: Record actual installed locations of panelboards and actual installed circuiting arrangements.

E. Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.

F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. Panelboard Keys: Two of each different key.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Receive, inspect, handle, and store panelboards in accordance with manufacturer's instructions and NECA 407.

B. Store in a clean, dry space. Maintain factory wrapping or provide an additional heavy canvas or heavy plastic cover to protect units from dirt, water, construction debris, and traffic.

C. Handle carefully in accordance with manufacturer's written instructions to avoid damage to panelboard internal components, enclosure, and finish.

1.8 FIELD CONDITIONS

A. Maintain ambient temperature within the following limits during and after installation of panelboards:
   1. Panelboards Containing Circuit Breakers: Between 23 degrees F and 104 degrees F.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Siemens Industry, Inc: www.usa.siemens.com.

B. Schneider Electric; Square D Products: www.schneider-electric.us/#sle.

C. Substitutions: See Section 016000 - Product Requirements.

D. Source Limitations: Furnish panelboards and associated components produced by the same manufacturer as the other electrical distribution equipment used for this project and obtained from a single supplier.

2.2 ALL PANELBOARDS

A. Provide products listed and labeled by testing firm acceptable to the authority having jurisdiction as suitable for the purpose indicated.

B. Unless otherwise indicated, provide products suitable for continuous operation under the following service conditions:
   1. Altitude: Less than 6,600 feet.
   2. Ambient Temperature:
      a. Panelboards Containing Circuit Breakers: Between 23 degrees F and 104 degrees F.

C. Short Circuit Current Rating:
   1. Provide panelboards with listed short circuit current rating not less than the available fault current at the installed location as indicated on the drawings.
   2. Listed series ratings are acceptable, except where not permitted by motor contribution according to NFPA 70.
   3. Label equipment utilizing series ratings as required by NFPA 70.

D. Mains: Configure for top or bottom incoming feed as indicated or as required for the installation.

E. Branch Overcurrent Protective Devices: Replaceable without disturbing adjacent devices.

F. Bussing: Sized in accordance with UL 67 temperature rise requirements.
   1. Provide fully rated neutral bus unless otherwise indicated, with a suitable lug for each feeder or branch circuit requiring a neutral connection.
   2. Provide solidly bonded equipment ground bus in each panelboard, with a suitable lug for each feeder and branch circuit equipment grounding conductor.

G. Conductor Terminations: Suitable for use with the conductors to be installed.

H. Enclosures: Comply with NEMA 250, and list and label as complying with UL 50 and UL 50E.
   1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
      a. Indoor Clean, Dry Locations: Type 1.
   2. Boxes: Galvanized steel unless otherwise indicated.
      a. Provide wiring gutters sized to accommodate the conductors to be installed.
      b. Increase gutter space as required where sub-feed lugs, feed-through lugs, gutter taps, or oversized lugs are provided.
   3. Fronts:
      a. Fronts for Surface-Mounted Enclosures: Same dimensions as boxes.
      b. Fronts for Flush-Mounted Enclosures: Overlap boxes on all sides to conceal rough opening.
      c. Finish for Painted Steel Fronts: Manufacturer's standard grey unless otherwise indicated.
   4. Lockable Doors: All locks keyed alike unless otherwise indicated.

I. Future Provisions: Prepare all unused spaces for future installation of devices including bussing, connectors, mounting hardware and all other required provisions.

J. Surge Protective Devices: Where factory-installed, internally mounted surge protective devices are provided in accordance with Section 264300, list and label panelboards as a complete assembly including surge protective device.

K. Multi-Section Panelboards: Provide enclosures of the same height, with feed-through lugs and feeders as indicated or as required to interconnect sections.

L. Load centers are not acceptable.

M. Provide the following features and accessories where indicated or where required to complete installation:
   1. Feed-through lugs.
   2. Sub-feed lugs.

2.3 LIGHTING AND APPLIANCE PANELBOARDS

A. Description: Panelboards complying with NEMA PB 1, lighting and appliance branch circuit type, circuit breaker type, and listed and labeled as complying with UL 67; ratings, configurations and features as indicated on the drawings.

B. Conductor Terminations:
   1. Main and Neutral Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
   2. Main and Neutral Lug Type: Mechanical.

C. Bussing:
   1. Phase Bus Connections: Arranged for sequential phasing of overcurrent protective devices.
   2. Phase and Neutral Bus Material: Aluminum or copper.
   3. Ground Bus Material: Aluminum or copper.

D. Circuit Breakers: Thermal magnetic bolt-on type unless otherwise indicated.

E. Enclosures:
   1. Provide surface-mounted or flush-mounted enclosures as indicated.
   2. Fronts: Provide lockable hinged door with concealed hinges for access to overcurrent protective device handles without exposing live parts.
   3. Provide clear plastic circuit directory holder mounted on inside of door.

2.4 LOAD CENTERS

A. Description: Circuit breaker type load centers listed and labeled as complying with UL 67; ratings, configurations, and features as indicated on the drawings.

B. Bussing:
   1. Phase Bus Connections: Arranged for sequential phasing of overcurrent protective devices.
   2. Bus Material: Aluminum or copper.

C. Circuit Breakers: Thermal magnetic plug-in type.

D. Enclosures:
   1. Provide flush-mounted enclosures unless otherwise indicated.
   2. Provide circuit directory label on inside of door or individual circuit labels adjacent to circuit breakers.

2.5 OVERCURRENT PROTECTIVE DEVICES

A. Molded Case Circuit Breakers:
   1. Description: Quick-make, quick-break, over center toggle, trip-free, trip-indicating circuit breakers listed and labeled as complying with UL 489; ratings, configurations, and features as indicated on the drawings.
   2. Interrupting Capacity:
      a. Provide circuit breakers with interrupting capacity as required to provide the short circuit current rating indicated.
      b. Fully Rated Systems: Provide circuit breakers with interrupting capacity not less than the short circuit current rating indicated.
      c. Series Rated Systems: Provide circuit breakers listed in combination with upstream devices to provide interrupting rating not less than the short circuit current rating indicated.
   3. Conductor Terminations:
      a. Provide mechanical lugs unless otherwise indicated.
      b. Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
   4. Thermal Magnetic Circuit Breakers: For each pole, furnish thermal inverse time tripping element for overload protection and magnetic instantaneous tripping element for short circuit protection.
   5. Multi-Pole Circuit Breakers: Furnish with common trip for all poles.
   6. Provide the following circuit breaker types where indicated:
      a. Ground Fault Circuit Interrupter (GFCI) Circuit Breakers: Listed as complying with UL 943, class A for protection of personnel.
      b. Ground Fault Equipment Protection Circuit Breakers: Designed to trip at 30 mA for protection of equipment.

c. Arc-Fault Circuit Interrupter (AFCI) Circuit Breakers: Combination type listed as complying with UL 1699.
d. 100 Percent Rated Circuit Breakers: Listed for application within the panelboard where installed at 100 percent of the continuous current rating.

7. Provide listed switching duty rated circuit breakers with SWD marking for all branch circuits serving fluorescent lighting.
8. Do not use tandem circuit breakers.
9. Do not use handle ties in lieu of multi-pole circuit breakers.
10. Provide multi-pole circuit breakers for multi-wire branch circuits as required by NFPA 70.
11. Provide the following features and accessories where indicated or where required to complete installation:
    a. Handle Pad-Lock Provision: For locking circuit breaker handle in OFF position.

2.6 SOURCE QUALITY CONTROL

A. Factory test panelboards according to NEMA PB 1.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that the ratings and configurations of the panelboards and associated components are consistent with the indicated requirements.

C. Verify that mounting surfaces are ready to receive panelboards.

D. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install panelboards securely, in a neat and workmanlike manner in accordance with NECA 1 (general workmanship), NECA 407 (panelboards), and NEMA PB 1.1.

C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.

D. Provide required supports in accordance with Section 260529.

E. Install panelboards plumb.

F. Install flush-mounted panelboards so that trims fit completely flush to wall with no gaps and rough opening completely covered.

G. Mount panelboards such that the highest position of any operating handle for circuit breakers or switches does not exceed 79 inches above the floor or working platform.

H. Provide minimum of six spare 1 inch trade size conduits out of each flush-mounted panelboard stubbed into accessible space above ceiling.

I. Provide grounding and bonding in accordance with Section 260526.

J. Install all field-installed branch devices, components, and accessories.

K. Multi-Wire Branch Circuits: Group grounded and ungrounded conductors together in the panelboard as required by NFPA 70.

L. Provide filler plates to cover unused spaces in panelboards.

M. Provide circuit breaker lock-on devices to prevent unauthorized personnel from de-energizing essential loads where indicated. Also provide for the following:
1. Fire detection and alarm circuits.
2. Communications equipment circuits.

N. Identify panelboards in accordance with Section 260553.

3.3 FIELD QUALITY CONTROL

A. Perform inspection, testing, and adjusting in accordance with Section 014000.

B. Inspect and test in accordance with NETA STD ATS, except Section 4.

C. Molded Case Circuit Breakers: Perform inspections and tests listed in NETA STD ATS, Section 7.6.1.1 for all main circuit breakers. Tests listed as optional are not required.

D. Test GFCI circuit breakers to verify proper operation.

E. Test AFCI circuit breakers to verify proper operation.

F. Correct deficiencies and replace damaged or defective panelboards or associated components.

3.4 ADJUSTING

A. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.

B. Adjust alignment of panelboard fronts.

3.5 CLEANING

A. Clean dirt and debris from panelboard enclosures and components according to manufacturer's instructions.

B. Repair scratched or marred exterior surfaces to match original factory finish.

END OF SECTION 262416

SECTION 262717

EQUIPMENT WIRING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Electrical connections to equipment.

1.2 RELATED REQUIREMENTS

A. Section 260534 - Conduit.

B. Section 260519 - Low-Voltage Electrical Power Conductors and Cables (600 V and Less).

C. Section 260537 - Boxes.

D. Section 262726 - Wiring Devices.

E. Section 262818 - Enclosed Switches.

1.3 REFERENCE STANDARDS

A. NEMA WD 1 - General Color Requirements for Wiring Devices; 1999 (R 2010).

B. NEMA WD 6 - Wiring Devices - Dimensional Specifications; 2012.

C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Obtain and review shop drawings, product data, manufacturer's wiring diagrams, and manufacturer's instructions for equipment furnished under other sections.
2. Determine connection locations and requirements.

B. Sequencing:

1. Install rough-in of electrical connections before installation of equipment is required.
2. Make electrical connections before required start-up of equipment.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide wiring device manufacturer’s catalog information showing dimensions, configurations, and construction.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

B. Products: Listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

PART 2 PRODUCTS

2.1 MATERIALS

A. Cords and Caps: NEMA WD 6; match receptacle configuration at outlet provided for equipment.

1. Colors: Conform to NEMA WD 1.
2. Cord Construction: NFPA 70, Type SO, multiconductor flexible cord with identified equipment grounding conductor, suitable for use in damp locations.
3. Size: Suitable for connected load of equipment, length of cord, and rating of branch circuit overcurrent protection.

B. Disconnect Switches: As specified in Section 16412 .

C. Wiring Devices: As specified in Section 262726.

D. Flexible Conduit: As specified in Section 260534.

E. Wire and Cable: As specified in Section 260519.

F. Boxes: As specified in Section 260537.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that equipment is ready for electrical connection, wiring, and energization.

3.2 ELECTRICAL CONNECTIONS

A. Make electrical connections in accordance with equipment manufacturer's instructions.

B. Make conduit connections to equipment using flexible metal conduit. Use liquidtight flexible metal conduit with watertight connectors in damp or wet locations.

C. Connect heat producing equipment using wire and cable with insulation suitable for temperatures encountered.

D. Provide receptacle outlet to accommodate connection with attachment plug.

E. Provide cord and cap where field-supplied attachment plug is required.

F. Install suitable strain-relief clamps and fittings for cord connections at outlet boxes and equipment connection boxes.

G. Install disconnect switches, controllers, control stations, and control devices to complete equipment wiring requirements.

H. Install terminal block jumpers to complete equipment wiring requirements.

I. Install interconnecting conduit and wiring between devices and equipment to complete equipment wiring requirements.

END OF SECTION 262717

SECTION 262726

WIRING DEVICES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Wall switches.

B. Wall dimmers.

C. Receptacles.

D. Wall plates.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems.

B. Section 260537 - Boxes.

C. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

D. Section 260923 - Lighting Control Devices: Devices for automatic control of lighting, including occupancy sensors.

E. Section 262717 - Equipment Wiring: Cords and plugs for equipment.

1.3 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NECA 130 - Standard for Installing and Maintaining Wiring Devices; 2010.

C. NEMA WD 1 - General Color Requirements for Wiring Devices; 1999 (R 2010).

D. NEMA WD 6 - Wiring Devices - Dimensional Specifications; 2012.

E. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

F. UL 20 - General-Use Snap Switches; Current Edition, Including All Revisions.

G. UL 498 - Attachment Plugs and Receptacles; Current Edition, Including All Revisions.

H. UL 514D - Cover Plates for Flush-Mounted Wiring Devices; Current Edition, Including All Revisions.

I. UL 943 - Ground-Fault Circuit-Interrupters; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the placement of outlet boxes with millwork, furniture, equipment, etc. installed under other sections or by others.
2. Coordinate wiring device ratings and configurations with the electrical requirements of actual equipment to be installed.
3. Coordinate the installation and preparation of uneven surfaces, such as split face block, to provide suitable surface for installation of wiring devices.
4. Notify Architect of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.

B. Sequencing:

1. Do not install wiring devices until final surface finishes and painting are complete.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer's catalog information showing dimensions, colors, and configurations.

C. Operation and Maintenance Data:

1. GFI Receptacles: Include information on status indicators and testing procedures and intervals.

D. Project Record Documents: Record actual installed locations of wiring devices.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND PROTECTION

A. Store in a clean, dry space in original manufacturer's packaging until ready for installation.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Arrow Hart, a brand of Cooper Industries; www.cooperindustries.com

B. Hubbell Incorporated; : www.hubbell-wiring.com.

C. Leviton Manufacturing Company, Inc; : www.leviton.com.

D. Pass & Seymour, a brand of Legrand North America, Inc; : www.legrand.us

E. Substitutions: See Section 016000 - Product Requirements.

F. Source Limitations: Where possible, for each type of wiring device furnish products produced by a single manufacturer and obtained from a single supplier.

2.2 APPLICATIONS

A. Provide wiring devices suitable for intended use and with ratings adequate for load served.

B. For single receptacles installed on an individual branch circuit, provide receptacle with ampere rating not less than that of the branch circuit.

C. Provide weather resistant GFI receptacles with specified weatherproof covers for all receptacles installed outdoors or in damp or wet locations.

D. Provide GFI protection for all receptacles installed within 6 feet of sinks.

E. Provide GFCI protection for receptacles installed in kitchens.

F. Provide GFCI protection for receptacles serving electric drinking fountains.

G. Unless noted otherwise, do not use combination switch/receptacle devices.

2.3 ALL WIRING DEVICES

A. Provide products listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

B. Finishes:
1. Wiring Devices Installed in Finished Spaces: Color as selected by Architect with nylon wall plate unless otherwise indicated.
2. Wiring Devices Installed in Unfinished Spaces: Gray with galvanized steel wall plate unless otherwise indicated.
3. Wiring Devices Installed in Wet or Damp Locations: Gray with specified weatherproof cover unless otherwise indicated.

2.4 WALL SWITCHES

A. All Wall Switches: AC only, quiet operating, general-use snap switches with silver alloy contacts, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 20; types as indicated on the drawings.
1. Wiring Provisions: Terminal screws for side wiring and screw actuated binding clamp for back wiring with separate ground terminal screw.

B. Standard Wall Switches: Commercial specification grade, 20 A, 120/277 V with standard toggle type switch actuator and maintained contacts; single pole single throw, double pole single throw, three way, or four way as indicated on the drawings.

2.5 WALL DIMMERS

A. Wall Dimmers - General Requirements: Solid-state with continuous full-range even control following square law dimming curve, integral radio frequency interference filtering, power failure preset memory, air gap switch accessible without removing wall plate, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 1472; types and ratings suitable for load controlled as indicated on the drawings.

B. Control: Slide control type with separate on/off switch.

C. Power Rating, Unless Otherwise Indicated or Required to Control the Load Indicated on the Drawings:
   1. Incandescent: 2000 W.
   2. 0-10V LED: 1500 VA

2.6 RECEPTACLES

A. All Receptacles: Self-grounding, complying with NEMA WD 1 and NEMA WD 6, and listed as complying with UL 498; types as indicated on the drawings.
   1. Wiring Provisions: Terminal screws for side wiring or screw actuated binding clamp for back wiring with separate ground terminal screw.
   2. NEMA configurations specified are according to NEMA WD 6.

B. Convenience Receptacles:
   1. Standard Convenience Receptacles: Commercial specification grade, 20A, 125V, NEMA 5-20R; single or duplex as indicated on the drawings.
   2. Weather Resistant Convenience Receptacles: Commercial specification grade, 20A, 125V, NEMA 5-20R, listed and labeled as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations; single or duplex as indicated on the drawings.
   3. Tamper Resistant Convenience Receptacles (All receptacles in dwelling units): Residential grade, 20A, 125V, NEMA 5-20R, listed and labeled as tamper resistant type; single or duplex as indicated on the drawings.

C. GFI Receptacles:
   1. All GFI Receptacles: Provide with feed-through protection, light to indicate ground fault tripped condition and loss of protection, and list as complying with UL 943, class A.
      a. Provide test and reset buttons of same color as device.
   2. Standard GFI Receptacles: Industrial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style.
   3. Weather Resistant GFI Receptacles: Commercial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style, listed and labeled as weather resistant type complying with UL 498 Supplement SE suitable for installation in damp or wet locations.
   4. Tamper Resistant GFCI Receptacles: Commercial specification grade, duplex, 20A, 125V, NEMA 5-20R, rectangular decorator style, listed and labeled as tamper resistant type.

2.7 WALL PLATES

A. All Wall Plates: Comply with UL 514D.
   1. Configuration: One piece cover as required for quantity and types of corresponding wiring devices.
   2. Size: Standard; .
   3. Screws: Metal with slotted heads finished to match wall plate finish.

B. Nylon Wall Plates: Smooth finish, high-impact thermoplastic.

C. Galvanized Steel Wall Plates: Rounded corners and edges, with corrosion resistant screws.

D. Weatherproof Covers for Damp Locations: Gasketed, cast aluminum, with self-closing hinged cover and corrosion-resistant screws; listed as suitable for use in wet locations with cover closed.

E. Weatherproof Covers for Wet Locations: Gasketed, cast aluminum, with hinged lockable cover and corrosion-resistant screws; listed as suitable for use in wet locations while in use with attachment plugs connected.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate devices and conductors in accordance with NFPA 70.

C. Verify that wall openings are neatly cut and will be completely covered by wall plates.

D. Verify that final surface finishes are complete, including painting.

E. Verify that branch circuit wiring installation is completed, tested, and ready for connection to wiring devices.

F. Verify that conditions are satisfactory for installation prior to starting work.

3.2 PREPARATION

A. Provide extension rings to bring outlet boxes flush with finished surface.

B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.3 INSTALLATION

A. Perform work in a neat and workmanlike manner in accordance with NECA 1 and, where applicable, NECA 130.

B. Coordinate locations of outlet boxes provided under Section 260537 as required for installation of wiring devices provided under this section.
   1. Mounting Heights: As indicated on the drawings.
   2. Orient outlet boxes for vertical installation of wiring devices unless otherwise indicated.
   3. Where multiple receptacles or wall switches are installed at the same location and at the same mounting height, gang devices together under a common wall plate.
   4. Locate wall switches on strike side of door with edge of wall plate 3 inches from edge of door frame. Where locations are indicated otherwise, notify Architect to obtain direction prior to proceeding with work.
   5. Locate receptacles for electric drinking fountains concealed behind drinking fountain according to manufacturer's instructions.

C. Install wiring devices in accordance with manufacturer's instructions.

D. Install permanent barrier between ganged wiring devices when voltage between adjacent devices exceeds 300 V.

E. Where required, connect wiring devices using pigtails not less than 6 inches long. Do not connect more than one conductor to wiring device terminals.

F. Connect wiring devices by wrapping conductor clockwise 3/4 turn around screw terminal and tightening to proper torque specified by the manufacturer. Where present, do not use push-in pressure terminals that do not rely on screw-actuated binding.

G. Unless otherwise indicated, connect wiring device grounding terminal to branch circuit equipment grounding conductor and to outlet box with bonding jumper.

H. Provide GFI receptacles with integral GFI protection at each location indicated. Do not use feed-through wiring to protect downstream devices.

I. Where split-wired duplex receptacles are indicated, remove tabs connecting top and bottom receptacles.

J. Install wiring devices plumb and level with mounting yoke held rigidly in place.

K. Install wall switches with OFF position down.

L. Install wall dimmers to achieve full rating specified and indicated after derating for ganging as instructed by manufacturer.

M. Do not share neutral conductor on branch circuits utilizing wall dimmers.

N. Install vertically mounted receptacles with grounding pole on bottom and horizontally mounted receptacles with grounding pole on left.

O. Install wall plates to fit completely flush to wall with no gaps and rough opening completely covered without strain on wall plate. Repair or reinstall improperly installed outlet boxes or improperly sized rough openings. Do not use oversized wall plates in lieu of meeting this requirement.

P. Install blank wall plates on junction boxes and on outlet boxes with no wiring devices installed or designated for future use.

Q. Identify wiring devices in accordance with Section 260553.

3.4 FIELD QUALITY CONTROL

A. Perform field inspection, testing, and adjusting in accordance with Section 014000.

B. Inspect each wiring device for damage and defects.

C. Operate each wall switch with circuit energized to verify proper operation.

D. Test each receptacle to verify operation and proper polarity.

E. Test each GFCI receptacle for proper tripping operation according to manufacturer's instructions.

F. Correct wiring deficiencies and replace damaged or defective wiring devices.

3.5 ADJUSTING

A. Adjust devices and wall plates to be flush and level.

3.6 CLEANING

A. Clean exposed surfaces to remove dirt, paint, or other foreign material and restore to match original factory finish.

END OF SECTION 262726

SECTION 262813

FUSES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Fuses.

1.2 RELATED REQUIREMENTS

A. Section 262818 - Enclosed Switches: Fusible switches.

1.3 REFERENCE STANDARDS

A. NEMA FU 1 - Low Voltage Cartridge Fuses; 2012.

B. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

C. UL 248-1 - Low-Voltage Fuses - Part 1: General Requirements; Current Edition, Including All Revisions.

D. UL 248-8 - Low-Voltage Fuses - Part 8: Class J Fuses; Current Edition, Including All Revisions.

E. UL 248-12 - Low-Voltage Fuses - Part 12: Class R Fuses; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:
   1. Coordinate fuse clips furnished in equipment provided under other sections for compatibility with indicated fuses.
      a. Fusible Enclosed Switches: See Section 262818.
   2. Coordinate fuse requirements according to manufacturer's recommendations and nameplate data for actual equipment to be installed.
   3. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. Product Data: Provide manufacturer's standard data sheets including voltage and current ratings, interrupting ratings, time-current curves, and current limitation curves.

B. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. See Section 016000 - Product Requirements, for additional provisions.
   2. Extra Fuses: One set(s) of three for each type and size installed.
   3. Fuse Pullers: One set(s) compatible with each type and size installed.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Cooper Bussmann, a division of Cooper Industries: www.cooperindustries.com/#sle.

B. Mersen (formerly Ferraz Shawmut): ferrazshawmut.mersen.com.

C. Littelfuse, Inc: www.littelfuse.com/#sle.

D. Substitutions: See Section 016000 - Product Requirements.

2.2 APPLICATIONS

A. Feeders:
   1. Fusible Switches up to 600 Amperes: Class J, time-delay.

B. General Purpose Branch Circuits: Class RK1, time-delay.

2.3 FUSES

A. Provide products listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose indicated.

B. Unless specifically indicated to be excluded, provide fuses for all fusible equipment as required for a complete operating system.

C. Provide fuses of the same type, rating, and manufacturer within the same switch.

D. Comply with UL 248-1.

E. Unless otherwise indicated, provide cartridge type fuses complying with NEMA FU 1, Class and ratings as indicated.

F. Voltage Rating: Suitable for circuit voltage.

G. Class R Fuses: Comply with UL 248-12.

H. Class J Fuses: Comply with UL 248-8.

I. Selectivity: Where the requirement for selectivity is indicated, furnish products as required to achieve selective coordination.

J. Provide the following accessories where indicated or where required to complete installation:
   1. Fuseholders: Compatible with indicated fuses.
   2. Fuse Reducers: For adapting indicated fuses to permit installation in switch designed for fuses with larger ampere ratings.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that fuse ratings are consistent with circuit voltage and manufacturer's recommendations and nameplate data for equipment.

B. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Do not install fuses until circuits are ready to be energized.

B. Install fuses with label oriented such that manufacturer, type, and size are easily read.

END OF SECTION 262813

SECTION 262818

ENCLOSED SWITCHES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Enclosed safety switches.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding for Electrical Systems.

B. Section 260529 - Hangers and Supports for Electrical Systems.

C. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

D. Section 262813 - Fuses.

1.3 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

C. NEMA KS 1 - Heavy Duty Enclosed and Dead-Front Switches (600 Volts Maximum); 2013.

D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

E. UL 50 - Enclosures for Electrical Equipment, Non-Environmental Considerations; Current Edition, Including All Revisions.

F. UL 50E - Enclosures for Electrical Equipment, Environmental Considerations; Current Edition, Including All Revisions.

G. UL 98 - Enclosed and Dead-Front Switches; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the work with other trades. Avoid placement of ductwork, piping, equipment, or other potential obstructions within the dedicated equipment spaces and within working clearances for electrical equipment required by NFPA 70.
2. Coordinate arrangement of electrical equipment with the dimensions and clearance requirements of the actual equipment to be installed.
3. Verify with manufacturer that conductor terminations are suitable for use with the conductors to be installed.
4. Notify Architect of any conflicts with or deviations from the contract documents. Obtain direction before proceeding with work.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets for enclosed switches and other installed components and accessories.

C. Shop Drawings: Indicate outline and support point dimensions, voltage and current ratings, short circuit current ratings, conduit entry locations, conductor terminal information, and installed features and accessories.

D. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.

E. Project Record Documents: Record actual locations of enclosed switches.

F. Maintenance Data: Include information on replacement parts and recommended maintenance procedures and intervals.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store in a clean, dry space. Maintain factory wrapping or provide an additional heavy canvas or heavy plastic cover to protect units from dirt, water, construction debris, and traffic.

B. Handle carefully in accordance with manufacturer's written instructions to avoid damage to enclosed switch internal components, enclosure, and finish.

1.8 FIELD CONDITIONS

A. Maintain ambient temperature between -22 degrees F and 104 degrees F during and after installation of enclosed switches.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Siemens Industry, Inc: www.usa.siemens.com.

B. Schneider Electric; Square D Products: www.schneider-electric.us/#sle.

C. Substitutions: See Section 016000 - Product Requirements.

D. Source Limitations: Furnish enclosed switches and associated components produced by the same manufacturer as the other electrical distribution equipment used for this project and obtained from a single supplier.

2.2 ENCLOSED SAFETY SWITCHES

A. Description: Quick-make, quick-break, enclosed safety switches complying with NEMA KS 1, type HD (heavy duty), and listed and labeled as complying with UL 98; ratings, configurations, and features as indicated on the drawings.

B. Provide products listed and labeled by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

C. Unless otherwise indicated, provide products suitable for continuous operation under the following service conditions:
   1. Altitude: Less than 6,600 feet.
   2. Ambient Temperature: Between -22 degrees F and 104 degrees F.

D. Horsepower Rating: Suitable for connected load.

E. Voltage Rating: Suitable for circuit voltage.

F. Provide with switch blade contact position that is visible when the cover is open.

G. Fuse Clips for Fusible Switches: As required to accept fuses indicated.
   1. Where NEMA Class R fuses are installed, provide rejection feature to prevent installation of fuses other than Class R.

H. Conductor Terminations: Suitable for use with the conductors to be installed.

I. Provide insulated, groundable fully rated solid neutral assembly where a neutral connection is required, with a suitable lug for terminating each neutral conductor.

J. Provide solidly bonded equipment ground bus in each enclosed safety switch, with a suitable lug for terminating each equipment grounding conductor.

K. Enclosures: Comply with NEMA KS 1 and NEMA 250, and list and label as complying with UL 50 and UL 50E.
   1. Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
      a. Indoor Clean, Dry Locations: Type 1.
      b. Outdoor Locations: Type 3R.

2. Finish for Painted Steel Enclosures: Manufacturer's standard, factory applied grey unless otherwise indicated.

L. Provide safety interlock to prevent opening the cover with the switch in the ON position with capability of overriding interlock for testing purposes.

M. Heavy Duty Switches:
1. Conductor Terminations:
a. Provide mechanical lugs unless otherwise indicated.
b. Lug Material: Aluminum, suitable for terminating aluminum or copper conductors.
2. Provide externally operable handle with means for locking in the OFF position, capable of accepting three padlocks.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that the ratings of the enclosed switches are consistent with the indicated requirements.

C. Verify that mounting surfaces are ready to receive enclosed safety switches.

D. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Install enclosed switches in accordance with manufacturer's instructions.

B. Install enclosed switches securely, in a neat and workmanlike manner in accordance with NECA 1.

C. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.

D. Provide required supports in accordance with Section 260529.

E. Install enclosed switches plumb.

F. Except where indicated to be mounted adjacent to the equipment they supply, mount enclosed switches such that the highest position of the operating handle does not exceed 79 inches above the floor or working platform.

G. Provide grounding and bonding in accordance with Section 260526.

H. Provide fuses complying with Section 262813 for fusible switches as indicated or as required by equipment manufacturer's recommendations.

I. Identify enclosed switches in accordance with Section 260553.

3.3 FIELD QUALITY CONTROL

A. Perform field inspection, testing, and adjusting in accordance with Section 014000.

B. Correct deficiencies and replace damaged or defective enclosed safety switches or associated components.

3.4 ADJUSTING

A. Adjust tightness of mechanical and electrical connections to manufacturer's recommended torque settings.

3.5 CLEANING

A. Clean dirt and debris from switch enclosures and components according to manufacturer's instructions.

B. Repair scratched or marred exterior surfaces to match original factory finish.

END OF SECTION 262818

SECTION 264300

SURGE PROTECTIVE DEVICES

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Surge protective devices for service entrance locations.

B. Surge protective devices for branch panelboard locations.

1.2 RELATED REQUIREMENTS

A. Section 260526 - Grounding and Bonding.

B. Section 262413 - Switchboards.

C. Section 262416 - Panelboards.

1.3 ABBREVIATIONS AND ACRONYMS

A. SPD: Surge Protective Device.

1.4 REFERENCE STANDARDS

A. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

B. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum); 2014.

C. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

D. UL 1283 - Standard for Electromagnetic Interference Filters; Current Edition, Including All Revisions.

E. UL 1449 - Standard for Surge Protective Devices; Current Edition, Including All Revisions.

1.5 ADMINISTRATIVE REQUIREMENTS

A. Coordination: Coordinate size and location of overcurrent device compatible with the actual surge protective device and location to be installed. Notify Architect of any conflicts or deviations from the contract documents to obtain direction prior to ordering equipment.

1.6 SUBMITTALS

A. Product Data: Include detailed component information, voltage, surge current ratings, repetitive surge current capacity, voltage protection rating (VPR) for all protection modes, maximum continuous operating voltage (MCOV), nominal discharge current (I-n), short circuit current rating (SCCR), connection means including any required external overcurrent protection, enclosure ratings, outline and support point dimensions, weight, service condition requirements, and installed features.

B. Shop Drawings: Include wiring diagrams showing all factory and field connections with wire and circuit breaker/fuse sizes.

C. Certificates: Manufacturer's documentation of listing for compliance with the following standards:
   1. UL 1449.
   2. UL 1283 (for Type 2 SPDs).

D. Manufacturer's Installation Instructions: Include application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

E. Operation and Maintenance Data: Include information on status indicators and recommended maintenance procedures and intervals.

F. Warranty: Submit sample of manufacturer's warranty and documentation of final executed warranty completed in Owner's name and registered with manufacturer.

G. Project Record Documents: Record actual connections and locations of surge protective devices.

1.7 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.8 DELIVERY, STORAGE, AND PROTECTION

A. Store in a clean, dry space in accordance with manufacturer's written instructions.

1.9 FIELD CONDITIONS

A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.10 WARRANTY

A. Manufacturer's Warranty: Provide minimum ten year warranty covering repair or replacement of surge protective devices showing evidence of failure due to defective materials or workmanship.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Field-installed, Externally Mounted Surge Protective Devices:
   1. Advanced Protection Technologies, Inc (APT); : www.aptspd.com.
   2. Current Technology; a brand of Thomas & Betts Power Solutions; : www.tnbpowersolutions.com.
   3. General Electric Company; : www.geindustrial.com.
   4. Square D; Schneider Electric; www.schneider-electric.com
   5. Eaton Corporaton; www.eaton.com/electrical
   6. Siemens Industry, Inc.; www.sea.siemens.com
   7. Substitutions: See Section 016000 - Product Requirements.

B. Factory-installed, Internally Mounted Surge Protective Devices:
   1. Same as manufacturer of equipment containing surge protective device, to provide a complete listed assembly including SPD.

C. Source Limitations: Furnish surge protective devices produced by a single manufacturer and obtained from a single supplier.

2.2 ALL SURGE PROTECTIVE DEVICES

A. Description: Factory-assembled surge protective devices (SPDs) for 60 Hz service, listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated; system voltage as indicated on the drawings.

B. Protected Modes:
   1. Wye Systems: L-N, L-G, N-G, L-L.

C. UL 1449 Voltage Protection Ratings (VPRs):
   1. 208Y/120V System Voltage: Not more than 700 V for L-N, L-G, and N-G modes and 1000 V for L-L mode.

D. UL 1449 Maximum Continuous Operating Voltage (MCOV): Not less than 115% of nominal system voltage.

E. Response Time: Less than one nanosecond

F. Enclosure Environment Type per NEMA 250: Unless otherwise indicated, as specified for the following installation locations:
   1. Indoor clean, dry locations: Type 1 or Type 4x.

G. Equipment Containing Factory-installed, Internally Mounted SPDs: Listed and labeled as a complete assembly including SPD.
   1. Switchboards: See Section 262413.
   2. Panelboards: See Section 262416.

2.3 SURGE PROTECTIVE DEVICES FOR SERVICE ENTRANCE LOCATIONS

A. Unless otherwise indicated, provide field-installed, externally mounted or factory-installed, internally mounted SPDs.

B. List and label as complying with UL 1449, Type 1 when connected on line side of service disconnect overcurrent device and Type 1 or 2 when connected on load side of service disconnect overcurrent device.

C. List and label as complying with UL 1283 and UL 1449, Type 1.

D. Surge Current Rating: Not less than 240 kA.

E. Repetitive Surge Current Capacity: Not less than 5,000 impulses.

F. UL 1449 Nominal Discharge Current (I-n): 20 kA.

G. UL 1449 Short Circuit Current Rating (SCCR): Not less than 100 kA.

H. Diagnostics:
   1. Protection Status Monitoring: Provide indicator lights to report the protection for each phase.
   2. Alarm Notification: Provide indicator light and audible alarm to report alarm condition. Provide button to manually silence audible alarm.
   3. Remote Status Monitoring: Provide Form C dry type contacts (normally open and normally closed) for remote annunciation of status.

I. Provide surge rated integral disconnect switch for SPDs not connected to a dedicated circuit breaker or fused switch or not direct bus connected.

2.4 SURGE PROTECTIVE DEVICES FOR BRANCH PANELBOARD LOCATIONS

A. Unless otherwise indicated, provide field-installed, externally mounted or factory-installed, internally mounted SPDs.

B. List and label as complying with UL 1449, Type 1 or Type 2.

C. Provide SPDs utilizing field-replaceable modular or non-modular protection circuits.

D. Surge Current Rating: Not less than 60 kA per mode/120 kA per phase.

E. Repetitive Surge Current Capacity: Not less than 5,000 impulses.

F. UL 1449 Nominal Discharge Current (I-n): 20 kA.

G. UL 1449 Short Circuit Current Rating (SCCR): Not less than 100 kA.

H. EMI/RFI Filtering: Provide EMI/RFI filter to attenuate electrical noise; listed as complying with UL 1283 for Type 2 SPDs (UL 1283 listing not available for Type 1 SPDs).

I. Diagnostics:
   1. Protection Status Monitoring: Provide indicator lights to report the protection status.
   2. Alarm Notification: Provide indicator light and audible alarm to report alarm condition. Provide button to manually silence audible alarm.
   3. Remote Status Monitoring: Provide Form C dry type contacts (normally open and normally closed) for remote annunciation of status.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that the service voltage and configuration marked on the SPD are consistent with the service voltage and configuration at the location to be installed.

C. Verify system grounding and bonding is in accordance with Section 260526, including bonding of neutral and ground for service entrance and separately derived systems where applicable. Do not energize SPD until deficiencies have been corrected.

D. Verify that conditions are satisfactory for installation prior to starting work.

3.2 INSTALLATION

A. Perform work in a neat and workmanlike manner in accordance with NECA 1.

B. Arrange equipment to provide minimum clearances in accordance with manufacturer's instructions and NFPA 70.

C. Unless indicated otherwise, connect service entrance surge protective device on load side of service disconnect main overcurrent device.

D. Install conductors between SPD and equipment terminations as short and straight as possible, not exceeding manufacturer's recommended maximum conductor length. Breaker locations may be reasonably rearranged in order to provide leads as short and straight as possible. Twist conductors together to reduce inductance.

E. Do not energize SPD until bonding of neutral and ground for service entrance and separately derived systems is complete in accordance with Section 260526 where applicable. Replace SPDs damaged by improper or missing neutral-ground bond.

3.3 FIELD QUALITY CONTROL

A. Procure services of a qualified manufacturer's representative to observe installation and assist in inspection, testing, and adjusting. Include manufacturer's reports with field quality control submittals.

3.4 CLEANING

A. Repair scratched or marred exterior surfaces to match original factory finish.

END OF SECTION 264300

SECTION 265100

INTERIOR LIGHTING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Interior luminaires.

B. Emergency lighting units.

C. Exit signs.

D. Ballasts.

E. Fluorescent emergency power supply units.

F. Lamps.

G. Luminaire accessories.

1.2 RELATED REQUIREMENTS

A. Section 260537 - Boxes.

B. Section 260553 - Identification for Electrical Systems: Identification products and requirements.

C. Section 260919 - Enclosed Contactors: Lighting contactors.

D. Section 260923 - Lighting Control Devices: Automatic controls for lighting including occupancy sensors.

E. Section 262726 - Wiring Devices: Manual wall switches.

F. Section 265600 - Exterior Lighting.

1.3 REFERENCE STANDARDS

A. ANSI C82.11 - American National Standard for Lamp Ballasts - High Frequency Fluorescent Lamp Ballasts - Supplements; 2011.

B. IEEE C62.41.2 - Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and less) AC Power Circuits; 2002 (Cor 1, 2012).

C. IES LM-79 - Approved Method: Electrical and Photometric Measurements of Solid-State Lighting Products; Illuminating Engineering Society; 2008.

D. IES LM-80 - Approved Method: Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays, and Modules; Illuminating Engineering Society; 2015.

E. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

F. NECA/IESNA 500 - Standard for Installing Indoor Commercial Lighting Systems; 2006.

G. NECA/IESNA 502 - Standard for Installing Industrial Lighting Systems; 2006.

H. NEMA LE 4 - Recessed Luminaires, Ceiling Compatibility; 2012.

I. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

J. NFPA 101 - Life Safety Code; 2015.

K. UL 924 - Emergency Lighting and Power Equipment; Current Edition, Including All Revisions.

L. UL 935 - Fluorescent-Lamp Ballasts; Current Edition, Including All Revisions.

M. UL 1598 - Luminaires; Current Edition, Including All Revisions.

N. UL 8750 - Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate the installation of luminaires with mounting surfaces installed under other sections or by others. Coordinate the work with placement of supports, anchors, etc. required for mounting. Coordinate compatibility of luminaires and associated trims with mounting surfaces at installed locations.
2. Coordinate the placement of luminaires with structural members, ductwork, piping, equipment, diffusers, fire suppression system components, and other potential conflicts installed under other sections or by others.
3. Coordinate the placement of exit signs with furniture, equipment, signage or other potential obstructions to visibility installed under other sections or by others.
4. Notify Architect of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.

1.5 SUBMITTALS

A. Shop Drawings:
1. Indicate dimensions and components for each luminaire that is not a standard product of the manufacturer.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, installed accessories, and ceiling compatibility; include model number nomenclature clearly marked with all proposed features.
1. LED Luminaires:
a. Include estimated useful life, calculated based on IES LM-80 test data.
2. Lamps: Include rated life, color temperature, color rendering index (CRI), and initial and mean lumen output.
3. Fluorescent Emergency Power Supply Unit: Include list of compatible lamp configurations and associated lumen output.

C. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, and installation of product.

D. Operation and Maintenance Data: Instructions for each product including information on replacement parts.

E. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
1. See Section 016000 - Product Requirements, for additional provisions.
2. Extra Lamps: Ten percent of total quantity installed for each type, but not less than two of each type.
3. Extra Ballasts: Two percent of total quantity installed for each type, but not less than one of each type.

F. Project Record Documents: Record actual connections and locations of luminaires and any associated remote components.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND PROTECTION

A. Receive, handle, and store products according to NECA/IESNA 500 (commercial lighting), NECA/IESNA 502 (industrial lighting), and manufacturer's written instructions.

B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

1.8 FIELD CONDITIONS

A. Maintain field conditions within manufacturer's required service conditions during and after installation.

1.9 WARRANTY

A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

B. Provide two year manufacturer warranty for all linear fluorescent ballasts.

C. Provide five year pro-rata warranty for batteries for emergency lighting units.

D. Provide ten year pro-rata warranty for batteries for self-powered exit signs.

E. Provide five year full warranty for fluorescent emergency power supply units.

PART 2 PRODUCTS

2.1 LUMINAIRE TYPES

A. Furnish products as indicated in luminaire schedule included on the drawings.

B. Substitutions: See Section 016000 - Product Requirements.

2.2 LUMINAIRES

A. Provide products that comply with requirements of NFPA 70.

B. Provide products that are listed and labeled as complying with UL 1598, where applicable.

C. Provide products listed and classified by Underwriters Laboratories Inc. or testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

D. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.

E. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, supports, trims, accessories, etc. as necessary for a complete operating system.

F. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.

G. Recessed Luminaires:
   1. Ceiling Compatibility: Comply with NEMA LE 4.

H. Fluorescent Luminaires:
   1. Provide ballast disconnecting means complying with NFPA 70 where required.
   2. Fluorescent Luminaires Controlled by Occupancy Sensors: Provide programmed start ballasts.
   3. Fluorescent Luminaires Controlled by Dual-Level Switching: Provide with two ballasts.

I. LED Luminaires:
   1. Components: UL 8750 recognized or listed as applicable.
   2. Tested in accordance with IES LM-79 and IES LM-80.
   3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.

J. Luminaires Mounted in Continuous Rows: Provide quantity of units required for length indicated, with all accessories required for joining and aligning.

2.3 EMERGENCY LIGHTING UNITS

A. Description: Emergency lighting units complying with NFPA 101 and all applicable state and local codes, and listed and labeled as complying with UL 924.

B. Operation: Upon interruption of normal power source or brownout condition exceeding 20 percent voltage drop from nominal, solid-state control automatically switches connected lamps to integral battery power for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.

C. Battery:
   1. Sealed maintenance-free lead calcium unless otherwise indicated.
   2. Size battery to supply all connected lamps, including emergency remote heads where indicated.

D. Diagnostics: Provide power status indicator light and accessible integral test switch to manually activate emergency operation.

E. Provide low-voltage disconnect to prevent battery damage from deep discharge.

F. Self-Diagnostics: Provide units that self-monitor functionality and automatically perform testing required by NFPA 101 where indicated; provide indicator light(s) to report test and diagnostic status.

2.4 EXIT SIGNS

A. All Exit Signs: Internally illuminated with LEDs unless otherwise indicated; complying with NFPA 101 and all applicable state and local codes, and listed and labeled as complying with UL 924.
   1. Number of Faces: Single or double as indicated or as required for the installed location.
   2. Directional Arrows: As indicated or as required for the installed location.

B. Self-Powered Exit Signs:
   1. Operation: Upon interruption of normal power source or brownout condition exceeding 20 percent voltage drop from nominal, solid-state control automatically switches connected lamps to integral battery power for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.
   2. Diagnostics: Provide power status indicator light and accessible integral test switch to manually activate emergency operation.
   3. Provide low-voltage disconnect to prevent battery damage from deep discharge.
   4. Self-Diagnostics: Provide units that self-monitor functionality and automatically perform testing required by NFPA 101 where indicated; provide indicator light(s) to report test and diagnostic status.

2.5 BALLASTS

A. Manufacturers:
   1. General Electric Company/GE Lighting; : www.gelighting.com/#sle.
   2. Osram Sylvania; : www.sylvania.com/#sle.
   3. Philips Lighting Electronics/Advance; : www.advance.philips.com.
   4. Substitutions: See Section 016000 - Product Requirements.
   5. Manufacturer Limitations: Where possible, for each type of luminaire provide ballasts produced by a single manufacturer.

B. All Ballasts:
   1. Provide ballasts containing no polychlorinated biphenyls (PCBs).
   2. Minimum Efficiency/Efficacy: Provide ballasts complying with all current applicable federal and state ballast efficiency/efficacy standards.

C. Fluorescent Ballasts:
   1. All Fluorescent Ballasts: Unless otherwise indicated, provide high frequency electronic ballasts complying with ANSI C82.11 and listed and labeled as complying with UL 935.
      a. Input Voltage: Suitable for operation at voltage of connected source, with variation tolerance of plus or minus 10 percent.
      b. Total Harmonic Distortion: Not greater than 10 percent.
      c. Power Factor: Not less than 0.95.
      d. Ballast Factor: Normal ballast factor between 0.85 and 1.15, unless otherwise indicated.
      e. Thermal Protection: Listed and labeled as UL Class P, with automatic reset for integral thermal protectors.
      f. Sound Rating: Class A, suitable for average ambient noise level of 20 to 24 decibels.
      g. Lamp Compatibility: Specifically designed for use with the specified lamp, with no visible flicker.
      h. Lamp Operating Frequency: Greater than 20 kHz, except as specified below.
      i. Lamp Current Crest Factor: Not greater than 1.7.
      j. Lamp Wiring Method:

1) Programmed Start Ballasts: Provide parallel or series/parallel wired where available; otherwise series wired is acceptable.

k. Provide automatic restart capability to restart replaced lamp(s) without requiring resetting of power.

l. Provide end of lamp life automatic shut down circuitry for T5 and smaller diameter lamp ballasts.

m. Surge Tolerance: Capable of withstanding characteristic surges according to IEEE C62.41.2, location category A.

n. Electromagnetic Interference/Radio Frequency Interference (EMI/RFI) Limits: Comply with FCC requirements of CFR, Title 47, Part 18, for Class A, non-consumer application.

o. Ballast Marking: Include wiring diagrams with lamp connections.

2. Non-Dimming Fluorescent Ballasts:

a. Lamp Starting Method:

1) T8 Lamp Ballasts: Programmed start unless otherwise indicated.

2) T5 Lamp Ballasts: Programmed start unless otherwise indicated.

3) Compact Fluorescent Lamp Ballasts: Programmed start unless otherwise indicated.

b. Lamp Starting Temperature: Capable of starting standard lamp(s) at a minimum of 0 degrees F, and energy saving lamp(s) at a minimum of 60 degrees F unless otherwise indicated.

D. Dimmable LED Drivers:

1. Dimming Range: Continuous dimming from 100 percent to five percent relative light output unless dimming capability to lower level is indicated, without flicker.

2. Control Compatibility: Fully compatible with the dimming controls to be installed.

2.6 FLUORESCENT EMERGENCY POWER SUPPLY UNITS

A. Manufacturers:

1. Iota Engineering, LLC; _____: www.iotaengineering.com/#sle.

2. Philips Emergency Lighting/Bodine; _____: www.bodine.com/#sle.

3. Substitutions: See Section 016000 - Product Requirements.

4. Manufacturer Limitations: Where possible, for each type of luminaire provide fluorescent emergency power supply units produced by a single manufacturer.

B. Description: Self-contained fluorescent emergency power supply units suitable for use with indicated luminaires, complying with NFPA 101 and all applicable state and local codes, and listed and labeled as complying with UL 924.

C. Compatibility:

1. Ballasts: Compatible with electronic, standard magnetic, energy saving, and dimming AC ballasts, including those with end of lamp life shutdown circuits.

2. Lamps: Compatible with low-mercury lamps.

D. Operation: Upon interruption of normal power source, solid-state control automatically switches connected lamp(s) to the fluorescent emergency power supply for minimum of 90 minutes of rated emergency illumination, and automatically recharges battery upon restoration of normal power source.

E. Battery: Sealed maintenance-free high-temperature nickel cadmium unless otherwise indicated.

F. Emergency Illumination Output:

1. As indicated in Light Fixture Schedule

G. Diagnostics: Provide accessible and visible multi-chromatic combination test switch/indicator light to display charge, test, and diagnostic status and to manually activate emergency operation.

H. Operating Temperature: From 32 degrees F to 122 degrees F unless otherwise indicated or required for the installed location.

2.7 LAMPS

A. Manufacturers:

1. General Electric Company/GE Lighting; _____: www.gelighting.com/#sle.
2. Osram Sylvania; _____: www.sylvania.com/#sle.
3. Philips Lighting Company; _____: www.lighting.philips.com.
4. Substitutions: See Section 016000 - Product Requirements.
5. Manufacturer Limitations: Where possible, provide lamps produced by a single manufacturer.

B. All Lamps:
1. Unless explicitly excluded, provide new, compatible, operable lamps in each luminaire.
2. Verify compatibility of specified lamps with luminaires to be installed. Where lamps are not specified, provide lamps per luminaire manufacturer's recommendations.
3. Minimum Efficiency: Provide lamps complying with all current applicable federal and state lamp efficiency standards.
4. Color Temperature Consistency: Unless otherwise indicated, for each type of lamp furnish products which are consistent in perceived color temperature. Replace lamps that are determined by the Architect to be inconsistent in perceived color temperature.

C. Incandescent Lamps: Wattage and bulb type as indicated, with base type as required for lighting fixture; 130 V rated.
1. Non-Reflector Type Incandescent Lamps: Inside frosted lamp finish unless otherwise indicated.

D. Compact Fluorescent Lamps: Wattage and bulb type as indicated, with base type as required for luminaire.
1. Low Mercury Content: Provide lamps that pass the EPA Toxicity Characteristic Leaching Procedure (TCLP) test for characteristic hazardous waste.
2. Correlated Color Temperature (CCT): 3,000 K unless otherwise indicated.
3. Color Rendering Index (CRI): Not less than 80.
4. Average Rated Life: Not less than 10,000 hours for an operating cycle of three hours per start.

E. Linear Fluorescent Lamps: Wattage and bulb type as indicated, with base type as required for luminaire.
1. Low Mercury Content: Provide lamps that pass the EPA Toxicity Characteristic Leaching Procedure (TCLP) test for characteristic hazardous waste.
2. T8 Linear Fluorescent Lamps:
a. Correlated Color Temperature (CCT): 3,000 K unless otherwise indicated.
b. Color Rendering Index (CRI): Not less than 80.
c. Average Rated Life: Not less than 20,000 hours for an operating cycle of three hours per start.
3. T5 Linear Fluorescent Lamps:
a. Correlated Color Temperature (CCT): 3,000 K unless otherwise indicated.
b. Color Rendering Index (CRI): Not less than 80.
c. Average Rated Life: Not less than 20,000 hours for an operating cycle of three hours per start.

2.8 ACCESSORIES

A. Stems for Suspended Luminaires: Steel tubing, minimum 1/2" size, factory finished to match luminaire or field-painted as directed.

B. Threaded Rods for Suspended Luminaires: Zinc-plated steel, minimum 1/4" size, field-painted as directed.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate conductors in accordance with NFPA 70.

C. Verify that suitable support frames are installed where required.

D. Verify that branch circuit wiring installation is completed, tested, and ready for connection to luminaires.

E. Verify that conditions are satisfactory for installation prior to starting work.

3.2 PREPARATION

A. Provide extension rings to bring outlet boxes flush with finished surface.

B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.3 INSTALLATION

A. Coordinate locations of outlet boxes provided under Section 260537 as required for installation of luminaires provided under this section.

B. Install products according to manufacturer's instructions.

C. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 1 (general workmanship), NECA 500 (commercial lighting), and NECA 502 (industrial lighting).

D. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.

E. Suspended Ceiling Mounted Luminaires:
   1. Do not use ceiling tiles to bear weight of luminaires.
   2. Do not use ceiling support system to bear weight of luminaires unless ceiling support system is certified as suitable to do so.
   3. Secure surface-mounted and recessed luminaires to ceiling support channels or framing members or to building structure.
   4. Secure pendant-mounted luminaires to building structure.
   5. Secure lay-in luminaires to ceiling support channels using listed safety clips at four corners.
   6. In addition to ceiling support wires, provide two galvanized steel safety wire(s), minimum 12 gage, connected from opposing corners of each recessed luminaire to building structure.
   7. See appropriate Division 9 section where suspended grid ceiling is specified for additional requirements.

F. Recessed Luminaires:
   1. Install trims tight to mounting surface with no visible light leakage.
   2. Non-IC Rated Luminaires: Maintain required separation from insulation and combustible materials according to listing.

G. Suspended Luminaires:
   1. Unless otherwise indicated, specified mounting heights are to bottom of luminaire.
   2. Install using the suspension method indicated, with support lengths and accessories as required for specified mounting height.
   3. Provide minimum of two supports for each luminaire equal to or exceeding 4 feet in length, with no more than 4 feet between supports.
   4. Install canopies tight to mounting surface.
   5. Unless otherwise indicated, support pendants from swivel hangers.

H. Wall-Mounted Luminaires: Unless otherwise indicated, specified mounting heights are to center of luminaire.

I. Install accessories furnished with each luminaire.

J. Bond products and metal accessories to branch circuit equipment grounding conductor.

K. Fluorescent Luminaires Controlled by Dual-Level Switching: Connect such that each switch controls the same corresponding lamps in each luminaire.

L. Emergency Lighting Units:
   1. Unless otherwise indicated, connect unit to unswitched power from same circuit feeding normal lighting in same room or area. Bypass local switches, contactors, or other lighting controls.

M. Exit Signs:

1. Unless otherwise indicated, connect unit to unswitched power from same circuit feeding normal lighting in same room or area. Bypass local switches, contactors, or other lighting controls.

N. Fluorescent Emergency Power Supply Units:
   1. For field-installed units, install inside luminaire unless otherwise indicated. Where installation inside luminaire is not possible, install on top of luminaire.
   2. Unless otherwise indicated, connect unit to unswitched power from same circuit feeding normal ballast(s) in luminaire. Bypass local switches, contactors, or other lighting controls.

O. Install lamps in each luminaire.

P. Lamp Burn-In: Operate lamps at full output for prescribed period per manufacturer's recommendations prior to use with any dimming controls. Replace lamps that fail prematurely due to improper lamp burn-in.

3.4 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements, for additional requirements.

B. Inspect each product for damage and defects.

C. Operate each luminaire after installation and connection to verify proper operation.

D. Test self-powered exit signs, emergency lighting units, and fluorescent emergency power supply units to verify proper operation upon loss of normal power supply.

E. Correct wiring deficiencies and repair or replace damaged or defective products. Repair or replace excessively noisy ballasts as determined by Architect.

3.5 ADJUSTING

A. Aim and position adjustable luminaires to achieve desired illumination as indicated or as directed by Architect. Secure locking fittings in place.

B. Aim and position adjustable emergency lighting unit lamps to achieve optimum illumination of egress path as required or as directed by Architect or authority having jurisdiction.

C. Exit Signs with Field-Selectable Directional Arrows: Set as indicated or as required to properly designate egress path as directed by Architect or authority having jurisdiction.

3.6 CLEANING

A. Clean surfaces according to NECA 500 (commercial lighting), NECA 502 (industrial lighting), and manufacturer's instructions to remove dirt, fingerprints, paint, or other foreign material and restore finishes to match original factory finish.

3.7 CLOSEOUT ACTIVITIES

A. Just prior to Substantial Completion, replace all lamps that have failed.

3.8 PROTECTION

A. Protect installed luminaires from subsequent construction operations.

END OF SECTION 265100

SECTION 265600

EXTERIOR LIGHTING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Exterior luminaires.

B. Poles and accessories.

1.2 RELATED REQUIREMENTS

A. Section 033000 - Cast-in-Place Concrete: Materials and installation requirements for concrete bases for poles.

B. Section 260526 - Grounding and Bonding for Electrical Systems.

C. Section 260537 - Boxes.

D. Section 260919 - Enclosed Contactors: Lighting contactors.

E. Section 260923 - Lighting Control Devices: Automatic controls for lighting including outdoor photo controls.

1.3 REFERENCE STANDARDS

A. ANSI C82.4 - American National Standard for Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type); 2002.

B. IES LM-79 - Approved Method: Electrical and Photometric Measurements of Solid-State Lighting Products; Illuminating Engineering Society; 2008.

C. IES LM-80 - Approved Method: Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays, and Modules; Illuminating Engineering Society; 2015.

D. NECA 1 - Standard for Good Workmanship in Electrical Construction; 2010.

E. NECA/IESNA 501 - Standard for Installing Exterior Lighting Systems; 2006.

F. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

G. UL 1598 - Luminaires; Current Edition, Including All Revisions.

H. UL 8750 - Light Emitting Diode (LED) Equipment for Use in Lighting Products; Current Edition, Including All Revisions.

1.4 ADMINISTRATIVE REQUIREMENTS

A. Coordination:

1. Coordinate placement of poles and associated foundations with utilities, curbs, sidewalks, trees, walls, fences, striping, etc. installed under other sections or by others. Coordinate elevation to obtain specified foundation height.
2. Notify Architect of any conflicts or deviations from the contract documents to obtain direction prior to proceeding with work.

1.5 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturer's standard catalog pages and data sheets including detailed information on luminaire construction, dimensions, ratings, finishes, mounting requirements, listings, service conditions, photometric performance, weight, effective projected area (EPA), and installed accessories; include model number nomenclature clearly marked with all proposed features.

1. LED Luminaires:
   a. Include estimated useful life, calculated based on IES LM-80 test data.
2. Poles: Include information on maximum supported effective projected area (EPA) and weight for the design wind speed.

C. Certificates for Poles and Accessories: Manufacturer's documentation that products are suitable for the luminaires to be installed.

D. Manufacturer's Installation Instructions: Indicate application conditions and limitations of use stipulated by product testing agency. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.

E. Operation and Maintenance Data: Instructions for each product including information on replacement parts.

F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
   1. Touch-Up Paint: 2 gallons, to match color of pole finish.

G. Project Record Documents: Record actual connections and locations of pole foundations, luminaires, and any pull or junction boxes.

1.6 QUALITY ASSURANCE

A. Conform to requirements of NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Receive, handle, and store products according to NECA/IESNA 501 and manufacturer's written instructions.

B. Keep products in original manufacturer's packaging and protect from damage until ready for installation.

1.8 WARRANTY

A. See Section 017800 - Closeout Submittals, for additional warranty requirements.

B. Provide five year manufacturer warranty for all LED luminaires, including drivers.

PART 2 PRODUCTS

2.1 LUMINAIRE TYPES

A. Furnish products as indicated in luminaire schedule included on the Drawings.

B. Substitutions: See Section 016000 - Product Requirements.

2.2 LUMINAIRES

A. Provide products that comply with requirements of NFPA 70.

B. Provide products that are listed and labeled as complying with UL 1598, where applicable.

C. Provide products listed and classified by testing firm acceptable to the authority having jurisdiction as suitable for the purpose specified and indicated.

D. Unless otherwise indicated, provide complete luminaires including lamp(s) and all sockets, ballasts, reflectors, lenses, housings and other components required to position, energize and protect the lamp and distribute the light.

E. Unless specifically indicated to be excluded, provide all required conduit, boxes, wiring, connectors, hardware, poles, foundations, supports, trims, accessories, etc. as necessary for a complete operating system.

F. Provide products suitable to withstand normal handling, installation, and service without any damage, distortion, corrosion, fading, discoloring, etc.

G. Provide luminaires listed and labeled as suitable for wet locations unless otherwise indicated.

H. LED Luminaires:
   1. Components: UL 8750 recognized or listed as applicable.
   2. Tested in accordance with IES LM-79 and IES LM-80.
   3. LED Estimated Useful Life: Minimum of 50,000 hours at 70 percent lumen maintenance, calculated based on IES LM-80 test data.

2.3 POLES

A. All Poles:
   1. Provide poles and associated support components suitable for the luminaire(s) and associated supports and accessories to be installed.
   2. Structural Design Criteria:
      a. Wind Load: Include effective projected area (EPA) of luminaire(s) and associated supports and accessories to be installed.
         1) Design Wind Speed: 100 miles per hour, with gust factor of 1.3.
      b. Dead Load: Include weight of proposed luminaire(s) and associated supports and accessories.
   3. Material: Steel, unless otherwise indicated.
   4. Shape: Round straight, unless otherwise indicated.
   5. Finish: Match luminaire finish, unless otherwise indicated.
   6. Mounting: Install on concrete foundation, height as indicated on the drawings, unless otherwise indicated.
   7. Unless otherwise indicated, provide with the following features/accessories:
      a. Top cap.
      b. Handhole.
      c. Anchor bolts with leveling nuts or leveling shims.
      d. Anchor base cover.

B. Metal Poles: Provide ground lug, accessible from handhole.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that field measurements are as shown on the drawings.

B. Verify that outlet boxes are installed in proper locations and at proper mounting heights and are properly sized to accommodate conductors in accordance with NFPA 70.

C. Verify that suitable support frames are installed where required.

D. Verify that branch circuit wiring installation is completed, tested, and ready for connection to luminaires.

E. Verify that conditions are satisfactory for installation prior to starting work.

3.2 PREPARATION

A. Provide extension rings to bring outlet boxes flush with finished surface.

B. Clean dirt, debris, plaster, and other foreign materials from outlet boxes.

3.3 INSTALLATION

A. Coordinate locations of outlet boxes provided under Section 260537 as required for installation of luminaires provided under this section.

B. Install products according to manufacturer's instructions.

C. Install luminaires securely, in a neat and workmanlike manner, as specified in NECA 1 (general workmanship) and NECA/IESNA 501 (exterior lighting).

D. Install luminaires plumb and square and aligned with building lines and with adjacent luminaires.

E. Recessed Luminaires:
   1. Install trims tight to mounting surface with no visible light leakage.

F. Pole-Mounted Luminaires:
   1. Foundation-Mounted Poles:
      a. Provide cast-in-place concrete foundations for poles as indicated, in accordance with Section 033000.

1) Install anchor bolts plumb per template furnished by pole manufacturer.
2) Position conduits to enter pole shaft.

b. Install foundations plumb.
c. Install poles plumb, using leveling nuts or shims as required to adjust to plumb.
d. Tighten anchor bolt nuts to manufacturer's recommended torque.
e. Install non-shrink grout between pole anchor base and concrete foundation, leaving small channel for condensation drainage.
f. Install anchor base covers as indicated.

2. Grounding:
   a. Bond luminaires, metal accessories, metal poles, and foundation reinforcement to branch circuit equipment grounding conductor.
   b. Provide supplementary ground rod electrode as specified in Section 260526 at each pole bonded to grounding system as indicated.
3. Install separate service conductors, 12 AWG copper, from each luminaire down to handhole for connection to branch circuit conductors.

G. Install accessories furnished with each luminaire.

H. Bond products and metal accessories to branch circuit equipment grounding conductor.

I. Install lamps in each luminaire.

3.4 FIELD QUALITY CONTROL

A. Inspect each product for damage and defects.

B. Operate each luminaire after installation and connection to verify proper operation.

C. Correct wiring deficiencies and repair or replace damaged or defective products. Repair or replace excessively noisy ballasts as determined by Architect.

3.5 ADJUSTING

A. Aim and position adjustable luminaires to achieve desired illumination as indicated or as directed by Architect. Secure locking fittings in place.

B. Luminaires with Field-Rotatable Optics: Position optics according to manufacturer's instructions to achieve lighting distribution as indicated or as directed by Architect.

3.6 CLEANING

A. Clean surfaces according to NECA/IESNA 501 and manufacturer's instructions to remove dirt, fingerprints, paint, or other foreign material and restore finishes to match original factory finish.

3.7 PROTECTION

A. Protect installed luminaires from subsequent construction operations.

END OF SECTION 265600

SECTION 283100

FIRE DETECTION AND ALARM

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Fire alarm system design and installation, including all components, wiring, and conduit.

B. Transmitters for communication with supervising station.

C. Maintenance of fire alarm system under contract for specified warranty period.

1.2 RELATED REQUIREMENTS

A. Section 213000 - Fire Pumps: Supervisory devices.

B. Section 211300 - Fire-Suppression Sprinkler Systems: Supervisory, alarm, and actuating devices installed in sprinkler system.

C. Section 142010 - Passenger Elevators: Elevator systems monitored and controlled by fire alarm system.

1.3 REFERENCE STANDARDS

A. 36 CFR 1191 - Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines; current edition.

B. IEEE C62.41.2 - Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and less) AC Power Circuits; 2002 (Cor 1, 2012).

C. IEEE C62.41 - IEEE Recommended Practice on Surge Voltages in Low-Voltage Power Circuits; 1991 (R1995).

D. NFPA 70 - National Electrical Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

E. NFPA 72 - National Fire Alarm and Signaling Code; 2016.

F. NFPA 101 - Life Safety Code; 2015.

1.4 SUBMITTALS

A. Proposal Documents: Submit the following with cost/time proposal:
   1. NFPA 72 "Record of Completion", filled out to the extent known at the time.
   2. Manufacturer's detailed data sheet for each control unit, initiating device, and notification appliance.
   3. Certification by Contractor that the system design will comply with the contract documents.
   4. Proposed maintenance contract.

B. Evidence of designer qualifications.

C. Design Documents: Submit all information required for plan review and permitting by authorities having jurisdiction, including but not limited to floor plans, riser diagrams, and description of operation:
   1. Copy (if any) of list of data required by authority having jurisdiction.
   2. NFPA 72 "Record of Completion", filled out to the extent known at the time.
   3. Clear and concise description of operation, with input/output matrix similar to that shown in NFPA 72 Appendix A-7-5-2.2(9), and complete listing of software required.
   4. System zone boundaries and interfaces to fire safety systems.
   5. Location of all components, circuits, and raceways; mark components with identifiers used in control unit programming.
   6. Circuit layouts; number, size, and type of raceways and conductors; conduit fill calculations; spare capacity calculations; notification appliance circuit voltage drop calculations.
   7. List of all devices on each signaling line circuit, with spare capacity indicated.
   8. Manufacturer's detailed data sheet for each component, including wiring diagrams, installation instructions, and circuit length limitations.

9. Description of power supplies; if secondary power is by battery include calculations demonstrating adequate battery power.
10. Certification by either the manufacturer of the control unit or by the manufacturer of each other component that the components are compatible with the control unit.
11. Certification by the manufacturer of the control unit that the system design complies with the contract documents.
12. Certification by Contractor that the system design complies with the contract documents.

D. Evidence of installer qualifications.

E. Evidence of maintenance contractor qualifications, if different from installer.

F. Inspection and Test Reports:
1. Submit inspection and test plan prior to closeout demonstration.
2. Submit documentation of satisfactory inspections and tests.
3. Submit NFPA 72 "Inspection and Test Form," filled out.

G. Operating and Maintenance Data: Revise and resubmit until acceptable; have one set available during closeout demonstration:
1. Complete set of specified design documents, as approved by authority having jurisdiction.
2. Additional printed set of project record documents and closeout documents, bound or filed in same manuals.
3. Contact information for firm that will be providing contract maintenance and trouble call-back service.
4. List of recommended spare parts, tools, and instruments for testing.
5. Replacement parts list with current prices, and source of supply.
6. Detailed troubleshooting guide and large scale input/output matrix.
7. Preventive maintenance, inspection, and testing schedule complying with NFPA 72; provide printed copy and computer format acceptable to Owner.
8. Detailed but easy to read explanation of procedures to be taken by non-technical administrative personnel in the event of system trouble, when routine testing is being conducted, for fire drills, and when entering into contracts for remodeling.

H. Project Record Documents: Have one set available during closeout demonstration:
1. Complete set of floor plans showing actual installed locations of components, conduit, and zones.
2. "As installed" wiring and schematic diagrams, with final terminal identifications.
3. "As programmed" operating sequences, including control events by device, updated input/output chart, and voice messages by event.

I. Closeout Documents:
1. Certification by manufacturer that the system has been installed in compliance with his installation requirements, is complete, and is in satisfactory operating condition.
2. NFPA 72 "Record of Completion", filled out completely and signed by installer and authorized representative of authority having jurisdiction.
3. Certificate of Occupancy.
4. Maintenance contract.

1.5 QUALITY ASSURANCE

A. Designer Qualifications: Registered engineer, employed by fire alarm control panel manufacturer, Contractor, or installer, with experience designing fire alarm systems in the jurisdictional area of the authorities having jurisdiction.

B. Installer Qualifications: Firm with minimum 3 years documented experience installing fire alarm systems of the specified type and providing contract maintenance service as a regular part of their business.
1. Authorized representative of control unit manufacturer; submit manufacturer's certification that installer is authorized; include name and title of manufacturer's representative making certification.

2. Installer Personnel: At least 2 years of experience installing fire alarm systems.
3. Supervisor: NICET level III or IV (3 or 4) certified fire alarm technician; furnish name and address.

C. Maintenance Contractor Qualifications: Same entity as installer or different entity with specified qualifications.

D. Product Listing Organization Qualifications: An organization recognized by OSHA as a Nationally Recognized Testing Laboratory (NRTL) and acceptable to authorities having jurisdiction.

1.6 WARRANTY

A. Provide control panel manufacturer's warranty that system components other than wire and conduit are free from defects and will remain so for 1 year after date of Substantial Completion.

B. Provide installer's warranty that the installation is free from defects and will remain so for 1 year after date of Substantial Completion.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Fire Alarm Control Units: Provided their products meet or exceed the performance of the basis of design product, products of the following are acceptable:
1. Honeywell Security & Fire Solutions/Notifier: www.notifier.com/#sle.
2. Siemens Building Technologies, Inc: www.usa.siemens.com/#sle.
3. Provide all control units made by the same manufacturer.

B. Initiating Devices, and Notification Appliances:
1. Same manufacturer as control units.
2. Provide all initiating devices and notification appliances made by the same manufacturer.

C. Substitutions: Not permitted.

2.2 FIRE ALARM SYSTEM

A. Fire Alarm System: Provide a new automatic fire detection and alarm system:
1. Provide all components necessary, regardless of whether shown in the contract documents or not.
2. Protected Premises: Entire building.
3. Comply with the following; where requirements conflict, order of precedence of requirements is as listed:
a. ADA Standards for Accessible Design.
b. The requirements of the State Fire Marshal.
c. The requirements of the local authority having jurisdiction .
d. Applicable local codes.
e. The contract documents (drawings and specifications).
f. NFPA 101.
g. NFPA 72; where the word "should" is used consider that provision mandatory; where conflicts between requirements require deviation from NFPA 72, identify deviations clearly on design documents.
4. Evacuation Alarm: general evacuation of entire premises.
5. Hearing Impaired Occupants: Provide visible notification devices in all public areas and in dwelling units.
6. Master Control Unit (Panel): New, location shown on plans .
7. Combined Systems: Do not combine fire alarm system with other non-fire systems.

B. Supervising Stations and Fire Department Connections:
1. Public Fire Department Notification: By on-premises supervising station.
2. Remote Supervising Station: UL-listed central station under contract to facility.
3. Means of Transmission to Remote Supervising Station: Digital alarm communicator transmitter (DACT), 2 telephone lines.

C. Circuits:
   1. Initiating Device Circuits (IDC): Class A, Style D.
   2. Signaling Line Circuits (SLC) : Class A, Style 6.
   3. Notification Appliance Circuits (NAC): Class B, Style Y.

D. Spare Capacity:
   1. Initiating Device Addresses: Minimum 25 percent spare capacity.
   2. Notification Appliance Circuits: Minimum 25 percent spare capacity.
   3. Master Control Unit: Capable of handling all circuits utilized to capacity without requiring additional components other than plug-in control modules.

E. Power Sources:
   1. Primary: Dedicated branch circuits of the facility power distribution system.
   2. Secondary: Storage batteries.
   3. Capacity: Sufficient to operate entire system for period specified by NFPA 72.

2.3 FIRE SAFETY SYSTEMS INTERFACES

A. Supervision: Provide supervisory signals in accordance with NFPA 72 for the following:
   1. Sprinkler/standpipe water control valves.
   2. Fire pump(s).
   3. Elevator shut-down control circuits.

B. Alarm: Provide alarm initiation in accordance with NFPA 72 for the following:
   1. Sprinkler water flow.
   2. Elevator lobby, elevator hoistway, and elevator machine room smoke detectors.
   3. Smoke and heat detectors.
   4. Manual Pull Stations.

C. Elevators:
   1. Elevator lobby, hoistway, and machine room smoke detectors: Elevator recall for fire fighters' service.
   2. Elevator Machine Room and hoistway Heat Detectors: Shut down elevator power prior to hoistway sprinkler activation.

D. Doors:
   1. Door Magnetic Holders: Release upon activation of general alarm.

2.4 COMPONENTS

A. General:
   1. Provide flush mounted units where installed in finish areas; in unfinished areas, surface mounted unit are acceptable.
   2. Provide legible, permanent labels for each control device, using identification used in operation and maintenance data.

B. Fire Alarm Control Units, Initiating Devices, and Notification Appliances: Analog, addressable type; listed by Underwriters Laboratories as suitable for the purpose intended.

C. Master Control Unit: As specified above.

D. Remote Annunciators: LCD display; .

E. Initiating Devices:
   1. Manual Pull Stations: Dual Action, non-coded, RED with white "FIRE" lettering.
   2. Smoke Detectors: Photoelectric, Addressable.
   3. Heat Detectors: Fixed temperature and Rate-of-Rise.
   4. Addressable Interface Devices.
      a. Provide 1 extra.

F. Notification Appliances:
   1. Bells.

2. Horns: Wall mounted, RED with white "FIRE" lettering, Temporal pattern.
3. Strobes: Wall mounted, RED with white "FIRE" lettering, Multi-candela selectable.
4. Horn/Strobes: Wall mounted, RED with white "FIRE" lettering.

G. Miscellaneous:
1. Door Holders: 24V Electromagnetic, Flush wall-mount FM998

H. Circuit Conductors: Copper; provide 200 feet extra; color code and label.

I. Surge Protection: In accordance with IEEE C62.41.2 category B combination waveform and NFPA 70; except for optical fiber conductors.
1. Equipment Connected to Alternating Current Circuits: Maximum let through voltage of 350 V(ac), line-to-neutral, and 350 V(ac), line-to-line; do not use fuses.

J. Locks and Keys: Deliver keys to Owner.

K. Instruction Charts: Printed instruction chart for operators, showing steps to be taken when a signal is received (normal, alarm, supervisory, and trouble); easily readable from normal operator's station.
1. Frame: Stainless steel or aluminum with polycarbonate or glass cover.
2. Provide one for each control unit where operations are to be performed.
3. Obtain approval of Owner prior to mounting; mount in location acceptable to Owner.
4. Provide extra copy with operation and maintenance data submittal.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with applicable codes, NFPA 72, NFPA 70, and the contract documents.

B. Conceal all wiring, conduit, boxes, and supports where installed in finished areas.

C. Install instruction cards and labels.

D. Provide one year monitoring service.

E. Verify location of all devices with Architect prior to installation.

3.2 INSPECTION AND TESTING FOR COMPLETION

A. Notify Owner 7 days prior to beginning completion inspections and tests.

B. Notify authorities having jurisdiction and comply with their requirements for scheduling inspections and tests and for observation by their personnel.

C. Provide the services of the installer's supervisor or person with equivalent qualifications to supervise inspection and testing, correction, and adjustments.

D. Prepare for testing by ensuring that all work is complete and correct; perform preliminary tests as required.

E. Provide all tools, software, and supplies required to accomplish inspection and testing.

F. Perform inspection and testing in accordance with NFPA 72 and requirements of local authorities; document each inspection and test.

G. Correct defective work, adjust for proper operation, and retest until entire system complies with contract documents.

3.3 PERSONNEL INSTRUCTION

A. Provide the following instruction to designated Owner personnel:
1. Hands-On Instruction: On-site, using operational system.

B. Administrative: One-hour session(s) covering issues necessary for non-technical administrative staff; classroom:
1. Initial Training: 1 session pre-closeout.

C. Basic Operation: One-hour sessions for attendant personnel, security officers, and engineering staff; combination of classroom and hands-on:

1. Initial Training: 1 session pre-closeout.

D. Furnish the services of instructors and teaching aids; have copies of operation and maintenance data available during instruction.

3.4 CLOSEOUT

A. Closeout Demonstration: Demonstrate proper operation of all functions to Owner.
   1. Be prepared to conduct any of the required tests.
   2. Have at least one copy of operation and maintenance data, preliminary copy of project record drawings, input/output matrix, and operator instruction chart(s) available during demonstration.
   3. Have authorized technical representative of control unit manufacturer present during demonstration.
   4. Demonstration may be combined with inspection and testing required by authority having jurisdiction; notify authority having jurisdiction in time to schedule demonstration.
   5. Repeat demonstration until successful.

B. Substantial Completion of the project cannot be achieved until inspection and testing is successful and:
   1. Approved operating and maintenance data has been delivered.
   2. All aspects of operation have been demonstrated to Owner.
   3. Final acceptance of the fire alarm system has been given by authorities having jurisdiction.
   4. Occupancy permit has been granted.
   5. Specified pre-closeout instruction is complete.

3.5 MAINTENANCE

A. Provide to Owner, at no extra cost, a written maintenance contract for entire manufacturer's warranty period, to include the work described below.

B. Perform routine inspection, testing, and preventive maintenance required by NFPA 72, including:
   1. Maintenance of fire safety interface and supervisory devices connected to fire alarm system.
   2. Repairs required, unless due to improper use, accidents, or negligence beyond the control of the maintenance contractor.
   3. Record keeping required by NFPA 72 and authorities having jurisdiction.

C. Provide trouble call-back service upon notification by Owner:
   1. Provide on-site response within 2 hours of notification.
   2. Include allowance for call-back service during normal working hours at no extra cost to Owner.
   3. Owner will pay for call-back service outside of normal working hours on an hourly basis, based on actual time spent at site and not including travel time; include hourly rate and definition of normal working hours in maintenance contract.

D. Provide a complete description of preventive maintenance, systematic examination, adjustment, cleaning, inspection, and testing, with a detailed schedule.

E. Maintain a log at each fire alarm control unit, listing the date and time of each inspection and call-back visit, the condition of the system, nature of the trouble, correction performed, and parts replaced. Submit duplicate of each log entry to Owner's representative upon completion of site visit.

F. Comply with Owner's requirements for access to facility and security.

END OF SECTION 283100